



REVIEW OF PRE-PRELIMINARY
CAPITAL COST ESTIMATE

SOUTHERN CALIFORNIA RAPID
TRANSIT DISTRICT

METRO RAIL PROJECT
LOS ANGELES, CALIFORNIA

5601 South Broadway
Littleton, Colorado 80121

303/794/1818

March 31, 1983

KC1223

JEK, AWJ, DDL, HEB,
REC, GHM, VET

GEH

METRO RAIL PROJECT
LOS ANGELES, CALIFORNIA

| | |
|--|---|
| OWNER: | Southern California Rapid Transit District |
| GENERAL ENGINEERING CONSULTANT: WAYS AND STRUCTURES | DMJM/PBQD A Joint Venture |
| GENERAL ARCHITECTURAL CONSULTANTS: STATIONS | Harry Weese & Associates Tippetts-Abbett-McCarthy- Stratton Environmental Collaborative, Inc. Gin Wong Associates |
| GENERAL GEOTECHNICAL CONSULTANTS: | Converse Ward Davis Dixon Earth Sciences Associates Geo/Resource Consultants |
| SUBSYSTEMS CONSULTANT: | Kaiser Engineering |

REVIEW OF PRE-PRELIMINARY
CAPITAL COST ESTIMATE

Southern California
Rapid Transit District
425 South Main Street
Los Angeles, California 90013
(213) 972-6562

James E. Crawley
Deputy Chief Engineer

Kellogg Corporation
5601 South Broadway
Suite 400
Littleton, Colorado 80121
(303) 794-1818

James E. Kelley
Project Executive
Alan W. Jongeneel
Project Manager

MTA LIBRARY

CONTENTS

| <u>SECTION</u> | | <u>Page</u> |
|----------------|---|-------------|
| 1 | INTRODUCTION | 1 |
| 2 | SUMMARY OF ESTIMATE REVIEW | 4 |
| 3 | KELLOGG CORPORATION METHODOLOGY AND SCOPE OF WORK | 9 |
| 4 | BASIS OF ESTIMATE | 12 |
| 5 | ESTIMATE REVIEW | 14 |
| | A. Estimate Organization | 14 |
| | B. Tunnels | 18 |
| | C. Station Shell | 23 |
| | D. Station Architectural | 28 |
| | E. Stations—Mechanical and Electrical | 30 |
| | F. Crossovers, Pocket Tracks and Tail Track | 35 |
| | G. Line Vent Structures—City and Mountain | 37 |
| | H. Vent Structures—Mechanical and Electrical | 39 |
| | I. Utilities | 40 |
| | J. Underpinning | 43 |
| | K. Traffic Maintenance | 46 |
| | L. Dewatering | 48 |
| | M. Trackwork | 50 |
| | N. Traction Power | 54 |
| | O. Main Yard | 56 |
| | P. Buildings—Structural and Architectural | 58 |
| | Q. Buildings—Mechanical and Electrical | 60 |

CONTENTS (Continued)

| <u>SECTION</u> | | <u>Page</u> |
|----------------|--|-------------|
| 5 | R. Parking | 61 |
| | S. Contingencies | 63 |
| | T. Contractor Markups | 65 |
| | U. Engineering, Design and Construction Management | 68 |
| | V. Agency Costs | 69 |
| | W. Wrap-Up Insurance | 71 |
| | X. Escalation | 72 |
| | Y. Construction Contract Packaging | 73 |
| 6 | APPENDIX | |
| | A. Estimate Organization | 76 |
| | B. Tunnels | 87 |
| | C. Station Shell | |
| | ● Station Shell Construction Summaries | 112 |
| | ● Station Shell Construction - Quantity Checks | 130 |
| | ● Station Shell Construction - Excavation | 132 |
| | ● Station Shell Construction - Soldier Pile and Lagging | 140 |
| | ● Station Shell Construction - Decking | 148 |
| | ● Station Shell Construction - Concrete | 153 |
| | ● Station Shell Construction - Muck Removal | 167 |
| | ● Station Shell Construction - Demolition | 169 |
| | ● Station Shell Construction - Depth Reduction | 176 |

CONTENTS (Continued)

| <u>SECTION</u> | | <u>Page</u> |
|----------------|---|-------------|
| 6 | ● Station Shell Construction - Parking Structure Deduction | 180 |
| | D. Station Architectural | 182 |
| | E. Stations - Mechanical and Electrical | 198 |
| | F. Crossovers, Pocket Tracks and Tail Track | 199 |
| | G. Line Vent Structures - City and Mountain | 211 |
| | H. Vent Structures - Mechanical and Electrical | 226 |
| | I. Utilities | 227 |
| | J. Underpinning | 228 |
| | K. Traffic Maintenance | 239 |
| | L. Dewatering | 241 |
| | M. Trackwork | 244 |
| | N. Traction Power | 269 |
| | O. Main Yard | 270 |
| | P. Buildings - Structural and Architectural | 277 |
| | Q. Buildings - Mechanical and Electrical | 278 |
| | R. Parking | 279 |
| | S. Contingencies | 283 |
| | T. Contractor Mark-Ups | 284 |
| | U. Engineering, Design and Construction Management | 285 |
| | V. Agency Costs | 286 |
| | W. Wrap-Up Insurance | 287 |
| | X. Escalation | 288 |
| | Y. Construction Contract Packaging | 289 |

SECTION 1
INTRODUCTION

Kellogg Corporation was retained by the Southern California Rapid Transit District (SCR TD) to review the \$2.3 billion pre-preliminary capital cost estimate for their Metro Rail Project. Metro Rail is the starter line of a 140-mile to 160-mile heavy/light rail rapid transit system which will serve the greater Los Angeles area. The initial project includes 18 miles of subway, 16 stations, and a storage and maintenance yard which will link the densely populated/employed areas of central Los Angeles and North Hollywood. SCR TD is currently in the preliminary engineering phase, with final design and construction to take place between 1984 and 1990.

The pre-preliminary cost estimate was prepared under the direction of DMJM/PBQD, A Joint Venture, which was responsible for the guideway, yard and trackwork estimates. Harry Weese & Associates (HWA), the general architectural consultant, was responsible for the stations, parking and control facility. Kaiser Engineers (KE) provided cost estimates for the specialty systems such as train control, traction power and vehicles. The City of Los Angeles estimated the cost of utility relocation.

The summaries of Kellogg Corporation's findings are presented in Section 2 of this report. Details of the analysis are discussed in Sections 5-A through 5-Y, with supporting documentation and computations contained in the corresponding alphabetical appendix. Section 3 presents Kellogg's scope of work, which is important since Kellogg was not required to review all elements of the estimate. Section 4 defines the documents which formed the basis of the estimate.

Kellogg's analysis indicates an estimated capital cost, for the scope of work defined, of \$3.0 billion. The pre-preliminary estimate is thus low by \$756 million or 25 percent. Both estimates are expressed in 1982 dollars with no allowance for escalation. Kellogg checked DMJM/PBQD's direct costs within 2-1/2 percent. The primary variances are in the indirect costs and the method of their application.

The cost of construction of the Metro Rail Project will be greatly influenced by a number of intangible factors which include:

- The commitment and cooperative spirit of all parties involved, including political interests, government interests, utility companies, private business, railroads, contractors, and the labor community.
- Construction management structured for problem-solving, in an effective and timely manner.
- Construction contract language equitable to both parties and clearly defining allocation of risk.
- Performance of comprehensive subsurface investigations and distribution of findings to all parties.

Kellogg Corporation's check of the pre-preliminary estimate assumed the above considerations would be addressed and implemented into the construction program.


ROUTE ALIGNMENT

Southern California Rapid Transit District Metro Rail Project

STATIONS

1. UNION STATION
2. FIRST & HILL
3. FIFTH & HILL
4. SEVENTH & FLOWER
5. WILSHIRE & ALVARADO
6. WILSHIRE & VERMONT
7. WILSHIRE & NORMANDIE
8. WILSHIRE & WESTERN
9. WILSHIRE & LA BREA
10. WILSHIRE & FAIRFAX
11. FAIRFAX & BEVERLY
12. FAIRFAX & SANTA MONICA
13. LA BREA & SUNSET
14. HOLLYWOOD & CAHUENGA
15. UNIVERSAL CITY
16. NORTH HOLLYWOOD

LEGEND



SECTION 2

SUMMARY OF ESTIMATE REVIEW

In Kellogg Corporation's opinion, the pre-preliminary capital cost estimate, revised January 7, 1983 is low by approximately \$756 million or 25 percent. Our analysis indicates an estimated capital cost, for the scope of work defined, of \$3.027 billion. This total estimate cost is expressed in 1982 dollars, with no allowance for escalation. This total also assumes that cost items not within Kellogg's scope of review are correct. These items, which are defined in Section 3 of this report, were not adjusted, and were carried in the estimate at their current defined values.

Kellogg Corporation computed variances from the pre-preliminary estimate on a direct cost basis. The DMJM/PBQD total estimate was reduced back to a direct cost level to which this net variance was applied. To this adjusted direct cost sum, was added recommended allowances for contractor mark-ups, engineering design and construction management, SCRTD agency costs, wrap-up insurance, contingencies and right-of-way.

The dollar summaries of Kellogg Corporation's findings are contained in the tables on the following three pages. At the direct cost level, the plus and minus variances largely offset each other resulting in Kellogg recommending a direct cost deduct of \$32.7 million or only 2 1/2 percent of DMJM/PBQD's direct costs.

The major areas of recommended increases are in the costs which are added onto the direct costs. This includes contractor mark-ups for which Kellogg recommends a rate of 43.45 percent versus DMJM/PBQD's rate of 15 1/2 percent. This factor alone results in an increase of \$338 million. Kellogg has also included an 11 percent allowance for change orders, differing site conditions, etc., which occur after contract bid and award. (Not to be confused with contractor's contingencies which are included in their bid mark-ups). The pre-preliminary estimate did not include an allowance for this item, hence the Kellogg recommended addition at 11 percent results in an addition of \$232 million.

Kellogg Corporation is in agreement with, and has included the same percentage allowances as DMJM/PBQD for design contingencies (20 percent), engineering design and construction management (13 percent), agency costs (5 percent), and wrap-up insurance (4.2 percent). The method of application, however, and resulting compounding of dollars is quite different. Kellogg believes that the engineering design and construction management, agency, and insurance percentages should be applied to a capital cost subtotal which includes the 20 percent design contingency. Kellogg's estimate would be \$117 million lower without this compounding. The method of application of these indirect cost items is subject to SCRTD's management philosophy.

REVISED CAPITAL COST ESTIMATE

| | |
|---|---------------------|
| Contractor's Costs in Pre-preliminary Estimate Including Markup @ 15.5% | \$1,455,100,000 |
| Deduct Contractor's Markup | <u>-195,300,000</u> |
| Direct Costs in Pre-preliminary Estimate | \$1,259,800,000 |
| Deduct Total Direct Cost Variance According to Kellogg Corporation's Estimate (See next page for calculation) | <u>-32,687,000</u> |
| Adjusted Direct Costs | \$1,227,113,000 |
| Contractor's Markup @ 43.45% | <u>533,181,000</u> |
| Contractor's Costs in Kellogg Corporation's Estimate | \$1,760,294,000 |
| Design Contingencies @ 20% | <u>352,059,000</u> |
| Capital Cost Subtotal | \$2,112,353,000 |
| Engineering Design and Construction Management @ 13% | 274,606,000 |
| Agency Costs @ 5% | 105,618,000 |
| Wrap-up Insurance @ 4.2% | 88,719,000 |
| Allowance for Change Orders, Differing Site Conditions, Etc. @ 11% | 232,359,000 |
| Right-of-Way Acquisition | <u>213,500,000</u> |
| Total Revised Capital Cost Estimate | \$3,027,155,000 |

**SUMMARY
DIRECT COST VARIANCE**

| <u>Reference Section</u> | <u>Description</u> | <u>Recommended Adjustment to Pre-preliminary Estimate</u> |
|------------------------------|---|---|
| 5B | Tunnels | -\$30,119,000 |
| 5C | Station Shell | -13,049,000 |
| 5D | Station Architectural | +1,350,000 |
| 5E | Stations—Mechanical and Electrical | -16,235,000 |
| 5F | Crossovers, Pocket Tracks and Tail Track | +21,400,000 |
| 5G | Line Vent Structures—City and Mountain | -870,000 |
| 5H | Vent Structures—Mechanical and Electrical | -2,700,000 |
| 5I | Utilities | +11,815,000 |
| 5J | Underpinning | -1,157,000 |
| 5K | Traffic Maintenance | +12,173,000 |
| 5L | Dewatering | +3,228,000 |
| 5M | Trackwork | -14,351,000 |
| 5N | Traction Power | (No Change) |
| 5O | Main Yard | -4,300,000 |
| 5P | Buildings—Structural and Architectural | (No Change) |
| 5Q | Buildings—Mechanical and Electrical | +128,000 |
| 5R | Parking | <u>(No Change)</u> |

Recommended Direct Cost Adjustment to
Pre-preliminary Estimate

-\$32,687,000

**SUMMARY OF
INDIRECT COST VARIANCES**

| <u>Description</u> | <u>Pre-preliminary Estimate</u> | <u>Kellogg Corporation Estimate</u> | | <u>Recommended Change</u> |
|--|-------------------------------------|---|-----|-------------------------------|
| Contractor's Markup | \$195,300,000 | \$533,181,000 | Add | \$337,881,000 |
| Design Contingencies | \$291,000,000 | \$352,059,000 | Add | \$ 61,059,000 |
| Engineering, Design, and Construction Management | \$189,200,000 | \$274,606,000 | Add | \$ 85,406,000 |
| Agency Costs | \$ 72,800,000 | \$105,618,000 | Add | \$ 32,818,000 |
| Wrap-up Insurance | \$ 50,000,000 | \$ 88,719,000 | Add | \$ 38,719,000 |
| Allowance for Changes, Differing Site Conditions, Etc. | \$ 0 | \$232,359,000 | Add | <u>\$232,359,000</u> |
| Total Recommended Changes for Indirect Costs | | | Add | \$788,242,000 |

SECTION 3

KELLOGG CORPORATION METHODOLOGY AND SCOPE OF WORK

Kellogg Corporation accomplished this scope of work in accordance with our proposal to SCRTD dated February 7, 1983. Work was commenced on March 1, 1983 and completed April 1, 1983. Work activities included the following:

- Meet with key personnel of SCRTD and their consultants to review the evolution and status of the construction cost estimates.
- Identify and review the pertinent documents which form the basis of the cost estimates.
- Perform a preliminary review of the cost estimate to determine the methodology and underlying assumptions upon which it is based.
- Identify high risk elements which could impact costs.
- Become familiar with the proposed alignment by actual site visit.
- Perform a detailed review of the cost estimates to identify specific areas for further study and analysis.
- Analyze items identified for detailed study.
- Draft final report.

During the site visits of the route alignment, station locations and main yard, more than 150 photographs were taken which were utilized by other Kellogg team members who were unable to visit the site. The geologic information was also transferred to the 20 sheet profile to allow a more detailed analysis of subsurface conditions expected to be encountered during construction.

The table below presents a summary of the DMJM/PBQD estimate, the consultant responsible for each section, and whether Kellogg did or did not review that part of the estimate. For those items not in Kellogg's scope of work, the DMJM/PBQD values were used as is to develop a total revised cost for the project. Also noted is the percentage that each item is of the capital cost subtotal. Inasmuch as stations and guideways compose 65 percent of this subtotal, Kellogg spent the major part of their effort analyzing the costs of these features. The Kellogg analysis

and organization of this report is based upon type of construction activity as well as the type of facility being constructed. This was done to allow analysis of that element of the construction process for the entire project by an individual having particular expertise in that area.

PRE-PRELIMINARY ESTIMATE REVISED JANUARY 7, 1983

| <u>Item</u> | <u>Responsible Consultant</u> | <u>Cost (1982)</u> | <u>Percent of Capital Cost Subtotal</u> | <u>In KC Scope of Work</u> |
|---|-------------------------------|------------------------|---|----------------------------|
| Guideways | DMJM/PBQD | \$503,800,000 | 35% | Yes |
| Stations | HWA | 430,900,000 | 30% | Yes |
| Utilities | City of Los Angeles | 25,000,000 | 2% | Yes |
| Parking | HWA | 44,200,000 | 3% | Yes |
| Central Control Facility | HWA | 1,500,000 | Nil | Yes |
| Main Yard | DMJM/PBQD | 46,200,000 | 3% | Yes |
| North Hollywood Tail Track | DMJM/PBQD | 23,500,000 | 2% | Yes |
| Trackwork | DMJM/PBQD | 62,300,000 | 4% | Yes |
| Train Control | KE | 64,600,000 | 4% | No |
| Communications | KE | 22,400,000 | 1% | No |
| Traction Power | KE | 42,600,000 | 3% | Yes |
| Fare Collection | KE | 18,800,000 | 1% | No |
| Vehicles- Passenger (140) | KE | 168,000,000 | 12% | No |
| Vehicle- Auxiliary | KE | 1,300,000 | Nil | No |
| Capital Cost Subtotal | | <u>\$1,455,100,000</u> | <u>100%</u> | |
| Design Contingency (20%) | | 291,000,000 | | Yes |
| Right-of-Way | SCRTD Spec. Consult. | 213,500,000 | | No |
| Engineering Design & Constr. Mgmt. (13%) | | 189,200,000 | | Yes |
| Agency Cost (5%) | | 72,800,000 | | Yes |
| Insurance | | <u>50,000,000</u> | | Yes |
| Total Cost (1982 Dollars without Escalation) | | <u>\$2,271,600,000</u> | | |

SECTION 4
BASIS OF ESTIMATE

Kellogg Corporation's estimate work was based upon the following documentation, which defined the scope of the project, the time frames, sequences and packaging of construction, and the current expression of the estimate.

- "SCRTD Metro Rail Project EIS Capital Cost Estimate," revised January 7, 1983, prepared by DMJM/PBQD.
- "Estimating Methodology and Procedures," dated February, 1983, prepared by DMJM/PBQD.
- DMJM/PBQD drawing No. AP-14AAA-C-103, "Metro Rail Starter Line Schematic Diagram," dated December 28, 1982 (also stamped "January 1, 1983 conceptual budget").
- DMJM plan and profile drawings (sheets 1 to 20) entitled "Milestone 3 Route Alignment Alternatives, Recommended Alignment," dated January 16, 1983 and January 17, 1983. (Drawing No's. AP-14AAA-C-046 to 055, 067 to 072, 081, 087, 088 and 101.)
- Harry Weese & Associates 8-1/2 x 11 footprint and section drawings of the 16 proposed stations.
- Harry Weese & Associates architectural, mechanical and electrical drawings as noted below:

| <u>Drawing</u> | <u>Title</u> | <u>Date</u> |
|----------------|--|-------------|
| GPM-1 | HVAC-Plumbing and Fire Protection | 10/12/82 |
| GPM-2 | HVAC-Flow Diagram | 10/12/82 |
| GPM-3 | Plumbing | 10/12/82 |
| GPM-4 | Fire Protection | 10/12/82 |
| GPM-5 | HVAC-Controls | 10/12/82 |
| GPM-6 | Schedules/Standard Details | 10/12/82 |
| GPE-1 | Station Electrical Service | — |
| GPE-1a | Station Electrical Service - Fifth & Hill | — |
| SK-11 | Station Sections and Plans | 8/24/82 |
| GPA-15 | Western Station - Site Plan | 10/1/82 |
| GPA-16 | Western Station - Plans and Sections | 10/1/82 |
| SK-26 | Fifth & Hill Station (Over-Under Section | 9/22/82 |

- DMJM/PBQD "Project Schedule - Facilities and Systemwide Construction-Normal," Sheets 1 to 5, Revision 2, dated January 12, 1983.
- "Geotechnical Investigation Report" By CEG, The General Geotechnical Consultant, dated November, 1981.
- Technical report, "Traffic Control Policies During Construction" by the Department of Transportation, City of Los Angeles, dated February, 1983.
- Draft report of the "Muck Disposal Study" by Sedway/Cook, cover letter dated November 23, 1982.
- A sample draft of a master cooperative agreement between SCRTD and the state of California.
- Detailed traction power estimate prepared by Kaiser Engineers.

The following additional documents were utilized for general concept and informational purposes since they relate to a later and revised design scope from that under Kellogg's review:

- SCRTD preliminary draft of the Metro Rail Project Milestone 10 report, dated February, 1983.
- SCRTD "Contract Unit Descriptions" for the Metro Rail Project, dated March, 1983.

The UMTA computerized station cost print-out was not utilized by Kellogg in our analysis.

SECTION 5-A
ESTIMATE ORGANIZATION

Description

Kellogg Corporation reviewed the pre-preliminary estimate for organization and coordination to ensure the estimate adequately covered the intended scope of the project, without major omissions or duplications. A part of this review was procedural, to check for extension, adding or transposition errors.

Basis of Analysis

The following documents were utilized in reviewing the estimate organization:

- The DMJM/PBQD estimate.
- The DMJM/PBQD methodology.
- The DMJM/PBQD metro rail schematic diagram.
- The DMJM/PBQD 20-sheet plan and profile drawings.

The following individuals were interviewed regarding estimate organization:

- James E. Crawley - SCRTD
- Howard J. Chaliff - DMJM/PBQD
- Donald King - SCRTD
- Charles J. Proctor - SCRTD
- John Bond - DMJM/PBQD
- Al Levy - SCRTD
- Robert Cutlip - TAMS
- Vern Montgomery - City of Los Angeles
- John E. Moss - DMJM/PBQD - Consultant
- David H. Holdaway - DMJM

General Discussion

Kellogg utilized several methods to look at the "big picture," attempting to check for and pick up any large discrepancies and errors. The objective of this analysis was to seek answers to the following questions:

- Are all of the elements included?
- Are there major quantity or unit price errors? Is a big piece left out?
- Are there errors in the extension, addition, or transposition of numbers?
- Are there major duplications of costs?
- Are there major judgement errors in the scope of work?

In addressing these issues, Kellogg first reviewed the estimate methodology in detail to determine how the estimate was planned to be organized and executed. The estimate was then reviewed in detail for consistency and compliance with the methodology. An outline of this review is included in the Appendix. During this review, the forwarding of numbers to the summary sheets and then to the summary spread sheet was checked. The major additions on this sheet were checked as well as the forwarding to the DMJM/PBQD summary letter of transmittal of January 6, 1983.

Kellogg also made more detailed checks of the system activities as a whole and in particular the estimates of the station shell and tunnel construction. The spread sheets listed below were made to check for major errors as well as for consistency between similar estimates. These spread sheets are contained in Appendix A.

- System feature take-off (similar to DMJM/PBQD's length analysis).
- Tunnel estimate check - dollar amounts.
- Tunnel estimate check - primary features.
- Station shell comparative check of dollar subtotals.
- Station shell estimate check - quantities.
- Station shell estimate check - unit prices.

Findings and Conclusions

In general, the various parts of the estimate are well organized and it tracks well. There are, however, a fair number of mathematical errors and duplications of costs. Kellogg did not check all extensions and additions but some major errors did come to light as a result of the previously described analysis. It is strongly recommended that all of the estimate sheets on this and future estimates be checked for mathematical accuracy and coordination.

Major errors and discrepancies discovered in the estimate include the following:

- Several addition errors were discovered in the station shell estimate in the range of one to two million dollars. These tended to cancel each other and resulted in a net overstatement of \$1 million.
- There are major errors in extension. Errors such as in the control building estimate (\$2.9 million), and the downtown vent shaft soldier pile and lagging (\$0.4 million).
- Duplication of costs for two parking structures in the station shell estimates and the G-1 to G-17 summary sheets resulted in an overstatement of \$15 million in costs.
- Duplication of underpinning costs resulted in an overstatement of \$4 million.
- Failure to add a shield pit in the tunnel estimate resulted in a \$0.4 million understatement.
- Failure to extend computations for the vent shaft earthwork, resulted in an understatement of \$1.2 million.
- Duplication of street restoration work in the station shell estimates and the utility relocation estimate resulted in an overstatement of nearly \$5 million.
- Duplication of costs for the mechanical work in the vent shafts resulted in a \$2.7 million overstatement.
- Builders risk insurance is listed in the indirect expense checklist and also added as a separate owner-incurred cost (a duplication).
- Labor rates utilized in the development of direct costs are in the range of \$22 to \$30 per hour which implies a full burden of fringes, insurance and taxes. These costs, however, are also listed to be a part of contractor indirect cost markup (a duplication).

- Mobilization is added in many cases as 4 percent of direct costs prior to markup for contractor's field overhead. Kellogg considers mobilization to be a part of field overhead.
- Contractor's bond cost should be applied after profit has been added, not before. Bond premiums are based on contractor's total job revenue.
- The DMJM/PBQD stated methodology for profit computation is in line with Kellogg philosophy, however, it was not followed which resulted in a gross understatement.
- Mark-up is added to estimates based upon total cost unit prices, resulting in a duplication.
- There is no allowance in the estimate for contractor's home office general and administrative expense.
- Corrosion protection does not appear to be addressed in the estimate; however, it may not be required in the Los Angeles area.
- There is no allowance in the estimate for costs related to changes or differing site conditions occurring after contract award.
- Dewatering cost allowances are extremely low.
- Traffic control and maintenance costs are extremely low.
- The schematic diagram shows the El Monte extension ending at Station 94+20. This indicates that none of the "Y" section under the Los Angeles River is to be constructed. This is inconsistent with the plan and profile drawings. There is no money in the estimate to construct the "Y" portion of the alignment except that connecting to the yard. There is, however, \$20 million to underpin the Santa Ana Freeway. Kellogg believed this was to underpin the freeway at the intersection with the Los Angeles River. The estimate also includes at-grade track in Reach No. 1 which is not consistent with the schematic or profile.

These items are all addressed in the detailed analysis sections of this report (Sections 5B - 5Y). The recommended additions or deletions to the estimate are included in the appropriate section. Fortunately, many of these errors were offsetting, minimizing the impact on the direct cost value of the estimate. Kellogg recommends the appointment of an estimate coordinator whose role will be to mitigate these types of problems on the final preliminary estimate.

SECTION 5-B

TUNNELS

Description

This item includes the direct costs to excavate, line and grout approximately 80,000 linear feet of twin bore tunnel. Also included in this item are direct costs for muck disposal, cross passages, steel tunnel liner and tunnel finishing.

This item does not include station work or contractor's mark-ups. These items are addressed separately in other sections of this report.

Basis of Analysis

The following documents have been reviewed concerning tunnel work:

- The DMJM/PBQD pre-preliminary cost estimate.
- Milestone 10 Definitive Fixed Facilities and Plans, Alignment Plan and Profile, Sheets 1 through 21 inclusive.
- Geotechnical Investigation report.
- Document WBS 14AAE "Estimating Methodology and Procedures."
- Phase A1, A2, A3 and A4 project schedule, updated January 6, 1983, stamped "Preliminary for Design Study Only."
- Drawing No. AP-14AAA-C-103 entitled "Metro Rail Starter Line Schematic Diagram."

The following individuals have been interviewed by Kellogg Corporation concerning tunneling:

- James E. Crawley - SCRTD
- Howard J. Chaliff - DMJM/PBQD
- John E. Moss - DMJM/PBQD - Consultant
- Charles J. Proctor - SCRTD

Kellogg cost estimates of direct tunnel costs are based on historical data for similar projects adjusted for productivity and escalation and experience in underground construction estimating.

General Discussion

TBM advance rates of 26 linear feet per day for A1, A3 and SP and 43 linear feet per day for A2, A4, C and 1-5 have been established for the Kellogg estimate. These advance rates are consistent with the rates presented in the pre-preliminary estimate, but are judged to be conservative. Kellogg estimate TBM advance rates are predicated on the assumption that precast tunnel liner segments must be installed before advancing the TBM. TBM advance rates of 45 linear feet per day and 90 linear feet per day may be realized if ground and construction conditions preclude the need for this constraint.

With the exception of steel lining for Reaches 5 and 8, no allowance has been taken in the Kellogg cost estimate for gassy or potentially gassy conditions in Reaches 2, 5, 6 and 8. If OSHA adopts regulations similar to those used by MSHA for gassy environment or should SCRTD adopt specifications consistent with such regulations, tunneling costs will be impacted by:

- The required use of certified gassy application electric and diesel equipment.
- Increased ventilation requirements.
- Increased standby and delay time.
- Probe holes in the tunnel face, two to three times the length of daily advance rate.

The Kellogg and the pre-preliminary cost estimates include costs for steel lining in Reaches 5 and 8, as well as precast liner segments in the same areas. It is customary to install steel lining, or steel lining and cast-in-place concrete in lieu of precast segments. Therefore, subject to design considerations, the installation of steel liner and precast segments in the same locations may be perceived as a "double dip."

Kellogg Corporation recommends tunneling through the stations at First and Hill, Fifth and Hill, and Fairfax and Wilshire. Advancing and restarting TBM's in a two-tier tunnel station arrangement will otherwise require a unique, risky and costly construction approach. (The two-tier configuration has since been eliminated from consideration.)

In view of the significant capital investment for TBM's in this estimate, SCRTD may wish to consider a sequential tunnel construction approach in lieu of parallel construction to maximize the reuse of the TBMs.

Findings and Conclusions

- Kellogg Corporation is, in general, in agreement with the pre-preliminary estimate construction quantity take-offs. Although a comparison of the pre-preliminary estimate and the Kellogg Corporation estimate will demonstrate significant variations in direct unit and total cost by generic cost classification, the total cost for all tunnel work varies by less than ten percent. The pre-preliminary tunnel cost estimate appears to be a sound estimate, pending final design definition.
- The pre-preliminary tunnel estimate includes a category for general expenses which has been deleted from the Kellogg Corporation direct tunnel cost estimate since these costs are considered by Kellogg Corporation and SCRTD (reference document WBS 14AAE "Estimating Methodology and Procedures") to be overhead costs. General expenses are included in the Kellogg Corporation estimate as overhead costs.
- The pre-preliminary and Kellogg Corporation estimates of tunnel excavation, lining and grout duration differ significantly for Reaches 8 and 14; however, cumulative estimates of duration for all reaches for tunnel excavation, lining and grout agree within 4 percent.
- Kellogg's pre-preliminary estimate of craft manpower per heading per shift is 83 percent of the pre-preliminary estimate (25 versus 30) and Kellogg's estimate of craft labor rate with fringes and burden is 90 percent of that used in the pre-preliminary estimate (\$27 per manhour versus \$30 per manhour). The Kellogg estimate of tunnel labor cost is 78 percent of that derived in the pre-preliminary estimate.
- Costs for equipment maintenance material, tunnel temporary utility lines and track, and small tools and supplies appear to have been overlooked in the pre-preliminary estimate. Kellogg's estimate for these consumables is \$24,160,000.
- Costs for electricity, fuel and lubricants show a significant variation in magnitude. Kellogg's estimate is 520 percent of the value used in the pre-preliminary estimate.

- The pre-preliminary and Kellogg Corporation estimates of unit cost and total cost for cross passages and finish tunnel show wide variations, probably due in part, but not totally, to planned construction approach. The Kellogg estimate of cross passages is 54 percent of the value derived in the pre-preliminary estimate and Kellogg's estimate of finish tunnel is 227 percent of the pre-preliminary estimate.
- There is no significant variance in total cost for the cost categories of muck disposal and steel liner.
- Ground water and shield pit cost categories show no variance.
- Kellogg's estimate of tunnel permanent material is 92 percent of the value shown in the pre-preliminary estimate.
- The Kellogg estimate of tunnel equipment is 83 percent of that shown in the pre-preliminary estimate.
- The Kellogg estimate of total cost per linear foot of tunnel is within .06 percent of the pre-preliminary total cost per linear foot of tunnel excluding general expenses.

The pre-preliminary cost estimate may be adjusted as noted below to attain the Kellogg Corporation cost estimate of direct cost. Supporting computations are included in Appendix B.

| | |
|--|--------------------|
| Pre-preliminary current cost estimate | \$384,200,000 |
| Round off variance (deduct) | -1,291,667 |
| Overhead and profit (deduct) | <u>-49,944,566</u> |
| Pre-preliminary estimate - direct cost | \$332,963,767 |
| *Shield pit (add) | <u>+391,000</u> |
| Corrected pre-preliminary estimate - direct cost | \$333,354,767 |
| Labor variance (deduct) | -23,652,000 |
| Material variance (deduct) | -7,139,000 |
| Equipment variance (deduct) | -8,813,000 |
| Consumables variance (add) | +32,625,000 |
| Muck disposal variance (deduct) | -3,287 |
| Cross passages variance (deduct) | -6,887,000 |
| Steel liner variance (deduct) | -370,980 |

*Deleted from pre-preliminary cost estimate rollup.

| | |
|--|--------------------|
| Finish tunnel variance (add) | +10,276,000 |
| General expenses (deduct) | <u>-25,254,500</u> |
| Kellogg Corporation estimate - direct cost | \$304,136,000 |
| Net change: | |
| Direct cost variance (deduct) | \$-29,218,767 |
| Shield pit (add) | +391,000 |
| Round off variance (deduct) | <u>-1,291,667</u> |
| Net change (deduct) | -30,119,434 |
| Call | \$-30,119,000 |

SECTION 5-C
STATION SHELL

Description

This item includes an analysis and estimate review of the heavy construction of the structural shell of the proposed 16 stations of the metro rail starter line.

This item does not include the normal completion contract work, or architectural features such as tile, painting, signing or electrical/mechanical. Also excluded are specialty items such as underpinning, traffic control, dewatering or utility supports which are covered in other sections of this report.

Basis of Analysis

The following documents were reviewed in the preparation of this section:

- The DMJM/PBQD pre-preliminary capital cost estimates.
- The metro rail starter line schematic diagram dated December 28, 1982.
- The geotechnical reports and drawings.
- Preliminary station drawings and sketches.

The following individuals were interviewed:

- James E. Crawley - SCRTD
- Howard J. Chaliff - DMJM/PBQD
- Donald King - SCRTD
- John E. Moss - DMJM/PBQD - Consultant
- Charles J. Proctor - SCRTD
- Al Levy - SCRTD
- Neil Richards - SCRTD

A complete site examination of all station locations was made in early March 1983.

References used for cost information and in estimating the station shell features (adjusted for productivity and escalation) were those retained during previous employment on the following rapid transit projects:

- San Francisco (BART)
- Washington (WMATA)
- Atlanta (MARTA)

General Discussion

The limitation of time and the absence of final design and related details prevented a definitive type estimate, however, the estimate check was accomplished as follows:

- A typical station, of average overall dimensions, was selected for the determination of unit costs. The Western Avenue Station was used and the developed unit costs adjusted for the other stations according to dimension or estimated difficulty variance.
- The high cost, high contingency or risk features such as excavation, soldier pile and lagging, muck disposal and decking quantities were checked by take off. These items were then "crewed up" in detailed estimating fashion and direct unit costs established.
- Concrete form quantity allowances, as estimated by DMJM/PBQD, were examined for reasonableness by comparing the various concrete placement type of work against the form ratio, i.e., square feet of form per cubic yard of concrete.
- Concrete placing costs for the various types of construction were "crewed up" and the unit price allowances checked by detailed estimating.
- Demolition allowances were estimated in detail for the Western Avenue Station. A special check of Union Station demolition was performed because of the unusual conditions and features relating only to this station.
- The general allowance of 200 pounds of reinforcing steel allowed per cubic yard of concrete was examined by prorating the total to the various concrete placement types. The required rebar ratio to concrete quantity for each feature was established and a total rebar quantity thereby determined.

- The secondary operations relating to concrete, such as curing and finishing, were rough checked as the completeness of design permitted for quantum. The unit costs were then compared with existing cost records and cross checked by the several available construction cost data publications.
- The site restoration items were estimated in detail and cross checked in cost data references.
- The quantity take off calculation sheets and detailed estimating back up studies are included in Appendix C of this report.

Findings and Conclusions

In general, we agree with the direct construction cost quantities and unit prices as estimated by DMJM/PBQD. The actual details of our estimate review are as follows:

- The machine excavation unit price is approximately 50 percent of what Kellogg Corporation estimates this cost to be.
- The excess soil disposal estimate is approximately 15 percent low. This does not reflect the possibility that a market exists for some of this material thereby offsetting this potential cost problem.
- The soldier pile and lagging estimate is 15 percent above Kellogg Corporation's estimated unit price.
- The decking allowance by DMJM/PBQD is approximately 15 percent below Kellogg Corporation's estimate.
- The formwork estimate requires no change.
- Concrete placing costs (estimated to be \$5.00 per cubic yard) are low for all concrete other than mass (grade slabs).
- The pre-preliminary estimate includes no allowance for concrete placed outside of excavation neat lines. An allowance of approximately 3 percent is recommended and has been included in Kellogg Corporation's analysis.
- There was no unit price analysis of compacted backfill as related to the degree of engineered fill requirements. The extent of hand work around utilities is also unknown. The unit price used in the estimate would allow for a very high percent of imported hand compaction. This unit price is probably high.
- Site restoration items were checked resulting in no recommendation for change.

- A straight line reduction of \$460,000 per foot for vertical reduction in station depth should be re-examined with more complete design. We have reviewed the calculations resulting in this savings and find no fault in the general theory. Unit pricing however, does change variably with depth which is not included in the computations. In addition, the analysis relates to major changes in depth, of 20 to 40 feet, but then the variance is applied to minor changes of only 2 to 8 feet. Kellogg Corporation estimates a generous depth reduction cost for minor variations to be roughly \$236,000 per vertical foot (direct cost). This results in a direct cost increase in the current estimate of \$5,084,000.
- The station estimates for the Beverly/Fairfax Station and the Universal City Station contain parking structures totaling \$15,150,000. This is a duplication, as these facilities are also priced on the "reach" summary sheets.

A tabulation of the cost variance is presented in the following two pages.

Summary of Station Shell Variances

| <u>No.</u> | <u>Station</u> | <u>Total Increase in Direct Costs</u> |
|------------|----------------|---|
| 1 | Union | \$ 167,000 |
| 2 | 1st Hill | 630,000 |
| 3 | 5th Hill | 1,100,000 |
| 4 | 7th Flower | 175,000 |
| 5 | Alvarado | 114,000 |
| 6 | Vermont | 90,000 |
| 7 | Normandie | 120,000 |
| 8 | Western | 140,000 |
| 9 | La Brea | 160,000 |
| 10 | Fairfax | 900,000 |
| 11 | Beverly | 65,000 |
| 12 | Santa Monica | 150,000 |
| 13 | Sunset | 160,000 |

| | | |
|----|---|-----------------------|
| 14 | Hollywood | 170,000 |
| 15 | Universal | 225,000 |
| 16 | North Hollywood | <u>175,000</u> |
| | Subtotal | \$4,541,000 |
| | Deduct parking structure duplication (included elsewhere) | -\$15,150,000 |
| | Deduct mobilization allowance dupli- cation (included elsewhere) | -\$ <u>7,524,000</u> |
| | Add for overstatement of depth reduction | +\$ <u>5,084,000</u> |
| | Net Variance | -\$ <u>13,049,000</u> |

SECTION 5-D

STATION ARCHITECTURAL

Description

This item includes the architectural finishes costs of the 16 passenger stations. Thirteen of these stations are single level stations and the remaining three are over-under type or bi-level stations. These cost figures assumed that the station shell work was properly finished and cleaned so as to allow the finish contractor to commence his work. No money was included for contingencies, construction management and the general contractors field overhead, general and administrative expenses and profit, all of which will be addressed elsewhere in the report.

Basis of Analysis

The following documents have been reviewed:

- Harry Weese and Associates drawings SK26 (9/22/82), GP-A16 (10/1/82), and preliminary station plans; 8-1/2 x 11 plans and sections (8/82).
- TAMS construction cost summaries dated November to December, 1982, from the DMJM/PBQD capital cost estimate.

The following individuals were contacted concerning architectural finishes:

- Donald L. Steeley - TAMS
- James Gilliam - MARTA

The following estimating references were utilized in checking the estimates.

- Means Building Construction Cost Data, 1982.
- Lee Saylor, Inc. Current Construction Costs, 1982.

General Discussion

Due to the conceptual nature of the drawings, a detailed estimate check could not be performed without numerous assumptions. Consequently, the estimate check was performed by checking the quantities for each work item in the TAMS' estimate for the two typical stations, i.e., Western/Wilshire (single level station) and Fifth and Hill (over-under station). The unit prices were checked only for the Western/Wilshire Station and then applied to the Fifth and Hill Station. Similarly, the head house costs were checked for unit prices.

The only question in the TAMS estimate is the derivation of total cost per square foot for the Western and Fifth and Hill stations and the subsequent application of these unit costs to the remaining stations. Kellogg Corporation could not verify the 23,140 square feet, nor the 50,800 square feet that TAMS used to derive the square footage unit prices that were then applied to the other stations. Likewise, Kellogg Corporation could not determine how TAMS established square footages for the remaining stations. This analysis assumed the square footages were correct, but Kellogg Corporation recommends that this question be addressed by TAMS, because it could lead to a large deviation in the estimated cost.

Findings and Conclusions

Assuming that the question of square footages and unit prices can be supported by TAMS, the TAMS estimate appears reasonable. The quantities and unit price check for the station finishes varied from the TAMS estimate, but overall, the Kellogg Corporation estimate was only five percent higher than the TAMS estimate. This five percent difference is reasonable given the conceptual nature of the design. When applied over all the stations, the five percent difference would add approximately \$1.35 million to the station finishes.

Net change: add \$1,350,000.

SECTION 5-E

STATIONS - MECHANICAL AND ELECTRICAL

Description

This item includes the cost of mechanical and electrical work in the stations. Excluded from this item but addressed elsewhere in this document are the costs of mechanical and electrical work in other types of structures.

Basis of Analysis

An analysis of the cost estimate of the station electrical/mechanical was made by reviewing the cost backup prepared by TAMS. Interviews with Jerry Chaing (electrical engineer) and Don Steely (cost engineer) of TAMS were conducted to determine some of the basis of their cost data.

The information was then evaluated based on Kellogg Corporation's experience and nationally recognized cost data (Means and Lee Saylor). Some actual cost estimates on motor control center equipment were used as well as the opinion of an outside expert in the HVAC installation.

General Discussion

There are 16 passenger stations to be constructed on the project. Thirteen of these are single level stations and the remaining three are two-level or over-under stations.

Two emergency vent shafts, each containing two fans, are located at single level stations without a crossover. Four emergency vent shafts, each containing two fans are located at over-under stations without a crossover. At single level stations with a crossover one vent shaft has an additional fan and two vent shafts, each have an additional fan at over-under stations with a crossover.

With the exception of two stations, each station contains a traction power substation. (See the diagram in Appendix E for location of the vents, crossovers and traction power substations.)

Power is supplied to the stations at 34.5 KV and is shared with the traction power substations. Each station contains stepdown transformers for auxiliary power and traction power. The power feeder will be furnished by the power company. The necessary supply side switchgear (two line breakers and a tie breaker) will either be purchased by SCRTD or supplied by the power company and amortized in the power rate structure.

TAMS prepared the estimate for the architectural/mechanical/electrical work on the stations. This section deals only with the mechanical and electrical costs. A detailed estimate was prepared for the western station and the cost per square foot was applied to all other single level stations. For the over-under stations, the single level station unit costs for mechanical and electrical features were increased by 50 percent. Fifth and Hill was used as the typical over-under station.

A separate discussion of each area is presented below:

Electrical. The electrical estimate was made in two parts i.e., auxiliary power and motor control centers. Auxiliary power includes the building transformer's distribution switchgear and internal building wiring and devices (including lighting). Motor control centers include the starters, wiring, and motors for the station mechanical equipment and vent shaft emergency exhaust fans.

Traction power substation feeders are included in the traction power estimate prepared by Kaiser Engineers. No allowance was made for the supply breakers in event they must be furnished by SCRTD. This could amount to approximately \$250,000 per station, if required. No addition to the estimate has been made for this item.

Unit pricing for the auxiliary power estimate was obtained from Jerry Chaing and the Means Mechanical and Electrical Cost manual. Generally, the pricing is reasonable though conservative. Two discrepancies appear: 1) the line item, motor control centers is added to the auxiliary power and is also in the motor control center estimate, thereby doubling up these costs; and 2) the lighting estimate is based on 50,000 square feet rather than 23,140 square feet. These items result in a reduction of approximately \$250,000 on the auxiliary power estimate.

Unit pricing for the motor control centers was obtained from the Westinghouse Quick Selector. The motor control center prices are grossly overstated resulting in a cost reduction of approximately \$400,000 for the western station.

Mechanical. The mechanical estimate is divided into four elements:

- Mechanical (elevators and escalators)
- HVAC
- Fire protection system
- Plumbing and sewage

The unit prices for elevators and escalators are based on actual quoted prices and appear to be very conservative. In applying the prices to the over-under stations, the elevator costs were priced on a vertical foot basis resulting in an overstatement of costs of approximately \$100,000 for each over-under station. The basic elevator cost should increase only approximately 3 percent per foot above a basic height of ten feet.

TAMS utilized the Means cost guide in computing HVAC unit prices. The resulting total cost per square foot for HVAC is approximately \$60. There are some overstatements of cost such as the chilled water and condenser water pumps (approximately \$130,000). An addition of \$238,000 for hangers, louvers and diffusers is very high since hangers are already included in the ductwork price. A reduction of \$150,000 would be reasonable to offset this duplication. The duct work prices are questionable regarding the manner in which they were calculated.

A total price reduction of \$300,000 on the HVAC system would still result in a conservative price. With the amount of detail provided in the HVAC drawings, more accuracy should have been obtained in the original estimate, particularly regarding ductwork and chill water piping quantities.

The fire protection system prices are derived from Means. The prices presented are reasonable, though conservative.

The plumbing and sewage prices utilized in the estimate are also derived from Means and do not include fixtures, water fountains, etc. A price per square foot of \$3.59 was estimated which is a bit understated. For the purposes of this analysis, a price of \$7.50 per square foot is considered more reasonable.

Findings and Conclusions

The prices derived for the mechanical and electrical systems are in general, very conservative. Information presented on the drawings was, in most cases, quite detailed and a more accurate estimate could have been produced. In many cases, actual price quotations could have been obtained and a more accurate estimate of unit prices would have resulted. It is apparent that some of the unit prices were picked out of standard estimating manuals without sufficient analysis or adequate knowledge of the equipment being priced. In most cases, this resulted in prices being greatly overstated.

The method of applying the costs calculated for the western to the other stations was reasonable. A summary of costs is presented in the table below. In summary, the reasonable cost reduction for the mechanical and electrical results is approximately a 17 percent reduction in these costs. This reduction would be approximately \$875,000 per single level station (13 each) plus \$1,620,000 per over-under station (3 each) or a total of approximately \$16,235,000.

STATION ANALYSIS - ELECTRICAL/MECHANICAL

Fifth and Hill - Over-Under

| | <u>Per Estimate</u> | <u>Revised</u> |
|-------------------------------------|-------------------------|--------------------|
| Mechanical (Elevator and Escalator) | \$3,071,200 | \$2,948,000 |
| Electrical (Auxiliary) | 2,635,000 | 2,257,500 |
| Electrical (MCC) | 1,096,000 | 170,475 |
| HVAC | 2,142,000 | 1,692,000 |
| Fire Protection | 447,000 | 447,000 |
| Plumbing and Sewage (@ 7.5/sq. ft.) | 125,000 | 381,000 |
| | <u>\$9,516,200</u> | <u>\$7,895,975</u> |
| Difference due to M/E = | \$1,620,225 | |
| Revised Cost/SF = | \$208 | |
| Percent Reduction = 17% | | |

Western

| | <u>Per Estimate</u> | <u>Revision</u> |
|-------------------------------------|-------------------------|--------------------|
| Mechanical (Elevator and Escalator) | \$1,204,000 | \$1,204,000 |
| Electrical (Auxiliary) | 1,757,000 | 1,505,000 |
| Electrical (MCC) | 528,000 | 113,650 |
| HVAC | 1,428,000 | 1,128,000 |
| Fire Protection | 298,000 | 298,000 |
| Plumbing and Sewage (@ 7.5/sq. ft.) | 83,000 | 175,000 |
| | <u>\$5,298,000</u> | <u>\$4,423,650</u> |
| Difference due to M/E = | \$874,350 | |
| Revised Cost/SF = | \$254 | |
| Percent Reduction = 17% | | |

Some items that were not specifically noted in the electrical and mechanical estimates were:

- a) Power factor correction equipment
- b) Emergency power and lighting systems
- c) Temporary light and power during construction
- d) Startup and testing costs.

Due to the conservative nature of the estimates, the estimated cost should adequately cover the above items, though these items need to be treated as separate line items.

Net change: Deduct \$16,235,000

SECTION 5-F

CROSSOVERS, POCKET TRACKS AND TAIL TRACK

Description

This item includes a review of the construction costs to build the structural portion of the crossovers, the dead train storage areas (pocket tracks), the North Hollywood tail track, and the cut-and-cover section between Union Station and the main yard. This item does not include cost allowances for track work or electrical/mechanical or other systemwide facilities.

Basis of Analysis

The documents reviewed in preparation of this estimate were as follows:

- The DMJM/PBQD pre-preliminary capital cost estimate.
- The metro rail starter line schematic diagram dated December 28, 1982.
- The geotechnical report and drawings.
- Sketch of the north tail track dated January 3, 1983.
- Milestone 3 route alignment alternative drawings.

Site visits to the various crossovers, pocket tracks, cut-and-cover section, and the north tail track were made in early March 1983.

General Discussion

There are a total of seven crossovers, two pocket tracks and one tail track. The dimensions of these structures were defined by obtaining the length from the DMJM/PBQD length analysis spread sheet contained in the DMJM/PBQD estimate, and equating the width and depth to adjacent station dimensions. The length of the box section adjacent to Union Station was computed from the schematic diagram with adjustments for actual station and crossover structure lengths.

Unit costs for these structures were obtained by extrapolating the applicable unit prices from the adjacent stations.

The crossover, pocket track, and box section estimates provide shell structures only. The north tail track estimate provides a shell plus a lump-sum allowance for some shop and repair facilities.

Contract packaging is covered in another section of this report. This is an area however, where interface problems resulting in cost increases could occur without prudent scheduling and contract packaging.

Findings and Conclusions

The pre-preliminary estimate for crossovers and pocket tracks is 25 percent lower than our estimate for these facilities. Kellogg Corporation is in agreement with the estimate for the North Hollywood tail track, if the allowance of \$4,762,000 for mechanical and electrical facilities is proper. For the box sections between Union Station and the main yard, Kellogg is nearly double the current estimate. This is partially due to quantity differences and the fact that part of this reach was estimated by DMJM/PBQD as "dual track at grade" which is not in accordance with the SCRTD schematic diagram.

In summary:

- Crossover structures are approximately \$7,700,000 low in total.
- Pocket tracks are approximately \$6,500,000 low in total.
- North tail track - no recommended change in price.
- Box sections adjacent to Union Station are approximately \$7,200,000 low in total.

Net change: add \$21,400,000.

SECTION 5-G

LINE VENT STRUCTURES - CITY AND MOUNTAIN

Description

This item includes an estimate for the structural portion of the three city line vents (soft ground) and the two mountain vents (hard rock). This item does not include the fans or related electrical/mechanical equipment. An allowance was made, however, for the hoist and hoist house.

Basis of Analysis

The following documents were reviewed in the preparation of this section of the report:

- The DMJM/PBQD pre-preliminary capital cost estimate.
- The geotechnical reports and drawings.

The following individuals were interviewed regarding various existing geological and jobsite construction conditions and problems:

- John E. Moss - DMJM/PBQD - Consultant
- Charles J. Proctor - SCRTD

A site visit that included observations of the probable vent structure locations was made. This site visit included a thorough examination of rock cut exposures of the many Santa Monica mountain outcroppings.

General Discussion

The downtown or soft ground vent shaft structures were estimated by prorating or extrapolating unit costs developed in detail on similar features of the stations and other cut-and-cover structures. The mountain or hard rock vent shaft structures were estimated by "crewing up" and estimating in detail, the various structural features of the vent shafts.

The detailed estimates for both types of vent shafts are included in Appendix G of this report.

Findings and Conclusions

In general, the pre-preliminary capital cost estimate for both the downtown and mountain vent shafts exceed Kellogg's estimates. The primary differences in the estimates are as follows:

- The pre-preliminary capital cost estimates for both the downtown and mountain vents contain several mathematical errors and extension omissions.
- For the soft ground or downtown estimates, Kellogg Corporation is in agreement with the pre-preliminary estimate as presented. (For the correctly extended three soft ground vents. The pre-preliminary estimate total exceeds the Kellogg Corporation estimate by \$1,250,000.)
- Each downtown vent shaft has an allowance of \$200,000 for architectural finishes. This seems extremely high for a small non-public structure. Kellogg included a total of \$30,000 for the three structures for a net savings or deduct of \$570,000.
- Utility support allowance seems very high for this small street excavation area of the downtown shafts.
- The pre-preliminary estimate for the mountain shafts failed to extend the earthwork section unit costs to the total. Incorporating this correction, the pre-preliminary estimate exceeds Kellogg Corporation's estimate by approximately \$2,000,000 total for both shafts. The pre-preliminary estimate as presented is \$300,000 higher than Kellogg's estimate.

Net Change: Deduct \$870,000

SECTION 5-H

VENT STRUCTURES - MECHANICAL AND ELECTRICAL

Description

This portion of the estimate includes the mechanical portion for all vent shafts and the mechanical/electrical portions for the vent shafts which are not located at stations. Vent electrical at the stations is included in the station estimates.

Basis of Analysis

An analysis was made of the pre-preliminary estimate and backup information for each of the items. Discussions were held with the estimators from DMJM/PBQD to answer questions. Reasonableness of the estimates was checked using the Means and Lee Saylor estimating manuals.

General Discussion

Unit prices were established for the vent shaft mechanical equipment based on relatively detailed specifications. Prices for each type of shaft i.e., over-under station, single level station, over-under crossover and single level crossover are shown on the DMJM/PBQD tunnel vent summary sheet, a copy of which appears in Appendix H. The number of shafts per reach was checked and found to be accurately stated in the summary sheet.

For the vent shafts not located at the stations, a lump-sum electrical price of \$300,000 was used. This price should be adequate. The line vent structural, architectural and electrical is shown in the last column of the summary sheet. It appears that the last column also includes the mechanical work. This was determined by analysis of the backup data. The line vent mechanical column, therefore, is redundant.

Findings and Conclusions

No problems were found with the emergency vent shaft mechanical estimates except in the line vents. The mechanical work appeared to be doubled resulting in a 2.7 million dollar over-statement.

Net change: deduct \$2,700,000.

SECTION 5-1

UTILITIES

Description

This item includes costs to support, maintain, relocate and restore utilities overlying and adjacent to excavations for subway structures. Excluded from this item are costs for surface restoration for these utilities, which costs are addressed elsewhere in this document.

Basis of Analysis

The following documents have been reviewed concerning utilities:

- The DMJM/PBQD estimate.
- Various composite utility drawings.
- Various correspondence, tables, sketches, and estimates proposed by the City of Los Angeles, Department of Public Works, Bureau of Engineering.
- Preliminary drawings.

The following individuals have been interviewed by Kellogg Corporation concerning utilities:

- Howard J. Chaliff - DMJM/PBQD
- James E. Crawley - SCRTD
- Robert Cutlip - TAMS
- Donald King - SCRTD
- Al Levy - SCRTD
- Vern Montgomery - City of Los Angeles

General Discussion

The DMJM/PBQD estimating effort has been limited due to, until very recently, constant changes in station and guideway locations. Estimates for utility support and maintenance costs have been prepared based upon historical percentage

ranges from other systems, particularly Baltimore and WMATA. Utility relocation estimates have been prepared and coordinated by the City of Los Angeles Department of Public Works with input from some of the private utility companies.

Findings and Conclusions

The current estimate for utility support and maintenance is based upon a percentage range (2 to 5 percent) of the station cost. This estimate excludes other adjacent open-cut and cut-and-cover areas.

The current estimate for utility relocation and restoration was developed for most stations but also excludes adjacent open-cut and cut-and-cover areas.

No allowance is included for utility work overlying or adjacent to tunnel excavation.

No allowance has been included for support, maintenance, relocation/closure, or restorations of private property in public space (i.e., sidewalk vaults, elevators, store fronts constructed under revocable permits).

After adjustments are made for the exclusions described above, Kellogg Corporation considers the estimate allowances made to be within a reasonable range considering the lack of specificity indicative of the current level of design. During the final design phase, the estimated amounts could vary appreciably from those currently in use. Utility costs should be considered highly sensitive to final location and design and a target for value engineering alternative studies.

The utility estimate should be adjusted as noted below. Supporting computations are included in Appendix I.

| | |
|----------------------------|-------------------|
| Current Total: Support | \$8,571,400 |
| Current Total: Relocation | <u>25,000,000</u> |
| Current Total Utility Work | \$33,571,400 |

| | | |
|---|---------------------|-------------------|
| Deduct duplication for surface restoration | - \$4,854,700 | |
| Add cut-and-cover open- cut support | + 5,627,000 | |
| Add cut-and-cover open- cut relocation | + <u>11,043,000</u> | |
| Adjusted Total Utility Work | \$45,386,700 | |
| Net Change: Add | \$11,815,300 | Call \$11,815,000 |

SECTION 5-J
UNDERPINNING

Description

This item includes costs to underpin, support, and restore structures overlying and adjacent to excavations for subway construction. This item excludes underpinning, support and restoration of utilities, the cost of which is addressed elsewhere in this document. For convenience, construction cost of the Bluffside Bridge is addressed in this item.

Basis of Analysis

The following documents have been reviewed concerning underpinning:

- The DMJM/PBQD estimate.
- The estimate summary matrix.
- Preliminary drawings.
- Drawings summarizing existing building and foundation sizes and types adjacent to the major structures.

The following individuals have been interviewed concerning underpinning.

- James E. Crawley - SCRTD
- Howard J. Chaliff - DMJM/PBQD
- Stephen S. Uy - DMJM/PBQD
- John Bond - DMJM/PBQD

All cut-and-cover and open-cut sites were visited by Kellogg Corporation during the engagement. Specific sites were visited to obtain a general observation of underpinning considerations. These include:

- Santa Ana Freeway/Los Angeles River
- Union Station

- First and Hill Station
- Fifth and Hill Station
- Seventh and Flower Station
- North Hollywood Station

General Discussion

Due to the current stage of design and political sensitivity, underpinning cannot be accurately defined until the final design phase. For these reasons, DMJM/PBQD has been limited to using "plug" values for underpinning estimates. Kellogg Corporation review of this item includes an assessment of reasonableness of the values used and a check for apparent omissions and duplications.

Findings and Conclusions

The estimate provides plug numbers for three major structures:

- Underpinning the Santa Ana Freeway/Los Angeles River crossing (\$20,000,000).
- Underpinning the Hill Street Bridge in Reach No. 2 (\$250,000).
- Construction of the Bluffside Bridge to provide access to the Universal City Station (\$3,000,000).

The estimate provides plug numbers for underpinning various buildings overlying or adjacent to cut-and-cover subway construction in the amount of \$21,250,000.

The estimate provides no allowance for underpinning in areas to be tunneled and some cut-and-cover areas.

The estimate apparently duplicates approximately \$4,087,000 of underpinning costs included under the station shell excavation item.

The estimate provides no allowance for underpinning the railroad tracks at Union Station (\$120,000/track) and at North Hollywood Station (\$125,000/track).

Considering the current stage of design, the estimate values appear reasonable. During the final design phase, the final estimated amounts could vary appreciably from those currently in use. Underpinning costs should be considered highly sensitive to final location and design and a target for value engineering alternative studies.

The underpinning estimate may be adjusted as follows:

| | | |
|---|-------------------|---------------------|
| Current total | | \$44,500,000 |
| Add railroad tracks | +1,210,000 | |
| Deduct duplications contained in station shell excavation | -4,087,000 | |
| Add for cut-and-cover areas not presently included | <u>+1,720,000</u> | |
| Net change | | <u>\$-1,157,000</u> |
| Adjusted total | | \$43,343,000 |

Detailed calculations of the above are contained in Appendix J.

SECTION 5-K
TRAFFIC MAINTENANCE

Description

This item includes costs to maintain and/or divert vehicular and pedestrian traffic, maintain access to properties adjacent to open-cut and cut-and-cover excavations, and control access to contractor's work and storage areas at or near the excavation sites. Excluded from this item are costs of flagmen used for traffic control on an isolated basis, and the costs of street and sidewalk decking, both of which are addressed elsewhere in this document.

Basis of Analysis

The following documents have been reviewed concerning traffic maintenance:

- The DMJM/PBQD estimate.
- Preliminary drawings.
- Technical Report: Traffic Control Policies During Construction, dated February, 1983, prepared by the Department of Transportation, City of Los Angeles.

The following individuals have been interviewed by Kellogg Corporation concerning traffic maintenance:

- James E. Crawley - SCRTD
- Al Levy - SCRTD
- Charlie J. Proctor - SCRTD
- Nadeem Tahir - SCRTD
- Joseph Kennedy - City of Los Angeles

In addition, Kellogg Corporation personnel visited the sites of construction to observe traffic conditions and maintenance considerations.

General Discussion

The success of a major urban construction project such as the SCRTD Metro Rail System depends heavily on the ability to minimize the impact of construction on existing heavy traffic movements. Elements to be considered include:

- Vehicular and pedestrian traffic demand.
- Ability to satisfy traffic demand and/or divert traffic as conveniently as possible to adjacent parallel streets.
- Provide access to businesses, residences, and public buildings neighboring the construction.

Findings and Conclusions

Traffic along the entire route is heavy, particularly during peak hours and in the central downtown business district.

There currently exists an admirable spirit of cooperation between the City of Los Angeles and SCRTD. The Technical Report: Traffic Control Policies During Construction represents a doable plan to construct the subway while maintaining traffic flow.

The current estimate for traffic maintenance allows only \$371,150 for the entire system.

It is Kellogg Corporation's opinion that a more appropriate estimated allowance for traffic maintenance is \$12,544,500 which is \$12,173,350 more than the current allowance. A detailed calculation of this amount is contained in Appendix K.

Net Change: Add \$12,173,000

SECTION 5-L
DEWATERING

Description

This item includes costs to dewater the open-cut and cut-and-cover excavations for subway construction. Excluded from this item are the costs of tunnel dewatering which are included elsewhere in this document.

Basis of Analysis

The following documents have been reviewed concerning dewatering:

- The DMJM/PBQD estimate.
- The geotechnical report.
- Preliminary drawings.

The following individuals have been interviewed concerning dewatering:

- James E. Crawley - SCRTD
- Howard J. Chaliff - DMJM/PBQD
- John E. Moss - DMJM/PBQD - Consultant

General Discussion

Most of the subway excavation will occur in areas above the permanent water table and, therefore, extensive well-point or deep-well systems should not be required. Water to be encountered during construction will include perched and trapped water, surface runoff, and water used during construction. Planned control of this water must be considered.

Findings and Conclusions

The DMJM/PBQD estimate provides an allowance of \$2,650 per month for each station for dewatering. This allowance totals \$824,150 for the entire project.

It is Kellogg Corporation's opinion that a dewatering maintenance allowance should be made for at least \$12,000 per month per station and a minimum lump-sum allowance of \$20,000 per station to cover settling basins, sumps, trenches and hoses. This allowance totals \$4,052,000 for the entire project or \$3,227,850 more than the current estimate. Details of this calculation are contained in Appendix L.

Net Change: Add \$3,228,000

SECTION 5-M

TRACKWORK

Description

This item includes the trackwork for the entire Metro Rail Project. The trackwork in the main yard includes both ballasted railroad and transit track, at-grade. Trackwork through the tunnels and stations is the direct fixation type, with concrete-embedded turnouts and crossovers.

Basis of Analysis

The following documents were reviewed as part of the trackwork analysis:

- The DMJM/PBQD estimate.
- The Metro rail starter line schematic diagram dated December 28, 1982.
- Metro Rail Project Milestone 10 Report.
- Milestone 3 route alignment alternative drawings, sheet 1 to 20.

Trackwork was discussed with the following individuals:

- Howard J. Chaliff - DMJM/PBQD
- John Bond - DMJM/PBQD
- George Stanske - DMJM/PBQD

The following references were utilized in checking trackwork pricing.

- DMJM/PBQD unit price data relative to trackwork (includes data from Means, Dodge and Lee Saylor cost guides, bid and estimate data from the Boston and Baltimore Rapid Transit systems, and quotes from several rail contractors).
- Denver RTD trackwork estimates.
- Dravo Corporation bid and actual cost information from construction of the San Francisco BART system.

- 1982 Dodge Guide.
- Railroad Builders, Inc., a trackwork contractor.

General Discussion

Track construction on the project can be divided into two general categories: ballasted, at-grade and direct fixation. In reviewing the DMJM/PBQD estimate, it appears that the subway track is considered to be direct fixation with floating slab, which is considerably more expensive than direct fixation. George Stanske, DMJM's trackwork expert, indicated that the ultimate design will include a combination of direct fixation, resiliently supported, and floating slab trackwork, based upon vibration and accoustical considerations. The January 1983 estimate was to be based upon all underground trackwork being direct fixation. Design criteria for the pre-preliminary trackwork estimate is summarized as follows:

- Subway-Transit Track
115-pound continuous welded rail, direct fixation
switches on timber ties embedded in concrete
- At-Grade Ballasted-Transit Track
115-pound continuous welded rail
concrete ties
- At-Grade Ballasted-Railroad Track
115-pound continuous welded rail
timber ties

DMJM/PBQD's method of pricing the direct fixation track was to use one price per linear foot of track which would be sufficient to cover costs for concreted turnouts and crossovers in the main line. Kellogg Corporation developed separate prices for the crossover features and the subway track.

Kellogg Corporation performed a system feature take-off to check quantities for trackwork construction. No major differences were discovered, although the crossover between Union Station and the main yard is not called out as such. This take-off appears in Appendix A.

A rough take-off was performed in the main yard from the drawings contained in the milestone 10 report, which may not be the basis of the January 1983 estimate. Crossover and turnout quantities checked closely, however track quantities for both railroad and transit track appeared to be higher than Kellogg could compute. In reviewing the estimate for the main yard, the DMJM/PBQD quantities were used in conjunction with Kellogg's unit prices.

Findings and Conclusions

In general, pricing for trackwork appears to be somewhat inflated. This is particularly so for the direct fixation track which accounts for over 70 percent of the total trackwork estimate. DMJM/PBQD's composite unit price for direct fixation track with crossovers is \$228.00 per linear foot total cost or \$197.00 per linear foot direct cost. Kellogg has derived a direct cost for direct fixation rail of \$125.00 per linear foot with separate pricing of concrete embedded No. 10 double crossovers at \$300,000 each. This accounts for the major portion of the difference between the Kellogg Corporation and DMJM/PBQD estimates.

Inasmuch as rapid transit trackwork is a specialized type of construction, and the unit prices developed by both DMJM/PBQD and Kellogg Corporation are based primarily upon estimates and rather old historical data, it is strongly recommended that additional and more recent data be obtained to utilize in pricing the final preliminary estimate. Actual bid tabulations from several of the more recently constructed transit systems would be extremely helpful in developing cost data sensitive to the competitive marketplace.

In dealing with bid prices and historical price data, it is important to be aware of possible bid unbalancing, and to reduce costs back to the direct cost level, without contractor mark-ups. It is unclear whether DMJM/PBQD was dealing with direct cost or total cost unit prices from other transit projects. In one instance, an additional 15-1/2 percent mark-up was applied to the \$228.00 per linear foot unit price for direct fixation rail, which already included 15-1/2 percent mark-up.

Details of Kellogg's trackwork analysis are contained in Appendix M. A summary of our findings is presented below.

- Main yard - Deduct \$3,510,000
- Reach No. 1 to 14 - Deduct \$10,865,000
- North Hollywood Rail Track - Add \$24,000

Net Change: Deduct \$14,351,000

SECTION 5-N
TRACTION POWER

Description

This item includes the costs of traction power equipment installations and construction of separate structures to house this equipment. Excluded from this item are the costs of traction power structures which are structural appendages of subway stations.

Basis of Analysis

Review of a comprehensive estimate submitted by Kaiser Engineers and discussion of the system with their engineers.

General Discussion

The traction power system supplies 700 volts direct current to power the trains. The system consists of 19 traction power substations. Of these 19 substations, 14 are located at train stations. A separate structure is required to be built for the five remaining substations not at a station.

Kaiser Engineers presented a very comprehensive estimate for the traction power system. The format of the estimate and its readability is excellent. Unit prices were derived by Kaiser based on historical data from similar systems.

The same problem regarding power service exists on the isolated traction power substations as exists on the stations. This problem is the unresolved question regarding who supplies the incoming electrical service equipment. The additional cost for this equipment will be approximately \$250,000 for each of the five isolated substations, if they are in fact to be supplied by SCRTD. No adjustment has been made to the estimate for this item.

In addition to the traction power substations, a cost of four buildings for housing the isolated stations is included at approximately \$800,000 per building. The cost for the buildings is \$106.53 per square foot.

Findings and Conclusions

There are no problems with the traction power estimates.

Net changed: \$0.

SECTION 5-0

MAIN YARD

Description

This item includes an analysis and estimate review of the following main yard facilities:

- Demolition
- Site preparation
- Structural
- Roads and pavement
- Fencing
- Yard lighting

This item does not include the main yard buildings, trackwork, fixed equipment, or yard vehicles, which are addressed in other parts of this report.

Basis of Analysis

The following documents were reviewed in the preparation of the estimate for this section of the report:

- The DMJM/PBQD pre-preliminary capital cost estimate.
- Drawings and sketches.
- Kellogg Corporation project photographs.

A thorough project site reconnaissance of all existing trackwork and structures as well as the areas for proposed construction features was performed.

References used for estimating the proposed facilities are as follows:

- Kellogg Corporation cost records.
- Building construction cost data publications.

General Discussion

The design and general information received for the construction of the main yard facilities was very preliminary. The quantity take off units however, are presented in detail indicating that the yard limits and general scope is well defined. Absent a design or scope definition, an independent take off was not performed. This estimate was prepared using the quantities stated in the pre-preliminary estimate.

The estimate check was performed on a unit price basis and the detailed backup sheets are included in Appendix O of this report.

Findings and Conclusions

In general, Kellogg Corporation finds that the pre-preliminary estimate for the main yard features estimated in this section is quite generous. The cost variance by feature is as follows:

- Demolition \$3,500,000 high (primarily in track removal.)
- Site preparation \$300,000 high.
- Structural \$300,000 high.
- Roads/paving \$300,000 high.
- Fencing - agree.
- Lighting \$100,000 low.

Net Change: Deduct \$4,300,000

SECTION 5-P

BUILDINGS - STRUCTURAL AND ARCHITECTURAL

General Description

This section includes a review of the construction costs for the following buildings: 1) main shop building; 2) maintenance of way building; 3) transportation building; 4) car cleaners building; 5) test building; 6) exterior car wash building; 7) traction power building and 8) the control building. The mechanical and electrical costs for these buildings are analyzed in a separate section.

Basis of Analysis

The following documents were reviewed:

- SCR TD Metro Rail Project EIS Capital Cost Estimate prepared by DMJM/PBQD dated December 3, 1982 and revised on January 7, 1983.
- Preliminary Draft Report for the Development of Milestone 10: Fixed Facilities, dated February 1983.

The following references were utilized for unit prices:

- Means Construction Cost Data, 1982.

General Discussion

Shop and yard buildings were estimated by DMJM/PBQD based on the conceptual designs. Gross unit prices were applied to the individual building square footages. The Kellogg Corporation analysis reviewed these figures for accuracies.

An analysis of the unit prices was performed for the various buildings, except the mechanical and electrical prices which are reviewed in Section 5-Q. Realizing that the pre-preliminary estimate was based on conceptual designs, the unit prices for all the buildings, except the control building which are very conservative, are within a reasonable range for this stage of the design.

The control building estimate has exaggerated unit prices for "Special Construction" and "Fixed Equipment" which are incorrectly extended yielding \$196,000. The correct extension of these items would yield nearly \$2,000,000. The \$196,000 cost for these items currently in the total cost for the control building is a reasonable allowance.

Findings and Conclusions

The unit prices for all the buildings are conservative, but reasonable except the control building. The control building estimate for "Special Construction" and "Fixed Equipment" have exaggerated unit prices, but the overall dollar value included in the estimate is reasonable.

Net Change: \$0.

SECTION 5-Q

BUILDINGS - MECHANICAL AND ELECTRICAL

Description

This item includes the mechanical portion for all vent shafts and the mechanical/electrical for the vent shafts which are not located at stations. Vent electrical at the stations is included in the station estimates.

Basis of Analysis

An analysis was made of the estimate and backup information for each of the items. Discussions were held with the estimators from DMJM to answer questions. Reasonableness of the estimates was checked using the Means and Lee Saylor estimating manuals.

Findings and Conclusions

The building estimates were reasonable for a conceptual estimate with the exception of the control building. The main shop and maintenance of way buildings had no separate provisions for electrical or mechanical, though discussions with the engineers indicated that these costs were included in the overall building square foot allowance. A comparison of square foot unit prices is included in Appendix Q.

In the control building estimate, an incorrect extension of overstated unit prices resulted in a low estimate. A \$25 per square foot figure for electrical and mechanical was applied for the control building resulting in a net addition of \$128,000.

An estimate was prepared for the north tail track building for a total of \$4,762,000 for architectural, mechanical and electrical. This estimate was based on conceptual information and analysis as to reasonableness was performed.

Net change: add \$128,000.

SECTION 5-R

PARKING

Description

This item includes the costs for the construction of two at-grade parking lots and five multi-story parking facilities. Costs for property acquisition are not included.

Basis of Analysis

The documents reviewed in preparation of this estimate are as follows:

- The DMJM/PBQD pre-preliminary capital cost estimate.
- The metro rail starter line schematic diagram dated March 28, 1982.

These documents present reach locations, the number of parking facilities and parking space requirements.

A site examination of possible garage/parking lot locations was made in early March 1983.

References used for estimating the parking facilities are as follows:

- Kellogg Corporation cost records.
- Building construction cost data publications.

General Description

The two at-grade parking lots have been estimated at \$2.50 per square foot. An independent estimate reveals that this unit price includes an allowance for the following facilities:

- Demolition
- Site grading/leveling
- Pre-compaction

- Base course/asphalt/stripping
- Fencing
- Bumpers/islands/landscaping
- Lighting

The five parking structures are defined only as to parking stall capacity for the various locations. This limits the degree of estimating to that of conceptual. DMJM/PBQD has included an allowance of \$5,000 per parking space in their estimate, which is reasonable.

An early purchase and demolition of these sites for temporary use as contractor work/storage areas would aid the congestion problem for several contractors.

Back up estimating worksheets are included in Appendix R.

Findings and Conclusions

The allowances provided in the pre-preliminary estimate for parking facilities is adequate. This is based on minimum "no-frills" type of construction; an open, elevated type of structure, without HVAC and similar facilities.

As stated in the station shell section of this report, there appears to be a duplication of \$15,000,000 for parking facilities, as the parking structures at the Fairfax/Beverly Station and the Universal City Station were included in the estimate twice; once in the detailed station shell estimate, and again on the reach summary sheets. This duplication is corrected in the station shell section of this report.

Net Change: \$0

SECTION 5-S
CONTINGENCIES

Description

This item addresses an allowance for change orders, differing site conditions, etc., which cannot be foreseen even during final design. This item is in addition to the "design contingency" item included in the pre-preliminary estimate, which covers the uncertainties of costs due to the preliminary status of design.

Basis of Analysis

The Kellogg Corporation estimate for contingency is based upon experience from other transportation and heavy construction projects.

General Discussion

A design contingency allowance alone is inadequate for the SCRTD Metro Rail Project. The pre-preliminary estimate contains an allowance of 20 percent of the direct construction costs for "design contingencies." The SCRTD Estimating Methodology and Procedures manual states:

- "The design contingency is applied as an allowance for uncertainties of design during the earlier stages of design."
- "The need for this allowance disappears as the design progresses toward the 100 percent level."

The above translates to mean that at the time of construction contract document formation, all contingency allowances have been absorbed.

A contingency allowance during construction should be provided. The amount of such a contingency should consider the following criteria:

- The degree of subsurface exploration.
- The nature of the contract language as it pertains to the allocation of risks.
- The type of construction (tunnels, stations, above-ground structures, etc.)

Findings and Conclusions

Assuming a comprehensive subsurface investigation program is performed and resulting information is supplied to construction contractors, and equitable contract language is utilized, the contingency allowance should be applied as follows:

- Tunnel construction 15 percent
- Underground station construction 10 percent
- Surface construction 5 percent

The weighted average of 11 percent of the construction capital cost subtotal is recommended.

SECTION 5-T
CONTRACTOR MARK-UPS

Description

This item addresses those elements added to contractors' direct costs including:

- Field overhead cost.
- Home office general and administrative expense.
- Profit.
- Bond.

Basis of Analysis

The Kellogg Corporation estimate for contractor mark-ups is based upon experience from other transportation and heavy construction projects.

General Discussion

Each of the categories of indirect cost was examined in light of the types of work to be performed on the project. These were grouped into three categories: (1) tunnels, (2) stations, and (3) above-ground structures. Each of these three will have slightly varying percentage applications for overhead and general and administrative expense and large variation in percentage application for profit. The bond percentage will stay the same for all categories of work.

Field overhead cost will increase, as a percentage of the direct cost, as the amount of work being performed by a contractor with his own forces increases. Therefore, the field overhead, as a percentage, would be expected to be higher on the tunnel and station work, than on the above-ground structures where more of the work would be subcontracted. On heavy construction projects, the field overhead cost runs from 17 to 22 percent of direct costs. On surface structures, it would be expected to be less than that. Since 4.2 percent is being allocated to wrap-up insurance, which will be purchased and paid for by the owner, the contractor's overhead should be reduced by that much, or slightly more, based on the

premise that the owner's wrap-up insurance is cheaper than having the contractor pay for the same coverage. For this project, a weighted 16 percent would be reasonable for field overhead, applied to total direct costs.

General and administrative expense runs between 6 and 12 percent of the total cost for contractors involved in heavy and building construction. In the case of specialty contractors, such as electrical, it could run as high as 20 percent. On this project, an average of 7 percent should be applied to the sum of the direct and field overhead costs.

The profit applied by contractors varies considerably based upon the complexity of the project, the duration, amount of risk labor the contractor will perform with his own forces, and the competitive market. Tunnel work would command a profit markup of 20 to 30 percent, station work 10 to 12 percent, and surface structures 6 to 7 percent. A weighted profit for this project would be 15 percent applied to the subtotal of direct costs, field overhead cost, and home office general and administrative expense.

Bond premium rates start at 0.75 percent and decrease according to a schedule of contract value to 0.40 percent for contract values in excess of \$10,000,000. An additional factor influencing bond premium rates is contract duration. An appropriate rate for this project is 0.50 percent applied to the subtotal of direct costs, field overhead cost, home office general and administrative expense and profit.

It is assumed that gross receipts taxes are not applicable to this project.

Findings and Conclusions

The pre-preliminary estimate allows only 10 percent for overhead, 4 percent for profit, and 1 percent for bond, which compounds to a total markup of 15.5 percent. No allowance was included in the pre-preliminary estimate for home office general and administrating expense.

Kellogg Corporation recommends a total markup of 43.45 percent be applied to the contractors direct cost. This percentage is calculated as follows:

| | |
|---|---------------|
| Direct cost of project | 100% |
| Field overhead cost @ 16% | <u>16.00</u> |
| Subtotal | 116.00% |
| General and administrative expense @ 7% | <u>8.12</u> |
| Subtotal | 124.12% |
| Profit @ 15% | <u>18.62</u> |
| Subtotal | 142.74% |
| Bond @ 0.5% | <u>.71</u> |
| Subtotal | 143.45% |
| Less direct cost of project | <u>100.00</u> |
| Total markup | 43.45 |

SECTION 5-U

ENGINEERING, DESIGN AND CONSTRUCTION MANAGEMENT

Description

This item addresses the design engineering and construction management allowances for the first phase of construction. This item does not cover SCRTD's costs for administration as this cost is addressed in the section entitled Agency Costs.

Basis of Analysis

Both the design engineering and construction management allowances were determined by evaluating cost records of the following projects:

- BART
- WMATA
- MARTA
- Denver RTD (estimate)

General Discussion

The allowance presented in the capital cost estimate provides for full design through contract document preparation. This allowance also provides for a modest design modification or change order organization throughout construction. Also included is a full range of construction management services by an independent construction management firm.

Findings and Conclusions

With the exception of the MARTA project, the average of the several recently constructed and estimated transit projects are in line with the percentage allowance contained in the pre-preliminary capital cost estimate.

The estimate for design/construction management as presented by DMJM/PBQD in the pre-preliminary is reasonable. We confirm the allowance of 13 percent of construction capital cost for design and construction management.

Net change \$0.

SECTION 5-V
AGENCY COSTS

Description

This item addresses the costs for SCRTD's administration of the project. This item does not include design or general construction management costs which are addressed in the preceding section.

General Discussion

This estimate of agency costs assumes that SCRTD will engage a general construction management firm to perform the overall field supervision of construction. SCRTD may elect to utilize the construction management organization in one of two ways:

- Restrict the construction management organization to field activities such as surveying, inspection and technical services (soils, concrete, geology, metallurgy and general quality control). In this case, SCRTD would provide the general supervisory personnel such as area managers, resident engineers and other field office staff. SCRTD's administrative costs in this type of arrangement would be approximately 5 percent of capital costs.

- Assignment by SCRTD of all of the field construction activities to the construction management firm. SCRTD, therefore, would maintain a minimum organization to function primarily as general overall supervisor. As general supervisor, SCRTD would render final decisions on major issues and generally coordinate all participating agencies - design, scheduling, construction management, contractors, utilities, etc. SCRTD's administrative costs for this level of effort would be roughly 3 percent of capital costs.

A compromise, and highly recommended alternative, would be to supplement the SCRTD staff with a small cadre of construction personnel experienced in underground transit work. This group would generally oversee the major activities of construction, scheduling, interfacing, proper change order administration, claim mitigation and early recognition of problems realized on previous projects.

Findings and Conclusions

The allowance provided in the pre-construction estimate of 5 percent of capital costs is adequate to cover a major role in construction management by SCRTD. If more of the construction management role is delegated to an outside entity, the agency costs will be reduced approaching a 3 percent level. A timely and proper staffing of the construction management organization would also reduce this cost.

Net Change: \$0

SECTION 5-W
WRAP-UP INSURANCE

Description

This item normally includes builder's risk, general liability and workmen's compensation insurance coverage provided for all contractors with all premiums paid by the owner. This insurance normally does not include automotive insurance nor errors and omissions coverage for design, both of which must be purchased by the contractor.

Basis of Analysis

The basis of the analysis is limited to review of the SCRTD Metro Rail Project Estimating Methodology and Procedures manual, an informal interview with an insurance consultant, and previous experiences of several Kellogg Corporation employees involved in subway construction subject to wrap-up insurance programs. The report entitled "Insurance Alternatives Analysis for the Construction of the Southern California Rapid Transit District Rail Project" prepared by David Ashley, January 4, 1982 was not reviewed by Kellogg Corporation.

General Discussion

An effective wrap-up insurance program must consider the following:

- A clear definition of coverage and exclusions.
- A clear definition of management and administration of the program.
- Incentives to the contractor to minimize insurance losses.

Findings and Conclusions

Builder's risk insurance is apparently covered in two places in the pre-preliminary estimate: Wrap-up Insurance, and Contractor's Overhead. The Kellogg Corporation estimate excludes Builder's Risk Insurance from Contractor's Field Overhead.

Without clear definitions of the elements described under the General Discussion above, Kellogg Corporation cannot properly address this item and must apply the 4.2 percent factor currently used in the pre-preliminary estimate.

SECTION 5-X
ESCALATION

Description

This item covers the projected escalation of costs over the construction duration, from the stated value in current (mid-1982) dollars.

General Discussion

Pursuant to instruction received from SCRTD in the initial meeting prior to preparation of this check estimate, escalation was not to be computed or included. The estimate was to represent construction costs in mid-1982 dollars.

With a construction duration for this phase of work extending to 1990, Kellogg Corporation recommends that strong emphasis be placed on calculation of this cost element before total cost is established.

Findings and Conclusions

The estimate was prepared:

- Using mid-1982 prices.
- Escalation was excluded.

Net change: \$0.

SECTION 5-Y
CONSTRUCTION CONTRACT PACKAGING

Description

This item addresses construction contract packaging of work but does not define specific variations of cost.

Basis of Analysis

The following documents have been reviewed concerning construction contract packaging:

- Preliminary drawings.
- A drawing entitled "Metro Rail Starter Line Schematic Diagram" dated January 3, 1983 and prepared by DMJM/PBQD.
- The geotechnical report.
- SCRTD contract unit descriptions dated March 1983.

The following individuals have been interviewed by Kellogg Corporation concerning construction contract packaging:

- James E. Crawley - SCRTD
- Donald King - SCRTD
- Howard J. Chaliff - DMJM/PBQD
- John E. Moss - DMJM/PBQD - Consultant

In addition, Kellogg Corporation traveled the entire route with specific emphasis on observing construction contract packaging considerations.

General Discussion

Construction contract packaging must consider and optimize the mix of the following criteria:

- Manageability by a single contracting organization.
- Scheduling integration to achieve systemwide completion milestones.
- Interface considerations between separate contracts.
- Geologic conditions: similarity as opposed to diversity.
- Jurisdictional boundaries between political subdivisions, and franchise boundaries between utility companies.

Findings and Conclusions

Construction contract packaging described most recently in SCRTD's Contract Unit Descriptions has eliminated most of the packaging problems presented in the earlier Schematic Diagram. By way of review, those earlier problems generally affected tunneling operations in the following areas:

- Reach No. 2 (over-under tunnel configuration).
- Reach No. 5 (tunneling interface with the Alvarado/Wilshire Station).
- Reach No. 8 (over-under tunnel configuration and starter tunnels requiring additional shafts or TBM's).
- Reaches No. 10 and 12 (tunnels on both ends of the packages requiring additional shafts or TBM's).

Additional costs of the above have not been evaluated since packaging and configuration have been recently revised. These costs and/or scheduling considerations would have been significant. For example, in the over-under tunnel configuration, the vertical portal relationship to station excavation and bracing was not addressed in the estimate or schedule.

The revised packaging presents manageable contract sizes attractive to general contractors and recognizes similarity of geological considerations. It is understood that construction scheduling is currently being re-analyzed by others, but if the present concurrency of tunneling operations is retained, the ability of the TBM manufacturing industry to provide TBM's on such a tight schedule must be analyzed.

Lack of detailed definition of packaging prevents analysis of interface considerations between separate contracts. This topic should receive a careful value engineering analysis.

No comparison between construction contract packaging and the jurisdictional boundaries between political subdivisions or franchise boundaries between utilities was made due to lack of data.

It is recommended that further evaluation of construction contract packaging considerations be performed early in the final design phase. This topic should be targeted for value engineering alternative studies.

To FILE

Date 3/10/83

From

AWJ

Subject SCRTD/MR.

Pg 1

ESTIMATE ORGANIZATION:

- 1) DMJM/PBQD LETTER OF 1/6/83 TO SCRTD
SUMMARY BY 14 DIRECT COST ITEMS
PLUS INDIRECTS, ADMIN & CONTINGENCY
COSTS.
- DATA FROM 2'x2' SPREAD SHEET.
- 2) 2'x2' ESTIMATE SUMMARY SPREAD SHEET
1/3/82 (SIC) BY JTS/DFM.
- DATA BY SUMMARY ITEM (IN ABOVE LTR)
AND BY REACH NO.
- REFERENCES TO PAGE NO. OF DETAILED
ESTIMATE
- SHEET SQUARED.
- INDIRECTS ADDED @ BOTTOM.
- 3) MAIN YARD/ TAIL TRACK (TAB # 1-Pg Y1-A TO Y5B)
- INCLUDES TRACKWORK
- " FIXED EQUIPMENT
- " YARD VEHICLES. } MAIN YARD
- " BUILDINGS
- " ROADS & PVT.

NORTH HOLLYWOOD TAIL TRACK 4-49 TO 4-54
TOTAL FWD FROM Pg 4-50 (\$23.5M)
(TRACKWORK NOT INCL - FROM 6-17)
FIXED EQUIPMENT & YARD VEHICLES
Pgs 4-44 TO 4-48
TOTAL FWD FROM Pg 4-46 (\$7.7M + 3.4M)

To

Date

From

Subject

Pg 2

- 4) REACH (G-1 TO G-17) - 2ND TAB Pgs G-1 TO G-17
- G-1 DESCRIPTION OF REACH No. 1 TO 14.
 - G-2 LENGTH ANALYSIS BY MAJOR PROJECT FEATURE BY REACH.
 - G-3 TO G-16 REACH No. 1 TO No. 14 SUMMARY COST INFO.
 - G-17 NORTH TAIL TRACK - TRACKWORK.

NOTE: TABS No. 1 & No. 2 SUMMARIZE THE FOLLOWING:

- 1.0 GUIDELAYS
- 2.0 STATIONS
- 3.0 PARKING
- 4.0 TRACKWORK
- 5.0 YARDS & SHOPS
- 10.2 TRACTION POWER STRUCTURE

EXCLUDED

- 6.0 CENTRAL CONTROL FACILITY
- 7.0 UTILITY RELOCATION
- 8.0 TRAIN CONTROL
- 9.0 COMMUNICATIONS
- 10.1 TRACTION POWER
- 11.0 FARE COLLECTION
- 12.0 VEHICLES

NOTE: YELLOW HIGHLIGHTED NUMBERS ARE THOSE CARRIED FORWARD TO 2'x2' SUMMARY SPREAD SHEET.

- 5) TUNNEL (3RD TAB Pgs G-18 TO G-66)
 DETAILED ESTIMATES FOR DUAL TRACK TWIN TUBE TUNNEL (\$ 384 M)
 REACH 2, 5, 6, 8, 10, 12, 14.
 DATA FORWARDED TO G-1 TO G-17.

To

Date

From

Subject

pg 3

6) UNDERPINNING (4TH TAB, PGS G-67 TO G-68)

G-67 @ C&C STATIONS
G-68 @ C&C CROSSOVERS

AMOUNTS NOTED L.S. WITH NO
DEVELOPMENT OR BACK-UP.

FORWARDED TO G-1 TO G-17 (STATIONS,
(ALSO TO STATION SHEET & FINISH SUMMARY
SHEETS)

X-OVER UNDERPINNING # FORWARDED TO
G-1 TO G-17 SUMMARIES (UNDER
GUIDEWAYS) AND TO 2x2
SPREAD SHEET "1.10 UNDERPINNING"

NOTE: ADDITIONAL UNDERPINNING IS ADDED
TO G-1 TO G-17 WHICH DOES NOT
APPEAR IN THIS SECTION:

G-3 UNDERPIN FREEWAY # 20M

G-4 UNDERPIN BRIDGE # 0.3M

7) TUNNEL VENT

MECHANICAL ONLY @ STATIONS & X-OVERS
MECHANICAL + STRUCT./ARCH/ELECT.

8) SPECIAL SYSTEMS.

ALL BY
KAISER
ENGRS

AUTOMATIC TRAIN CONTROL SYSTEM
COMMUNICATIONS SYSTEMS
FARE COLLECTION SYSTEM
AUXILIARY VEHICLES
PASSENGER VEHICLES
TRACTION POWER SYSTEM * ONLY ITEM
(+ TRACTION POWER STRUCTURE) TO BE CHECKED
BY KC.

INCLUDES NARRATIVE & SEMI-DETAILED COST.

To

Date

From

Subject

pg 4

7) STATION SHELL:

DETAILED 3-4 PAGE UNIT PRICE ESTIMATE FOR EACH OF 16 STATIONS.

SUMMARY SHEET IN FRONT SHELL CONST \$ CARRIED TO Pgs G-1 TO G-17

8) STATION FINISH:

ITEMIZED COST FOR EACH STATION BUT BASED ON ESTIMATED COST PER SF FOR A TYPICAL SINGLE LEVEL AND O/U STATION, APPLIED TO THE OTHER STATIONS.

BREAKDOWN:

- ARCHITECTURAL
- MECHANICAL (ELEVATORS/ESCALATORS)
- ELECTRICAL (AUXILIARY SYSTEM)
- ELECTRICAL (MCC)
- HVAC
- FIRE PROTECTION SYSTEM
- PLUMBING/SEWERAGE.

SINGLE LEVEL STATIONS @ 291⁰⁰/SF - 300⁰⁰/SF
O/U STATIONS " @ 240⁰⁰/SF.

NOTE: LAST 2 PGS PERTAIN TO PARKING STRUCTURES BUT DATA DOES NOT APPEAR TO BE CARRIED FORWARD. (PARKING CALCULATED @ \$ 5000/CAR ON G-1 TO G-17)

To

Date

From

Subject

95

9) CONTROL BUILDING:

1. PAGE ESTIMATE ON 10000 SF BLDG.
(EXCLUDES TRAIN CONTROL COST)
\$1.5M CARRIED TO T&E SUMMARY

10) UTILITY COSTS:

- a) RELOCATION COSTS FOR UTILITIES
@ STATION LOCATIONS ESTIMATED
BY CITY OF L.A. = \$21.7 M
- b) RELOCATION & SUPPORT FOR
VENT STRUCTURES
ALLOWANCE OF \$ 3.3 M
- c) \$25 M. TOTAL CARRIED TO T&E
SUMMARY.

11) PARKING

UNIT PRICE OF \$5000 / CAR SPACE USED
FOR 3-LEVEL PARKING STRUCTURE.

PRICING ACCOMPLISHED ON
Pgs G-1. TO G-17 SUMMARIES

SIZE OF STRUCTURE (# CARS)
NOT INDICATED ANYWHERE
EXCEPT ON SUMMARY SHEET

AT GRADE PARKING PRICED
AT \$25/CF. (NO BACKUP FOR
THIS UNIT PRICE)

To

Date

From

Subject

pg 6

12) TRACKWORK

THREE SOURCES

- ESCALATED BID PRICES, BOSTON TRANS II
- COST WORKUP BY PB&D TRACK EXPERT
- RS. MEANS

USED WORKED-UP PRICE FOR FIXED RAIL
@ \$ 228⁰⁰/TF

USED MEANS + DODGE + SUB QUOTES
FOR BALLASTED AT GRADE
@ 75⁰⁰/TF

USED BOSTON PRICES FOR SWITCHES &
X-OVERS IN MAIN YARD (BUT NOT
BALLASTED TRACK (125⁰⁰/TF VS 75⁰⁰/TF USED)

SCPTD/IMR
ESTIMATE CHECK
SYSTEM FEATURE

REF: 1/3/83 CONCEPTUAL SCHEMATIC 3/50/83
(W)

TAKEOFF (EXCLUDING YARDS)

| 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 | | |
|--------------|---|------------------------|------------------------|----------------|-----------------|------------|---------------------|--------------------------|-----------------|-----------------|-----------------|--------------------------|-------------------------------|------------------------------|
| REACH No. | STA DESCRIPTION | TWIN BORE TUNNEL | TWIN CUT & COVER | CROSS- OVER | POCKET TRACK | STATION | TWIN OPEN UNT | QUAD C/C w/ X-OVER | TOTAL LENGTH | TRACK LENGTH | PARK STRUCT. | VENT SHAFT STRUCT. | VENT SHAFT STR. w/ SHFT | TRACTION POWER STRUCT. |
| 1 | UNION STATION | | 945 | | | 690 | - | 792 (40) | 2377 | 6338 | 1 | 1 | | |
| 2 | FIRST & HILL STA. FIFTH & HILL STA. | 7324 | | 460 (1) | | 681 681 | | | 9046 | 18092 | | | | |
| 3 | SEVENTH & FROUHL | | | | | 740 | | | 740 | 1480 | | | | |
| 4 | ALVARADO | | | | | 490 | | | 490 | 980 | | | | |
| 5 | VERMONT/WILSHIRE NORMANDIE/WILSHIRE | 11768 | | 920 (2) | | 667 672 | | | 13927 | 27854 | | | | 1 |
| 6 | WESTERN/WILSHIRE | 10980 | | | 1010 (50) | 660 | | | 12150 | 25310 | | | | |
| 7 | LA BELLA/WILSHIRE | | | | | 660 | | | 660 | 1320 | | | | |
| 8 | FAIRFAX - WILSHIRE | 7837 | | 920 (6) | | 935 | | | 9092 | 18184 | 1 | | | |
| 9 | BEVERLY - FAIRFAX | | | | | 685 | | | 685 | 1370 | 1 | | | |
| 10 | SANTA MONICA - FAIRFAX LA BELLA - SUNSET | 16162 | | 460 (1) | | 680 690 | | | 17992 | 35984 | | 1 | | |
| 11 | HOLLY WOOD - CAMDEN | | | | 1250 (50) | 655 | | | 1885 | 5020 | | | | |
| 12 | | 16154 | | | | - | | | 16154 | 32308 | | | 2 | 2 |
| 13 | UNIVERSAL CITY | | | | | 630 | | | 630 | 1260 | 1 | | | |
| 14 | METH HOLLY WOOD | 10688 | | 460 (1) | | 672 | | | 11820 | 23640 | 1 | 1 | | 1 |
| KC TOTAL | | 79,813 | 945 | 3220 (7) | 2260 | 10,618 | 0 | 792 | 97,683 | 199,190 | 5 | 3 | 2 | 4 |
| DMJM/PSGD | | 80,800 | 1677 | 3220 (7) | 2260 | 10,800 | 600 | 0 | 99,357 | 198,714 | 5 | 3 | 2 | 4 |
| Δ | | <987> | <732> | - | - | <182> | <400> | 792 | <1709> | 426 | - | - | - | - |

-82-

SCRIPD / MISTED RAIL
TUNNEL ESTIMATE CHECK - \$

3/14/83
duffy / GMM

| REACH → | 2 | 5 | 6 | 8 | 10 | 12 | 14 | TOTALS |
|-----------------------------|------------|------------|------------|------------|------------|------------|------------|-------------|
| ESTIMATED COST (\$M) | \$42.4M | \$69.1M | \$79.4M | \$57.6M | \$71.2M | \$65M | \$2.9 | \$383M |
| L- TWIN BORE (LF) | 7,500 LF | 12,100 LF | 10,400 LF | 7,800 LF | 17,000 LF | 14,500 LF | 9,700 LF | 89,000 LF |
| UNIT COST (\$/LF) | \$5,400/LF | \$5,300/LF | \$4,500/LF | \$6,200/LF | \$4,200/LF | \$4,000/LF | \$4,400/LF | \$4,700/LF |
| EQUIPMENT | 7,000,000 | 6,600,000 | 7,000,000 | 7,200,000 | 7,000,000 | 11,000,000 | 7,000,000 | 52,800,000 |
| UNIT COST | \$933/LF | \$545/LF | \$673/LF | \$947/LF | \$412/LF | \$667/LF | \$720/LF | \$653/LF |
| LABOR | 13,176,000 | 15,768,000 | 13,176,000 | 15,120,000 | 20,760,000 | 19,224,000 | 11,448,000 | 108,864,000 |
| UNIT | \$1757/LF | \$1303/LF | \$1266/LF | \$1989/LF | \$1232/LF | \$1165/LF | \$1180/LF | \$1347/LF |
| GENERAL EXPENSE | 2,994,500 | 4,154,000 | 2,994,500 | 3,869,000 | 4,213,500 | 1,001,500 | 3,047,500 | 25,254,500 |
| UNIT | \$399/LF | \$342/LF | \$288/LF | \$509/LF | \$248/LF | \$243/LF | \$314/LF | \$313/LF |
| MATERIALS | 7,550,000 | 10,675,000 | 13,100,000 | 9,400,000 | 21,000,000 | 13,495,000 | 10,925,000 | 86,245,000 |
| UNIT | \$1007/LF | \$887/LF | \$1250/LF | \$1237/LF | \$1235/LF | \$830/LF | \$1126/LF | \$1067/LF |
| CONSUMABLES | 244,000 | 292,000 | 244,000 | 284,000 | 388,000 | 356,000 | 212,000 | 2,016,000 |
| UNIT | \$33/LF | \$24/LF | \$23/LF | \$37/LF | \$23/LF | \$24/LF | \$22/LF | \$25/LF |
| MUCK DISPOSAL | 1,518,966 | 2,450,400 | 2,106,300 | 1,539,220 | 3,442,991 | 3,313,530 | 1,801,630 | 16,173,287 |
| UNIT | \$203/LF | \$203/LF | \$203/LF | \$202/LF | \$203/LF | \$20/LF | \$186/LF | \$200/LF |
| GROUND WATER LOWERING | 500,000 | - | - | - | - | - | - | 500,000 |
| UNIT | \$67/LF | - | - | - | - | - | - | \$67/LF * |
| CROSS PASSAGES | 1,400,000 | 2,200,000 | 2,400,000 | 1,200,000 | 3,200,000 | 3,200,000 | 1,900,000 | 15,100,000 |
| UNIT | \$187/LF | \$182/LF | \$192/LF | \$157/LF | \$188/LF | \$194/LF | \$196/LF | \$187/LF |
| FINISH TUNNEL | 750,000 | 1,210,000 | 1,040,000 | 760,000 | 1,700,000 | 1,650,000 | 970,000 | 8,080,000 |
| UNIT | \$100/LF | \$100/LF | \$100/LF | \$100/LF | \$100/LF | \$100/LF | \$100/LF | \$100/LF |
| STEEL LINER | - | 12,449,100 | - | 5,484,000 | - | - | - | 17,933,100 |
| UNIT | - | \$1085/LF | - | \$726/LF | - | - | - | \$910/LF * |
| SHIELD BIT (LEFT UNIT ONLY) | - | - | - | - | - | 391,000 | - | 391,000 |
| UNIT | - | - | - | - | - | \$24/LF | - | \$24/LF * |
| SUBTOTAL | 35,133,966 | 55,713,700 | 41,560,800 | 44,895,100 | 61,896,491 | 56,233,000 | 37,304,130 | 332,963,767 |
| D.M. & PROFIT | 5,270,020 | 8,366,055 | 6,234,120 | 6,728,265 | 9,284,474 | 8,366,020 | 5,675,620 | 44,444,566 |
| UNIT | \$705/LF | \$691/LF | \$600/LF | \$875/LF | \$546/LF | \$574/LF | \$571/LF | \$500/LF |
| TOTAL | 40,403,986 | 64,079,755 | 47,794,920 | 51,623,365 | 71,180,965 | 64,599,020 | 42,979,750 | 377,408,333 |
| UNIT COST | \$5582/LF | \$5,300/LF | \$4,597 | \$6,787/LF | \$4187/LF | \$3454/LF | \$4423/LF | \$4739/LF |

* UNIT COSTS BASED ON ACTUAL LINEAL FEET

-83-

SCRTD / METRO RAIL
TUNNEL ESTIMATE CHECK

3/11/83
MWT/CHM

1 of 3 SHEETS

| REACH → | 2 | 5 | 6 | 8 | 10 | 12 | 14 | TOTALS |
|----------------------------|------------|-----------|------------|-----------|------------|------------|------------|--------------|
| TWIN BORE LENGTH (LF) 7500 | | | | | | | | |
| UNIT COST / LF \$400 | | | | | | | | |
| EST. COST (M) \$40.9 | | | | | | | | |
| 1. DEPOSIT MATL: (LF) | | | | | | | | |
| WATER LOGGED SAND | 1300 | | | | | | 1500 | |
| PUNTE / FERNANDO | 4000 | 12,100 | 10,400 | | 17,000 | 14,500 | 8,200 | |
| DRY SAND | 2200 | | | | | | | |
| TOTAL | 7500 | 12,100 | 10,400 | | 17,000 | 14,500 | 9,700 | |
| TIME ALLOTMENT (WEEKS) | | | | | | | | |
| EXCAVATION | 48 | 61 | 52 | 61 | 85 | 83 | | |
| ASSEMBLE / LAUNCH | 4 | 4 | 4 | 4 | 4 | 4 | | |
| MODIFY TBW | 1 | | | | | | | |
| SKID TRAY STA. | 6 | 6 | 3 | 3 | 6 | | | |
| ONSHORE / REMOVE | 2 | 2 | 2 | 2 | 2 | 2 | | |
| TOTAL | 61 | 73 | 61 | 70 | 97 | 89 | 53 | |
| RATE OF ADVANCE (FT/DAY) | | | | | | | | |
| ALLUVIAL DEPOSITS | 25 | | | | | | | |
| SEDIMENTARY | 40 | 40 | 40 | | 40 | 40 | 40 | |
| OIL + GAS BEARING | | | | 25 | | | | |
| BELOW WATER TABLE | | | | | | | 25 | |
| 2. EQUIPMENT | | | | | | | | |
| No. TBW'S | 2 | 2 | 2 | 2 | 2 | 2 | 2 | |
| COST / EA | \$2.5M | \$2.2M | \$2.5M | \$2.5M | \$2.5M | \$4.5M | \$2.5M | |
| OTHER PLANT EQUIP | \$2M | \$2.2M | \$2.0M | \$2.2 | \$2.0M | \$2.0M | \$2.0M | |
| TOTAL | \$7.0M | \$6.6M | \$7.0M | \$7.2M | \$7.0M | \$1.0M | \$7.0M | \$62.8M |
| 3. LASER | | | | | | | | |
| TOTAL W.W. | 61 | 73 | 61 | 70 | 97 | 89 | 53 | |
| UNIT COST | \$216K | \$216K | \$216K | \$216K | \$216K | \$216K | \$216K | |
| COST | \$13,176M | \$15,768M | \$13,176M | \$15,120M | \$20,782M | \$19,224M | \$11,448M | \$108,869M |
| 4. GEN EXPENSE | | | | | | | | |
| TOTAL W.W. | 113 | 156 | 113 | 146 | 159 | 151 | 115 | |
| UNIT COST | \$26.5K | \$26.5K | \$26.5K | \$26.5K | \$26.5K | \$26.5K | \$26.5K | |
| COST | \$2,994.5M | \$4,134M | \$2,994.5M | \$3,869M | \$4,213.5M | \$4,003.5M | \$3,045M | \$25,254.5M |
| SUBTOTAL | \$23,170.5 | \$26,502 | \$23,170.5 | \$26,189 | \$32,165.5 | \$34,225.5 | \$21,495.5 | \$186,918.5M |

-84-

SOFTD / METRO RAIL
TUNNEL ESTIMATE CHECK

3/11/83
AWJ/GHM

2 of 3 SHEETS

| REACH → | 2 | 5 | 6 | 8 | 10 | 12 | 14 | TOTAL |
|-------------------------|-------------|--------------|-------------|-------------|-------------|-------------|-------------|------------|
| 5. MATERIALS | | | | | | | | |
| # OF RINGS W/ GASKET | 800 | — | 6,500 | 4,700 | 10,500 | — | 1,000 | |
| # OF RINGS W/OUT GASKET | 3,400 | 4,100 | — | — | — | 8,300 | 5,100 | |
| UNIT COST W/ GASKET | \$2,000 | — | \$2,000 | \$2,000 | \$2,000 | — | \$2,000 | |
| UNIT COST W/OUT GASKET | \$1,750 | 1,750 | — | — | — | \$1,650 | \$1,750 | |
| TOTAL COST | \$7.55M | \$10.675M | \$13.0M | \$9.4M | \$21.0M | \$13.65M | \$10.925M | \$66.245M |
| 6. CONSUMABLES | | | | | | | | |
| TOTAL W W | 61 | 73 | 61 | 70 | 97 | 89 | 53 | |
| UNIT COST | \$4K | \$4K | \$4K | \$4K | \$4K | \$4K | \$4K | |
| COST | \$244K | \$292K | \$244K | \$280K | \$388K | \$356K | \$212K | 2.016M |
| 7. MIXED DISPOSAL | | | | | | | | |
| CY | 253,141 | 408,433 | 351,050 | 256,536 | 573,832 | 582,263 | 300,272 | |
| UNIT COST (\$/CY) | \$6.0 | \$6.0 | \$6.0 | \$6.0 | \$6.0 | \$6.0 | \$6.0 | |
| TOTAL | \$1,518,966 | \$2,450,600 | \$2,106,300 | \$1,539,220 | \$3,442,991 | \$5,313,580 | \$1,801,630 | 16.173207M |
| 8. DEWATERING | | | | | | | | |
| L.S. | 500K | — | — | — | — | — | — | 0.5M |
| 9. CROSS PASSAGES | | | | | | | | |
| SPACING | 500' | 500' | 500' | 500' | 500' | 500' | 500' | |
| # | 14 | 22 | 20 | 12 | 32 | 32 | 10 | |
| UNIT COST | \$100K | \$100K | \$100K | \$100K | \$100K | \$100K | \$100K | |
| TOTAL | \$1.4M | \$2.2M | \$2.0M | \$1.2M | \$3.2M | \$3.2M | \$1.0M | 15.1M |
| 10. FINISH | | | | | | | | |
| LF | 7,500 | 12,100 | 10,400 | 7,600 | 17,000 | 16,500 | 9,700 | |
| UNIT COST (\$/LF) | \$100 | \$100 | \$100 | \$100 | \$100 | \$100 | \$100 | |
| TOTAL | \$750K | \$1.21M | \$1.04M | \$760K | \$1.7M | \$1.65M | \$970K | 8.08M |
| SHIELD PIT | — | — | — | — | — | 500K | — | \$914M |
| 11. STEEL LINER | | | | | | | | |
| LF | — | 12,100 | — | 5,380 | — | — | — | |
| UNIT COST (MTL) | — | \$721 | — | \$721 | — | — | — | |
| TOTAL | — | \$8,724,100 | — | \$3,880,880 | — | — | — | |
| LABOR (W W) | — | — | — | — | — | — | — | |
| UNIT COST | — | 31 | — | 14 | — | — | — | |
| TOTAL | — | \$120,000 | — | \$120K | — | — | — | |
| TOTAL | — | \$12,444,000 | — | \$5,486,880 | — | — | — | 17.930480M |

PAGE
SUBTOTAL
\$46,436,647

-85-

SCED ESTIMATE CHECK
STATIONS - COMPARATIVE CHECK (SHELL) 3/9/83
AWJ/VET/GHM

FOOTNOTES: * FIGURE NOT INCLUDED IN DMJM/PBQD ESTIMATE
** ARITHMETIC MISTAKE IN DMJM/PBQD ESTIMATE
++ DMJM ROUNDED OFF FIGURE TO \$14,890,000

| ITEM | UNION STA | 1 st HILL | 5 th HILL | 7 th HILL | Wil-hire & Alvarado | Wilshire VERMONT | Wilshire NORMANDIE | Wilshire WESTERO | Wilshire LABREA | Wilshire FAIRFAX | FAIRFAX BEVERLY | FAIRFAX SANTA MONICA | SUNSET LABREA | Hollywood & Cahuenga | Universal City | N. Hollywood | TOTALS | SUBTOTAL FOR CONCRETE | % OF TOTAL COST | % OF CONCRETE SUBTOTAL |
|-----------------------|------------|----------------------|----------------------|----------------------|---------------------|------------------|--------------------|------------------|-----------------|------------------|---------------------|----------------------|---------------|----------------------|----------------|--------------|------------|-----------------------|-----------------|------------------------|
| LEVEL TYPE | ONE "B" | ONE "E" | ONE "E" | ONE "A" | ONE "B" | ONE "C" | ONE "C" | ONE "C" | ONE "C" | TWO "E" | ONE "B" | ONE "C" | - | - | - | ONE "C" | - | - | - | - |
| L | 640' | 631' | 631' | 740' | 740' | 567' | 672' | 660' | 662' | 735' | 685' | 682' | 680' | 635' | 630' | 612' | - | - | - | - |
| W | 66'-8" | 60'-9" | 60'-9" | 62'-9" | 62'-9" | 66'-8" | 61'-8" | 64'-8" | 65' | 65' | 62'-8" | 65' | 65' | 65' | 65' | 64'-8" | - | - | - | - |
| T | 29' | - | - | - | - | VARIES | 42'-4" | 46'-4" | 45'-6" | 46'-8" | 27'-3" | 46'-3" | 46'-3" | 46'-3" | 46'-2" | 42'-4" | - | - | - | - |
| D | 39.5' | 66'-10" | 66'-6" | 53'(44) | 53'(44) | 45'-10" | 63'-7" | 54'-6" | 52.5' | 84' | 42' | 45' | 55' | 55' | 55' | 63'-7" | - | - | - | - |
| 1) DEMOLITION | 300,000 | 504,500 | 400,500 | 109,850 | 70,000 | 39,000 | 39,700 | 150,000 | 123,750 | 131,200 | 64,250 | 30,000 | 85,000 | 170,000 | 500,000 | 39,700 | 1,924,150 | | 0.8 | |
| 2) EARTHWORK | 2,764,150 | 6,983,750 | 9,347,550 | 7,694,050 | 3,080,600 | 3,126,700 | 5,711,400 | 5,174,400 | 5,076,750 | 11,830,150 | 3,901,200 | 4,295,050 | 5,093,100 | 4,231,600 | 3,834,100 | 5,711,400 | 89,952,050 | | 36.0 | |
| 3) CONCRETE | | | | | | | | | | | | | | | | | | | | |
| A) FORMWORK | 1,600,950 | 2,568,200 | 3,156,250 | 1,495,100 | 590,150 | 990,600 | 486,350 | 1,759,700 | 1,627,750 | 2,922,850 | 1,087,000 | 1,675,300 | 1,630,700 | 1,509,250 | 1,448,100 | 1,649,150 | | 27,141,700 | | 28.9 |
| B) CONCRETE | 2,029,400 | 2,434,600 | 3,081,800 | 1,818,150 | 1,083,700 | 1,430,700 | 1,654,400 | 1,244,900 | 1,814,500 | 3,439,250 | 1,189,050 | 1,643,550 | 1,760,100 | 1,473,950 | 1,555,300 | 1,654,340 | | 29,827,670 | | 31.7 |
| C) REBAR | 2,218,600 | 2,738,750 | 3,490,300 | 1,964,100 | 1,213,300 | 1,575,000 | 1,791,200 | 1,825,000 | 1,902,300 | 3,669,300 | 1,226,300 | 1,724,400 | 1,905,500 | 1,703,250 | 1,683,400 | 2,120,400 | | 32,870,350 | | 35.0 |
| D) CURING | 14,200 | 19,800 | 31,450 | 14,050 | 7,500 | 11,000 | 10,550 | 13,200 | 19,150 | 12,750 | 10,900 | 17,850 | 19,500 | 17,900 | 18,550 | 259,1750 | | 3,945,650 | | 4.2 |
| E) FINISHING | 272,400 | 309,850 | 113,650 | 95,450 | 58,050 | 102,900 | 229,550 | 180,500 | 304,000 | 480,350 | 246,150 | 214,700 | 319,950 | 292,300 | 43,300 | 299,550 | | 99,045,140 | | 100.0% |
| TOTAL CONC | 6,142,550 | 8,079,600 | 10,174,150 | 5,387,450 | 2,952,700 | 4,069,200 | 5,249,950 | 5,449,000 | 5,727,700 | 10,534,500 | 3,709,450 | 5,335,800 | 5,635,750 | 5,097,650 | 4,727,800 | 5,735,990 | | 99,045,140 | | 38.5 |
| 4) WATER PROOFING | 85,100 | 312,000 | 219,650 | 186,300 | 70,050 | 126,600 | 177,300 | 140,900 | 172,600 | 1,188,000 | 116,600 | 177,650 | 183,600 | 166,300 | 165,100 | 177,300 | | 2,725,050 | | 1.1 |
| 5) SITE RESTORATION | 1,045,000 | 128,250 | 176,500 | 254,000 | 100,000 | 169,350 | 162,000 | 184,300 | 140,000 | 773,000 | 191,400 | 180,000 | 179,000 | 101,300 | 12,468,500 | 161,900 | | 16,369,520 | | 6.7 |
| 6) TRAFFIC MAINT | 15,000 | 41,650 | 49,000 | 53,600 | 11,000 | 15,000 | 15,400 | 17,000 | 15,600 | 21,700 | 16,100 | 16,600 | 19,100 | 17,000 | 30,000 | 15,400 | | 371,150 | | 0.2 |
| 7) UTILITIES SUPPORT | 517,600 | 773,850 | 1,003,650 | 684,650 | 73,800 | 379,600 | 567,800 | 558,300 | 562,850 | 1,186,300 | 239,500 | 501,800* | 564,900 | 286,400 | 103,000 | 567,800 | | 8,571,800 | | 3.5 |
| 8) MOBILIZATION | 434,800 | 69,150 | 802,950 | 547,400 | 253,000 | 310,800 | 476,950 | 446,400 | 472,800 | 983,850 | 328,900 | 421,500* | 474,500 | 469,700 | 415,400 | 476,950 | | 7,945,850 | | 3.2 |
| | | | | | | | | | | | 4,108,000 (OFF-LOG) | | | | | | | 1,109,000 | | 1.7 |
| SUB TOTAL DIRECT COST | 14,304,200 | 16,979,300 | 21,879,500 | 14,917,300 | 6,629,150 | 8,290,350 | 12,400,400 | 12,170,500 | 12,292,050 | 25,603,700 | 12,675,400 | 10,958,400 | 12,235,050 | 10,535,950 | 22,754,400 | 12,886,400 | | 229,012,710 | | 91.6 |
| G.C. OVERHEAD % | 10% | 10% | 10% | 10% | 10% | 10% | 10% | 10% | 10% | 10% | 10% | 10% | 10% | 10% | 10% | 10% | | | | 9.2 |
| BOND % | 1% | 1% | 1% | 1% | 1% | 1% | 1% | 1% | 1% | 1% | 1% | 1% | 1% | 1% | 1% | 1% | | | | 1.0 |
| PROFIT % | 4% | 4% | 4% | 4% | 4% | 4% | 4% | 4% | 4% | 4% | 4% | 4% | 4% | 4% | 4% | 4% | | | | 4.0 |
| SUB TOTAL | 13,061,300 | 15,939,300 | 20,280,500 | 17,236,000 | 7,660,000 | 9,573,000 | 14,328,000 | 14,062,000 | 14,202,100 | 29,583,539 | 14,645,700 | 12,661,773 | 14,130,867 | 12,173,458 | 25,118,400 | 14,889,500 | | 253,832,453 | | 105.8 |
| DEPTH REDUCTION TOTAL | 13,961,322 | 15,939,300 | 22,000,500 | 17,236,000 | 4,900,000 | 3,059,000 | 10,643,000 | 14,202,000 | 14,202,100 | 29,583,539 | 14,645,700 | 12,661,773 | 14,130,867 | 12,173,458 | 25,118,400 | 14,889,500 | | 253,832,453 | | 105.8 |

KC 1223 SCRTD/METRO RAIL
ESTIMATE CHECK - STATIONS
UNIT PRICES

3/17/83
1 OF 3

| STATIONS | UNITS | UNION STATION | 13 TH + HILL | 5 TH + HILL | 7 TH + FLOWER | ALVARADO + WILSHIRE | VERMONT + WILSHIRE | NORMANDIE + WILSHIRE | WESTERN + WILSHIRE | LEBBEAT + WILSHIRE | FAIRFAX + WILSHIRE | BEVERLY + FAIRFAX | SANTA MONICA | LEBBEAT + SUNSET | HOLLYWOOD + CANUENGA | UNIVERSAL CITY | LANKERSHIM | |
|----------------------------|-------|---------------|-------------------------|------------------------|--------------------------|---------------------|--------------------|----------------------|--------------------|--------------------|--------------------|-------------------|--------------|------------------|----------------------|----------------|------------|-------|
| 1. DEMOLITION | | | | | | | | | | | | | | | | | | |
| REMOVE RR. TRACKS | LF | 15 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| REMOVE RR CANOPIES | LF | 200 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| DEMOLISH CONC. BLDG. | CF | 0.22 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| A-C PAVING | SF | 0.15 | 0.15 | 0.15 | 0.15 | 0.15 | 0.15 | 0.15 | 0.15 | 0.15 | 0.15 | 0.15 | 0.15 | 0.15 | 0.15 | 0.15 | 0.15 | 0.15 |
| MISCELLANEOUS | LS | 18,850 | - | - | - | 2,400 | - | - | - | - | - | - | 2,150 | 19,800 | 22,650 | 41,200 | - | - |
| HALLWAY | CY | 6 | 6.80 | 6.80 | 6.80 | 6.80 | 6.80 | 6.80 | 5.57 | 6 | 6 | 6 | 6 | 6 | 6 | 6 | 6 | 6 |
| CONCRETE PAVING (SLABS) | SF | - | 1.50 | 1.50 | 1.50 | - | 1.50 | 1.50 | 1.50 | 0.50 | - | - | - | 1.50 | 1.30 | - | - | 1.50 |
| CONCRETE STRIPS | SF | - | 2.80 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| TRAFFIC LIGHTS | EA | - | 500 | 500 | 500 | - | - | 500 | 500 | 500 | - | - | 500 | - | - | - | - | 500 |
| STREET LIGHTS | EA | - | 500 | 500 | 500 | - | 500 | 500 | 500 | 500 | - | - | 500 | - | - | - | - | 500 |
| MANHOLES | EA | - | 250 | 250 | 250 | - | 250 | 250 | 250 | 250 | - | - | - | - | - | - | - | 250 |
| SIGNS | EA | - | 50 | 50 | 50 | - | 50 | 50 | 50 | 50 | - | - | - | - | - | - | - | 50 |
| PARKING METERS | EA | - | 85 | 85 | 85 | - | 85 | 85 | 85 | 85 | - | - | - | - | - | - | - | 85 |
| FIRE HYDRANTS | EA | - | 250 | 250 | 250 | - | 250 | 250 | 250 | 250 | - | - | - | 250 | - | - | - | 250 |
| LIGHT STANDARDS | EA | - | 500 | 500 | 500 | - | - | - | - | - | - | - | - | - | - | - | - | - |
| PLANTERS | EA | - | 100 | 100 | 100 | - | - | - | - | - | - | - | - | - | - | - | - | - |
| CONCRETE CURBING | LF | - | 1.30 | 1.30 | 1.30 | 1.30 | 1.30 | 1.30 | 1.30 | 1.30 | 1.30 | 1.30 | 1.30 | 1.30 | 1.30 | 1.30 | 1.30 | 1.30 |
| BUILDING BRICK (2 STORIES) | CF | - | - | - | - | 0.15 | - | - | - | - | - | - | - | - | - | - | - | - |
| MASONRY BLDG. CANOPY | CF | - | - | - | - | - | - | - | 0.20 | 0.20 | - | - | - | - | - | - | - | - |
| REMOVE BLDG. FRONT | SF | - | - | - | - | - | - | - | 10 | - | - | - | - | - | - | - | - | - |
| CONCRETE SIDEWALKS | SF | - | - | - | - | - | - | - | - | 0.50 | - | - | - | - | - | - | - | - |
| CLEAR + GRUB | SF | - | - | - | - | - | - | - | - | 0.25 | - | 0.20 | - | - | - | - | - | - |
| BLDG. DEMOLITION | CF | - | - | - | - | - | - | - | - | 0.15 | - | - | - | 0.15 | - | 0.15 | - | - |
| 2'-3' MASONRY WALLS | LF | - | - | - | - | - | - | - | - | - | - | 4 | - | - | - | - | - | - |
| 6' CL. FENCING | LF | - | - | - | - | - | - | - | - | - | - | 1 | - | - | - | - | - | - |
| POLE LIGHTS | EA | - | - | - | - | - | - | - | - | - | - | 300 | - | - | - | - | - | - |
| SERVICE STATION | L.S. | - | - | - | - | - | - | - | - | - | - | - | 10,000 | - | - | - | - | - |
| 2. EARTHWORK | | | | | | | | | | | | | | | | | | |
| EXCAVATION MACHINE | CY | 4 | 3.30 | 3.30 | 3.30 | 3.30 | 3.30 | 3.30 | 3.30 | 3.30 | 3.30 | 3.30 | 3.30 | 3.30 | 3.30 | 3.30 | 3.30 | 3.30 |
| EXCAVATION HAND | CY | 24 | 24 | 24 | 24 | 24 | 24 | 24 | 24 | 24 | 24 | 24 | 24 | 24 | 24 | 24 | 24 | 24 |
| COMPACTED BALLFILL | CY | 15.75 | 15.75 | 15.75 | 15.75 | 15.75 | 15.75 | 15.75 | 15.75 | 15.75 | 15.75 | 15.75 | 15.75 | 15.75 | 15.75 | 15.75 | 15.75 | 15.75 |
| EXCESS SOIL DISPOSAL | CY | 6 | 5.57 | 5.57 | 5.57 | 5.57 | 5.57 | 5.57 | 5.57 | 6 | 6 | 6 | 5.57 | 6 | 5.57 | 6 | 6 | 5.57 |
| SOLIDIC PILE + LAGGING | SF | 34 | 34 | 34 | 34 | 34 | 34 | 34 | 34 | 34 | 34 | 34 | 34 | 34 | 34 | 34 | 34 | 34 |
| DECKING WALKWAYS/ENTRIES | SF | 6 | 6 | 6 | 6 | 6 | 6 | 6 | 6 | 6 | 6 | 6 | 6 | 6 | 6 | 6 | 6 | 6 |
| DEWATERING | MA. | 2,650 | 2,650 | 2,650 | 2,650 | 2,650 | 2,650 | 2,650 | 2,650 | 2,650 | 2,650 | 2,650 | 2,650 | 2,650 | 2,650 | 2,650 | 2,650 | 2,650 |
| SOLDER STRIPEL/SHALLOW | SF | - | 24 | 24 | 24 | 24 | 24 | 24 | 24 | 24 | 24 | 24 | 24 | 24 | 24 | 24 | 24 | 24 |
| DECKING, ROADWAY | SF | - | 13.72 | 13.72 | 13.72 | 13.72 | 13.72 | 13.72 | 13.72 | 13.72 | 13.72 | 13.72 | 13.72 | 13.72 | 13.72 | 13.72 | 13.72 | 13.72 |
| UNLESS PILING CONT. | CY | - | 800 | - | 800 | - | - | - | 800 | - | - | - | - | - | 800 | - | - | - |

KC 1223 SCRTD/METRO RAIL
ESTIMATE CHECK - STATIONS
UNIT PRICES

3/17/23
2 OF 3

| STATIONS | UNITS | UNION | 1st & HILL | 5th & HILL | 7th & | ALVARADO | VERMONT | NORMANDIE | WESTERN | LEBREA | FAIRFAX | BEVERLY | SANTA MONICA | LEBREA | HOLLYWOOD | UNIVERSAL CITY | LANKESHIM |
|--------------------------|-------|---------|------------|------------|--------|----------|----------|-----------|----------|----------|----------|---------|--------------|--------|-----------|----------------|-----------|
| | | STATION | | | FLOWER | WILSHIRE | WILSHIRE | WILSHIRE | WILSHIRE | WILSHIRE | WILSHIRE | FAIRFAX | FAIRFAX | SUNSET | CAHUENGA | | |
| 2. EARTHWORK (Cont'd) | | | | | | | | | | | | | | | | | |
| UNDERPINNING - JACKED | LF | - | - | 50- | - | - | - | - | - | - | - | - | - | - | - | - | - |
| 3. CONCRETE WORK | | | | | | | | | | | | | | | | | |
| A. FORMWORK (1 USE) | | | | | | | | | | | | | | | | | |
| WALLS to 8'0" | SF | 4.98 | 4.98 | 4.98 | 4.98 | 4.98 | 4.98 | 4.98 | 4.98 | 4.98 | 4.98 | 4.98 | 4.98 | 4.98 | 4.98 | 4.98 | 4.98 |
| WALLS to 8'0"-16'0" | SF | 6.27 | 6.27 | 6.27 | 6.27 | 6.27 | 6.27 | 6.27 | 6.27 | 6.27 | 6.27 | 6.27 | 6.27 | 6.27 | 6.27 | 6.27 | 6.27 |
| WALLS >16'0" | SF | 7.39 | 7.39 | 7.39 | 7.39 | 7.39 | 7.39 | 7.39 | 7.39 | 7.39 | 7.39 | 7.39 | 7.39 | 7.39 | 7.39 | 7.39 | 7.39 |
| ELEV SLAB WALLS/MEZZ | SF | 6.40 | 6.40 | 6.40 | 6.40 | 6.40 | 6.40 | 6.40 | 6.40 | 6.40 | 6.40 | 6.40 | 6.40 | 6.40 | 6.40 | 6.40 | 6.40 |
| ELEV SLAB - LIGHT | SF | 3.92 | 3.92 | 3.92 | 3.92 | 3.92 | 3.92 | 3.92 | 3.92 | 3.92 | 3.92 | 3.92 | 3.92 | 3.92 | 3.92 | 3.92 | 3.92 |
| ELEV SLAB - HEAVY | SF | 5.05 | 5.05 | 5.05 | 5.05 | 5.05 | 5.05 | 5.05 | 5.05 | 5.05 | 5.05 | 5.05 | 5.05 | 5.05 | 5.05 | 5.05 | 5.05 |
| ELEV SLAB - EDGE | SF | 3.00 | 3.00 | 3.00 | 3.00 | 3.00 | 3.00 | 3.00 | 3.00 | 3.00 | 3.00 | 3.00 | 3.00 | 3.00 | 3.00 | 3.00 | 3.00 |
| GRADE SLAB/RAIN SLOTS | SF | 3.00 | 3.00 | 3.00 | 3.00 | 3.00 | 3.00 | 3.00 | 3.00 | 3.00 | 3.00 | 3.00 | 3.00 | 3.00 | 3.00 | 3.00 | 3.00 |
| COLUMNS/PILLARS | SF | 5.92 | 5.92 | 5.92 | 5.92 | 5.92 | 5.92 | 5.92 | 5.92 | 5.92 | 5.92 | 5.92 | 5.92 | 5.92 | 5.92 | 5.92 | 5.92 |
| BEAMS - SIDES | SF | 5.92 | 5.92 | 5.92 | 5.92 | 5.92 | 5.92 | 5.92 | 5.92 | 5.92 | 5.92 | 5.92 | 5.92 | 5.92 | 5.92 | 5.92 | 5.92 |
| BEAMS - BOTTOMS | SF | 7.25 | 7.25 | 7.25 | 7.25 | 7.25 | 7.25 | 7.25 | 7.25 | 7.25 | 7.25 | 7.25 | 7.25 | 7.25 | 7.25 | 7.25 | 7.25 |
| BLAST SHAFT WALLS | SF | 7.39 | 7.39 | 7.39 | 7.39 | 7.39 | 7.39 | 7.39 | 7.39 | 7.39 | 7.39 | 7.39 | 7.39 | 7.39 | 7.39 | 7.39 | 7.39 |
| ROOF - MEZZ | SF | - | 5.05 | 5.05 | 5.05 | - | 5.05 | - | 5.05 | - | 5.05 | - | 5.05 | - | 5.05 | - | 5.05 |
| ELEV SLABS | SF | - | - | - | - | - | - | 4.45 | - | - | - | - | - | - | - | - | 4.45 |
| INTERIOR ANCILLARY WALLS | SF | - | - | - | - | - | - | - | 7.39 | - | - | - | - | - | - | - | - |
| B. CONCRETE-IN-PLACE | | | | | | | | | | | | | | | | | |
| WALLS ≤ 15" THICK | CY | 23.50 | 23.50 | 23.50 | 23.50 | 23.50 | 23.50 | 23.50 | 23.50 | 23.50 | 23.50 | 23.50 | 23.50 | 23.50 | 23.50 | 23.50 | 23.50 |
| WALLS > 15" THICK | CY | 21- | 21- | 21- | 21- | 21- | 21-* | 21- | 21- | 21- | 21- | 21- | 21- | 21- | 21- | 21- | 21- |
| ELEVATED SLABS | CY | 15.10 | 15.10 | 15.10 | 15.10 | 15.10 | 15.10 | 15.10 | 15.10 | 15.10 | 15.10 | 15.10 | 15.10 | 15.10 | 15.10 | 15.10 | 15.10 |
| GRADE SLABS | CY | 13.55 | 13.55 | 13.55 | 13.55 | 13.55 | 13.55 | 13.55 | 13.55 | 13.55 | 13.55 | 13.55 | 13.55 | 13.55 | 13.55 | 13.55 | 13.55 |
| COLUMNS/PILLARS | CY | 19.60 | 19.60 | 19.60 | 19.60 | 19.60 | 19.60 | 19.60 | 19.60 | 19.60 | 19.60 | 19.60 | 19.60 | 19.60 | 19.60 | 19.60 | 19.60 |
| BEAMS | CY | 37 | - | - | - | - | 44- | 37- | 37- | 37- | 37- | 37- | 37- | 37- | 37- | 37- | 37- |
| BLAST SHAFT WALLS | CY | 23.50 | - | - | - | - | 21- | 21- | 21- | 21- | 21- | 21- | - | 21- | 21- | 21- | 21- |
| 4000 PSI CONCRETE | CY | 52- | 52- | 52- | 52- | 52- | 52- | 52- | 52- | 52- | 52- | 52- | 52- | 52- | 52- | 52- | 52- |
| BEAMS - LARGE | CY | - | 44- | 44- | 44- | - | - | - | - | - | - | - | - | - | - | - | - |
| - SMALL | CY | - | 44- | 44- | 30- | - | - | - | - | - | - | - | - | - | - | - | - |
| ELEV SLAB WALL | CY | - | - | - | - | - | - | 23.50 | - | 21- | 23.50 | - | 23.50 | - | - | - | 23.50 |
| C. REBAR | LB | 0.88 | 0.88 | 0.88 | 0.88 | 0.88 | 0.88 | 0.88 | 0.88 | 0.88 | 0.88 | 0.88 | 0.88 | 0.88 | 0.88 | 0.88 | 900-* |
| D. CURING | SF | 0.25 | 0.25 | 0.25 | 0.25 | 0.25 | 0.25 | 0.25 | 0.25 | 0.25 | 0.25 | 0.25 | 0.25 | 0.25 | 0.25 | 0.25 | 0.25 |

*7th & Flower, Grade Slab EST. not extended.

*Vermont/Wilshire, Walls > 15" thick EST. not extended

900-* Lankeshim Rebar calculated in tons.

KC 1223 SCRTD/METRO RAIL
ESTIMATE CHECK - STATIONS
UNIT PRICES

3/17/83
3 OF 3

| STATIONS | UNITS | UNION STATION | 1st + HILL | 5th + HILL | 7th + FLOWER | ALVARADO WILSHIRE | VERMONT WILSHIRE | NORMANDIE WILSHIRE | WESTERN WILSHIRE | LEBREA WILSHIRE | FAIRFAX WILSHIRE | BEVERLY FAIRFAX | SANTA MONICA | LEBREA SUNSET | HOLLYWOOD CAHUENGA | UNIVERSAL CITY | LANKERSHIM | |
|---------------------------|-------|---------------|------------|------------|--------------|-------------------|------------------|--------------------|------------------|-----------------|------------------|-----------------|--------------|---------------|--------------------|----------------|------------|--|
| 3. CONCRETE WORK (Cont'd) | | | | | | | | | | | | | | | | | | |
| F. FINISHING | | | | | | | | | | | | | | | | | | |
| TRONEL | SF | 0.24 | 0.24 | 0.24 | 0.24 | 0.24 | 0.24 | 0.24 | 0.24 | 0.24 | 0.24 | 0.24 | 0.24 | 0.24 | 0.24 | 0.24 | 0.24 | 0.24 |
| FLOAT | SF | 0.29 | 0.29 | 0.29 | 0.29 | 0.29 | 0.29 | 0.29 | 0.29 | 0.29 | 0.29 | 0.29 | 0.29 | 0.29 | 0.29 | 0.29 | 0.29 | 0.29 |
| PATCH/RUB | SF | 0.21 | 0.21 | 0.21 | 0.21 | 0.21 | 0.21 | 0.21 | 0.21 | 0.21 | 0.21 | 0.21 | 0.21 | 0.21 | 0.21 | 0.21 | 0.21 | 0.21 |
| SANDBLAST | SF | 0.59 | 0.59 | 0.59 | 0.59 | 0.59 | 0.59 | 0.59 | 0.59 | 0.59 | 0.59 | 0.59 | 0.59 | 0.59 | 0.59 | 0.59 | 0.59 | 0.59 |
| 4. WATERPROOFING | | | | | | | | | | | | | | | | | | |
| 5/16" BENTONITE | SF | 0.26 | 0.26 | 0.26 | 0.26 | 0.26 | 0.26 | 0.26 | 0.26 | 0.26 | 0.26 | 0.26 | 0.26 | 0.26 | 0.26 | 0.26 | 0.26 | 0.26 |
| WATERSTOP | LF | 6.52 | 6.52 | 6.52 | 6.52 | 6.52 | 6.52 | 6.52 | 6.52 | 6.52 | 6.52 | 6.52 | 6.52 | 6.52 | 6.52 | 6.52 | 6.52 | 6.52 |
| JOINT PACKING | LF | 5.60 | 5.60 | 5.60 | 5.60 | 5.60 | 5.60 | 5.60 | 5.60 | 5.60 | 5.60 | 5.60 | 5.60 | 5.60 | 5.60 | 5.60 | 5.60 | 5.60 |
| 5. SITE RESTORATION | | | | | | | | | | | | | | | | | | |
| AC PAVING | SF | 1.28 | 1.28 | 1.28 | 1.28 | 1.28 | 1.28 | 1.28 | 1.28 | 1.28 | 1.28 | 1.28 | 1.28 | 1.28 | 1.28 | 1.28 | 1.28 | 1.28 |
| CONCRETE PAVING | SF | 2.20 | - | - | - | - | - | 2.20 | - | 2.20 | 3.20 | - | - | 2.20 | 2.20 | 2.20 | 2.20 | 2.20 |
| RR. CANOPY | SF | 85- | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| RR. TRACK + BALLAST | LF | 100- | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| SEAL BLDG. WALL | SF | 20- | - | - | - | - | - | - | - | - | 1.20 | - | - | - | - | - | - | - |
| LANDSCAPING | SF | 2- | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - |
| CONCRETE SIDEWALKS | SF | - | 1.87 | 1.87 | 1.87 | 1.87 | 1.87 | - | 1.87 | - | 2- | - | - | - | - | - | - | - |
| CONCRETE CURBING | LF | - | 9.40 | 9.40 | 9.40 | 9.40 | 9.40 | 9.40 | 9.40 | 9.40 | 9.40 | 9.40 | 9.40 | 9.40 | 9.40 | 9.40 | 9.40 | 9.40 |
| SIGNS-REINSTALL | EA | - | 100- | 100- | 100- | - | 100- | 100- | 100- | 100- | - | - | - | - | - | - | - | 100- |
| TRAFFIC SIGNALS " | EA | - | 600- | 600- | 600- | - | 600- | 600- | 600- | 600- | - | - | 600- | - | - | - | - | 600- |
| STREET LIGHTS " | EA | - | 600- | 600- | 600- | - | 600- | 600- | 600- | 600- | - | - | 600- | - | - | - | - | 600- |
| PARKING METERS " | EA | - | 100- | 100- | 100- | - | 100- | 100- | 100- | 100- | - | - | 100- | - | - | - | - | 100- |
| MANHOLES | EA | - | - | 1500- | 1500- | - | 1500- | 1500- | 1500- | 1500- | - | - | - | - | - | - | - | 1500- |
| FIRE HYDRANTS | EA | - | - | 1000- | 1000- | - | 1000- | 1000- | 1000- | 1000- | - | - | 1000- | - | - | - | - | 1000- |
| LIGHT STANDARDS | EA | - | - | 600- | 600- | - | - | - | - | - | - | - | - | - | - | - | - | - |
| MISC. | % | LS | LS | LS | LS | LS | - | - | - | LS | LS | LS | LS | LS | LS | - | - | - |
| PARKING LOT STRIPING | SF | - | - | - | - | - | - | - | - | - | 0.20 | 0.20 | - | - | - | - | - | 0.20 |
| PARKING LOT LIGHTING | EA | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | 3000- |
| PARKING LOT BUMPERS | EA | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | 25- |
| PARKING STRUCTURE | CAR. | - | - | - | - | - | - | - | - | - | - | 6320- | - | - | - | - | - | 6320- |
| 6. TRAFFIC MAINTENANCE | | | | | | | | | | | | | | | | | | |
| 6" C.I. FENCING | LF | 6- | 5.25 | 5.25 | 5.25 | 5.25 | 5.25 | 6 | 5.25 | 6 | 6 | 6 | 6 | 6 | 6 | 6 | 6 | 6 |
| MISC. | % | LS | LS | LS | LS | LS | LS | LS | LS | LS | LS | LS | LS | LS | LS | LS | LS | LS |
| 7. UTILITIES SUPPORT | | | | | | | | | | | | | | | | | | |
| | % | 5 | 5 | 5 | 5 | 1330* | 5 | 5 | 5 | 5 | 5 | 3 | 5 | 5 | 2.5 | 1 | 5 | *ALVARADO'S WILSHIRE CALCULATED BY LF (UNIT) |
| 8. MOBILIZATION | | | | | | | | | | | | | | | | | | |
| | % | 4 | 4 | 4 | 4 | 4 | 4 | 4 | 4 | 4 | 4 | 4 | 4 | 4 | 4 | 4 | 4 | 4 |

KC 1222 - SCRTD METRO RAIL
ESTIMATE CHECK - STATIONS
QUANTITIES

3/22/83
2 OF 3

| STATIONS | UNITS | UNION | 1st HILL | 5th HILL | 7th | ALVARADO | VERMONT | NORMANDIE | WESTERN | LEBREA | FAIRFAX | BEVERLY | SANTA MONICA | LEBREA | HOLLYWOOD | UNIVERSAL CITY | LANKERSHIM | TOTAL | |
|------------------------------|-------|---------|----------|----------|---------|----------|----------|-----------|----------|----------|----------|---------|--------------|---------|-----------|----------------|------------|------------|----------|
| | | STATION | 1st HILL | 5th HILL | FLOWER | WILSHIRE | WILSHIRE | WILSHIRE | WILSHIRE | WILSHIRE | WILSHIRE | FAIRFAX | FAIRFAX | MONICA | SUNSET | CAHUENGA | CITY | LANKERSHIM | TOTAL |
| 2. EARTHWORK (Cont'd) | | | | | | | | | | | | | | | | | | | |
| Underpinning - Jacked | LF | - | - | 6295 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | 6295 |
| 3. CONCRETE WORK | | | | | | | | | | | | | | | | | | | |
| A. FORMWORK (1 use) | | | | | | | | | | | | | | | | | | | |
| Walls to 8'0" | SF | 14550 | 51322 | 55144 | 14553 | 15197 | 14874 | 14550 | 14550 | 14550 | 29100 | 14700 | 14550 | 14550 | 14550 | 14550 | 14550 | 14550 | 325840 |
| Walls 8'0" to 16'0" | SF | 12400 | 62861 | 70288 | - | - | - | 13440 | 9940 | 8650 | 10560 | - | 15008 | 8710 | - | - | - | 13440 | 220297 |
| Walls > 16'0" | SF | 98600 | 80764 | 83396 | 59138 | 18483 | 48350 | 58640 | 52680 | 58250 | 81160 | 33885 | 53522 | 50370 | 46355 | 41147 | 58640 | 58640 | 722980 |
| Elev. Slab Walls/Mezz. | SF | 1525 | 11862 | 11862 | 7299 | - | - | 3885 | 4050 | 5150 | 22400 | 1150 | 3833 | 1200 | 4200 | 600 | 3885 | 3885 | 77901 |
| Elev. Slab - Light | SF | 14400 | 40384 | 43392 | 24020 | 15040 | 14720 | - | 21060 | 52922 | 14400 | 14400 | 30876 | 52340 | 33804 | 31600 | - | - | 372558 |
| Elev. Slab - Heavy | SF | 54950 | 34170 | 37121 | - | 25694 | - | - | - | 30932 | 58430 | 26670 | - | 32340 | 29760 | 27526 | - | - | 359573 |
| Elev. Slab - Edge | SF | 900 | 2848 | 3036 | 900 | 900 | 920 | 900 | 900 | 900 | 900 | 1370 | 900 | 900 | 1270 | 900 | 900 | 900 | 19348 |
| Grade Slab/Drain Slots | SF | 720 | 1262 | 1356 | 740 | 470 | 567 | 672 | 660 | 660 | 935 | 685 | 680 | 670 | 635 | 630 | 672 | 672 | 12034 |
| Columns/Pillars | SF | 20450 | 29590 | 33990 | 16417 | 15045 | - | 63773 | 40220 | 62634 | 40372 | 17330 | 61332 | 72633 | 67155 | 67221 | 63773 | 63773 | 671255 |
| Beams-Sides | SF | 15445 | 72884 | 95651 | 35928 | - | 17600 | 34420 | 18304 | 41312 | 94215 | 54347 | 41275 | 59825 | 40558 | 39123 | 34820 | 34820 | 671347 |
| Beams-Bottoms | SF | 10400 | 18559 | 23631 | 13696 | - | 3204 | 14670 | 12452 | 14671 | 22142 | 13412 | 14857 | 14550 | 14305 | 13947 | 14690 | 14690 | 219186 |
| Blast Shaft Walls | SF | 13600 | - | 31635 | 9440 | 13860 | 17508 | 13600 | 35100 | 13600 | 75500 | 13600 | 13600 | 13600 | 13600 | 14300 | 13600 | 13600 | 306143 |
| Roof & Mezz. | SF | - | 40887 | 51888 | 62521 | - | 37800 | - | 35125 | - | 24000 | - | 31870 | - | - | - | - | - | 289491 |
| Elev. Slab | SF | - | - | - | - | - | - | 61250 | - | - | - | - | - | - | - | - | - | 61250 | 122500 |
| Interior Ancillary Walls | SF | - | - | - | - | - | - | - | 36800 | - | - | - | - | - | - | - | - | - | 36800 |
| B. CONCRETE-IN-PLACE | | | | | | | | | | | | | | | | | | | |
| Walls ≤ 15" Thick | CY | 275 | 2191 | 2316 | 400 | 575 | 267 | 544 | 1086 | 1424 | 943 | 272 | 544 | 578 | 596 | 590 | 544 | 544 | 15145 |
| Walls > 15" Thick | CY | 7647 | 12837 | 15699 | 9287 | 1048 | 2820 | 3387 | 3772 | 3947 | 18090 | 4402 | 4038 | 4366 | 3219 | 3176 | 3337 | 3337 | 103242 |
| Elevated Slabs | CY | 6746 | 8375 | 9541 | 5402 | 6310 | 4840 | 4662 | 4731 | 5124 | 10080 | 1622 | 4708 | 5019 | 4532 | 4434 | 173 | 173 | 86349 |
| Grade Slabs | CY | 10453 | 7890 | 12268 | 8920 | 6029 | 10475 | 8624 | 8733 | 9140 | 10679 | 17074 | 8727 | 8855 | 8150 | 8085 | 8624 | 8624 | 142776 |
| Columns/Pillars | CY | 552 | 818 | 957 | 388 | 692 | 1330 | 3708 | 2043 | 3641 | 1142 | 350 | 3752 | 3807 | 3503 | 3476 | 3708 | 3708 | 33867 |
| Beams | CY | 704 | - | - | - | - | 1111 | 1846 | 2024 | 1813 | 3216 | 1448 | 1624 | 1332 | 1796 | 1752 | 1846 | 1846 | 21222 |
| Blast Shaft Walls | CY | 615 | - | - | - | 1310 | - | 615 | 1842 | 615 | 3565 | 268 | - | 615 | 615 | 615 | 615 | 615 | 11920 |
| 4000 PSI Conc. | CY | 29192 | 34311 | 43582 | 25843 | 15964 | 20723 | 23559 | 24531 | 25819 | 42280 | 16136 | 23479 | 25072 | 22411 | 22150 | 23559 | 23559 | 424411 |
| Beams - Large | CY | - | 1047 | 1494 | 1041 | - | - | - | - | - | - | - | - | - | - | - | - | - | 3582 |
| Beams - Small | CY | - | 1053 | 1307 | 605 | - | - | - | - | - | - | - | - | - | - | - | - | - | 2965 |
| Elev. Slab Wall | CY | - | - | - | - | - | - | 173 | - | 85 | 565 | - | 86 | - | - | - | - | - | 909 |
| C. REBAR | | | | | | | | | | | | | | | | | | | |
| | LB | 5838400 | 7205600 | 9184950 | 5168600 | 3192800 | 4144600 | 4711800 | 4802600 | 5163800 | 9656000 | 3427200 | 4695800 | 5014400 | 4482200 | 4430000 | 4712000 | 4712000 | 15630750 |
| D. CURING | | | | | | | | | | | | | | | | | | | |
| | SF | 284190 | 395400 | 628364 | 220800 | 149225 | 219350 | 310900 | 277432 | 382447 | 455000 | 218078 | 356300 | 389410 | 257130 | 153900 | 370900 | 370900 | 5189326 |

KC 1223 SORTIMETRO RAIL
ESTIMATE CHECK - STATIONS
QUANTITIES

3/22/83
3 OF 3

| STATIONS | UNITS | UNION | 1st * HILL | 5th * HILL | 7th * FLOWER | ALVARADO | VERMONT | NORMANDIE | WESTERN | LEBREA | FAIRFAX | BEVERLY | MONICA | LEBREA | HOLLYWOOD | UNIVERSAL | LANKERSHIM | TOTAL | |
|----------------------------------|-------|---------|------------|------------|--------------|----------|----------|-----------|----------|----------|----------|---------|---------|--------|-----------|-----------|------------|-------|---------|
| | | STATION | | | | WILSHIRE | WILSHIRE | WILSHIRE | WILSHIRE | WILSHIRE | WILSHIRE | FAIRFAX | FAIRFAX | SUNSET | CAHUENGA | CITY | | | |
| 3. CONCRETE WORK (Cont'd) | | | | | | | | | | | | | | | | | | | |
| E. FINISHING | | | | | | | | | | | | | | | | | | | |
| Trowel | SF | 139950 | 63000 | 117689 | 32650 | 28200 | 43660 | 47500 | 53834 | 49220 | 80730 | 33800 | 4800 | 49837 | 48917 | 47380 | 47500 | | 932667 |
| Float | SF | 38610 | 39600 | 57667 | 46400 | 30400 | 37800 | 55650 | 42683 | 57200 | 120250 | 42750 | 3950 | 59800 | 55033 | 54600 | 55650 | | 858243 |
| Patch/Rub | SF | 152600 | 313400 | 407356 | 64800 | 8500 | 11868 | 185700 | 128630 | 207210 | 298547 | 161544 | 7100 | 311187 | 186700 | 8070 | 183700 | | 2547172 |
| Sandblast | SF | 152600 | 39930 | 45652 | 31150 | 41700 | 114221 | 200750 | 87451 | 190220 | 298547 | 154794 | 23960 | 194137 | 183442 | 8070 | 200750 | | 2153474 |
| 4. WATERPROOFING | | | | | | | | | | | | | | | | | | | |
| 5/16" Bentonite | SF | 49580 | 264422 | 159250 | 148380 | 47000 | 99374 | 111721 | 109900 | 109833 | 120700 | 85800 | 3980 | 114553 | 105900 | 105113 | 111721 | | 1856107 |
| Waterstop | LF | 2880 | 8328 | 15910 | 5700 | 2140 | 2535 | 3206 | 2900 | 2900 | 6000 | 2990 | 3980 | 3019 | 2800 | 2780 | 3206 | | 68274 |
| Joint Packing | LF | 4250 | 5440 | 7018 | 6800 | 2800 | 4390 | 10775 | 4850 | 10572 | 8075 | 4172 | 3903 | 11063 | 10182 | 10101 | 10775 | | 121576 |
| 5. SITE RESTORATION | | | | | | | | | | | | | | | | | | | |
| AC Paving | SF | 28500 | 44810 | 56550 | 49800 | 33150 | 71300 | 58600 | 51200 | 53380 | 199800 | 89200 | 3150 | 68000 | 41300 | 252000 | 58600 | | 1241750 |
| Conc. Paving | SF | 18500 | - | - | - | - | - | 260 | 2000 | 250 | 2200 | - | - | 18700 | 7700 | 100000 | 260 | | 144870 |
| RR Canopy | SF | 18400 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | | 18400 |
| RR Track & Ballast | LF | 3590 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | | 3590 |
| Seal Bldg. Wall | SF | 1800 | - | - | - | - | - | - | - | - | - | - | - | - | - | - | - | | 1800 |
| Landscaping | SF | 5000 | - | - | - | - | - | - | - | - | 102700 | - | - | - | - | LS | - | | 107700 |
| Conc. Sidewalks | SF | - | 43025 | 4825 | 40960 | 7975 | 2050 | - | - | - | 61000 | - | - | - | - | - | - | | 129335 |
| Conc. Curbing | LF | - | 1010 | 1855 | 1590 | 360 | 2450 | 1840 | 1540 | 1460 | 6150 | 2170 | 250 | 1560 | 650 | 7400 | 1840 | | 32125 |
| Signs - Reinstall | EA | - | 3 | 4 | 8 | - | 5 | 15 | 5 | 7 | - | - | - | - | - | - | 15 | | 62 |
| Traffic Signals | EA | - | 4 | 8 | 16 | - | - | 10 | 8 | 4 | - | - | 2 | - | - | LS | 10 | | 62 |
| Street Lights | EA | - | 11 | 14 | 40 | - | 6 | 18 | 14 | 12 | - | - | 2 | - | - | - | 18 | | 155 |
| Parking Meters | EA | - | 3 | 10 | 5 | - | 24 | 60 | 11 | 15 | - | - | - | - | - | - | 60 | | 138 |
| Manholes | EA | - | - | 13 | 12 | - | 4 | 7 | 36 | 4 | - | - | - | - | - | - | 11 | | 83 |
| Fire Hydrants | EA | - | - | 3 | 4 | - | 3 | 5 | 6 | 4 | - | - | 1 | - | - | - | 5 | | 31 |
| Light Standards | EA | - | - | 8 | 8 | - | - | - | - | - | - | - | - | - | - | - | - | | 16 |
| Miscellaneous | % | LS | LS | LS | LS | LS | - | - | - | LS | LS | LS | S | LS | LS | LS | LS | | LS |
| Parking Lot Striping | SF | - | - | - | - | - | - | - | - | - | 800 | 220 | - | - | - | 9000 | - | | 10220 |
| Parking Lot Lighting | EA | - | - | - | - | - | - | - | - | - | - | - | - | - | - | 26 | - | | 26 |
| Parking Lot Bumpers | EA | - | - | - | - | - | - | - | - | - | - | - | - | - | - | 550 | - | | 550 |
| Parking Structure | CAR | - | - | - | - | - | - | - | - | - | - | 650 | - | - | - | 1700 | - | | 2350 |
| 6. TRAFFIC MAINTENANCE | | | | | | | | | | | | | | | | | | | |
| 6' C.L. Fencing | LF | 1500 | 1550 | 1700 | 1860 | 1140 | 2140 | 1540 | 1760 | 1560 | 2160 | 1610 | 660 | 2250 | 2240 | 3700 | 1540 | | 29910 |
| Miscellaneous | % | LS | LS | LS | LS | LS | LS | LS | LS | LS | LS | LS | S | LS | LS | LS | LS | | LS |
| 7. UTILITIES SUPPORT | | | | | | | | | | | | | | | | | | | |
| | % | LS | LS | LS | LS | 60(LF) | LS | LS | LS | LS | LS | LS | S | LS | LS | LS | LS | | 60 (LF) |
| 8. MOBILIZATION | | | | | | | | | | | | | | | | | | | |
| | % | LS | LS | LS | LS | LS | LS | LS | LS | LS | LS | LS | S | LS | LS | LS | LS | | LS |

| | | |
|-------------|----------|------|
| Prepared by | Initials | Date |
| Approved by | | |

SCPTD METRO RAIL PROJECT TUNNEL DIRECT COST SUMMARY & COMPARISON - ALL (7) REACHES

| DESCRIPTION | 1 | | 2 | | 3 | | 4 | | 5 | | 6 | | 7 | | 8 | | 9 | | 10 | |
|---|--------------|-----------------|-----------|-------------------|------------------|-----------|------------------|-----------|------------------|-----------|------------------|-----------|------------------|-----------|------------------|-----------|------------------|-----------|------------------|-----------|
| | EST QUANTITY | EST. QUAN. UNIT | EST. U.C. | KELLOGG EXTENSION | U.C./L.F. TUNNEL | DMJM/PBOD | U.C./L.F. TUNNEL | DMJM/PBOD | U.C./L.F. TUNNEL | DMJM/PBOD | U.C./L.F. TUNNEL | DMJM/PBOD | U.C./L.F. TUNNEL | DMJM/PBOD | U.C./L.F. TUNNEL | DMJM/PBOD | U.C./L.F. TUNNEL | DMJM/PBOD | U.C./L.F. TUNNEL | DMJM/PBOD |
| TUNNEL EXCAV., LINING & GROUT | (200800) | DMJM/PBOD | | | | | | | | | | | | | | | | | | |
| LABOR | 174210 | KL. LF. TUNNEL | 162000 | 85212 | 1067.68 | 108864 | 134733 | (23652) | (279.62) | | | | | | | | | | | |
| PERMANENT MATERIAL | 159620 | LF. TUNNEL | 895 | 79106 | 991.18 | 86245 | 1067.39 | (7139) | (76.21) | | | | | | | | | | | |
| EQUIPMENT (RENTAL) | 1 | L.S. | 43987000 | 43987 | 551.15 | 52800 | 653.46 | (8813) | (102.31) | | | | | | | | | | | |
| (EQUIP. MAINT. MAT'L) | 1 | L.S. | 10912000 | 10912 | 136.73 | | | 10912 | 136.73 | | | | | | | | | | | |
| ELEC., FUEL, LUBES | 1 | L.S. | 10481000 | 10481 | 131.33 | 2016 | 24.75 | 8465 | 106.78 | | | | | | | | | | | |
| TUNNEL UTILITY LINES & TRACK | 159620 | LF. TUNNEL | 63 | 10091 | 126.44 | | | 10091 | 126.44 | | | | | | | | | | | |
| SMALL TOOLS & SUPPLIES | 3157200 | MAN HOURS | 1 | 3157 | 39.55 | | | 3157 | 39.55 | | | | | | | | | | | |
| MUCK DISPOSAL | 2674000 | C.Y. | 6 | 16170 | 202.60 | 16173.3 | 200.16 | (33) | 2.44 | | | | | | | | | | | |
| CROSS PASSAGES | 146 | EACH | 56250 | 8213 | 102.91 | 15100 | 186.88 | (6887) | (83.97) | | | | | | | | | | | |
| STEEL LINER (REACHES 5 & 6) | 17050 | LF. TUNNEL | 1029 | 17560 | 270.02* | 17931 | 221.92* | (371) | (1.70) | | | | | | | | | | | |
| FINISH TUNNEL | 159620 | LF. TUNNEL | 115 | 18356 | 230.00 | 8080 | 100.00 | 10276 | 130.00 | | | | | | | | | | | |
| GROUND H ₂ O PROGRAM (REACH 2) | 1 | L.S. | 500000 | 500 | 6.16* | 500 | 6.19* | | 0.07 | | | | | | | | | | | |
| SHIELD PIT (REACH 12) | 1 | EACH | 391000 | 391 | 4.70* | 391*** | 4.84* | | 0.06 | | | | | | | | | | | |
| GENERAL EXPENSES | | | | 1M ON | | 25254.5 | 312.56** | (25254.5) | (312.56) | | | | | | | | | | | |
| TOTAL DIRECT COST | | | | 304136 | 301075 | 333354.8 | 4125.68 | (29210.8) | (314.93) | | | | | | | | | | | |

-87-

* NOT NEARLY FULL MOJ SINCE THESE UNIT COSTS REPRESENT AN AVERAGE IMPACT TO ALL TUNNEL FOOTAGE WHEN IN FACT THE COSTS FOR THESE ITEMS ARE INTENDED FOR SPECIFIC REACHES

** THE UNIT COST FOR GENERAL EXPENSES IS REMOVED FROM TOTAL UNIT COST FOR DMJM/PBOD TO MAKE IT MORE CONSISTENT WITH KLS UNIT COST VARIANCE IS \$(2.37)/LF OR (.06)%

*** DMJM/PBODS EST OF SHIELD PIT COST WAS LEFT OUT OF THEIR COST ACCLUM & SUMMARY

To

Date 3-22-83

From HEB

Subject SC RTD METRO RAIL
TUNNEL GEOLOGY

- A, (A₂) SAND, GRAVEL, SOME COBBLES & BOULDERS IN 2 & 8;
PRIMARILY DENSE, BUT RANGES FROM LOOSE TO VERY DENSE.
- A₁(A₂) CLAYS, SILTS, COHESIVE SANDS; PRIMARILY STIFF BUT RANGES
FROM FIRM TO HARD.
- C FERMANNO & PUENTE FORM. CLAY STONE, SILTSTONE &
SANDSTONE; PRIMARILY LOW HARDNESS, W/ RAK TO MOD. STRONG.
- SP SAN PEDRO FORM. PREDOM. CLEAN COHESIVE SANDS BUT INCL.
LAYERS OF SILT & GRAVELS, MISO DENSE TO VERY DENSE, OIL STAR IN REACHS
- 1-5 37% INTRUSIVE BASALT, HARD - MASSIVE MOD. JOINTED; 63% ARM HARD
CONGLOMERATE, SANDSTONE, & SILTSTONE, MOD. BLOCKY & SEAMY TO HARD
+ STRATIFIED

| | FROM STA | TO STA | LF |
|-----------------|----------|-------------|--------------------------------------|
| <u>REACH 2</u> | .113+12 | 146+18 | 3306 |
| | 152+49 | 171+10 | 1861 |
| | 177+41 | 198+98 | 2157 |
| | | | <u>7324 CHK</u> |
| <u>REACH 5</u> | 206+38 | 254+39 | 4801 |
| | 263+89 | 308+18 | 4429 |
| | 318+45 | 343+83 | 2538 |
| | | | <u>11768 CHK</u> |
| <u>REACH 6</u> | 350+55 | 365+27 | 1472 |
| | 371+87 | 461+94 | 9007 |
| | | | <u>10479 CHK</u> |
| <u>REACH 8</u> | 478+64 | 503+32 | 2468 |
| | 517+27 | 561+64 | 4437 |
| | 500+00 | 503+32 STUB | 332 |
| | | | <u>7237 CHK</u> |
| <u>REACH 10</u> | 573+09 | 622+45 | 4936 |
| | 629+25 | 692+45 | 6320 |
| | 703+95 | 753+01 | 4906 |
| | | | <u>16162 CHK</u> |
| <u>REACH 12</u> | 771+86 | 933+40 | 16154 CHK |
| <u>REACH 14</u> | 939+70 | 1046+58 | 10688 CHK |
| | | | <u>79812 OK 2 LF REMAINING FOR R</u> |



5601 South Broadway
Littleton, Colorado 80121
303/794/1818

To

Date 3-22-83

From HEB

Subject SC RTD METRO RAIL
TUNNEL GEOLOGY

| <u>FROM STA</u> | <u>TO STA</u> | <u>A₁A₂</u> | <u>C</u> | <u>A₂</u> | <u>SP</u> | <u>I-5</u> | <u>Perched H₂O</u> | <u>Perm. H₂O</u> |
|-----------------|---------------|-----------------------------------|----------|----------------------|-----------|------------|-------------------------------|-----------------------------|
| 110+00 | 122+50 | X _{A₁} | | | | | X | |
| 122+50 | 140+00 | | X | | | | X | X |
| 140+00 | 171+30 | | X | | | | X | |
| 171+30 | 204+20 | X _{A₁} | | | | | | |
| 204+20 | 352+50 | | X | | | | X | |
| 352+50 | 394+00 | | | X | | | X | |
| 394+00 | 398+50 | | | | X | | X | |
| 398+50 | 492+00 | | | X | | | X | |
| 492+00 | 517+00 | | | | X | | X | |
| 517+00 | 594+00 | | | X | | | X | |
| 594+00 | 626+50 | X | | | | | | |
| 626+50 | 678+00 | | | X | | | | |
| 678+00 | 687+00 | X | | | | | | |
| 687+00 | 740+50 | X | | | | | X | |
| 740+50 | 760+00 | X | | | | | | |
| 760+00 | 949+50 | | | | | X | X | |
| 949+50 | 965+00 | X _{A₁} | | | | | X | |
| 965+00 | 1061+50 | X _{A₁} | | | | | | |

KELLOGG CORPORATION
DIRECT COST ESTIMATE

Item Analysis

JOB S C RTD METRO RAIL

DATE 3-22-83

DCE. 6-91-3000 HOECKEL'S 340621

Sheet 1 of 2 Estm. HEB Ckd. _____ ITEM _____

Plan Sheet No. _____ Bid Quantity _____

Spec. Ref. _____ Take-off Quantity _____

Item Desc. LF BY GROUND CONDITION

REACH 2

| | | | | | |
|-----------------------|---|--------------------------------------|--------|-----------------------------------|-------------|
| FROM 113+12 TO 146+18 | 113+12 TO 122+50, A, PERCH H ₂ O | } 938 LF, A, PERCH H ₂ O | } 3095 | | |
| | 122+50 TO 140+00, C, PERM. H ₂ O | | | } 2157 LF, A, NO H ₂ O | } @26 |
| | 140+00 TO 146+18, C, PERCH H ₂ O | | | | |
| FROM 152+49 TO 171+10 | 152+49 TO 171+10, C, PERCH H ₂ O | } 2479 LF, C, PERCH H ₂ O | } @43 | | |
| FROM 177+41 TO 198+98 | 177+41 TO 198+98, A, NO H ₂ O | | | 7324 LF | <u>7324</u> |

REACH 5

| | | | | |
|-----------------------|--|---------------------------------------|---------|-------|
| FROM 206+38 TO 254+39 | 206+38 TO 254+39, C, PERCH. H ₂ O | } 11768 LF, C, PERCH H ₂ O | } 11768 | |
| FROM 263+89 TO 308+18 | 263+89 TO 308+18, C, PERCH. H ₂ O | | | } @43 |
| FROM 318+45 TO 343+83 | 318+45 TO 343+83, C, PERCH. H ₂ O | | | |

REACH 6

| | | | | |
|-----------------------|--|--|--------------|-------------------------------------|
| FROM 350+55 TO 365+27 | 350+55 TO 352+50, C, PERCH. H ₂ O | } 450 LF, SP, PERCH H ₂ O | } 450 LF @26 | |
| | 352+50 TO 365+27, A ₄ , PERCH. H ₂ O | | | } 195 LF, C, PERCH H ₂ O |
| FROM 371+87 TO 461+94 | 371+87 TO 394+00, A ₄ , PERCH. H ₂ O | } 9834 LF, A ₄ , PERCH H ₂ O | | |
| | 394+00 TO 398+50, SP, PERCH. H ₂ O | | 10479 LF | |
| | 398+50 TO 461+94, A ₄ , PERCH H ₂ O | | | |

-90-

KELLOGG CORPORATION
DIRECT COST ESTIMATE

Item Analysis

JOB SC RTD METRO RAIL

DATE 3-22-83

DCE. 8-81-3000 HOECKEL'S 340821

Sheet 2 of 2 Estm. HEB Ckd. _____ ITEM _____

Plan Sheet No. _____ Bid Quantity _____

Spec. Ref. _____ Take-off Quantity _____

Item Desc. LF BY GROUND CONDITION

REACH 8

| | | |
|-----------------------|--|--|
| FROM 478+64 TO 503+22 | 478+64 TO 492+00, A ₄ , PERCH. H ₂ O | } 1464 LF, SP, PERCH. H ₂ O } 1464 @ 26 |
| | 492+00 TO 503+32, SP, PERCH. H ₂ O | |
| FROM 517+27 TO 561+64 | 517+27 TO 561+64, A ₄ , PERCH. H ₂ O | |
| FROM 500+00 TO 503+32 | 500+00 TO 503+32, SP, PERCH. H ₂ O | 7237 LF } 7237 |

REACH 10

| | | | |
|-----------------------|--|--|---|
| FROM 573+09 TO 622+45 | 573+09 TO 594+00, A ₄ , PERCH. H ₂ O | } 2091 LF, A ₄ , PERCH. H ₂ O } 16162 @ 43 | |
| | 594+00 TO 622+45, A ₂ , NO H ₂ O | | |
| FROM 629+25 TO 692+45 | 629+25 TO 678+00, A ₄ , NO H ₂ O | | } 4200 LF, A ₂ , PERCH. H ₂ O } 4996 LF, A ₂ , NO H ₂ O |
| | 678+00 TO 687+00, A ₂ , NO H ₂ O | | |
| | 687+00 TO 692+45, A ₂ , PERCH. H ₂ O | | 16162 LF |
| FROM 703+95 TO 753+01 | 703+95 TO 740+50, A ₂ , PERCH. H ₂ O | } 740+50 TO 753+01, A ₂ , NO H ₂ O | |
| | 740+50 TO 753+01, A ₂ , NO H ₂ O | | |

REACH 12

FROM 771+86 TO 933+40 771+86 TO 933+40, 1-5, PERCH. H₂O } 16154 LF, 1-5, PERCH. H₂O } 16154 @ 43

REACH 14

| | | |
|------------------------|--|---|
| FROM 939+70 TO 1046+58 | 939+70 TO 949+50, 1-5, PERCH. H ₂ O | } 8158 LF, A ₁ , NO H ₂ O } 9708 @ 26 |
| | 949+50 TO 965+00, A ₁ , PERCH. H ₂ O | |
| | 965+00 TO 1046+58, A ₁ , NO H ₂ O | |
| | | 980 LF, 1-5, PERCH. H ₂ O } 10688 LF } 10688 |

To

From

HEB

Subject SC RTD METRO RAIL
TUNNEL PRODUCTION RATE

GENERAL

- ADVANCE RATE IN WET OR DRY SAND OF 2703 LF / HR (UNADJ. AVE.)
- ADVANCE RATE IN PUENTE / FERNANDO OF 40 LF / HR (UNADJ. AVE.)
- ALLOW 45 MIN TO INSTALL 6 PRECAST SEGMENTS (1 RING)
- ALLOW 3 HR / DAY SCHEDULED MAINTENANCE
- ALLOW 1 HR / DAY UNSCHEDULED MAINT., TBM CORRECTION & STANDBY
- ALLOW 1/2 HR / SHIFT CREW CHANGE
- ALLOW 1/2 HR / SHIFT LUNCH BREAK
- ALLOW 2 DAYS / MO MAJOR REALIGNMENT, FIXIT, BAD GROUND, H₂O, PROBE
- ALLOW 6 WKS @ 50% FOR LEARNING CURVE = 3 WKS HOURS FOR GAS
- ALLOW 6 WKS FOR MOLE ASSEMBLY & LAUNCH
- ALLOW 3 DAYS FOR TBM MOOS @ ALLUVIAL / SED. INTERFACES
- ALLOW 3 WKS FOR SKIDDING THEN STA & TURN UNDER
- ALLOW 3 WKS FOR TBM DISMANTLE & REMOVAL

A DRY & WET SAND *** (A₁, A₂, SP)

MACHINE AVAILABILITY (HRS / DAY) =

$$24 - 3 - 1 - (3)(1/2) - (3)(1/2) - (2)(24) / (4.33)(5) = 15 \text{ HRS / DAY}$$

PRODUCTION RATE WITH RING INSTALLATION

ADVANCE MOLE @ 20 MIN / LF
 INSTALL RING = 45 MIN / 3.25 LF = 14 MIN / LF
 TOTAL RATE = 34 MIN / LF
 (60 MIN / HR) (1 LF / 34 MIN) = 1.75 LF / HR

ADVANCE RATE / DAY = (15 HRS / DAY) (1.75 LF / HR) = 26.25 LF / DAY

A PUENTE / FERNANDO ** (A₂, A₂, C, 1-5)

CALL 26 LF / DAY

MACHINE AVAILABILITY = 15 HRS / DAY

PROD. RATE WITH RING INSTALLATION

ADVANCE MOLE @ 10 MIN / LF
 * INSTALL RING = 45 MIN / 4 LF = 11 MIN / LF
 TOTAL RATE = 21 MIN / LF
 (60 MIN / HR) (1 LF / 21 MIN) = 2.86 LF / HR

ADVANCE RATE / DAY = (15 HRS / DAY) (2.86 LF / HR) = 42.86 LF / DAY

CALL 43 LF / DAY

* MAY BE ABLE TO ADVANCE MOLE WITHOUT RING INSTALLATION & IMPROVE ADVANCE RATE SIGNIFICANTLY
 ** USE PUENTE / FERNANDO RATE OF ADVANCE FOR BASSET IN GRACHIZ
 *** USE DRY / WET SAND RATE OF ADVANCE FOR SAN PEDRO FORMATION

To

Date 3-23-83

From

HEB

Subject

SCRTD METRO RAIL
TUNNEL PRODUCTION RATE

GROUT CYCLE

$$\text{GROUT VOL/LE} = \pi (9.835^2 - 9.665^2) / 27 = .386 \text{ CY/LE}$$

$$\text{USE 3 CY PUMP @ 50\%} = 1.5 \text{ CY/HR}$$

$$\text{LE GROUT/HR} = (1.5 \text{ CY/HR}) (1 \text{ LE} / .386 \text{ CY}) =$$

$$3.89 \text{ LE/HR CALL } \underline{4 \text{ LE/HR}}$$

PUMP DURING TBH SCH MAINT & DURING PRODUCTION

21 HRS AVAIL X 4 LE/HR = 84 LE HOUR ADV RATE
BEFORE EXC CYCLE IMPACT
BY GROUT

MAX. AVE. ADV. RATE

DRY / WET SAND

$$\text{MACHINE AVAILABILITY} = 24 - 3 - (3)(\frac{1}{2}) - (3)(\frac{1}{2})$$
$$= 18 \text{ HR/DY}$$

$$\text{ADVANCE RATE ASSUMING NO DELAY FOR RING INSTALLATION}$$
$$= 3 \text{ LE/HR}$$

$$\text{MAX. AVE. RATE ADV/DY} = (18 \text{ HR/DY}) (3 \text{ LE/HR}) = \underline{54 \text{ LE/DY}}$$

PUEENTE/FERNANDO

$$\text{MACHINE AVAILABILITY} = 18 \text{ HR/DY}$$

$$\text{ADV. RATE} = 6 \text{ LE/HR}$$

$$\text{MAX. AVE. RATE ADV/DY} = (18 \text{ HR/DY}) (6 \text{ LE/HR}) = \underline{108 \text{ LE/DY}}$$



5601 South Broadway
Littleton, Colorado 80121

303/794/1818

P1

To

Date 3-24-83

From HEB

SCRTD METRO RAIL
Subject TUNNEL LABOR COST

WORK WEEKS OF TWIN BORE - ALL REACHES = 526.2

COMPOSITE LABOR COST/WORK WEEK =

$$(25 \text{ MEN/HOG} - 3H)(2 \text{ HOG})(3 \text{ SH/DY})(5 \text{ DY/WK})(8 \text{ HR/DY})(\$27/\text{HR})$$

$$= \$162,000/\text{WW}$$

$$(\$162,000/\text{WW})(526.2 \text{ WW}) = \$85,212,000 \text{ INCL FRINGE \& BURDEN}$$

Date **3-24-83**

To

From **HEB**

Subject **SCRIPD METRO RAIL
TUNNEL CREWS & SUPPORT**

P2

| <u>CRAFT LABOR</u> | <u>DAY</u> | <u>SWING</u> | <u>GRAVEYARD</u> | <u>TOTAL</u> |
|-----------------------------|------------|--------------|------------------|--------------|
| SUPPORT CREW | | | | |
| CRANE OR HOIST OP. (MUCK) | 1 | 1 | 1 | 3 |
| CRANE OR HOIST OILER (MUCK) | 1 | 1 | 1 | 3 |
| TOPMAN | 1 | 1 | 1 | 3 |
| BULL GANG LEADER | 1 | 1 | 1 | 3 |
| BULL GANG LABORERS | 3 | 2 | 2 | 7 |
| SHOP MECHANIC FOREMAN | 1 | — | — | 1 |
| SHOP MECHANICS | 3 | 1 | 1 | 5 |
| ELEC FOREMAN | 1 | — | — | 1 |
| ELECTRICIANS | 2 | 1 | 1 | 4 |
| COMPRESSOR OPERATOR | 1 | 1 | 1 | 3 |
| TOTAL | 15 | 9 | 9 | 33 |
| HEADING CREWS | | | | |
| WALKER OR SHIFTER | 2 | 2 | 2 | 6 |
| ELECTRICIAN | 2 | 2 | 2 | 6 |
| TBM OPERATOR | 2 | 2 | 2 | 6 |
| TBM OILER | 2 | 2 | 2 | 6 |
| TRAILING FLOOR OPER. | 2 | 2 | 2 | 6 |
| LOCI OPERATORS | 5 | 5 | 5 | 15 |
| LOCI BRAKEMAN | 5 | 5 | 5 | 15 |
| MECHANIC | 2 | 2 | 2 | 6 |
| TRACK LAYER | 2 | 2 | 2 | 6 |
| UTILITY MAN | 2 | 2 | 2 | 6 |
| PUMP MAN | 2 | 2 | 2 | 6 |
| LINER MAN | 2 | 2 | 2 | 6 |
| FRONT MAN | 2 | 2 | 2 | 6 |
| TOTAL | 32 | 32 | 32 | 96 |
| OTHER SUPPORT | | | | |
| YARD CRANE OPERATOR | 1 | 1 | 1 | 3 |
| YARD CRANE HELPER | 1 | 1 | 1 | 3 |
| WAREHOUSEMAN | 1 | 1 | 1 | 3 |
| TOTAL | 3 | 3 | 3 | 9 |
| TOTAL w/SUPPORT | 50 | 44 | 44 | 138 |

$$\text{AVE MEN/HEADING SHIFT} = \frac{138}{6} = 23 \quad \text{CALL 25*}$$

$$\text{(ADD 1 STREET SWEEPER GRAVEYARD SHIFT \therefore AVE = 23.17)}$$

IN ALLOW. FOR UNKNOWN'S

* ADD 2 MEN/HEADING/SHIFT FOR UNKNOWN'S
ELEC OP, CARPENTER, ETC



5601 South Broadway
Littleton, Colorado 80121

303/794/1818

To

Date 3-24-83

From HEB

Subject SCRTD METRO RAIL
CRAFT COMPOSITE LABOR RATE

SOURCE = MEANS

FROM CRAFT LABOR WORKUP (138 + 12)

| | | |
|-------------------|----------------------|---------|
| FOREMEN (OUTSIDE) | 8 EA @ 20.70 AVE = | 165.60 |
| SKILLED WORKERS | 126 EA @ 18.70 AVE = | 2356.20 |
| LABORERS | 16 EA @ 14.45 AVE = | 231.20 |

54 SURFACE
96 U/G ADD \$1/HR FOR U/G 96.00

54 DAY SHIFT
96 SWING & GRAVYARD - ADD 0.50/MH SHIFTOFF 48.00
\$2897

$\frac{\$2897}{150 MEN} = 19.30 / MH$ WITH FRINGE

ASSUME 1.083 PREMIUM PAY FACTOR*
ASSUME 1.300 BURDEN FACTOR

AVE COMPOSITE HRLY RATE = $(19.30)(1.083)(1.300)$
= 27.19 / MH

CALL 27.00 / MH WITH FRINGE
O.T. & PAYROLL
TAXES

* ASSUME 40 HR W.W. WITH 5% SAOT O.T.
1/2 HR TRAVEL TIME / DAY @ ST. TIME

PREMIUM PAY FAC = $\frac{42\frac{1}{2} + (40)(.05)(1.5)}{(40)(1.05)} = 1.083$

To

Date 3-26-83

From HEB

Subject SC RTD METRO RAIL

TUNNEL PERM MAT'L

PRECAST & REINFORCED

RINGS (ASSUME 4 LF RINGS IN 6 SEGMENTS)

RING SEGMENT U.C. = \$250

$$\text{LF OF TUNNEL} = 79810 \text{ LF} \times 2 = 159620$$

$$\begin{aligned} \text{SEGMENTS REQUIRED} &= \frac{159620 \text{ LF}}{4 \text{ LF/RING}} \left(\frac{6 \text{ SEG}}{\text{RING}} \right) \times 1.02 \text{ BREAKAGE} \\ &= 244219 \end{aligned}$$

$$\begin{aligned} \therefore \text{SEGMENT COST} &= (244219 \text{ SEG}) (\$250/\text{SEG}) \\ &= \underline{\underline{61,055,000}} \end{aligned}$$

ALLOW 350- / RING FOR BOLTS, CALKING, GASKETS, ETC

$$\text{RINGS} = \frac{159620 \text{ LF}}{4 \text{ LF/RING}} = 39905$$

$$\begin{aligned} \text{COST} &= (39905 \text{ RINGS}) (\$350/\text{RING}) \times 1.05 \text{ LOSS} \\ &= \underline{\underline{14,665,000}} \end{aligned}$$

GROUT

$$\text{GROUT REQ'D} = 61568 \text{ CY} \times 1.10 \text{ LOSS} = 67725 \text{ CY}$$

$$\text{PEA GRAVEL} = \$25/\text{CY}$$

$$\text{CEMENT 6 SACKS/CY @ \$4/SACK} = \$24/\text{CY}$$

$$\text{CALL COST CY} = \$50 -$$

$$\text{GROUT COST} = (67725 \text{ CY}) (\$50/\text{CY}) = \underline{\underline{3,386,000}}$$

$$\text{TOTAL MAT'L COST} = \underline{\underline{\$79,106,000}}$$

| | | |
|-------------|----------|---------|
| | Initials | Date |
| Prepared by | HFB | 3-25-83 |
| Approved by | | |

SC RTD EQUIPMENT SPREAD SHEET (EXC. LINE # GROUT ONLY)

\$1000

| EQUIPMENT | DISTRIBUTION | QUANTITY | UNIT PRICE | EXTENSION | SALVAGE | PROJECT COST | MONTHLY RENTAL RATE | LIFE MONTHS OF SERVICE | PROJECT COST \$ X 1000 | PROJ COST SUMMARY \$ X 1000 | |
|--------------------------------------|-----------------|----------|------------|-----------|---------|--------------|---------------------|------------------------|------------------------|-----------------------------|----|
| | | | | | | | | | | | |
| TBM (REP ZOKOR) | 2 X 2 | 12 EA | 2000 | 24000 | 4000 | 20000 | | | | 20000 | 1 |
| TBM (ROBBINS) | 1 X 2 | 2 EA | 3500 | 7000 | 1000 | 6000 | | | | 6000 | 2 |
| TBM TRAILING GEAR (ZOKOR) | 6 X 2 | 12 EA | 500 | 6000 | 1000 | 5000 | | | | 5000 | 3 |
| TBM TRAILING GEAR (ROBBINS) | 1 X 2 | 2 EA | 1000 | 2000 | 400 | 1600 | | | | 1600 | 4 |
| ZOTON DIESEL LOCIS | 5 X 4 2 X 6 | 32 EA | 95 | 3040 | 1963 | 1077 | | | | 1077 | 5 |
| BCY MUCK CARS | 5 X 4 2 X 2 | 148 EA | 18 | 2664 | 1720 | 944 | | | | 944 | 6 |
| FLAT CARS | 7 X 6 | 42 EA | 18 | 756 | 488 | 268 | | | | 268 | 7 |
| 6 CY AGITATOR CARS | 7 X 4 | 28 EA | 34 | 952 | 615 | 337 | | | | 337 | 8 |
| MAN CARS | 7 X 2 | 14 EA | 20 | 280 | 181 | 99 | | | | 99 | 9 |
| 3 CY / HR GROUT PUMPS W/ POTS | 7 X 2 | 14 EA | 18 | 252 | 163 | 89 | | | | 89 | 10 |
| 5 TON TRACTORS | 7 X 4 | 28 EA | 5 | 140 | 90 | 50 | | | | 50 | 11 |
| 1200 CFM SCRAWPAD BELC COMP. | 7 X 2 | 14 EA | 55 | 770 | 497 | 273 | | | | 273 | 12 |
| 900 CFM " " " " | 7 X 2 | 14 EA | 45 | 630 | 407 | 223 | | | | 223 | 13 |
| OIL SWITCH / MISC BURG. EQUIP | 7 X 2 | 14 LOTS | 150 | 2100 | 1356 | 744 | | | | 744 | 14 |
| 125 HP, 60,000 CFM FANS (REV. 10/82) | 1 EA / 2000 HRS | 7 EA | 8 | 56 | 403 | 221 | | | | 221 | 15 |
| AIMOS? SHP FLYGT | 7 X 10 | 70 EA | 3 | 210 | 136 | 74 | | | | 74 | 16 |
| MISC SHIP EQUIP. | 7 X 1 | 7 LOTS | 30 | 210 | 136 | 74 | | | | 74 | 17 |
| MISC TUNNEL EQUIP. | 7 X 2 | 14 LOTS | 30 | 420 | 271 | 149 | | | | 149 | 18 |
| 2 1/2 TON 4 X 2 FLAT BED | 7 X 1 | 7 EA | 25 | 175 | 113 | 62 | | | | 62 | 19 |
| 4 1/2 CY FUEL DIESEL | 7 X 1 | 7 EA | 275 | 1925 | 1244 | 681 | | | | 681 | 20 |
| 20 TON CRAWLER DIESEL CRANE | 7 X 1 | 7 EA | | | | | 12750 | 17 | 1515 | 1515 | 21 |
| 20 TON HYDR. DIESEL CRANE | 7 X 1 | 7 EA | | | | | 4270 | 17 | 508 | 508 | 22 |
| PICKUPS (IN OH) | --- | | | | | | | | | | 23 |
| BUILDINGS (IN OH) | --- | | | | | | | | | | 24 |
| TEMP CONST. (IN OH) | --- | | | | | | | | | | 25 |
| | | | | | | | | | | | 26 |
| TOTAL | | | | 54140 | 14183 | 37965 | | | 2023 | 39988 | 27 |
| | | | | | | | | | SALES TAX @ 4.0% (10%) | 3999 | 28 |
| | | | | | | | | | TOTAL EQUIP | 43987 | 29 |
| | | | | | | | | | | | 30 |

-86-

} IN OH

} IN OH

} IN OH

QUANTITY SHEET

PROJECT SC RTD METRO RAIL ESTIMATOR HEB ESTIMATE NO.

LOCATION EXTENSIONS SHEET NO.

ARCHITECT ENGINEER CHECKED DATE 3-25-83

CLASSIFICATION QUANT. TAKE OFF

| DESCRIPTION | NO. | DIMENSIONS | ESTIMATED QUANTITY | UNIT |
|--|-----|--|--------------------|------|
| <u>TUNNEL EXC.</u> | | <u>(19.67 OD X 79810 LF X 2)</u> | | |
| $\text{TOTAL CY EXC. W/SWELL} = (2)(79810)(\pi) \left(\frac{19.67}{2} \right)^2 (1.5) / 27$ $= \underline{2694719}$ | | | | |
| $\text{TOTAL CY EXC. W/O SWELL} = 2694719 / 1.5$ $= \underline{1796479}$ | | | | |
| $\text{REACH 12 CY EXC W/O SWELL} = (2)(16154)(\pi) \left(\frac{19.67}{2} \right)^2 / 27$ $= \underline{363618}$ | | | | |
| <u>BACKFILL GROUT</u> | | <u>(19.67 OD, 19.33 ID X 79810 LF X 2)</u> | | |
| $\text{TOTAL CY BACKFILL GROUT} = (2)(79810)(\pi) \left[\left(\frac{19.67}{2} \right)^2 - \left(\frac{19.33}{2} \right)^2 \right] / 27$ $= \underline{61568}$ | | | | |



5601 South Broadway
Littleton, Colorado 80121

303/794/1818

P1

To

Date 3-25-83

From HGB

Subject SCRTD METRO RAIL

FAN ANALYSIS (W/ ALLOWANCE TAKEN FOR HOUR THAN)

FANS REQ'D

| | | |
|----------|--------|--------------|
| REACH 2 | 2 x 3 | 6 |
| REACH 5 | 2 x 4 | 8 |
| REACH 6 | 2 x 6 | 12 |
| REACH 8 | 2 x 3 | 6 |
| REACH 10 | 2 x 5 | 10 |
| REACH 12 | 2 x 11 | 22 |
| REACH 14 | 2 x 7 | 14 |
| | | <u>78 EA</u> |

FAN DAYS

| | |
|----------------|----------------------|
| <u>REACH 2</u> | 3 x 306 = 918 |
| | 2 x 1500 = 3000 |
| | 1 x 1500 = 1500 |
| | <u>2 x 361 = 722</u> |
| | 1 x 1500 = 1500 |
| | 2 x 657 = 1314 |
| | 1 x 1500 = 1500 |

$2(10454 \text{ FAN FT}) / (30.77 \text{ FT/DY}) = \underline{679 \text{ FAN DAYS}}$

REACH 5

| |
|------------------------|
| 4 x 301 = 1204 |
| 6 x 1500 = 9000 |
| <u>3 x 1429 = 4287</u> |
| 3 x 1500 = 4500 |
| 2 x 1038 = 2076 |
| 1 x 1500 = 1500 |

$(22568)(2) / 40.72 = \underline{1108 \text{ FAN DAYS}}$



5601 South Broadway
Littleton, Colorado 80121

303/794/1818

To

Date 3-25-83

From HEB

Subject SCRTD METRO RAIL

REACH 6

$$\begin{aligned}
 1 \times 1472 &= 1472 \\
 6 \times 1507 &= 9042 \\
 15 \times 1500 &= 22500 \\
 \hline
 &= 33014 \\
 (33014)(2) / 39.10 &= \underline{1689 \text{ FAN DAYS}}
 \end{aligned}$$

REACH 8

$$\begin{aligned}
 2 \times 968 &= 1936 \\
 1 \times 1500 &= 1500 \\
 3 \times 1437 &= 4311 \\
 3 \times 1500 &= 4500 \\
 1 \times 332 &= 332 \\
 \hline
 &= 12579 \\
 (12579)(2) / 35.30 &= \underline{713 \text{ FAN DAYS}}
 \end{aligned}$$

REACH 10

$$\begin{aligned}
 4 \times 436 &= 1744 \\
 6 \times 1500 &= 9000 \\
 5 \times 320 &= 1600 \\
 10 \times 1500 &= 15000 \\
 4 \times 406 &= 1624 \\
 6 \times 1500 &= 9000 \\
 \hline
 &= 37968 \\
 (37968)(2) / 41.34 &= \underline{1837 \text{ FAN DAYS}}
 \end{aligned}$$

REACH 12

$$\begin{aligned}
 11 \times 1154 &= 12694 \\
 53 \times 1500 &= 82500 \\
 \hline
 &= 95194 \\
 (95194)(2) / (41.31) &= \underline{4608 \text{ FAN DAYS}}
 \end{aligned}$$

REACH 14

$$\begin{aligned}
 7 \times 1688 &= 11816 \\
 21 \times 1500 &= 31500 \\
 \hline
 &= 43316 \\
 (43316)(2) / 25.82 &= \underline{3356 \text{ FAN DAYS}}
 \end{aligned}$$

TOTAL FAN DAYS = 13990

| | | |
|-------------|----------|---------|
| | Initials | Date |
| Prepared by | HEB | 3-25-58 |
| Approved by | | |

SC RTD EQUIPMENT MAINT. MAT'L & OPERATING COST (EXC. LINE & GROUT ONLY)

| EQUIPMENT | MAINT. MAT'L CALC. | | MAINT. MAT'L \$/1000 | OPERATING COST CALC. | | | | | | OPERATING COST \$/1000 | | |
|-----------------------------|--|--|----------------------|---|--|--|--|--|--|------------------------|-----------|----|
| | | | | | | | | | | | | |
| BOKOR TBM & TRAILING GEAR | (#270) X (192061 CY) | | 5731 | (200 HR) X (740) (#270/HR) (SIN/HR) (12 HR/D) (SDY/WK) (60 WKS) | | | | | | 2900 | 1 | |
| ROBBINS TBM & TRAILING GEAR | (#870) X (303618 CY) | | 2909 | (200 HR) X (740) (#870/HR) (SIN/HR) (12 HR/D) (2 AGS) (SDY/WK) (75 WKS) | | | | | | 943 | 2 | |
| 20 TON DIESEL LOCS | (#320/HR-CA) X (32 EA) X (1.0) (18 HR/D) (SDY/WK) (60 WKS) | | 609 | (#425/HR-CA) X (32 EA) X (1.0) (18 HR/D) (SDY/WK) (69 WKS) | | | | | | 755 | 3 | |
| 8 CY MUCK CARS | (#15/HR-CA) X (2674719 CY) | | 674 | | | | | | | | 4 | |
| FLAT CARS | (#5/HR-CA) X (4244) X (1.0) (SDY/WK) (69 WKS) | | 58 | | | | | | | | 5 | |
| 6 CY AQUAIDE CARS | (#25/HR-CA) X (67725 CY) | | 169 | | | | | | | | 6 | |
| MAN CARS | (#5/HR-CA) X (1424) X (1.0) (SDY/WK) (69 WKS) | | 24 | | | | | | | | 7 | |
| 3 CY/HR GROUT PUMPS | (#1/HR) X (67725 CY) | | 68 | | | | | | | | 8 | |
| 1200 CFM COMPRESSORS | (#35/HR-CA) X (444) X (1.0) (12 HR/D) (SDY/WK) (75 WKS) | | 198 | (#35/HR-CA) X (444) X (1.0) (12 HR/D) (SDY/WK) (75 WKS) | | | | | | 1411 | 9 | |
| 900 CFM COMPRESSORS | (#25/HR-CA) X (444) X (2.0) (12 HR/D) (SDY/WK) (75 WKS) | | 30 | (#25/HR-CA) X (444) X (2.0) (12 HR/D) (SDY/WK) (75 WKS) | | | | | | 200 | 10 | |
| ELECTRICAL GEAR | (#70/HR-CA) X (1424) X (1.0) (SDY/WK) (75 WKS) | | 37 | SOME LOSS, BUT NOT CALCULATED | | | | | | | | 11 |
| 125 HP FANS | (#0.5/HR) X (24 HR/D) X (3900 HOURS) | | 17 | (125 HP) X (24 HR/D) X (3900 HOURS) | | | | | | 2010 | 12 | |
| 5 HP FLYGT PUMPS | (#0.5/HR-CA) X (70 EA) X (5) X (24 HR/D) X (70 WKS) (69 WKS) | | 61 | (5 HP) X (70 EA) X (5) X (24 HR/D) X (70 WKS) (69 WKS) | | | | | | 136 | 13 | |
| 70 TN CRANE | (#7/HR-CA) X (7 EA) X (1.0) (12 HR/D) (SDY/WK) (75 WKS) | | 221 | (#7/HR-CA) X (7 EA) X (1.0) (12 HR/D) (SDY/WK) (75 WKS) | | | | | | 315 | 14 | |
| 20 TN CRANE | (#8/HR-CA) X (7 EA) X (1.0) (12 HR/D) (SDY/WK) (75 WKS) | | 94 | (#8/HR-CA) X (7 EA) X (1.0) (12 HR/D) (SDY/WK) (75 WKS) | | | | | | 220 | 15 | |
| SHOP EQUIP. (MISC.) | (#300/MO-LO) X (7 LOTS) X (1.0) (75 WKS) X (1.33) | | 12 | (75 WKS) X (1.33) X (1.0) X (1.0) (SDY/WK) (75 WKS) | | | | | | 35 | 16 | |
| TUNNEL EQUIP. (MISC.) | (#300/MO-LO) X (10 LOTS) X (1.0) (69 WKS) X (1.33) | | 23 | | | | | | | | 17 | |
| 2 1/2 TN FLAT BED | (#0.5/HR-CA) X (7 EA) X (2.0) (6 HR/D) (SDY/WK) (75 WKS) | | 6 | (#0.5/HR-CA) X (7 EA) X (2.0) (6 HR/D) (SDY/WK) (75 WKS) | | | | | | 205 | 18 | |
| 4 1/2 CY FEL | (#3/HR-CA) X (7 EA) X (1.0) (8 HR/D) (SDY/WK) (75 WKS) | | 63 | (#3/HR-CA) X (7 EA) X (1.0) (8 HR/D) (SDY/WK) (75 WKS) | | | | | | 252 | 19 | |
| TUNNEL LIGHTING | (#300/MO-MA) X (10 WKS) X (5) (69 WKS) X (1.33) | | 11 | (1000 WKS) X (1.33) X (5) X (1.0) (69 WKS) (1.33) | | | | | | 297 | 20 | |
| BUILDINGS (IN OH) | | | | | | | | | | | 21 | |
| PICKUPS (IN OH) | | | | | | | | | | | 22 | |
| TOTAL | | | 10912 | | | | | | | 10481 | 23 | |

- 102 -

To

Date 3-24-83

From

HAB

Subject SCRTD METRO RAIL

TUNNEL TEMPORARY UTILITY LINES & RAIL

- | | |
|---|------------------------------------|
| 1.) WATER LINE - 109 WALL 4" WITH VIC COUPLINGS, NIPPLES & VALVES | \$4 / LF |
| 2.) COMPRESSOR AIR LINE - 109 WALL 8" WITH VIC COUPLINGS, NIPPLES & VALVES | \$10 / LF |
| 3.) DEWATERING LINE - 109 WALL 8" WITH VIC COUPLINGS & MANIFOLDING | \$10 / LF |
| 4.) VENT LINE - (FOR 60,000 CFM, 125 HP FANS TO HANDLE 2 EA 20TH LOCIS @ 25,000 CFM/EA) 36" WITH COUPLERS & ELBOWS (FANS EVERY 1500 LF, ^{COST} VENT EQUIPMENT) | \$15 / LF |
| 5.) LOW VOLTAGE ELEC. W/ LIGHTS STEP DOWN TRANSFORMERS. (@ 2500/EA) EVERY 1500 LF | \$5 / LF \$2 ³⁰ / LF |
| 6.) POWER CABLE TO TBM (800 HP, 1000 MCM) WITH JOY PLUGS | \$8 / LF |
| 7.) TELEPHONE LINE PHONE (\$600/EA) EVERY 2000 LF | \$2 / LF \$0 ³⁰ / LF |
| 8.) RAIL & TIES - USED 80 LB RAIL INCL. TIES, SWITCHES, TURNOUTS, SAKES & BOOTS @ \$200/TN, ASSUME 70 LB/LF | \$7 / LF |

CALC'S NEXT PAGE

ALLOWANCE FOR SMALL TOOLS & SUPPLIES \$1.00/MH

$$MH = (25 \text{ MEN / HGT-SH}) (2 \text{ HDG}) (3 \text{ SHIFTS / DAY}) (5 \text{ DI / WK}) (52.2 \text{ WKS}) (84\%)$$

$$= 3,157,200 \text{ MH}$$

$$(3,157,200 \text{ MH}) (1.00 / \text{MH}) = 3,157,200$$

CALC \$3,157,000

To

Date 3-24-83

From HEB

Subject SCRTD

UTILITY COST

ALL ^{ALL} UTILITIES CARRIED THRU STATIONS BUT VENT LINE
REUSE VENT LINE AFTER HOLE THEN

ALL UTILITIES BUT VENT LINE = \$48⁶⁰/LF

FOOTAGE

| <u>REACH</u> | <u>LF</u> |
|--------------|----------------|
| 2 | 8586 |
| 5 | 13745 |
| 6 | 11133 |
| 8 | 8632 |
| 10 | 17992 |
| 12 | 16154 |
| 14 | 10688 |
| <u>TOTAL</u> | <u>86930LF</u> |

$$(86930LF)(\$48^{60}/LF) = \underline{\underline{\$4,224,798}}$$

VENT LINE = \$15⁻/LF

FOOTAGE REQ'D (LONGEST PARS IN REACH)

| <u>REACH</u> | <u>LF</u> |
|--------------|--------------|
| 2 | 3300 |
| 5 | 4800 |
| 6 | 9000 |
| 8 | 4400 |
| 10 | 6300 |
| 12 | 16200 |
| 14 | 10700 |
| <u>TOTAL</u> | <u>54700</u> |

$$(54700LF)(\$15^{-}/LF) = \underline{\underline{\$820,500}}$$



5601 South Broadway
Littleton, Colorado 80121

303/794/1818

To

Date 3-24-83

From *HeB*

Subject SCRTD

TOTAL UTILITY COST = (4,224,798 + 820,500) 2

= 10,090,596

CALL 10,091,000

To

Date 3-26-83

From

HAB

SC RTD METRO RAIL
Subject MUCK DISPOSAL

GENERALLY SUBCONTRACTED

TYPICALLY RUNS FROM \$4⁵⁰ TO \$5⁰⁰ /CY
FOR L.A. \$6⁰⁰ /CY IS PROBABLY OK

SCATTER

NO. IS REASONABLE

SEE QUAN CALC. SHEET

TOTAL TUNNEL EXC. W/SWELL = 2,695,000 CY

$2,695,000 \text{ CY} \times \$6/\text{CY} = \$16,170,000$

To

Date 3-27-83

From HEB

Subject SCRTD

CROSS PASSAGES - ASSUME 6W X 8H X 30 L FINISHED

DURATION

PER PASSAGE

DRILL BLAST & MUCK 3 DAYS

FORM POUR & STRIP 3 DAYS

INVERT & CLEANUP 1 DAY

7 DAYS/EA

PERM. LIGHTING, ETC STAGGERED NO DUR. IMPACT

NO. OF PASSAGES

REACH 2 13 EA

5 21 EA

6 19 EA

8 12 EA

10 30 EA

12 31 EA

14 20 EA

TOTAL 146 EA

$$(146 \text{ EA})(7 \text{ DAYS/EA}) + (7 \text{ REACHES})(5 \text{ DAYS LEARNING/EA}) = 1057 \text{ DAYS}$$

$$1057 \text{ DAYS} / 146 \text{ EA} = 7.24 \text{ DAYS/EA}$$

$$1.44 \text{ WW/EA}$$

ASSUME CONSTRUCTION OF CROSS PASSAGES CONCURRENT WITH TUNNEL CONSTRUCTION.

COST

NORMAL COST 6X8 FINISHED IS \$1000-\$1800/LF

ASSUME CONSERV. CASE + ALLOWANCE FOR LIGHTING & TRAFFIC CASE

$$\text{COST} = (146 \text{ EA})(30 \text{ LF/EA})(\$1500/\text{LF})(1.25 \text{ ADJ. FAC.})$$

$$= \$8,212,500 / 146 = \$56250/\text{EA}$$

To

Date 3-27-83

From HAB

Subject SC RTD

STEEL LINER

5280+11770

STEEL LINER TAKE OFF QUANTITY OF 17050 LF ^{TwinBo}
ACCEPT MATERIAL COST OF \$721/LF CALL \$720/LF TWIN BOLE
LABOR & PLANT

TUNNEL L&P

| | |
|-------------------------|---------------------|
| LABOR EX TRMS | 143,000 / ww |
| EQUIP EX TRMS | 15,000 / ww |
| MAINT MAT'L EX TRMS | 4,000 / ww |
| ELEC, FUEL, ETC EX TRMS | 13,000 / ww |
| ST&S EX TRM | 3,000 / ww |
| TOTAL | <u>178,000 / ww</u> |

REDUCTION FOR PROJ PHASE

| | | |
|-------|-----|---------------------|
| LABOR | 30% | 100,000 / ww |
| EQUIP | 20% | 12,000 / ww |
| M.M. | 40% | 2,000 / ww |
| CONS. | 40% | 8,000 / ww |
| ST&S | 30% | 2,000 / ww |
| | | <u>124,000 / ww</u> |

ACCEPT PRODUCTION RATE OF 78 LF/DY CALL 80 LF/DY

$$\begin{aligned} \text{MATERIAL COST} &= (17050 \text{ LF}) (\$720/\text{LF}) = \$12,276,000 \\ \text{L \& P COST} &= (17050 \text{ LF}) (\$124,000/\text{ww}) (1 \text{ ww}/5 \text{ DY}) (80 \text{ LF}/\text{DY}) \\ &= \underline{\underline{5,285,500}} \end{aligned}$$

$$\text{TOTAL COST} = \$17,561,500 \quad \text{CALL } \underline{\underline{\$17,560,000}}$$



5601 South Broadway
Littleton, Colorado 80121

303/794/1818

PI

To

Date 3-26-83

From

HEB

Subject SCRTD

FINISH TUNNEL

ROUGH EST OF U.C./LF = \$115 ^{SEE BACKUP}

$$\text{COST} = (2404)(79810\text{LF}/404)(\$115/\text{LF}) = 18,356,300$$

CALL
18,356,000

GROUND ALO CONTROL IN REACH 2

SMALL NO. , LIMITED BASIS DATA
ACCEPT EST OF \$500,000

SHIELD PIT IN REACH 12

SMALL NO. , ACCEPT EST OF \$391,000



5601 South Broadway
Littleton, Colorado 80121
303/794/1818

To


Date 3-26-83

From HEB

Subject SC RTD

FINISH TUNNEL - U.C. EST.

HISTORY 1972 PROJ SAME CONFIGURATION
SIZE \$57/LF USING FORM @ 50 LF/DAY
EX LABOR FRINGE & BURDEN



ASSUME \$57 IS 40% L = 22.80
ADD 50% FOR FRINGE & BURDEN = 34.20

COST/LF = 57 - 22.80 + 34.20 = 68.40

ESC FAK.
(\$68.40/LF)(2.0) = 136.80/LF IN 1982

ASSUME MECH. APPROACH YIELDS ONLY 15% REDUCTION
IN U.C.

(.85)(136.80/LF) = \$116.1/LF



DURATION = $\frac{79810}{300}$ + 7x15 + 7x5 = 406 DAYS = 81 WKS

REDUCED P&L COST (FROM STEEL LINER ITEM) = \$124,000/WK

L&P = 81 WKS @ \$124,000 = 10,044,000
M&L = 79810 x 2 x 50 = 7,981,000

TOTAL 18,025,000

COST/LF = $\frac{18,025,000}{79810 \times 2}$ = \$113.1/LF

CALL \$115/LF

| | | |
|-------------|----------|---------|
| | Initials | Date |
| Prepared by | HEB | 3-28-81 |
| Approved by | | |

SC RTD REACH DURATIONS

WILSON-JONES
MADE IN U.S.A.

| | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | |
|---|--|---------|---------|---------|----------|----------|----------|-------|-------|-----|----|
| TIME ALLOTMENT (DAYS) | REACH 2 | REACH 5 | REACH 6 | REACH 8 | REACH 10 | REACH 12 | REACH 14 | TOTAL | AVE | CMV | |
| A ₁ , A ₂ , & SP @ 26L/DY | 119 | --- | 17 | 56 | --- | --- | 373 | | | | 1 |
| A ₂ , A ₃ , C, & 1-S @ 43L/DY | 40 | 274 | 233 | 134 | 376 | 376 | 23 | | | | 2 |
| LEARNING TIME @ 15 DY | 15 | 15 | 15 | 15 | 15 | 15 | 15 | | | | 3 |
| ASSEMBLY & LAUNCH @ 30 DY | 30 | 30 | 30 | 30 | 30 | 30 | 30 | | | | 4 |
| MODIFY TBM @ 3 DY / EA | 6 | --- | 3 | --- | --- | --- | 3 | | | | 5 |
| SKID THRU STA & TURN UNDER @ 30 DY/EA | 30 | 30 | 15 | 15 | 30 | --- | --- | | | | 6 |
| DISMANTLE & REMOVE @ 15 DY | 15 | 15 | 15 | 15 | 15 | 15 | 15 | | | | 7 |
| * TUNNEL SUB - TOTAL (DYS) | 313 | 364 | 328 | 265 | 466 | 436 | 459 | | | | 9 |
| * TUNNEL SUB - TOTAL (WKS) | 62.6 | 72.8 | 65.6 | 53.0 | 93.2 | 87.2 | 91.8 | 526.2 | 75.2 | 75 | 10 |
| CROSS PASSAGES (500'C-C) | CONCURRENT INSTALLATION WITH TUNNEL - NO SCHEDULE TIME | | | | | | | | | | 12 |
| STEEL LINER (8X4/DAY) | --- | 30.3 | --- | 13.2 | --- | --- | --- | 43.5 | 6.2 | 6 | 13 |
| FINISH TUNNEL (300L/DY + 20) | 8.9 | 11.8 | 11.0 | 8.8 | 14.8 | 14.8 | 11.1 | 81.2 | 11.6 | 12 | 14 |
| MOB / DEMOB & CLEANUP | 19.0 | 19.0 | 19.0 | 19.0 | 19.0 | 19.0 | 19.0 | 133.0 | 19.0 | 19 | 15 |
| GROUND HD LOWERING (WEEK) | CONCURRENT WITH MOB - NO SCHEDULE TIME | | | | | | | | | | 16 |
| SHIELD PIT (WEEKS) | CONCURRENT WITH MOB - NO SCHEDULE TIME | | | | | | | | | | 17 |
| SET UP FOR FINISH DURING ST-LN. (3WKS/EA) | --- | (30) | --- | (30) | --- | --- | --- | (60) | (0.9) | (1) | 18 |
| CONSTRUCTION TOTAL DURATION | 98.5 | 130.9 | 95.6 | 91.0 | 127.0 | 121.0 | 121.9 | 777.9 | 111.1 | 111 | 20 |
| * EXC. LINING & BACKFILL GRANT | | | | | | | | | | | 30 |

- III -

STATIONS

3-24-82

DOL

| | 2 | 3 | 4 | 5 |
|----|--------------|-------------|---|---|
| | | TOTAL | | |
| | | CHANGE | | |
| | | DIRECT | | |
| | | \$ | | |
| 1 | 2nd St | 167,000 | | |
| 2 | 1st Hill | 630,000 | | |
| 3 | 5th Hill | 1,100,000 | | |
| 4 | 7th Flower | 175,000 | | |
| 5 | ALVARADO | 114,000 | | |
| 6 | VERMONT | 90,000 | | |
| 7 | NORMANDIE | 120,000 | | |
| 8 | WESTERN | 140,000 | | |
| 9 | LA BREA | 160,000 | | |
| 10 | FAIRFAX | 900,000 | | |
| 11 | BEVERLY | 65,000 | | |
| 12 | SANTA MONICA | 150,000 | | |
| 13 | SUNSET | 160,000 | | |
| 14 | HOLLYWOOD | 170,000 | | |
| 15 | UNIVERSAL | 275,000 | | |
| 16 | No Hollywood | 175,000 | | |
| | | + 4,541,000 | ✓ | |

SUMMARY - STATION SHELLS
FOR COMPARATIVE PURPOSES ONLY*

3-24-83 004

| No | STATION | DIRECT COST SUMMARY | |
|----|--------------|---------------------|-----------------|
| | | DM-SM-P&SO | KC |
| 1 | UNION | \$ 11,304,000 ✓ | \$ 11,471,000 ✓ |
| 2 | 1ST HILL | 13,300,000 ✓ | 13,930,000 ✓ |
| 3 | 5TH HILL | 18,660,000 ✓ | 19,760,000 ✓ |
| 4 | 7TH FLOWER | 14,917,000 ✓ | 15,092,000 ✓ |
| 5 | ALVARADO | 3,869,000 ✓ | 3,983,000 ✓ |
| 6 | VERMONT | 7,370,000 ✓ | 7,460,000 ✓ |
| 7 | NORMANDIE | 8,720,000 ✓ | 8,840,000 ✓ |
| 8 | WESTERN | 12,170,000 ✓ | 12,310,000 ✓ |
| 9 | LABREA | 12,292,000 ✓ | 12,457,000 ✓ |
| 10 | FAIRFAX | 25,582,000 ✓ | 26,482,000 ✓ |
| 11 | BEVERLY | 12,675,000 ✓ | 12,740,000 ✓ |
| 12 | SANTA MONICA | 10,035,000 ✓ | 10,185,000 ✓ |
| 13 | SUNSET | 12,338,000 ✓ | 12,498,000 ✓ |
| 14 | HOLLYWOOD | 12,210,000 ✓ | 12,380,000 ✓ |
| 15 | UNIVERSAL | 22,254,000 ✓ | 22,479,000 ✓ |
| 16 | No Hollywood | 12,886,000 ✓ | 13,061,000 ✓ |
| | | 210,582,000 ✓ | 215,123,000 ✓ |

* NOTE: DEWATERING - UNDERPINNING - UTILITY SUPPORT - TRAFFIC MAINTENANCE AND PARKING GARAGES STILL INCLUDED

①

UNION STATION SHELL

3-23-83

ONE LEVEL - TYPE "B"

DDG

640' L 66'-9" W 29 T 34.5 D

| ITEM | DESCRIPTION | DMJM-PBDD | | KC | | CHANGE |
|------|-----------------|-----------|-----------|----|-----------|----------|
| | | @ | \$ | @ | \$ | |
| 1 | | | | | | |
| 2 | (1) DEMOLITION | | 300,000 | | 300,000 | - |
| 3 | | | | | | |
| 4 | (2) EARTHWORK | | | | | |
| 5 | EX. MACH | | | | 271,600 | |
| 6 | EX. HAND | | | | 187,000 | |
| 7 | CAMP BE. | | | | 177,700 | |
| 8 | SOIL DISP | | 2,764,160 | | 398,000 | - |
| 9 | SOLD PILE/LAG | | | | 1,463,000 | |
| 10 | DECKING | | | | 256,000 | |
| 11 | DEWATER | | | | | |
| 12 | | | | | 2,753,300 | PU 500 |
| 13 | | | | | | |
| 14 | (3) CONCRETE | | | | | |
| 15 | (A) FORMS | | 1,601,000 | | 1,601,000 | - |
| 16 | | | | | | |
| 17 | (B) CONC. | | | | | |
| 18 | PLACE | | 511,400 | | 600,000 | |
| 19 | SUPPLY | | 1,518,000 | | 1,518,000 | +166,600 |
| 20 | OVER RUN | | | | 78,000 | |
| 21 | | | | | | |
| 22 | | | | | 2,196,000 | |
| 23 | | | | | | |
| 24 | (C) REBAR | | 2,218,600 | | 2,218,600 | - |
| 25 | | | | | | |
| 26 | | | | | | |
| 27 | (D) CURING | | 14,200 | | 14,200 | - |
| 28 | | | | | | |
| 29 | | | | | | |
| 30 | (E) FINISHING | | 279,400 | | 279,400 | - |
| 31 | | | | | | |
| 32 | | | | | | |
| 33 | (A) WATERPROOF | | 85,100 | | 85,100 | - |
| 34 | | | | | | |
| 35 | (5) SITE REST. | | 1,045,000 | | 1,045,000 | - |
| 36 | | | | | | |
| 37 | (6) TRAFFIC | | | | | |
| 38 | (7) UTIL. SUPT. | | | | | |
| 39 | (8) MOB | | 434,800 | | 434,800 | - |
| 40 | | | | | | |

②

3-73-83

1ST & HILL ST. STA. SHELL

004

OVER-UNDER TYPE "E"

631 6

62-9 W

66-10 D

| ITEM | DESCRIPTION | Q M I M P B A D | K C | CHANGE |
|------|--------------|-----------------|-----------|---------|
| (1) | DEMOLITION | 50650 | 50600 | - |
| (2) | EARTHWORK | | | |
| | EX. MACH | | 700000 | |
| | EX. HAND | | 187000 | |
| | COMP. B.F. | | 263000 | |
| | SOIL DISP | 5933000 | 833000 | +440000 |
| | SOLD PILE | | 3539000 | |
| | " STAIRS | | 365550 | |
| | DECKING | | 486000 | |
| | UNDERPIN | - | - | |
| | DEWATER | - | - | |
| | | | 6,774,000 | |
| (3) | UTILITIES | | | |
| (4) | MOBILIZATION | | | |
| (5) | CONCRETE | | | |
| (A) | FARMS | - | - | - |
| (B) | CONC | | | |
| | PLACE | 650400 | 750000 | |
| | SUPPLY | 1784200 | 1784000 | |
| | OVER RUN | | 90000 | |
| | | 2434000 | 2624000 | +190000 |

3

5TH & HILL ST STA SUELL
OVER UNDER TYPE E

5-23-83

DDL

631 L 62-9 W 86-6 O

| ITEM | DESCRIPTION | DMJM | POOD | KC | CHANGE |
|------|----------------|-----------|------|-----------|---------|
| (1) | DEMOLITION | - | - | - | - |
| (2) | EARTHWORK | | | | |
| | EX. MACH | 540000 | | 700000 | |
| | EX. HAND | 200550 | | 187000 | |
| | COMP. BF | 957300 | | 957000 | |
| | EX. SOIL DISP. | 813000 | | 973000 | |
| | SOLD PILE | 5598000 | | 6,086,000 | |
| | DECK ROAD | 819500 | | 705000 | |
| | DECK SW | 39600 | | 39600 | |
| | UNDERPIN | - | | - | |
| | DEWATER | - | | - | |
| | | 8,976,000 | | 9,848,000 | 872,000 |
| (3) | UTIL | | | | |
| (4) | MOB | | | | |
| (5) | CONCRETE | | | | |
| (A) | FORMS | - | | - | |
| (B) | CONC. | | | | |
| | PLACE | 474300 | | 570000 | |
| | SUPPLY | 1,343,850 | | 1,343,850 | |
| | OVER RUN | - | | 90000 | |
| | | 1,818,000 | | 2,003,000 | 185,000 |

CALL \$ 1,100,000

④

7TH & FLOWER STA SHELL

ONE LEVEL TYPE "A"

DDL

740 L 62-9 W 53 P

| ITEM | DESCRIPTION | DMJM | PBOO | RC | CHANGE |
|------|-------------------|------|-----------|-----------|----------|
| 1 | | | | | |
| 2 | (1) DEMO | | - | - | - |
| 3 | | | | | |
| 4 | (2) EARTHWORK | | | | |
| 5 | EX MACH | | | 490,000 | |
| 6 | EX HAND | | | 187,000 | |
| 7 | COMP BF | | | 509,000 | |
| 8 | SOIL DISP. | | 5,430,000 | 447,000 | |
| 9 | SOLA PLS LAG | | | 3,049,000 | |
| 10 | " STAIRS | | | 216,000 | |
| 11 | DECKING RD | | | 509,760 | |
| 12 | " SIDE WALK | | | 35,600 | |
| 13 | UNDERPIN | | - | - | |
| 14 | DENATER | | - | - | |
| 15 | | | | 5,440,000 | - |
| 16 | | | | | |
| 17 | | | | | |
| 18 | 3 MAJOR UTILITIES | | - | - | - |
| 19 | | | | | |
| 20 | 4 MOR. | | - | - | - |
| 21 | | | | | |
| 22 | 5 CONCRETE | | | | |
| 23 | (A) FORMS | | | | |
| 24 | | | | | |
| 25 | (B) CONC | | | | |
| 26 | PLACE | | 474,300 | 569,000 | |
| 27 | SUPPLY | | 1,344,000 | 1,344,000 | |
| 28 | OVERRUN | | - | 80,000 | |
| 29 | | | | | |
| 30 | | | 1,818,000 | 1,993,000 | +175,000 |
| 31 | | | | | |
| 32 | | | | | |
| 33 | | | | | |
| 34 | | | | | |
| 35 | | | | | |
| 36 | | | | | |
| 37 | | | | | |
| 38 | | | | | |
| 39 | | | | | |
| 40 | | | | | |

5

ALVARADO STATION SHELL
ONE LEVEL TYPE "B"

3-23-83

DAL

| ITEM | DESCRIPTION | UNIT | QTY | PRICE | TOTAL | REMARKS |
|------|---------------|------|------|-------|-----------|-----------|
| (1) | DEMO. | | - | | - | |
| (2) | EXCAVATION | | | | | |
| | EX MACH | | | | 273,000 | |
| | EX HAND | | | | 187,000 | |
| | COMP BF | | 3062 | 100 | 306,200 | |
| | SOIL DISP. | | | | 220,000 | |
| | SOLD PIPE/LAG | | | | 168,000 | |
| | DECK | | | | 55,000 | |
| | DEWATER | | - | | - | |
| | | | | | 3,059,000 | PUSH |
| (3) | UTILITY | | - | | - | |
| (4) | MOB | | - | | - | |
| (5) | (A) FORMS | | - | | - | |
| | (B) CONCRETE | | | | | |
| | PLACE | | | | 254,000 | |
| | SUPPLY | | | | 830,000 | |
| | OVERRUN | | | | 40,000 | |
| | | | | | 1,084,000 | |
| | | | | | 1,198,000 | + 114,000 |

⑥

VERMONT AVE STA

3-23-83

SINGLE TYPE "B"

DRL

567 L 66-8 W 45-10 0

| ITEM | DESCRIPTION | DMJM | PBAQ | KC | CHANGE |
|------|-------------|-----------|-----------|-----------|----------|
| (1) | DEMO | - | - | - | - |
| (2) | EARTHWORK | | | | |
| | EXCAV MACH | | | 312,000 | |
| | EX. HAND | | | 165,000 | |
| | CAMP BF | 3,144,000 | | 50,400 | |
| | SOIL DISP | | | 507,000 | |
| | SOLD PILE | | | 2,040,000 | |
| | DECK | | | 59,000 | |
| | DEWATER | - | | - | - |
| | | | | 3,133,000 | -100,000 |
| (3) | UTILITY | | | | - |
| (4) | MOB | | | | - |
| (5) | CONCRETE | | | | |
| - A- | FORMS | - | | - | - |
| - B- | CONCRETE | | | | |
| | PLACE | | 355,000 | 405,000 | |
| | SUPPLY | | 1,077,000 | 1,077,000 | |
| | OVERRUN | | | 50,000 | |
| | | 1,432,000 | | 1,532,000 | 100,000 |

7

NORMANDIE AVE STA

3-23-83

ONE LEVEL TYPE C

R.O.L.

672 - L 65 W 42 T 64 D

| ITEM DESCRIPTION | | DMJM PB00 | KC | CHANCE |
|------------------|---------------|-----------|-----------|-----------|
| 1 | (1) DEMO | | | - |
| 3 | (2) EARTHWORK | | | |
| 5 | EX. MACH | 378,000 | 605,000 | |
| 6 | EX. HAND | 130,000 | 187,000 | |
| 7 | COMP BF | 750,000 | 750,000 | |
| 8 | SOIL DIMP | 493,000 | 629,000 | |
| 9 | SOLO PILE | 3,208,000 | 2,830,000 | |
| 10 | STAIRS | 170,000 | 170,000 | |
| 11 | DECKING RD | 599,000 | 515,000 | |
| 12 | WALLS | 25,000 | 25,000 | |
| 14 | | | PUSH | |
| 15 | | 5,653,000 | 5,661,000 | + 8,000 |
| 18 | (3) UTIL. | | | - |
| 20 | (4) MOB | | | - |
| 22 | 5 CONCRETE | | | |
| 23 | A FORMS | | | - |
| 25 | B CONC | | | |
| 26 | PLACE | 428,000 | 563,000 | |
| 27 | SUPPLY | 1,225,000 | 1,225,000 | |
| 28 | OVER RUN | | 36,000 | |
| 30 | | 1,653,000 | 1,764,000 | + 111,000 |
| 36 | | | | |
| 39 | | | | |
| 40 | | | | + 17,000 |

8

WESTERN AVE STA

3-24-83

ONE LEVEL TYPE "C"

DDI

660 L x 64-8 W 46-4 T 54-2 0

| ITEM | DESCRIPTION | QTY | UNIT PRICE | TOTAL | DEF. |
|------|------------------|------|------------|-----------|----------|
| 1 | | | | | |
| 2 | (1) DEMO | - | | - | - |
| 3 | | | | | |
| 4 | (2) EARTHWORK | | | | |
| 5 | | | | | |
| 6 | EX MACH | | | 567,000 | |
| 7 | EX HAND | | | 187,000 | |
| 8 | CONC BF | | | 469,000 | |
| 9 | SOIL ASP | | | 625,000 | |
| 10 | SOLD PILE LAG | 4922 | 900 | 2,370,000 | |
| 11 | " SMALL | | | 210,000 | |
| 12 | DECK ROAD | | | 506,000 | |
| 13 | WATER | | | 18,000 | |
| 14 | DEWATER | | | - | - |
| 15 | UNDER PIN | | | - | - |
| 16 | | | | | |
| 17 | | | | 4,952,000 | + 30,000 |
| 18 | | | | | |
| 19 | (3) UTILITIES | | | | - |
| 20 | | | | | |
| 21 | (4) MOBILIZATION | | | | - |
| 22 | | | | | |
| 23 | (5) CONCRETE | | | | |
| 24 | | | | | |
| 25 | (A) FORMS | | | | - |
| 26 | | | | | |
| 27 | (B) CONCRETE | | | | |
| 28 | | | | | + 70 |
| 29 | PLACE | 448 | 000 | 518,000 | |
| 30 | SUPPLY | 1765 | 000 | 1,265,000 | |
| 31 | OVER PIN | | | 40,000 | |
| 32 | | | | | |
| 33 | | | | | |
| 34 | | 1713 | 000 | 1,832,000 | 110,000 |
| 35 | | | | | |
| 36 | | | | | |
| 37 | | | | | |
| 38 | | | | | |
| 39 | | | | | |
| 40 | | | | | |

140,000

9

L A BREA WILSHIRE

3-24 83

DDL

660 L 65 W 45-6 T 5750

| ITEM | DESCRIPTION | DMJM | PB&O | NO | CHANGE |
|------|--------------|------|-----------|-----------|---------|
| (1) | DEMO | | - | - | - |
| (2) | UTILITIES | | | | |
| (3) | MOB. | | | | |
| (4) | CONCRETE | | | | |
| (A) | FORMS | | - | - | - |
| (B) | CONC. | | | | |
| | PLACE | | 472,000 | 547,000 | |
| | SUPPLY | | 1,343,000 | 1,343,000 | |
| | OVER RUN | | - | 40,000 | |
| | | | 1,815,000 | 1,930,000 | 115,000 |
| (5) | WATERPROOF | | | | - |
| (6) | SITE REST. | | | | - |
| (7) | EARTHWORK | | | | |
| | EX MACH. | | | 588,000 | |
| | HAND | | | 187,000 | |
| | CAMP BE | | | 391,000 | |
| | - SOIL DISP. | | 5,037,000 | 6,277,000 | |
| | SOLID PILE | | | 2,520,000 | |
| | SHALLOW | | | 235,000 | |
| | ROAD DECK | | | 506,000 | |
| | WALK DECK | | | 29,000 | |
| | DENATER | | - | - | - |
| | | | | 5,083,000 | 46,000 |
| | | | | | \$ |
| | | | | | 160,000 |

10

FAIRFAX STA. SHELL

3-24-83

DPL

TWO LEVEL TYPE "E"

935' L, 65' W, 66-RT, 24

| ITEM | DESCRIPTION | DM/LM | PB&O | KC | CHANGE |
|------|---------------|-------|----------|----------|--------|
| 1 | (1) DEMO | | - | - | - |
| 2 | (2) EARTHWORK | | | | |
| 3 | EXC. MACH | | | 1099000 | |
| 4 | EXC. HAND | | | 310000 | |
| 5 | COMP BACKFILL | | | 1880000 | |
| 6 | EX. SOIL DISP | | 11757000 | 1627000 | |
| 7 | SOLD PILE LAG | | | 5712000 | |
| 8 | SHORE EXITS | | | 998000 | |
| 9 | DECK RD | | | 716000 | |
| 10 | ENTRIES | | | 61000 | |
| 11 | | | | 12400000 | 646000 |
| 12 | (3) CONCRETE | | | | |
| 13 | (A) FORMS | | - | - | - |
| 14 | (B) CONC. | | | | |
| 15 | PLACE | | 928000 | 1068000 | |
| 16 | SUPPLY | | 2510650 | 2510650 | |
| 17 | OVER RUN | | | 120000 | |
| 18 | | | 3438000 | 3698000 | 260000 |

CAN 200000 ✓

BEVERLY FAIRFAX

11

DDL

685 L 628 W 27-3 T 42

| | ITEM DESCRIPTION | DMJM | PBSD | LCO | DIFF |
|----|------------------|------|-----------|-----------|---------|
| 1 | (1) DEMO | | - | - | - |
| 2 | | | | | |
| 3 | (2) EARTHWORK | | | | |
| 4 | | | | | |
| 5 | | | | | |
| 6 | Ex Mascl | | | 350,000 | |
| 7 | Hand | | | 187,000 | |
| 8 | Comp BE | | 3,839,000 | 487,000 | |
| 9 | Soil Disp | | | 376,000 | |
| 10 | SOLA PIPE | | | 1,883,000 | |
| 11 | DECKING | | | 506,000 | |
| 12 | DEWATER | | - | - | - |
| 13 | | | | | |
| 14 | | | | 3,789,000 | -50,000 |
| 15 | (3) CONCRETE | | | | |
| 16 | | | | | |
| 17 | (A) FORMS | | - | - | - |
| 18 | | | | +90 | |
| 19 | PLACE | | 300,000 | 390,000 | |
| 20 | SUPPLY | | 839,000 | 839,000 | |
| 21 | OVERVIEW | | | 25,000 | |
| 22 | | | | | |
| 23 | | | 1,139,000 | 1,254,000 | 115,000 |
| 24 | | | | | |
| 25 | | | | | |
| 26 | 4 WATERPROOF | | | | - |
| 27 | | | | | |
| 28 | 5 SITE | | | | - |
| 29 | | | | | |
| 30 | 6 UTILITIES | | | | - |
| 31 | | | | | |
| 32 | 7 MOB | | | | - |
| 33 | | | | | |
| 34 | 8 TRAFFIC | | | | - |
| 35 | | | | | |
| 36 | | | | | |
| 37 | | | | | |
| 38 | | | | | |
| 39 | | | | | |
| 40 | | | | | |

650,000

12

SANTA MONICA STR

3/24/83

DDL

680 L 65 W 46-3 45

| ITEM | DESCRIPTION | DMJM | PBAO | KC | CHANGE |
|------|--------------|----------|------|----------|---------------|
| (1) | DEMO | - | - | - | - |
| (2) | EARTHWORK | | | | |
| | Ex MACH | | | 399,000 | |
| | Ex HAND | | | 187,000 | |
| | CAMP BF | | | - | |
| | SOIL DISP | 424,500 | | 654,000 | |
| | SOLD PILE | | | 195,500 | |
| | RO DECK | | | 52,000 | |
| | DECK SW | | | 480,000 | |
| | DEWATER | | | 419,600 | 49,000 |
| 3 | UTILITIES | | | | - |
| 4 | MOBILIZATION | | | | - |
| 5 | CONCRETE | | | | |
| (A) | FORMS | | | | - |
| (B) | CONCRETE | | | | |
| | PLACE | 423,000 | | 488,000 | |
| | SUPPLY | 127,000 | | 127,000 | |
| | QUERRUM | - | | 38,000 | |
| | | 1644,000 | | 1747,000 | 103,000 |
| | | | | | SAY + 150,000 |

13 LA BREA SUNSET

690 L, 65 W, 46-3 T, 55 D

| ITEM | DESCRIPTION | DMJM | PRAD | KC | CHANGE |
|------|---------------|------|----------|----------|-----------|
| 1 | (1) DEMO | | | | — |
| 4 | (2) TRAFFIC | | | | — |
| 6 | (3) EARTHWORK | | | | |
| 8 | (4) EX MACH | | | 518,000 | |
| 9 | EX HAND | | | 187,000 | |
| 10 | COMP BF | | | 297,000 | |
| 11 | SOIL DISP | | 5035000 | 667,000 | |
| 12 | SOLD PILE | | | 2575,000 | |
| 13 | DECK RD | | | 529,000 | |
| 14 | DECK WALK | | | 61,000 | |
| 15 | SOLD PILE SW | | | 245,000 | |
| 17 | | | | 5079,000 | |
| 18 | | | | | 44,000 |
| 21 | (5) UNDERPIN | | | | — |
| 23 | (6) CONCRETE | | | | |
| 25 | (A) FORMS | | | | — |
| 27 | (B) CONCRETE | | | | |
| 29 | PLACE | | 457,000 | 532,000 | |
| 30 | SUPPLY | | 1304,000 | 1304,000 | |
| 31 | OVER RUN | | | 40,000 | |
| 33 | | | 1761,000 | 1876,000 | |
| 34 | | | | | 115,000 |
| 40 | | | | | # 160,000 |

14

690 L 65 W 96-3 T 550

| ITEM | DESCRIPTION | QTY | UNIT | PRICE | TOTAL |
|------|--------------|-----------|------|-----------|-----------|
| (1) | DEMO | | | | - |
| (2) | TRAFFIC | | | | - |
| (3) | EARTHWORK | | | | |
| (4) | EX MACH | | | 469,000 | |
| | EX HAND | | | 187,000 | |
| | COMP 13F | | | 274,000 | |
| | EX MUCK DUMP | | | 614,000 | |
| | SOLD PILE | | | 2,310,000 | |
| | DECK | | | 61,000 | |
| | | 3840,000 | | | |
| | DEWATER | | | - | - |
| | | | | 391,500 | 75,000 |
| (5) | UNDERPIN | | | | |
| (6) | CONCRETE | | | | |
| (A) | FORMS | | | | - |
| (B) | CONCR | | | | |
| | PLACE | | | 407,000 | 467,000 |
| | SUPPLY | | | 1,165,000 | 1,165,000 |
| | OVERRAN | | | - | 36,000 |
| | | 1,572,000 | | 1,668,000 | 96,000 |
| (7) | WATERPROOF | | | | |
| (8) | SITE | | | | - |
| (9) | UTILITY | | | | - |
| (10) | MOR | | | | - |

Price 17,000

630 L 65 W 46 T 550 DOL

| ITEM | DESCRIPTION | QTY | UNIT | PRICE | TOTAL | CHANGE |
|------|-------------|------|------|-------|-----------|---------|
| (1) | DEMO | - | | - | - | - |
| (2) | TRAFFIC | - | | - | - | - |
| (3) | EARTHWORK | | | | | |
| (4) | EX. MACH | | | | 464,000 | |
| | EX. HAND | | | | 187,000 | |
| | COMP. BF | 3783 | 000 | - | 274,000 | |
| | SOIL DISP. | | | | 607,000 | |
| | SOLD. PILE | | | | 2370,000 | |
| | DECK | - | | - | - | |
| | DEWATER | | | | 3,902,000 | 119,000 |
| (5) | UNDERPIN | - | | - | - | - |
| (6) | CONCRETE | | | | | |
| (A) | FORMS | - | | - | - | - |
| (B) | CONCR. | | | | | |
| | PLACE | 403 | 000 | | 473,000 | |
| | SUPPLY | 1152 | 000 | | 1,152,000 | |
| | OVERRUN | - | | - | 36,000 | |
| | | 1555 | 000 | | 1,661,000 | 106,000 |
| (7) | WATER PR | | | | | - |
| (8) | SITE | | | | | - |
| (9) | UTIL | | | | | - |
| (10) | MOB | | | | | - |

275,000

16

NORTH HOLLYWOOD

| ITEM DESCRIPTION | QTY | UNIT PRICE | TOTAL | REMARKS |
|------------------|-----------|------------|-----------|---------|
| (1) DEMO | - | - | - | - |
| (2) EARTHWORK | | | | |
| EX MACH | | | 605,000 | |
| EX HAND | | | 187,000 | |
| COMP BE | | | 750,000 | |
| SOIL DISPOSAL | | | 591,000 | |
| SOLO PILE/LAG | 56520.0 | | 2925,000 | |
| - STAIRS | | | 120,000 | |
| DECKING R/D | | | 515,000 | |
| DECK WALKS | | | 25,000 | |
| DEWATERING | - | - | 5,718,000 | 606,000 |
| (3) UTILITIES | | | | |
| (4) MOB. | | | | |
| (5) | | | | |
| (A) FORM | - | - | - | - |
| (B) CONCRETE | | | | 75 |
| PLACE | 429,000 | | 5,040,000 | |
| SUPPLY | 1,725,000 | | 1,725,000 | |
| OVER RUN | | | 37,000 | |
| | 1,654,000 | | 1,766,000 | 112,000 |
| (6) WATERPROOF | | | | - |
| (7) SITE | | | | - |
| (8) TRAFFIC | | | | - |
| | | | | 175,000 |

CALC

CHECK ESTIMATE

UNION STATION

EARTHWORK:

QUANTITIES Rough Cr:

EXCAV. $640 \times 66.75 \times 34.5 = 54,587 \text{ CY} = 54,525 \checkmark$
DMJM
27

EXCAV. HAND: UNDER DECKING AND AROUND UTILITIES - DMJM ALLOWS APPROX 2 FT THICKNESS - PROBABLY O.K.

COMP. BACKFILL $640 \times 66.75 \times 5.5 = 8700 \text{ CY} - 11,780$
DMJM
27

EXCESS SOIL DISPOSAL

$54,587 - 11,780 = 42,807 \times \text{SWELL FACTOR}$
DMJM
 SAY 30% = 56,300 CY - 59,600 \checkmark

DECKING: $640 \times 66.75 = 42,720 \text{ D}' - 42,670 \checkmark$
DMJM

SOLDIER PILE LAGGING:

$(640 + 640 + 66.75 + 66.75) \times 34.5'$
DMJM
 $= 1413.5 \times 34.5 = 48765 \rightarrow 48760 \checkmark$

DEWATERING: SCHEDULE SHOWS 2 1/2 YEARS TOTAL CONSTRUCTION - DMJM ALLOWS 16 MOS DEWATERING - PROBABLY IN THE ROW AREA 16-18 MOS - O.K.

CHECK ESTIMATE

3

4

5

WESTERN AVE

EARTHWORK:

QUANTITIES ROUGH OK:

EXCAV. 660 x 64.8 x 54.5 = 86,260 - 93830 DMJM

27

+ ENTRANCE -

EXCAV: HAND UNDER DECKING AND @ UTILITIES

HERE DMJM ALLOWS 5% THIS IS ABOUT 3 FT - OK OVERALL

COMP. BACKFILL 660 x 64.75 x 19.5 = 30072 - 29780 DMJM

27

EXCESS SOIL DISP: 98770 - 29780 = 68990 CY x SWELL

SAY 30% = 89687 - 93700 DMJM

DECKING: 660 x 64.75 = 42735 - 42900 DMJM

SOLDIER PILE & LAGGING:

(660 + 660 + 64.75 + 64.75) 54.5

1449.5 x 54.5 = 78,998 - 79,030 DMJM

+ ENTRANCE - OK

DEWATERING: SCHEDULE SHOWS STAGE I AT 7 YEARS - DMJM ALLOWS 18 MONTHS IN THE WET OK.

STATION SHELL CONSTRUCTION - EXCAVATION

SUMMARY

KELLOGG CORPORATION
DIRECT COST ESTIMATE

Sheet 9 of 7 Estm DLK Ckd ✓ ITEM.....

Plan Sheet No..... Bid Quantity.....

Spec. Ref..... Take-off Quantity.....

Item Desc EXCAVATION

JOB SCRTD DATE 3-15-83

WESTERN STATION

FORM E240R HOECKEL'S 336481

| DESCRIPTION | QUANTITY | DIR. LABOR | | REP. LABOR | | MAT'L | | SUB-BID | | E.O.E. | | TOTAL | |
|-------------------------|----------|------------|--------|------------|--------|-------|--------|---------|------------|--------|--------|--|--------|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT |
| REMOVE UPPER | 5000 CY | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| REMOVE NEXT | 8000 CY | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| REMOVE BULK | 86000 CY | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| MISC (SURGE BIN - DUST) | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | \$ 791,526 | | | | |
| | | | | | | | | | | | | KC \$ 791,526 / 99,000 CY = \$ 8.00 / CY. | |
| | | | | | | | | | | | | DMJM \$ 428,200 / 98,770 CY = \$ 4.34 / CY | |

-132-

KELLOGG CORPORATION
DIRECT COST ESTIMATE

Sheet 1 of 7 Estm DPK Ckd ✓ ITEM.....

Plan Sheet No..... Bid Quantity.....

Spec. Ref..... Take-off Quantity 95,830 CY

Item Desc EXCAVATION - MACHINE

JOB SCRIPT DATE 3-15-83

WESTERN STATION

FORM E240R HOECKEL'S 336481

| DESCRIPTION | QUANTITY | DIR. LABOR | | REP. LABOR | | MAT'L | | SUB-BID | | E.O.E. | | TOTAL | |
|--|----------|------------|--------|------------|--------|-------|--------|---------|--------|--------|--------|-------|--------|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT |
| <p><i>ASSUMPTIONS:</i></p> <p><i>THE TOP SEVERAL FEET UNDER DECKING AND AROUND SUSPENDED UTILITIES WILL BE A COMBINATION OF MACHINE AND HAND MUCKING. THIS COULD BE BUCKED UP WITH A COMBINATION OF SMALL LOADERS AND HAND EFFORT AND REMOVED WITH CONVEYORS OR SMALL RUBBER TIED CRANES.</i></p> <p><i>MINE SHAFTS AND MINE HOISTS MIGHT BE EMPLOYED. DEEP CUT -</i></p> <p><i>MUST ASSUME THAT OFF SITE DISPOSAL WILL NOT BE PERMITTED DURING RUSH HOURS ∴ SOME TYPE OF HOLDING BIN OR FACILITY MUST BE CONSTRUCTED TO HOUSE EXCAVATED MATERIAL UNTIL OFF SITE DISPOSAL IS ALLOWED.</i></p> <p><i>FOR THIS ESTIMATE A CONVENTIONAL SPREAD OF DOZERS OR LOADERS (BELOW DECKING) WILL BE EMPLOYED FOR BUCKING MATERIAL TO A CENTRAL SURGE AND CRANE / CLAMSHELL REMOVAL ON THE DECKING WITH OUTRIGGER RUBBER TIRE PILES.</i></p> | | | | | | | | | | | | | |

-133-

KELLOGG CORPORATION
DIRECT COST ESTIMATE

Sheet 2 of 7 Estm. DDL Ckd. ITEM

Plan Sheet No. _____ Bid Quantity _____

JOB SCR TD DATE 3-15-83

Spec. Ref. _____ Take-off Quantity 93,830 CY

WESTERN STATION

Item Desc. EXCAVATION - MACHINE

FORM E240R HOECKEL'S 336481

| DESCRIPTION | QUANTITY | DIR. LABOR | | REP. LABOR | | MAT'L | | SUB-BID | | E.O.E. | | TOTAL | |
|--|----------|------------|--------|------------|--------|-------|--------|---------|--------|--------|--------|-------|--------|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT |
| <p>PIONEER OR DEVELOP 200 PLUS FEET OF THE SOLDIER PILE & DECKED AREA WITH SMALL MACHINE / LOADER AND HAND OPERATION WORKING AROUND UTILITIES TO A DEPTH DEVELOPING A GOOD HEAD ROOM AREA THEN FOLLOW (IN ABOUT 30 DAYS) WITH HEAVY EXCAVATION SPREAD.</p> | | | | | | | | | | | | | |
| <p>DMJM ALLOWED 4940 CY OF HAND OR SHALLOW OPERATION PREDICT WILL NEED 7 FT UNPER DECIC BEAMS OR 8 PLUS FEET TOTAL BEFORE COMPLETELY FREE FOR HEAVY EQUIPMENT MASS OPERATION.</p> | | | | | | | | | | | | | |
| <p>AGREE IN PART W/ ABOVE THAT 5000 CY OR TOP THREE FEET SLOW OR SAY 30 C.Y. /HR TOP EFFICIENCY OR AT 80% SAY 25 C.Y. /HR.</p> | | | | | | | | | | | | | |
| <p>∴ 5000 CY / 25 = 200 HRS - MONTH PLUS OK.</p> | | | | | | | | | | | | | |
| <p>TAKE NEXT 5 FEET OR 8000 ± CY AT 60 C.Y. /HR OR A TOTAL OF 8000/60 = 134 HRS MONTH MINUS OK.</p> | | | | | | | | | | | | | |
| <p>NOTE: TRAFFIC CONTROL & DECK REMOVAL SCHEDULING MUST BE CLOSELY MAINTAINED AS MUCH OF THE ABOVE MUST BE ACHIEVED WITH DECK SECTIONS OFF.</p> | | | | | | | | | | | | | |

KELLOGG CORPORATION
DIRECT COST ESTIMATE

Sheet 3 of 7 Estm. DDL Ckd. ITEM.....

Plan Sheet No..... Bid Quantity.....

JOB SCRIPD DATE 3-15-83

Spec. Ref..... Take-off Quantity 5000 CY

Item Desc EXCAVATION

WESTERN STATION

FORM E240R HOECKEL'S 336481

DEPT ON FOG ADV. ADV.

| DESCRIPTION | QUANTITY | DIR. LABOR | | REP. LABOR | | MAT'L | | SUB-BID | | E.O.E. | | TOTAL | |
|--|----------|------------|------------------|------------------|--------|------------------|--------|----------------------------|--------|----------------------------|--------|------------------|--------|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT |
| REMOVE UPPER 5000 CY / 25 CY = 200 HRS. | 5000 | C.Y. | | OR 3 ± FT | | BELOW DECK. | | | | | | | |
| FOREMAN OPER. | 1 | | 33 ⁰⁰ | - | | - | | 33 ⁰⁰ | | 33 ⁰⁰ | | | |
| 1/2-CY CRANE | 1 | | 63 ⁰⁰ | 47 ⁵⁰ | | 21 ⁴⁰ | | 126 ⁹⁰ | | 176 ⁹⁰ | | | |
| FRONT END LOAD | 1 | | 30 ⁰⁰ | 7 ⁰⁰ | | 5 ⁵⁰ | | 42 ⁵⁰ | | 42 ⁵⁰ | | | |
| DOZER D6 | 1 | | 30 ⁰⁰ | 16 ⁷⁵ | | 13 ²⁵ | | 60⁰⁰ | | 60⁰⁰ | | 60 ⁰⁰ | |
| STINGER CRANE | 1/2 | | 30 ⁰⁰ | 19 ⁵⁰ | | 14 ¹⁰ | | 63 ⁶⁰ | | 31 ⁸⁰ | | | |
| FOREMAN LABOR | 1 | | 28 ⁰⁰ | - | | - | | 28 ⁰⁰ | | 28 ⁰⁰ | | | |
| LABORERS | 3 | | 26 ⁰⁰ | - | | - | | 26 ⁰⁰ | | 78 ⁰⁰ | | | |
| TRUCK | 2 | | 28 ⁰⁰ | 12 ⁵⁰ | | 17 ⁰⁰ | | 57 ⁵⁰ | | 115 ⁰⁰ | | | |
| P.U. | 1 | | - | 2 ⁷⁰ | | 3 ⁰⁰ | | 5 ⁹⁰ | | 5 ⁹⁰ | | | |
| SMALL TOOLS | | | | | | | | | | 521 ¹⁰ | | | |
| | | | | | | | | | | 10 ⁰⁰ | | | |
| | | | | | | | | | | 531 ¹⁰ | | | |
| | | | | | | | | | | 531 ¹⁰ | | | OK |

∴ 200 HRS @ $531^{10}/HR = 106,220$ ✓
531¹⁰

-135-

KELLOGG CORPORATION
DIRECT COST ESTIMATE

Sheet 4 of 7 Estm. DPL Ckd ITEM

Plan Sheet No. _____ Bid Quantity _____

Spec. Ref. _____ Take-off Quantity _____

Item Desc. EXCAVATION

JOB SCRTD DATE 3-15-83

WESTERN STATION

FORM E240R HOECKEL'S 336481

DEPT OR FDG ADJ.

| DESCRIPTION | QUANTITY | DIR. LABOR | | REP. LABOR | | MAT'L | | SUB-BID | | E.O.E. | | TOTAL | |
|--|----------|------------|------------------|------------------|------------------|-------------------|-------------------|------------------|------------------|--------|--------|-------------------|--|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT |
| REMOVE HEAD ROOM AREA OR 8000 ± C.Y. BELOW DECK. | | | | | | | | | | | | | |
| 8000 / 60 = 134 HRS. | | | | | | | | | | | | | |
| FOREMAN OPER | 1 | | 33 ⁰⁰ | - | - | - | - | 33 ⁰⁰ | 33 ⁰⁰ | | | | |
| 1 1/2 CY CRANE | 1 | | 63 ⁰⁰ | 42 ⁵⁰ | 21 ⁴⁰ | 126 ⁹⁰ | 126 ⁹⁰ | | | | | | |
| FRONT END LOAD. | 1 | | 30 ⁰⁰ | 7 ⁰⁰ | 5 ⁵⁰ | 42 ⁵⁰ | 42 ⁵⁰ | | | | | | |
| DOZER D6 | 1 | | 30 ⁰⁰ | 16 ⁷⁵ | 13 ²⁵ | 50 ⁰⁰ | 50 ⁰⁰ | | | | | | |
| DOZER D8 | 1 | | 30 ⁰⁰ | 44 ⁰⁰ | 31 ⁰⁰ | 105 ⁰⁰ | 105 ⁰⁰ | | | | | | |
| STINGER CRANE 1/2 | 1/2 | | 30 ⁰⁰ | 19 ⁵⁰ | 14 ¹⁰ | 63 ⁶⁰ | 31 ⁸⁰ | | | | | | |
| FOREMAN LAB | 1 | | 28 ⁰⁰ | - | - | 28 ⁰⁰ | 28 ⁰⁰ | | | | | | |
| LABORERS | 2 | | 26 ⁰⁰ | - | - | 26 ⁰⁰ | 54 ⁰⁰ | | | | | | |
| TRUCK | 2 | | 28 ⁰⁰ | 12 ⁵⁰ | 17 ⁰⁰ | 57 ⁵⁰ | 115 ⁰⁰ | | | | | | |
| P.U. | 1 | | - | 27 ⁰⁰ | 3 ⁰⁰ | 59 ⁰⁰ | 59 ⁰⁰ | | | | | | |
| | | | | | | | | | | | | 592 ¹⁰ | ✓ |
| SMALL TOOLS | | | | | | | | | | | | 10 ⁰⁰ | |
| | | | | | | | | | | | | 602 ¹⁰ | |
| | | | | | | | | | | | | \$ | |
| | | | | | | | | | | | | ∴ | 134 HRS @ 602 ¹⁰ /HR = 80,681 |

-136-

KELLOGG CORPORATION
DIRECT COST ESTIMATE

Sheet 5 of 7 Estm DDC Ckd ITEM

Plan Sheet No. Bid Quantity

Spec. Ref. Take-off Quantity

Item Desc. EXCAVATION

JOB SCRTP DATE 3-15-83

WESTERN STATION

FORM E240R HOECKEL'S 336481

| DESCRIPTION | QUANTITY | DIR. LABOR | | REP. LABOR | | MAT'L | | SUB-BID | | E.O.E. | | TOTAL | |
|--|----------|------------|--------|------------|--------|-------|--------|---------|--------|--------|--------|-------|--------|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT |
| <p>DMJM SHOWS A TOTAL OF 98,770 CY OF STATION EXCAVATION.</p> <p>REMOVAL OF TOP 8 FT = 13,000 CY OR CALL 86,000 CY OF EXCAVATION BY HEAVY OR MASS REMOVAL.</p> <p>USING A 3 1/2 CY. BUCKET AND ALLOWING A SWELL FACTOR. OR SAY 110,000 CY EXCAVATION</p> <p>CYCLE TIME TO MID DEPTH OF CUT SAY 30 FEET ALLOW ONE MIN AT 100% EFFICIENCY.</p> <p>SAY 80% EFFICIENCY. = CALL 1 1/4 MIN CYCLE @ 3 CY = 144 CY / HR</p> <p>110,000 CY @ 144 CY / HR = 765 HRS MUCK TIME.</p> <p>100 WORK DAYS ON SINGLE SHIFT OR MULTIPLE IF PERMITTED. (ALLOW 1 WK. UP TO SPEED)</p> <p>4 MONTHS TOTAL EXCAVATION -</p> <p>PROBABLY WOULD GO 5-10s OR 6-9s AND ACCOMPLISH IN 3 MOS.</p> | | | | | | | | | | | | | |

-137-

KELLOGG CORPORATION
DIRECT COST ESTIMATE

Sheet 6 of 7 Estm. DDL Ckd. ✓ ITEM.....

Plan Sheet No..... Bid Quantity.....

Spec. Ref..... Take-off Quantity.....

Item Desc. EXCAVATION

JOB SCRTD DATE 3-15-80

FORM E240R HOECKEL'S 936481

DEPT. ON FOG ADJ.

| DESCRIPTION | QUANTITY | DIR. LABOR | | REP. LABOR | | MAT'L | | SUB-BID | | E.O.E. | | TOTAL | |
|--|----------|------------|------------------|------------|------------------|-------|------------------|---------|-------------------|--------|-------------------|---------------------------------|--------|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT |
| EXCAVATE HEAVY. | | | | | | | | | | | | | |
| 11000 CY EXCAV @ 144 CY/HR = 765 HRS OPER. | | | | | | | | | | | | | |
| FOREMAN OPER | 1 | | 33 ⁰⁰ | - | - | - | - | | 33 ⁰⁰ | | 33 ⁰⁰ | | |
| CRANE 3 1/2 C.Y. | 1 | | 63 ⁰⁰ | | 95 ⁵² | | 48 ⁰⁰ | | 206 ⁵⁰ | | 206 ⁵⁰ | | |
| D 6 DOZER | 1 | | 30 ⁰⁰ | | 16 ⁷⁵ | | 13 ²⁵ | | 60 ⁰⁰ | | 60 ⁰⁰ | | |
| STINGER CRANE | 1 | | 30 ⁰⁰ | | 19 ⁵⁰ | | 14 ¹⁰ | | 63 ⁶⁰ | | 63 ⁶⁰ | | |
| D 8 DOZERS | 1 | | 30 ⁰⁰ | | 44 ⁰⁰ | | 31 ⁰⁰ | | 105 ⁰⁰ | | 105 ⁰⁰ | | |
| FOREMAN LAB | 1 | | 28 ⁰⁰ | | - | | - | | 28 ⁰⁰ | | 28 ⁰⁰ | | |
| LABORERS | 2 | | 26 ⁰⁰ | | - | | - | | 26 ⁰⁰ | | 52 ⁰⁰ | | |
| FLAEMEN - DUMPMEN | 2 | | 26 ⁰⁰ | | - | | - | | 26 ⁰⁰ | | 52 ⁰⁰ | | |
| DUMP TRUCKS | 2 | | 28 ⁰⁰ | | 12 ⁵⁰ | | 17 ⁰⁰ | | 57 ⁵⁰ | | 115 ⁰⁰ | | |
| PICK UP. | 2 | | - | | 2 ⁰⁰ | | 3 ⁰⁰ | | 5 ⁰⁰ | | 5 ⁰⁰ | | |
| | | | | | | | | | | | 721 ⁰⁰ | | |
| SMALL TOOLS | | | | | | | | | | | 4 ⁰⁰ | | |
| | | | | | | | | | | | 725 ⁰⁰ | | |
| | | | | | | | | | | | | ∴ 765 HRS @ 725/HR = \$ 554,625 | |

-138-

STATION SHELL CONSTRUCTION - SOLDIER PILE AND LAGGING

SUMMARY

**KELLOGG CORPORATION
DIRECT COST ESTIMATE**

Sheet 0 of Estm 22 Ckd. ITEM.....

Plan Sheet No. Bid Quantity.....

JOB SCRTP DATE 3-16-83

Spec. Ref. Take-off Quantity.....

WESTERN STATION

Item Desc. SOLDIER PILE / LAGGING

FORM E240R HOECKEL'S 330481

| DESCRIPTION | QUANTITY | DIR. LABOR | | REP. LABOR | | MAT'L | | SUB-BID | | E.O.E. | | TOTAL | |
|------------------|--------------|------------|--------|------------|--------|-------|--------|---------|--------|--------|--------|-------|---------------------|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT |
| DRILL PILING | (SHEET # 4) | | | | | | | | | | | | 185,060 |
| PILE SEATING | (SHEET # 5) | | | | | | | | | | | | 205,070 |
| LAGGING / STRUTS | (SHEET # 6) | | | | | | | | | | | | 393,260 |
| MATERIALS | (SHEET # 7) | | | | | | | | | | | | 1,614,440 |
| | | | | | | | | | | | | | <u>\$ 2,397,830</u> |
| KC | \$ 2,397,830 | | | 80,000 | = | 29.97 | | | | | | | CALL # 30.00 |
| DMJM | \$ 2,687,000 | | | 79,030 | = | 34.00 | | | | | | | 10' |

KELLOGG CORPORATION
DIRECT COST ESTIMATE

Sheet 1 of 7 Estm. DRK Ckd. ITEM.....

Plan Sheet No. Bid Quantity.....

JOB SCRTP DATE 3-15-83

Spec. Ref. Take-off Quantity 88,000 B'

WESTERN STATION

Item Desc. SOLDIER PILE LAGGING

FORM E240R HOECKEL'S 336491

| DESCRIPTION | QUANTITY | DIR. LABOR | | REP. LABOR | | MAT'L | | SUB-BID | | E.O.E. | | TOTAL | |
|---|----------|------------|--------|------------|--------|-------|--------|---------|--------|--------|--------|-------|--------|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT |
| <u>SOLDIER PILE & LAGGING.</u> | | | | | | | | | | | | | |
| THE ASSUMPTIONS FOR SOLDIER PILE & LAGGING: | | | | | | | | | | | | | |
| PILING TO BE PLACED ON 8 FT. CENTERS WITH THE HOLES PREDRILLED TO NEAR INVERT AND THE FINAL 10 FT STUCK OR DRIVEN. | | | | | | | | | | | | | |
| PIPE OR STRUCTURAL STRUTS SPANNING THE EXCAVATION WILL BE SPACED AT 14 FT. CTES VERTICALLY THEREFORE WESTERN WILL HAVE A PILE CAP STRUT (SUPPORTING THE DECKING) PLUS 3 STRUT LAYERS SPACED AS EXCAVATION PROGRESSES. | | | | | | | | | | | | | |
| LAGGING ASSUMED SOLID WILL BE 3" TO 4" THICK AS DEPTH INCREASES. | | | | | | | | | | | | | |
| LONG. GIRDERS WILL CARRY LOADING AS REQUIRED. | | | | | | | | | | | | | |
| NOTE & MAKE ALLOWANCE. | | | | | | | | | | | | | |
| NOTE: NO OVERHEADS TO HAMPER OPERATIONS | | | | | | | | | | | | | |

-141-

KELLOGG CORPORATION
DIRECT COST ESTIMATE

Sheet 2 of 7 Estm. Ckd. ITEM

Plan Sheet No. Bid Quantity

Spec. Ref. Take-off Quantity 88,000 lb

Item Desc. SOLDIER PILE / BRACING

JOB SCRTD DATE 3-15-83

WESTERN STATION

FORM E240R HOECKEL'S 336461

| DESCRIPTION | QUANTITY | DIR. LABOR | | REP. LABOR | | MAT'L | | SUB-BID | | E.O.E. | | TOTAL | |
|--|----------|------------|--------|------------|--------|-------|--------|---------|--------|--------|--------|-------|--------|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT |
| | | | | | | | | | | | | | |
| <p>84 PILING EACH FACE</p> <p>PRE DRILLED PILING 186 EACH</p> <p>186 x 65 = 12,100 FT. @ 120 # / FT. = 730 TON</p> <p>STRUTS 106 EACH @ 65' = 7000 FT @ 80# 280 TON</p> <p>GIRDERS / WHALERS = 2800 FT @ 150 # = 210 TON</p> <p>PLUS CAPS - CLIPS ETC - CALL 1300 DN</p> | | | | | | | | | | | | | |

KELLOGG CORPORATION
DIRECT COST ESTIMATE

Sheet 3 of 7 Estm. DR Ckd. ITEM.....

Plan Sheet No..... Bid Quantity.....

JOB SCRID DATE 3-16-83 Spec. Ref..... Take-off Quantity 80,000 ft'

Item Desc. SOLDIER PILE LAGGING

FORM E240R HOECKEL'S 395481

| DESCRIPTION | QUANTITY | DIR. LABOR | | REP. LABOR | | MAT'L | | SUB-BID | | E.O.E. | | TOTAL | |
|---|----------|------------|--------|------------|--------|-------|--------|---------|--------|--------|--------|-------|--------|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT |
| <p>THE PRE DRILLED PILING HOLES WILL BE DRILLED AT A RATE OF 4 HOLES PER DAY AFTER UP TO SPEED.</p> <p>186 HOLES @ 4 = 46.5 DAYS. ALLOW BREAK IN = 1 WEEK CALL 52 SHIFTS</p> <p>AS A SPECIALIZED ITEM THE PILE EXCAVATION & DRIVING WILL PROBABLY BE A SUB CONTRACT ITEM.</p> <p>ASSUME THE HOLES DRILLED & CAPPED AND THAT THE PILE SETTING, & STICKING WILL FOLLOW BY APPROX 3-4 WEEKS AS THIS OPERATION SHOULD PROCEED AT 8 ± PILE PER DAY (TWICE AS FAST)</p> <p>THE STUCK PILE HOLES WILL THEN BE FILLED WITH LEAN CONCRETE</p> <p>LAGGING, OF COURSE WILL FOLLOW EXCAVATION DOWN - BY SMALL CREW.</p> | | | | | | | | | | | | | |

KELLOGG CORPORATION
DIRECT COST ESTIMATE

Sheet 4 of 7 Estm DD Ckd ✓ ITEM

Plan Sheet No. _____ Bid Quantity _____

JOB SCRIP DATE 3-16-83

Spec. Ref. _____ Take-off Quantity 80,000 ft

Item Desc. SOLDIER PILE / LAGAINS

WESTERN STATION
DEP 90M FOG

FORM E240R HOECKEL'S 336481

| DESCRIPTION | QUANTITY | DIR. LABOR | | REP. LABOR | | MAT'L | | SUB-BID | | E.O.E. | | TOTAL | |
|----------------------|----------|------------|------------------|------------|------------------|-------|------------------|---------|-------------------|--------|--------|-------|-------------|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT |
| <u>DRILL PILING</u> | | | | | | | | | | | | | |
| FOREMAN | 420 | HR | 35 ⁰⁰ | | | | | | 35 ⁰⁰ | | | | 14,700 ✓ |
| DRILL RIG | 420 | | | | 72 ⁰⁰ | | 38 ⁰⁰ | | 110 ⁰⁰ | | | | 46,200 ✓ |
| OPERATOR | 420 | | 33 ⁰⁰ | | | | | | 33 ⁰⁰ | | | | 13,860 ✓ |
| OILER | 420 | | 28 ⁰⁰ | | | | | | 28 ⁰⁰ | | | | 11,760 ✓ |
| RIGGER | 420 | | 30 ⁰⁰ | | | | | | 30 ⁰⁰ | | | | 12,600 ✓ |
| PILE BUTTS | 840 | | 26 ⁰⁰ | | | | | | 26 ⁰⁰ | | | | 21,840 ✓ |
| FLAT BED | 420 | | 23 ⁰⁰ | | 7 ⁰⁰ | | 44 ⁰⁰ | | 39 ⁴⁰ | | | | 16,550 ✓ |
| DUMP TRUCK | 420 | | 28 ⁰⁰ | | 12 ⁵⁰ | | 17 ⁰⁰ | | 57 ⁵⁰ | | | | 24,150 ✓ |
| FLAGMAN | 420 | | 26 ⁰⁰ | | | | | | 26 ⁰⁰ | | | | 10,920 ✓ |
| PICK UP | 420 | | | | 2 ⁷⁰ | | 3 ²⁰ | | 5 ⁹⁰ | | | | 2,480 ✓ |
| MISC. DRILL SUPPLIES | | | | | | | | | | | | | 10,000 ✓ |
| | | | | | | | | | | | | | # 185,060 ✓ |

-144-

KELLOGG CORPORATION
DIRECT COST ESTIMATE

Sheet 5 of 7 Estm 224 Ckd ITEM.....

Plan Sheet No..... Bid Quantity.....

JOB SCRIP DATE 3-16-83

Spec. Ref..... Take-off Quantity.....

WESTERN STATION

Item Desc. SOLDIER PILE / LAFRING

FORM E240R HOECKEL'S 336491

DEPT 04 FIG

| DESCRIPTION | QUANTITY | DIR. LABOR | | REP. LABOR | | MAT'L | | SUB-BID | | E.O.E. | | TOTAL | |
|---|----------|------------|------------------|------------------|------------------|------------------|--------|---------|--------|-------------------|--------|-------------------------|--------------------|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT |
| <u>PILE SEATING</u> | | | | | | | | | | | | | |
| FOREMAN | 300 Hr | | 35 ⁰⁰ | | | | | | | 35 ⁰⁰ | | | 10500 [✓] |
| PILE DRIVER | 300 | | | 140 ⁻ | | 110 ⁻ | | | | 250 ⁰⁰ | | | 75000 [✓] |
| OPERATOR | 300 | | 33 ⁰⁰ | | | | | | | 33 ⁰⁰ | | | 9900 [✓] |
| OILER | 300 | | 28 ⁰⁰ | | | | | | | 28 ⁰⁰ | | | 8400 [✓] |
| RIGGER | 300 | | 30 ⁰⁰ | | | | | | | 30 ⁰⁰ | | | 9000 [✓] |
| PILE BUTTS | 900 | | 26 ⁰⁰ | | | | | | | 26 ⁰⁰ | | | 23400 [✓] |
| FLATBED | 300 | | 28 ⁰⁰ | | 7 ⁰⁰ | 44 ⁰⁰ | | | | 39 ⁴⁰ | | | 11820 [✓] |
| BOOM TUGGER | 300 | | 28 ⁰⁰ | | 16 ⁰⁰ | 8 ⁴⁰ | | | | 52 ⁴⁰ | | | 15720 [✓] |
| FLAGMAN | 300 | | 26 ⁰⁰ | | | | | | | 26 ⁰⁰ | | | 7800 [✓] |
| PICK UP | 300 | | - | | 2 ⁷⁰ | 3 ²⁰ | | | | 5 ⁹⁰ | | | 1770 [✓] |
| WELDER | 300 | | 30 ⁰⁰ | | 3 ²⁰ | 6 ⁰⁰ | | | | 39 ²⁰ | | | 11760 [✓] |
| <u>MISC DRIVE SUPPLIES - WELD - CABLE - HOORS - RIGGING -</u> | | | | | | | | | | | | 20000 [✓] | |
| | | | | | | | | | | | | \$ 205,070 [✓] | |

-145-

KELLOGG CORPORATION
DIRECT COST ESTIMATE

Sheet 6 of 7 Estm DDLCkd ITEM

Plan Sheet No. Bid Quantity

Spec. Ref. Take-off Quantity

Item Desc. SOLDIER PILE-LAG

JOB SCRIPT DATE 3-16-83

DEP-OH FOG

FORM E240R HOECKEL'S 335481

| DESCRIPTION | QUANTITY | DIR. LABOR | | REP. LABOR | | MAT'L | | SUB-BID | | E.O.E. | | TOTAL | |
|---|-------------|-----------------|------------------------|----------------------------|------------------------|----------------|--------|-------------------------|------------------------|-----------------|--------|-------------------|---------------|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT |
| <u>LAGGING / STRUT</u> | | <u>SPREAD</u> | | <u>GEAR TO EXCAVATION:</u> | | | | | | | | | |
| <u>EXCAVATION</u> | | <u>1099 HRS</u> | | <u>5%</u> | | <u>OVERLAP</u> | | <u>CALL</u> | | <u>1050 HRS</u> | | | |
| <u>FOREMAN</u> | <u>1050</u> | | <u>35⁰⁰</u> | | | | | | <u>35⁰⁰</u> | | | | <u>36750-</u> |
| <u>CRANE (SINGER)</u> | <u>1050</u> | | <u>32⁰⁰</u> | <u>19⁵⁰</u> | <u>14⁰⁰</u> | | | <u>65⁶⁰</u> | | | | | <u>68880</u> |
| <u>CRANE - PICK -</u> | <u>200</u> | <u>(CREW)</u> | <u>91⁰⁰</u> | <u>72⁰⁰</u> | <u>38⁰⁰</u> | | | <u>201⁰⁰</u> | | | | | <u>40200</u> |
| <u>FLAT RACK</u> | <u>1050</u> | | <u>28⁰⁰</u> | <u>7⁰⁰</u> | <u>44⁰⁰</u> | | | <u>394⁰⁰</u> | | | | | <u>41370</u> |
| <u>LABORERS</u> | <u>3150</u> | | <u>26⁰⁰</u> | | | | | <u>26⁰⁰</u> | | | | | <u>81900</u> |
| <u>IRON WORKERS</u> | <u>2100</u> | | <u>30⁰⁰</u> | | | | | <u>30⁰⁰</u> | | | | | <u>63000</u> |
| <u>WELDER</u> | <u>1050</u> | | <u>30⁰⁰</u> | <u>3²⁰</u> | <u>6⁰⁰</u> | | | <u>39²⁰</u> | | | | | <u>41160</u> |
| <u>MISC SUPPLIES - WELDING - SLINGS - WEDGING</u> | | | | | | | | | | | | <u>20000</u> | |
| | | | | | | | | | | | | <u>\$ 393,260</u> | |

KELLOGG CORPORATION
DIRECT COST ESTIMATE

Sheet 7 of 7 Estm. DRL Ckd. ITEM.....

Plan Sheet No..... Bid Quantity.....

Spec. Ref..... Take-off Quantity.....

Item Desc. SOLDIER PILE LAGGING

JOB SCRIP DATE 3-16-83

WESTERN STATION

FORM E240R HOECKEL'S 336481

| DESCRIPTION | QUANTITY | DIR. LABOR | | REP. LABOR | | MAT'L | | SUB-BID | | E.O.E. | | TOTAL | |
|-------------------------|----------|------------|--------|------------|--------|-------|--------|---------|--------|--------|--------|-----------|-----------|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT |
| <u>MATERIALS</u> | | | | | | | | | | | | | |
| <u>STRUCTURAL STEEL</u> | | | | | | | | | | | | | |
| SHAPES | 1300 TON | | | | | 1000 | ° | | | | | 1,300,000 | |
| GUSS-CLIPS | 5% | | | | | | | | | | | 65000 | |
| <u>TIMBER</u> | | | | | | | | | | | | | |
| LAGGING | 280 M | | | | | 500 | ° | | | | | 140,000 | |
| WEDGES | | | | | | | | | | | | 5000 | |
| <u>CONCRETE</u> | | | | | | | | | | | | | |
| FILL HOLES | 1860 CT. | | | | | 40 | ° | | | | | 74,440 | |
| <u>MISC.</u> | | | | | | | | | | | | | |
| | | | | | | | | | | | | 30000 | |
| | | | | | | | | | | | | | 1,614,440 |

STATION SHELL CONSTRUCTION - DECKING

SUMMARY

KELLOGG CORPORATION
DIRECT COST ESTIMATE

Sheet 1 of 1 Estm DL Ckd 1 ITEM
Plan Sheet No. _____ Bid Quantity _____
Spec. Ref. _____ Take-off Quantity 42,900 sq'
Item Desc. DECOR

JOB SCRTD DATE 3-11-83
WESTERN AVE STATION

FORM E240R HOBCKEL'S 336481

| DESCRIPTION | QUANTITY | DIR. LABOR | | REP. LABOR | | MAT'L | | SUB-BID | | E.O.E. | | TOTAL | |
|--|-------------------|------------|--------|------------|--------|-------|--------|---------|--------|--------|----------------|-------|--------|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT |
| DECORING ROADWAY | 42,900 sq' | | | | | | | | | | | | |
| DECORING WALKWAY | 3,000 sq' | | | | | | | | | | | | |
| | <u>45,900 sq'</u> | | | | | | | | | | | | |
| KC DECORING INSTALLATION & MAINT. | | | | | | | | | | \$ | 483,636 | | |
| NON SKID APPLICATION 50% AREA @ 250 = 22950 @ 250 | | | | | | | | | | | 57,375 | | |
| | | | | | | | | | | \$ | <u>541,011</u> | | |
| KC | 541,000 | / | 45,900 | = | 11 79 | / | sq'. | | | | | | |
| DMJM | 606,600 | / | 45,900 | = | 13 22 | / | sq'. | | | | | | |

KELLOGG CORPORATION
DIRECT COST ESTIMATE

Sheet 1 of 4 Estm DD Ckd 1 ITEM

Plan Sheet No. Bid Quantity

JOB SCRIP DATE 3-16-83

Spec. Ref. Take-off Quantity 42,900 sq'

Item Desc DECKING

WESTERN STATION

FORM E240R HOECKEL'S 338481

| DESCRIPTION | QUANTITY | DIR. LABOR | | REP. LABOR | | MAT'L | | SUB-BID | | E.O.E. | | TOTAL | |
|---|------------|------------|--------|------------|--------|-------|--------|---------|--------|--------|--------|--------------------------|--------|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT |
| <p>THE DECKING WILL BE DOUGLAS FIR - STRUCTURAL GRADE - 12" X 12" CABLED TOGETHER IN SECTIONS RANGING FROM 12 TO 20 FOOT SECTIONS. THE SECTIONS INSTALLED TO PROVIDE SEATING THAT WILL ALLOW UNIFORM TRAFFIC FLOW AND YET PROVIDE EASY REMOVAL AND RESEATING.</p> <p>CITY TRAFFIC CONTROL MAY REQUIRE THAT SOME NON SKID PROVISION BE REQUIRED FOR RAINY WEATHER / SLIPPERY CONDITIONS.</p> | | | | | | | | | | | | | |
| TAKE OFF: | 660 x 65 = | 42,900 | | | | | | | | | | 42,900 sq' | ✓ |
| SIDEWALK ALLOWANCE | | | | | | | | | | | | 3000 sq' | |
| | | | | | | | | | | | | 42,900 sq' x 12" THICK = | 515 M. |

-149-

KELLOGG CORPORATION
DIRECT COST ESTIMATE

Sheet 2 of 4 Estm 226 Ckd V ITEM

Plan Sheet No. _____ Bid Quantity _____

JOB SCRTD DATE 3-16-83

Spec. Ref. _____ Take-off Quantity _____

WESTERN STATION

Item Desc. DECKING

FORM E240R HOECKEL'S 336481

| DESCRIPTION | QUANTITY | DIR. LABOR | | REP. LABOR | | MAT'L | | SUB-BID | | E.O.E. | | TOTAL | |
|--|----------|------------|--------|------------|--------|-------|--------|---------|--------|--------|--------|-------|--------|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT |
| <p>MAKE UP STREET DECKING SECTIONS:</p> <p>THE 12 X 12 TIMBERS WILL BE THREADED WITH $\frac{5}{8}$ INCH CABLE INTO SECTIONS OR SQUARES TO FIT THE CONTRACTOR'S SELECTED PILE CAP / STRINGER CONFIGURATION.</p> <p>FOR ESTIMATING USE 16' FT SQUARE SECTIONS.</p> <p>$42,900 \text{ sq' } / 256 = \text{CALL } 170 \text{ SECTIONS.}$</p> <p>MAKE UP DECKING - DECKING, FOR THE MOST PART WILL BE REHANDLED BY EXCAV. / PILE CREWS. HOWEVER MAKE SOME ALLOWANCE</p> | | | | | | | | | | | | | |

-150-

KELLOGG CORPORATION
DIRECT COST ESTIMATE

Sheet 3 of 4 Estm DDK Ckd V ITEM

Plan Sheet No. _____ Bid Quantity _____

JOB SCRTD DATE 3-16-83

Spec. Ref. _____ Take-off Quantity _____

WESTERN STATION

Item Desc. DECKING

DEP-OH FOG

FORM E240R HOECKEL'S 336481

| DESCRIPTION | QUANTITY | DIR. LABOR | | REP. LABOR | | MAT'L | | SUB-BID | | E.O.E. | | TOTAL | |
|--|-----------------|------------|------------------------|------------------------|--------|------------------------|--------|------------|------------------------|--------|--------|----------|---------------------------|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT |
| <i>STREET DECICKING</i> | | | | | | | | | | | | | |
| <i>MATERIAL & ASSEMBLY</i> | | | | | | | | | | | | | |
| <i>MAKE UP INSTALL REFIT 4 PER DAY</i> | | | | | | | | | | | | | |
| <i>MTLS:</i> | | | | | | | | | | | | | |
| <i>DECKING STREET</i> | <i>515M</i> | | | | | | | <i>600</i> | | | | | <i>30900</i> |
| <i>DECKING SIDEWALK</i> | <i>10M</i> | | | | | | | <i>500</i> | | | | | <i>5000</i> |
| <i>CABLE</i> | <i>12000 LF</i> | | | | | | | | | | | | <i>18000</i> |
| <i>CLAMPS / SHAYLES</i> | <i>LS</i> | | | | | | | | | | | | <i>4000</i> |
| <i>CREW:</i> | | | | | | | | | | | | | |
| <i>FOREMAN</i> | <i>340 HR</i> | | <i>33⁰⁰</i> | | | | | | <i>33⁰⁰</i> | | | | <i>11220</i> |
| <i>CRANE SMALL</i> | <i>340 HR</i> | | <i>30⁰⁰</i> | <i>19⁵⁰</i> | | <i>14¹⁰</i> | | | <i>63⁶⁰</i> | | | | <i>21624</i> |
| <i>CARPENTERS (2)</i> | <i>680 HR</i> | | <i>28⁰⁰</i> | | | | | | <i>28⁰⁰</i> | | | | <i>19040</i> |
| <i>LABORER</i> | <i>340 HR</i> | | <i>26⁰⁰</i> | | | | | | <i>26⁰⁰</i> | | | | <i>8840</i> |
| <i>SM. TOOLS</i> | <i>L.S.</i> | | | | | | | | | | | | <i>2000</i> |
| <i>FLAT-BED</i> | <i>340 HR</i> | | <i>28⁰⁰</i> | <i>7⁰⁰</i> | | <i>44⁰⁰</i> | | | <i>39⁴⁰</i> | | | | <i>13396⁰⁰</i> |
| <i>DECK-REHANDLE ALLOW</i> | | | | | | | | | | | | | <i>-0-</i> |
| | | | | | | | | | | | | <i>#</i> | <i>412120</i> |

-151-

(PAGE 4)

KELLOGG CORPORATION
DIRECT COST ESTIMATE

Sheet 4 of 4 Estm DD Ckd ITEM.....

Plan Sheet No..... Bid Quantity.....

JOB 5 CRTD DATE 3-16-83

Spec. Ref..... Take-off Quantity.....

WESTERN STATION

Item Desc DECKING

FORM E240R HOEGL'S 330481

DEC. FOG

| DESCRIPTION | QUANTITY | DIR. LABOR | | REP. LABOR | | MAT'L | | SUB-BID | | E.O.E. | | TOTAL | |
|--|--------------|------------|------------------|------------|------------------|-----------------|------------------|---------|------------------|--------|--------|-------|----------|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT |
| PAGE 3 FORWARD | | | | | | | | | | | | \$ | 412120 ✓ |
| WALKWAY DECKING | | | | | | | | | | | | | |
| CARD FORE | 60 Hr | | 33 ⁰⁰ | | | | | | 33 ⁰⁰ | | | | 1980 ✓ |
| CARPENTERS | 120 | | 28 ⁰⁰ | | | | | | 28 ⁰⁰ | | | | 3360 ✓ |
| LABORER | 60 | | 26 ⁰⁰ | | | | | | 26 ⁰⁰ | | | | 1560 ✓ |
| FLATRACK | 60 | | 28 ⁰⁰ | | 7 ⁰⁰ | 4 ¹⁰ | | | 39 ¹⁰ | | | | 2364 ✓ |
| SM. TOOLS | LS. | | | | | | | | | | NIL | | - |
| REHANDLE DECKING ALLOW 8 HRS / WK FOR DECKED PERIOD SAY 18 MO. | | | | | | | | | | | | | |
| FOREMAN FROM MAIN SPREAD | | | | | | | | | | | | | |
| CRANE | 620 HR | | 30 ⁰⁰ | | 19 ⁵⁰ | | 14 ¹⁰ | | 63 ⁶⁰ | | | | 39432 ✓ |
| PICK MAN | 620 HR | | 26 ⁰⁰ | | | | | | 26 ⁰⁰ | | | | 16120 ✓ |
| CARPENTER | 20% / 150 HR | | 28 ⁰⁰ | | | | | | 28 ⁰⁰ | | | | 4200 ✓ |
| MISC | | | | | | | | INCL | SM. TOOLS | | | | 2500 ✓ |
| | | | | | | | | | | | | \$ | 483636 ✓ |

STATION SHELL CONSTRUCTION - CONCRETE

STATION CONCRETE STUDY

| STATION | DIRECTION | 1 | 2 | 3 | 4 | 5 | 6 | 7 | 8 | 9 | 10 | 11 | 12 | 13 |
|---------|---------------|--------|--------|-------|-------|---------|-------|-------|------------|------------|--------|---------|----------|----------|
| | | WALLS | WALLS | FLEV | GRADE | COLUMNS | BEAMS | BLUES | TOTAL | TOTAL | TOTAL | TOTAL | CONCRETE | CONCRETE |
| | | 2 1/2" | 7 1/2" | SEALS | SLABS | PILLARS | | | CONCRETE | FINISH/10' | REBAR | | | |
| CY | CY | CY | CY | CY | CY | CY | WALLS | CY | FORM RATIO | RATIO | \$ | \$/CY | | |
| 1 | UNION STATION | 6 | 275 | 7617 | 6716 | 10453 | 592 | 708 | 615 | 29122 | 252926 | 583840 | 6142550 | 210 |
| 2 | 1ST & HILL | E | 2191 | 12937 | 8375 | 7876 | 812 | 2102 | 43 | 34311 | 446721 | 720560 | 8007000 | 235 |
| 3 | 5TH & HILL | E | 2316 | 15699 | 9541 | 12262 | 957 | 2801 | 43 | 43582 | 522170 | 7124350 | 10174450 | 232 |
| 4 | 7TH & FLOWER | A | 402 | 9087 | 5402 | 8920 | 388 | 1640 | 43 | 25247 | 260652 | 5162400 | 5387450 | 208 |
| 5 | WILSHIRE/ALY. | B | 575 | 1048 | 6310 | 6029 | 632 | - | 1810 | 15764 | 148729 | 3192400 | 2952100 | 186 |
| 6 | VERMONT | C | 267 | 2810 | 4810 | 10175 | 1330 | 1111 | - | 22827 | 122583 | 3144600 | 4062700 | 195 |
| 7 | NORMANDIE | C | 594 | 3387 | 4251 | 8624 | 3702 | 1846 | 615 | 23557 | 279200 | 4114300 | 5249850 | 222 |
| 8 | WESTERN | C | 1084 | 3772 | 4781 | 8733 | 2042 | 2224 | 1842 | 24321 | 281881 | 4802400 | 5472000 | 220 |
| 9 | LA BREA | C | 1024 | 3747 | 6149 | 9140 | 3641 | 1843 | 615 | 25817 | 279221 | 5163300 | 5477000 | 221 |
| 10 | FAIRFAX | E | 943 | 18090 | 10645 | 10679 | 1142 | 3014 | 5565 | 48180 | 474124 | 7656000 | 10722500 | 222 |
| 11 | BEVERLY | B | 272 | 4402 | 1622 | 7074 | 350 | 1448 | 902 | 16116 | 185707 | 3222300 | 3709450 | 220 |
| 12 | SANTA MONICA | C | 544 | 4028 | 4774 | 8727 | 3752 | 1624 | - | 23329 | 284623 | 4425800 | 5335800 | 227 |
| 13 | SUNSET | | 578 | 4366 | 5017 | 8855 | 3807 | 1831 | 615 | 25072 | 282676 | 5814400 | 5635750 | 225 |
| 14 | HOLLYWOOD | | 596 | 3219 | 4532 | 8150 | 3503 | 1796 | 615 | 22411 | 263292 | 4323700 | 5191650 | 227 |
| 15 | UNV CITY | | 590 | 3176 | 4174 | 8085 | 3476 | 1752 | 615 | 22143 | 253604 | 4439000 | 4737800 | 214 |
| 16 | N. HOLLYWOOD | | 544 | 3387 | 4835 | 8624 | 3702 | 1846 | 615 | 23557 | 274820 | 4712000 | 5725900 | 242 |

-153-

KELLOGG CORPORATION
 DIRECT COST ESTIMATE

Sheet 1 of 1 Estm DDC Ckd ✓ ITEM.....
 Plan Sheet No..... Bid Quantity.....
 Spec. Ref..... Take-off Quantity.....
 Item Desc. CONCRETE SUMMATION

JOB SCRIPD DATE 3-17-83
WESTERN AVE STATION

FORM E240R HOECKEL'S 896481

| DESCRIPTION | QUANTITY | DIR. LABOR | | REP. LABOR | | MAT'L | | SUB-BID | | E.O.E. | | TOTAL | |
|---|--------------------|------------|--------|------------|--------|-------|--------|---------|--------|--------|--------|-------|--------|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT |
| RECOMMEND THAT AN ALLOWANCE FOR OVERRUN CONCRETE BE MADE. | | | | | | | | | | | | | |
| NEAT LINE | 24331 CY | | | | | | | | | | | | |
| | ADDED 1000 CY @ 4% | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| UNIT PRICING OF MASS CONCRETE ABOUT 20%. | | | | | | | | | | | | | |
| | LIGHT 15483 C.Y. | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |

-154-

KELLOGG CORPORATION
DIRECT COST ESTIMATE

Sheet 1 of 12 Estm. DDL Ckd. ✓ ITEM.....

Plan Sheet No..... Bid Quantity.....

JOB SCRIP DATE 3-17-83

Spec. Ref..... Take-off Quantity.....

WESTERN STATION

Item Desc. CONCRETE

FORM E240R HOECKEL'S 336481

| DESCRIPTION | QUANTITY | DIR. LABOR | | REP. LABOR | | MAT'L | | SUB-BID | | E.O.E. | | TOTAL | | |
|------------------------|---------------------------------|------------|--------|------------|--------|-------|--------|---------|--------|--------|--------|-------|--------|--|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | |
| TAKE OFF - QUANTITIES: | | | | | | | | | | | | | | |
| WALL FORMS: | $(660 + 660 + 65 + 65)$ | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | |
| INTERIOR | $(400 + 240)$ | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | |
| DMJM | $14,550 + 9940 + 52,680 + 4050$ | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | |
| TOTAL FORMS | 281,840 sq' ✓ | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | |
| TOTAL CONCRETE | 24,331 C.Y. ✓ | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | |
| FORM RATIO | $= 281,840 / 24,331 = 11.58$ | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | |
| REBAR RATIO | USED 197# DMJM SAYS 200 OK. | | | | | | | | | | | | | |

-155-

KELLOGG CORPORATION
DIRECT COST ESTIMATE

Sheet 2 of 12 Estm. DK Ckd. ✓ ITEM.....

Plan Sheet No..... Bid Quantity.....

JOB SCRIP DATE 3-17-83

Spec. Ref..... Take-off Quantity.....

WESTERN STATION.

Item Desc. CONCRETE

FORM E240R HOECKEL'S 339481

| DESCRIPTION | QUANTITY | DIR. LABOR | | REP. LABOR | | MAT'L | | SUB-BID | | E.O.E. | | TOTAL | |
|---|----------|------------|--------------|------------|--------|-------|--------|---------|--------|--------|--------|-------|----------------------|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT |
| <i>TOTAL IN WESTERN AVENUE FOR CONCRETE & APPURT.</i> | | | | | | | | | | | | | |
| FORMS: | | | 1,758,700 | | | | 24,331 | = | | | | | 72 ²⁸ |
| CONCRETE: | | | 1,714,900 | | | | 24,331 | = | | | | | 70 ⁴⁸ |
| CURE | | | 13,900 | | | | 24,331 | = | | | | | 57 |
| FINISH | | | 186,500 | | | | 24,331 | = | | | | | 7 ⁶⁷ |
| | | | \$ 3,674,000 | | | | 24,331 | = | | | | | \$ 151 ⁰⁰ |
| REBAR | | | \$ 1,825,000 | | | | 24,331 | = | | | | | \$ 75 ⁰⁰ |
| | | | 5,499,000 | | | | 24,531 | = | | | | | \$ 226 ⁰⁰ |

-156-

KELLOGG CORPORATION
DIRECT COST ESTIMATE

Sheet 3 of 17 Estm. 100 Ckd. ✓ ITEM.....

Plan Sheet No..... Bid Quantity.....

JOB..... SCRTD DATE 3-17-83

Spec. Ref..... Take-off Quantity.....

WESTERN AVE STA.

Item Desc..... CONCRETE

FORM E240R HOECKEL'S 336491

| DESCRIPTION | QUANTITY | DIR. LABOR | | REP. LABOR | | MAT'L | | SUB-BID | | E.O.E. | | TOTAL | |
|--|-----------------|------------|--------|------------|--------|-----------------------------|-----------------|---------|--------|--------|--------|-------------------|--------|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT |
| <i>CONCRETE:</i> | | | | | | | | | | | | | |
| <i>TOTAL CONCRETE</i> | | | | | | <i>24,331 CY.</i> | | | | | | | |
| <i>MASS TO SEMI MASS CONCRETE OR CONCRETE</i> | | | | | | | | | | | | | |
| <i>THAT CAN BE PLACED AT HIGH RATE OF PRODUCTION</i> | | | | | | | | | | | | | |
| <i>GRADE SLAB</i> | <i>8783 CY</i> | | | | | <i>36%</i> | <i>OF TOTAL</i> | | | | | <i>FAST/CRANE</i> | |
| <i>EXTERIOR WALLS</i> | <i>4858 CY.</i> | | | | | <i>20%</i> | <i>OF TOTAL</i> | | | | | <i>SEMI FAST</i> | |
| <i>BLAST WALLS</i> | <i>1842 CY</i> | | | | | <i>8%</i> | <i>OF TOTAL</i> | | | | | <i>" "</i> | |
| | | | | | | <i>64% FAIRLY HI SPEED.</i> | | | | | | | |
| <i>NOTE: THIS CONCRETE WILL REQUIRE SOME TYPE OF LOWERING WITH CRANE & TRUNKED INTO THE WALL SECTIONS.</i> | | | | | | | | | | | | | |

-157-

KELLOGG CORPORATION
DIRECT COST ESTIMATE

Sheet 4 of 12 Estm DDLCkd ITEM.....

Plan Sheet No..... Bid Quantity.....

JOB SCRTD DATE 3-17-93 Spec. Ref..... Take-off Quantity.....

Item Desc. CONCRETE

WESTERN AVE STATION

FORM E240R HOECKEL'S 336481

| DESCRIPTION | QUANTITY | DIR. LABOR | | REP. LABOR | | MAT'L | | SUB-BID | | E.O.E. | | TOTAL | |
|--|----------|------------|--------|------------|--------|-------|--------|---------|--------|--------|--------|-------|--------|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT |
| <p>SPREAD TO PLACE A PORTION OF THE INVERT SLAB - THIS SLAB CONTAINS A NEAT LINE QUANTITY OF 8783 CUBIC YARDS - ASSUME BULK HEAD OFF AND POUR OUT IN 4 - WEEKS OR AT RATE OF 440 NEAT PER POUR. $440 + 5\% \text{ OVERRUN} = 465 \text{ CY.}$</p> <p>PLACING RATE - SET UP POUR FOR 10 HR DAY WITH A 9 HR PRODUCTION.</p> <p>ALLOW ONE HOUR CLEAN UP & READY POUR</p> <p>$465 / 9 = 52 \text{ CY. / HR.}$</p> <p>CONCRETE CAN BE LOWERED AND 90% PLACED DIRECTLY IN PLACE.</p> <p>ALLOW SOME IRISH BUGGY & CHUTE WORK.</p> <p>52 CY. / HR WITH A 3 CY BUCKET PAY</p> <p>$2\frac{1}{2} \text{ CY} = 52 / 2.5 = 21 \text{ CYCLES PER HR.}$</p> <p>$60 \text{ MIN} / 21 = 3 \text{ MIN CYCLE @ 100\% EFF}$</p> <p><small>Unit = 30 ... 21.5 ... 45 ... = 21 MIN - 75% EFF OR</small></p> | | | | | | | | | | | | | |

KELLOGG CORPORATION
DIRECT COST ESTIMATE

Sheet 5 of 12 Estm DD Ckd ✓ ITEM

Plan Sheet No. Bid Quantity

Spec. Ref. Take-off Quantity

Item Desc CONCRETE

04-Dec FOG

JOB SCRTP DATE 3-17-83

WESTERN AVE STA

FORM E240R HOECKEL'S 3364B1

| DESCRIPTION | QUANTITY | DIR. LABOR | | REP. LABOR | | MAT'L | | SUB-BID | | E.O.E. | | TOTAL | |
|-----------------------------|-----------|--------------|------------------------|------------------------|-----------------------|------------------------|--------------------------------|-------------------------|----------|--------|--------|-------|----------------------------|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT |
| <u>INVERT SLAB PLACING.</u> | | | | | | <u>440</u> | <u>CY</u> | <u>NEAT</u> | | | | | |
| <u>DECK CREW</u> | | | | | | | | | | | | | |
| FOREMAN | <u>10</u> | <u>HR</u> | <u>35⁰⁰</u> | | | | | <u>35</u> | <u>-</u> | | | | <u>350</u> |
| CRANE | <u>10</u> | <u>HR</u> | | <u>98⁰⁰</u> | | <u>51⁰⁰</u> | | <u>149⁵⁰</u> | | | | | <u>1495</u> |
| OPER | <u>16</u> | <u>HR</u> | <u>33⁰⁰</u> | | | | | <u>33⁰⁰</u> | | | | | <u>330</u> |
| OILER | <u>10</u> | <u>HR</u> | <u>30⁰⁰</u> | | | | | <u>30⁰⁰</u> | | | | | <u>300</u> |
| HOOKEMAN | <u>10</u> | <u>HR</u> | <u>28⁰⁰</u> | | | | | <u>28⁰⁰</u> | | | | | <u>280</u> |
| P.U. | <u>10</u> | <u>HR</u> | | <u>2⁰⁰</u> | | <u>3⁰⁰</u> | | <u>59⁰⁰</u> | | | | | <u>60</u> |
| <u>INVERT CREW</u> | | | | | | | | | | | | | |
| FOREMAN | <u>10</u> | <u>HR</u> | <u>35⁰⁰</u> | | | | | <u>35⁰⁰</u> | | | | | <u>350</u> |
| VICKADORMEN | <u>3</u> | <u>30 HR</u> | <u>29⁰⁰</u> | | <u>3⁵⁰</u> | <u>2⁶⁰</u> | | <u>35¹⁰</u> | | | | | <u>1053</u> |
| LABORERS | <u>3</u> | <u>30 HR</u> | <u>28⁰⁰</u> | | | | | <u>28⁰⁰</u> | | | | | <u>840</u> |
| CARPENTER | <u>10</u> | <u>HR</u> | <u>30⁰⁰</u> | | | | | <u>30⁰⁰</u> | | | | | <u>300</u> |
| <u>BUGGIES - CHUTES ETC</u> | | | | | | | | | | | | | |
| OVER RUN CONOR | | | | | | <u>20</u> | <u>CY @ 50.</u> | | | | | | <u>100</u> |
| | | | | | | | | | | | | | <u>1000</u> |
| | | | | | | | | | | | | | <u># 6458⁰⁰</u> |
| | | | | | | <u>6458</u> | <u>/ 440 = 14⁶⁸</u> | | | | | | |

-159-

KELLOGG CORPORATION
DIRECT COST ESTIMATE

Sheet 6 of 17 Estm. DDL Ckd. _____ ITEM _____

Plan Sheet No. _____ Bid Quantity _____

JOB SCRTD DATE 3-17-83

Spec. Ref. _____ Take-off Quantity _____

WESTERN AVE STATION

Item Desc. CONCRETE

FORM E240R HOECKEL'S 336481

| DESCRIPTION | QUANTITY | DIR. LABOR | | REP. LABOR | | MAT'L | | SUB-BID | | E.O.E. | | TOTAL | |
|---|----------|------------|--------|------------|--------|-------|--------|---------|--------|--------|--------|-------|--------|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT |
| <u>ELEVATED SLAB PLACING.</u> | | | | | | | | | | | | | |
| <p>THE ELEVATED SLABS ARE SLIGHTLY LESS MASSIVE THAN THE INVERT SLAB -</p> <p>SAY 2 FT FOR ROOF AND 12" FOR MEZZANINE WITH 8 INCH FOR PLATFORM.</p> <p>THE SLABS WILL MOSTLY HAVE TWO LAYERS OF REBAR HENCE REDUCING PRODUCTIVITY AND VIBRATION REQUIREMENTS WILL BE INCREASED.</p> <p>SAY 60% PRODUCTION ATTAINED WHEN RELATED TO THE INVERT.</p> <p>WITH PROPER SCHEDULING, HOWEVER, PLACING FROM THE TOP DECK SHOULD OFFER NO GREAT PROBLEM</p> <p>CYCLE INCREASED TO 5 MIN AT EFFICIENCY</p> <p>9 HRS @ 2 1/2 CY X 12 = 270 C.Y. / HR SAY 10 CY OVERRUN.</p> | | | | | | | | | | | | | |

-160-

KELLOGG CORPORATION
DIRECT COST ESTIMATE

Sheet 7 of 17 Estm DDL Ckd ITEM.....
 Plan Sheet No.....Bid Quantity.....
 Spec. Ref.....Take-off Quantity.....
 Item Desc. CONCRETE

JOB. SCRTD DATE 3-17-83

WESTERN AVE STA.

FORM E240R HOECKEL'S 336491

| DESCRIPTION | QUANTITY | DIR. LABOR | | REP. LABOR | | MAT'L | | SUB-BID | | E.O.E. | | TOTAL | |
|------------------|----------|------------|--------|------------|--------|-------|--------|---------|--------|--------|--------|-------|--------|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT |
| <u>TAKE OFF</u> | | | | | | | | | | | | | |
| <u>TOP DECK.</u> | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |

$580 \times 50 \times 2 = 58000 \text{ CF.}$

$470 \times 30 \times \frac{1}{2} = 21150 \text{ CF}$

$450 \times 28 \times .75 = 9450 \text{ CF}$

$88600 \text{ CF} / 27 = 3280 \text{ CY.}$

$QMLM = 4781 \text{ (} 50\% \text{ MORE SLAB THICKNESS)}$

∴ ASSUME ELEVATED SLAB THICKNESS

AVERAGE = 2 FT OVERALL

STILL IN RATHER MASSIVE POURS.

∴ CALL 80% PRODUCTION, OR 4 MIN CYCLE
 $15 \text{ EA } @ 2\frac{1}{2} \text{ CY } @ 9 \text{ HR} = 337 \text{ C.Y.}$

KELLOGG CORPORATION
DIRECT COST ESTIMATE

Sheet 8 of 12 Estm. DD Ckd. ITEM

Plan Sheet No. _____ Bid Quantity _____

JOB SCRIP DATE 3-17-88

Spec. Ref. _____ Take-off Quantity _____

Item Desc. CONCRETE

WESTERN AVE STATION

FORM E240R HOECKEL'S 335481

| DESCRIPTION | QUANTITY | DIR. LABOR | | REP. LABOR | | MAT'L | | SUB-BID | | E.O.E. | | TOTAL | |
|-----------------------------|----------------|------------|--------|------------|--------|----------------------|--------|-------------------------|--------|--------|--------|-----------------------------|-------------|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT |
| <u>ELEVATED SLAB SPREAD</u> | | | | | | <u>337 CY / NEAT</u> | | | | | | | |
| <u>DECK CREW</u> | | | | | | | | | | | | | |
| <u>FOREMAN</u> | <u>10 HR</u> | | | | | | | <u>35</u> | | | | | <u>350</u> |
| <u>CRANE</u> | <u>10 HR</u> | | | | | | | <u>149⁵⁰</u> | | | | | <u>1495</u> |
| <u>OPER</u> | <u>10 HR</u> | | | | | | | <u>33⁰⁰</u> | | | | | <u>330</u> |
| <u>OILER</u> | <u>10 HR</u> | | | | | | | <u>30⁰⁰</u> | | | | | <u>300</u> |
| <u>HOOKMAN</u> | <u>10 HR</u> | | | | | | | <u>28⁰⁰</u> | | | | | <u>280</u> |
| <u>PU</u> | <u>10 HR</u> | | | | | | | <u>5⁰⁰</u> | | | | | <u>60</u> |
| <u>INVERT CREW</u> | | | | | | | | | | | | | |
| <u>FOREMAN</u> | <u>10 HR</u> | | | | | | | <u>35⁰⁰</u> | | | | | <u>350</u> |
| <u>VIBRATOR MEN</u> | <u>20</u> | | | | | | | <u>35⁰⁰</u> | | | | | <u>700</u> |
| <u>LABORERS</u> | <u>30</u> | | | | | | | <u>28⁰⁰</u> | | | | | <u>840</u> |
| <u>CARP</u> | <u>10</u> | | | | | | | <u>30⁰⁰</u> | | | | | <u>300</u> |
| <u>BUCKIES CHUTES</u> | | | | | | | | | | | | | <u>100</u> |
| <u>OVER RUN</u> | <u>10 C.Y.</u> | | | | | | | | | | | | <u>500</u> |
| | | | | | | | | | | | | <u>\$ 5605⁰⁰</u> | |

$5605 / 337 = 16⁶⁵$

-162-

KELLOGG CORPORATION
DIRECT COST ESTIMATE

Sheet 9 of 12 Estm. DDL Ckd. ✓ ITEM.....

Plan Sheet No..... Bid Quantity.....

Spec. Ref..... Take-off Quantity.....

Item Desc. CONCRETE

JOB SCRTD DATE 3-17-83

WESTERN AVE STATION

FORM E240R HOECKEL'S 336481

| DESCRIPTION | QUANTITY | DIR. LABOR | | REP. LABOR | | MAT'L | | SUB-BID | | E.O.E. | | TOTAL | |
|---|----------|------------|--------|------------|--------|----------|--------|---------|--------|--------|--------|-------|--------|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT |
| COLUMN TAKE OFF | 34 EA | | | | | | | | | | | | |
| FROM DWG - GP-A16 COLUMNS SEEM TO | | | | | | | | | | | | | |
| BE 18" TO 24" MAX. | | | | | | | | | | | | | |
| 30 COLUMNS | 32.75 = | 982.5 FT | } | | TOTAL | 1046 FT. | | | | | | | |
| 4 COLUMNS | 16' = | 64 FT | | | | | | | | | | | |
| SAY 24" THEN: | | | | | | | | | | | | | |
| $1046 \times \frac{2 \times 2 \pi}{4} = 3286 / 27 = 122 \text{ C.Y.}$ | | | | | | | | | | | | | |
| DMSM HAS 343 C.Y. | | | | | | | | | | | | | |
| $1046 \times \frac{\pi \times \pi}{4} = 9261 \text{ CF.}$ | | | | | | | | | | | | | |
| $\pi^2 = 4 \times 9261 / 1046 \pi = 11.27$ | | | | | | | | | | | | | |
| $\sqrt{11.27} = \underline{40" \text{ COLUMNS}}$ | | | | | | | | | | | | | |

KELLOGG CORPORATION
DIRECT COST ESTIMATE

Sheet 10 of 12 Estm DDL Ckd ITEM

Plan Sheet No. _____ Bid Quantity _____

JOB SCRIP DATE 3-17-83 Spec. Ref. _____ Take-off Quantity _____

Item Desc. CONCRETE

WESTERN AVE STA
REP-OH FIG

FORM E240R HOECKEL'S 336481

| DESCRIPTION | QUANTITY | DIR. LABOR | | REP. LABOR | | MAT'L | | SUB-BID | | E.O.E. | | TOTAL | |
|---|-----------------|------------|------------------|------------|------------------|-------|------------------|---------|------------------|--------|--------|-------|--------|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT |
| COLUMN SPREAD | 10 CY / COLUMN. | | | | | | | | | | | | |
| MOST COLUMNS 33 FT - REQUIRE WINDOWS & SAFEWAY SCAFFOLDING - TOP OUT IN PLATFORM SUSPENDED FROM DECK. | | | | | | | | | | | | | |
| STEEL FORMS 4 EACH - REUSE FOR TOTAL. | | | | | | | | | | | | | |
| WHYNOT SPRING FORM - TWO-LIFT & BUSH HAMMER. | | | | | | | | | | | | | |
| 4 COLS SET UP PLACE IN DAY | | | | | | | | | | | | | |
| 40 CY. 42 CY TOTAL. | | | | | | | | | | | | | |
| TOP- | | | | | | | | | | | | | |
| FOREMAN | 10 HR | | 35 ⁰⁰ | | | | | | 35 ⁰⁰ | | | | 350- |
| STINGER CRANE | 10 ↓ | | 63 ⁰⁰ | | 19 ⁵⁰ | | 14 ¹⁰ | | 96 ⁶⁰ | | | | 960- |
| HOOKMAN | 10 ↓ | | 28 ⁰⁰ | | 2 ⁰⁰ | | 3 ⁰⁰ | | 5 ⁰⁰ | | | | 60- |
| P-U | 10 ↓ | | | | | | | | | | | | |
| PIER-COL. | | | | | | | | | | | | | |
| FOREMAN (ABOVE) | 10 HR | | 29 ⁰⁰ | | 3 ⁰⁰ | | 2 ⁰⁰ | | 35 ¹⁰ | | | | 350- |
| VIBRATOR | 10 ↓ | | 28 ⁰⁰ | | | | | | | | | | 280- |
| LABORER | 10 ↓ | | 30 ⁰⁰ | | | | | | | | | | 300- |
| CARP. | | | | | | | | | | | | | |
| MISC. SCAFFOLD RENT - CHUTE TRUNK - | | | | | | | | | | | | | 100- |
| CONCR OVERRUN | 2 CY @ 50 | | | | | | | | | | | | 100- |
| | | | | | 2500 / 40 = | | 62 ⁰⁰ | | | | | | 7.500- |

-164-

KELLOGG CORPORATION
DIRECT COST ESTIMATE

Sheet 11 of 17 Estm. DD Ckd. X ITEM.....

Plan Sheet No. Bid Quantity.....

JOB. SCRIP DATE 3-17-83

Spec. Ref. Take-off Quantity.....

WESTERN AVE STATION

Item Desc. CONCRETE

FORM E240R HOECKEL'S 396491

| DESCRIPTION | QUANTITY | DIR. LABOR | | REP. LABOR | | MAT'L | | SUB-BID | | E.O.E. | | TOTAL | |
|--|----------|------------|--------|------------|--------|-------|--------|---------|--------|--------|--------|-------|--------|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT |
| <p>WALL POOR -</p> <p>PROVIDE 2 WINDOWS PER POOR</p> <p>GET 3-50 FT SECTIONS / 9 HR</p> <p>OR 3 HR. PER SECTION.</p> <p>SCAFFOLD & WINDOW -</p> <p>TOP OUT FROM DECK</p> <p>$120 \text{ FT} \times 34 \text{ FT} \times 1.25 / 27 = 189 \text{ CY NEAR}$</p> <p>EACH SECTION 63 CY + 3 CY OVERRUN</p> <p>66 CY IN 3 HRS</p> <p>2 CY / SWING WOULD REQUIRE 11 / HR</p> <p>11 / 2 65 - HALF FROM DECK @ 4 MIN</p> <p>CYCLE (COULD GO DIRECT BY CHUTE).</p> <p>9 HRS - TO GET 200 CY - 55 MIN CYCLE</p> <p>4 @ TOP 7 MIN @ WINDOW GR</p> | | | | | | | | | | | | | |

KELLOGG CORPORATION
DIRECT COST ESTIMATE

Sheet 12 of 12 Estm DDL Ckd ✓ ITEM.....
Plan Sheet No.....Bid Quantity.....
Spec. Ref.....Take-off Quantity.....
Item Desc. CONCRETE

JOB SCR TD DATE 3-17-83
WESTERN AVE. STATION

FORM E240R HOECKEL'S 336481

| DESCRIPTION | QUANTITY | DIR. LABOR | | REP. LABOR | | MAT'L | | SUB-BID | | E.O.E. | | TOTAL | |
|-----------------------|--------------|---|--------|------------|--------|-------|--------|-------------------------|--------|--------|--------|-------|-------------|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT |
| <u>WALL SPREAD.</u> | | <u>MUST PERMIT MIDWAY JOINTS OR WINDOW THE POURS.</u> | | | | | | | | | | | |
| | | <u>ASSUME NO JOINT & WINDOW - SCAFFOLD REQD.</u> | | | | | | | | | | | |
| <u>DECK CREW</u> | | | | | | | | | | | | | |
| <u>FOREMAN</u> | <u>10 Hr</u> | | | | | | | <u>35⁰⁰</u> | | | | | <u>350</u> |
| <u>CRANE OPER</u> | <u>10</u> | | | | | | | <u>149⁰⁰</u> | | | | | <u>1495</u> |
| <u>OILER</u> | <u>10</u> | | | | | | | <u>33⁰⁰</u> | | | | | <u>330</u> |
| <u>HOOKMAN</u> | <u>10</u> | | | | | | | <u>30⁰⁰</u> | | | | | <u>300</u> |
| <u>P.U.</u> | <u>10</u> | | | | | | | <u>28⁰⁰</u> | | | | | <u>280</u> |
| | | | | | | | | <u>5⁰⁰</u> | | | | | <u>60</u> |
| <u>WINDOW CREW</u> | <u>10</u> | | | | | | | | | | | | |
| <u>FOREMAN</u> | <u>10 Hr</u> | | | | | | | <u>35⁰⁰</u> | | | | | <u>350</u> |
| <u>VIBRATORS</u> | <u>20</u> | | | | | | | <u>35⁰⁰</u> | | | | | <u>700</u> |
| <u>LABORERS</u> | <u>30</u> | | | | | | | <u>28⁰⁰</u> | | | | | <u>840</u> |
| <u>CARPENTER</u> | <u>10</u> | | | | | | | <u>30⁰⁰</u> | | | | | <u>300</u> |
| <u>SCAFFOLD CHUTE</u> | | | | | | | | | | | | | <u>100</u> |
| <u>OVER RUN CONC.</u> | <u>10 CY</u> | | | | | | | | | | | | <u>500</u> |
| | | | | | | | | | | | | | <u>5605</u> |
| | | | | | | | | | | | | | <u>5605</u> |

5605 / 189 = 2966

-166-

STATION SHELL CONSTRUCTION - MUCK REMOVAL

KELLOGG CORPORATION
DIRECT COST ESTIMATE

Sheet 1 of 2 Estm DDL Ckd..... ITEM.....

Plan Sheet No..... Bid Quantity.....

Spec. Ref..... Take-off Quantity 93,000 CY

Item Desc. EXCESS MUCK REMOVAL

JOB SCRIPD DATE 3-15-83
WESTERN

FORM E240R HOECKEL'S 336481

| DESCRIPTION | QUANTITY | DIR. LABOR | | REP. LABOR | | MAT'L | | SUB-BID | | E.O.E. | | TOTAL | |
|--|----------|------------|--------|------------|--------|-------|--------|---------|--------|--------|--------|-------|--------|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT |
| EXCESS MUCK - OFF SITE DISPOSAL. | | | | | | | | | | | | | |
| GEAR OPERATION TO EXCAVATION @ 144 CY/HR. | | | | | | | | | | | | | |
| TRUCK HAULS 18 CY. OR 20 CY WITH SWELL FACTOR. | | | | | | | | | | | | | |
| CYCLE PER TRUCK 90 MIN = 1 1/2 HOURS - AT OFF PEAK HAULING - WILL GET 4 TO 5 TRIPS / DAY - SAY 5 | | | | | | | | | | | | | |
| AT 12 CY/HR TO GET 150 CY/HR = 13 TRUCKS (1/2 STANDBY) | | | | | | | | | | | | | |
| AT 5 TRIPS/DAY/TRUCK IN ONE DAY SPREAD WILL HAUL | | | | | | | | | | | | | |
| 5 X 18 CY X 13 TRUCKS = 1170 CY / DAY = 146/HR OK | | | | | | | | | | | | | |
| ∴ 13 TRUCKS RENTED FOR 93,000 CY AT 12 CY PER TRUCK HOUR = 7750 TRUCK HRS. | | | | | | | | | | | | | |
| SAY 170 TRUCK HRS = ONE TRUCK MONTH ∴ 7750 / 170 = 46 TRUCK MONTHS | | | | | | | | | | | | | |
| 46 / 13 = 4 - TRUCK MOS = EXCAVATION SPREAD. | | | | | | | | | | | | | |

-167-

KELLOGG CORPORATION
DIRECT COST ESTIMATE

Sheet 2 of 2 Estm. DDLCkd ITEM.....

Plan Sheet No..... Bid Quantity.....

Spec. Ref..... Take-off Quantity 93,000 CY

Item Desc.....

JOB SCRTD DATE 3-15-83

WESTERN

FORM E240R HOECKEL'S 336481

-168-

| DESCRIPTION | QUANTITY | DIR. LABOR | | REP. LABOR | | MAT'L | | SUB-BID | | E.O.E. | | TOTAL | |
|---|----------|------------|--------|------------|--------|-------|--------|---------|--------|--------|--------|-------|--------|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT |
| <i>EXCESS MUCK - OFF SITE DISPOSAL</i> | | | | | | | | | | | | | |
| <i>SPREAD</i> | | | | | | | | | | | | | |
| <i>FOREMAN (EXCAVATION SPREAD FOREMAN OK)</i> | | | | | | | | | | | | | |
| <i>FRONT END LOADER</i> | | | | | | | | | | | | | |
| <i>TRUCK RENTAL</i> | | | | | | | | | | | | | |
| <i>13 EA @ 4 MO</i> | | | | | | | | | | | | | |
| <i>13 EA @ 3600 @ 4 MO. =</i> | | | | | | | | | | | | | |
| <i>OPERATION COSTS</i> | | | | | | | | | | | | | |
| <i>TRUCKS 7750 HRS 28⁰⁰ — 20⁰⁰ 48⁰⁰ 372,000</i> | | | | | | | | | | | | | |
| <i>LOADER 600 HRS 30⁰⁰ 24⁵⁰ 2180 76³⁰ 45,780</i> | | | | | | | | | | | | | |
| <i>DUMP MAN 600 HRS 26⁰⁰ — — 26⁰⁰ 15,600</i> | | | | | | | | | | | | | |
| <i>620,580 / 93,000 = 6.67</i> | | | | | | | | | | | | | |
| <i>DMJM</i> | | | | | | | | | | | | | |
| <i>\$ 620,580 → \$ 521,900</i> | | | | | | | | | | | | | |
| <i>(NOTE: POSSIBLE CREDIT - IF SELL MUCK)</i> | | | | | | | | | | | | | |

\$ 187,700

\$ 620,580

STATION SHELL CONSTRUCTION - DEMOLITION

SUMMARY

KELLOGG CORPORATION
DIRECT COST ESTIMATE

Sheet 0 of Estm. DM Ckd. ITEM

Plan Sheet No. Bid Quantity

Spec. Ref. Take-off Quantity

Item Desc. DEMOLITION

JOB SCRTD DATE 3-18-83

WESTERN AVE STATION

FORM E240R HOECKEL'S 336481

-169-

| DESCRIPTION | QUANTITY | DIR. LABOR | | REP. LABOR | | MAT'L | | SUB-BID | | E.O.E. | | TOTAL | |
|--------------------------|------------|------------|--------|------------|--------|-------|--------|---------|--------|--------|--------|-----------------|-----------|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT |
| AC PAVING | (SHEET #1) | | | | | | | | | | | | \$ 7200 ✓ |
| - OK - IF AC ONLY - | | | | | | | | | | | | | |
| CONCRETE SLABS | (SHEET #1) | | | | | | | | | | | | 3512 ✓ |
| CONCRETE CURBS | (SHEET #2) | | | | | | | | | | | | 1256 ✓ |
| TRAFFIC/STREET LIGHTS | (SHEET #2) | | | | | | | | | | | | 11600 ✓ |
| TRAFFIC MUST BE MAIN. | | | | | | | | | | | | | |
| MANHOLES | (SHEET #3) | | | | | | | | | | | | 8718 ✓ |
| SIGNS | (SHEET #4) | | | | | | | | | | | | 250 ✓ |
| PARKING METERS | (SHEET #4) | | | | | | | | | | | | 950 ✓ |
| FIRE HYDRANTS | (SHEET #4) | | | | | | | | | | | | 1500 ✓ |
| MASONRY BLDG | (SHEET #5) | | | | | | | | | | | | 48,570 ✓ |
| CANOPY | (SHEET #6) | | | | | | | | | | | | 36,400 ✓ |
| HAUL AWAY | (SHEET #6) | | | | | | | | | | | | 25580 ✓ |
| DMVM # 150,000 (AGREE) ✓ | | | | | | | | | | | | KC - \$ 144,436 | |

KELLOGG CORPORATION
DIRECT COST ESTIMATE

Sheet 1 of 6 Estn DDL Ckd ITEM.....

Plan Sheet No..... Bid Quantity.....

Spec. Ref..... Take-off Quantity.....

Item Desc. DEMOLITION -

JOB SCRTD DATE 3-18-83

WESTERN AVE STATION

FORM E240R HOECKEL'S 336481

DEP. ON FOG

| DESCRIPTION | QUANTITY | DIR. LABOR | | REP. LABOR | | MAT'L | | SUB-BID | | E.O.E. | | TOTAL | |
|--|------------------|------------|--------------|--------------|--------|--------------|--------|---------|--------------|--------|--------|-------|---------------|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT |
| <u>AC PAVING -</u> | <u>51,260 D'</u> | | | | | | | | | | | | |
| <p><i>NOTE: FREQUENTLY THE A.C. IS MERELY AN OVERLAY WITH SOME 8 TO 12 INCHES OF CONCRETE BENEATH.</i></p> <p><i>IF ASPHALT ONLY - CAN BE RIPPED UP & HAULED OFF AS PRICED.</i></p> <p><i>51,260 D' @ 0.15 = 7700 OK</i></p> | | | | | | | | | | | | | |
| <u>CONCRETE SLABS / PAVING.</u> | <u>2000 D'</u> | | | | | | | | | | | | |
| <u>SPREAD</u> | | | | | | | | | | | | | |
| <u>FOREMAN</u> | <u>16 HR</u> | | <u>32.00</u> | | | | | | <u>32.00</u> | | | | <u>512</u> |
| <u>COMPRESSOR 600</u> | <u>16 HR</u> | | <u>30.00</u> | <u>12.50</u> | | <u>14.50</u> | | | <u>57.00</u> | | | | <u>912</u> |
| <u>AIR (2 BREAKERS)</u> | <u>32 HR</u> | | <u>28.00</u> | <u>5.50</u> | | <u>0.50</u> | | | <u>34.00</u> | | | | <u>1088</u> |
| <u>LOADER</u> | <u>8 HR</u> | | <u>30.00</u> | <u>32.00</u> | | <u>6.00</u> | | | <u>68.00</u> | | | | <u>544</u> |
| <u>TRUCK</u> | <u>8 HR.</u> | | <u>28.00</u> | <u>12.50</u> | | <u>17.00</u> | | | <u>57.50</u> | | | | <u>456</u> |
| | | | | | | | | | | | | | <u>\$3512</u> |

-170-

KELLOGG CORPORATION
DIRECT COST ESTIMATE

Sheet 7 of 6 Estm DPL Ckd ✓ ITEM.....
Plan Sheet No..... Bid Quantity.....
Spec. Ref..... Take-off Quantity.....
Item Desc..... DEMOLITION -

JOB..... SCRTD DATE 3-18-83
WESTERN AVE STATION

FORM E240R HOECKEL'S 3984B1

| DESCRIPTION | QUANTITY | DIR. LABOR | | REP. LABOR | | MAT'L | | SUB-BID | | E.O.E. | | TOTAL | |
|---|----------|------------|--------|------------|--------|-------|--------|---------|------------------|--------|--------|-------|-------------------|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT |
| <u>CONCRETE CURBS.</u> | | | | | | | | | | | | | |
| SAME SPREAD AS CONCRETE SLAB. - LOADER / TRUCK WILL PICK UP IN SAME SHIFT / OPERATION AS CONG SLAB. | | | | | | | | | | | | | |
| FOREMAN | 8 HR | | | | | | | | 32 ⁰⁰ | | | | 256 ⁰⁰ |
| COMPRESSOR | 8 HR | | | | | | | | 57 ⁰⁰ | | | | 456 ⁰⁰ |
| AIR (2-BREAKERS) | 16 HR | | | | | | | | 34 ⁰⁰ | | | | 544 ⁰⁰ |
| LOADER } IN CONCR. SLAB REMOVAL | | | | | | | | | | | | | \$ 1256 |
| TRUCK } | | | | | | | | | | | | | |
| <u>TRAFFIC LIGHTS / STREET LIGHTS</u> | | | | | | | | | | | | | |
| OPERATION PERFORMED BY CITY / POWER COMPANY - | | | | | | | | | | | | | |
| NOTE: TRAFFIC MUST BE MAINTAINED WITH SOME PROVISIONS IN TRAFFIC CONTROL - | | | | | | | | | | | | | |
| FOR SHEAR REMOVAL \$ 500 EA OK | | | | | | | | | | | | | |
| ZZEA @ 500 ⁰⁰ = \$ 11,000 | | | | | | | | | | | | | |

-171-

KELLOGG CORPORATION
DIRECT COST ESTIMATE

Sheet 3 of 6 Estm DDL Ckd ✓ ITEM.....

Plan Sheet No..... Bid Quantity.....

JOB SCRTD DATE 3-18-83 Spec. Ref..... Take-off Quantity.....

WESTERN AVE STATION Item Desc. DEMOLITION

DEP-04 FOG

FORM E240R HOECKEL'S 336481

| DESCRIPTION | QUANTITY | DIR. LABOR | | REP. LABOR | | MAT'L | | SUB-BID | | E.O.E. | | TOTAL | |
|--|----------|---|------------------|------------|------------------|-------|------------------|---------|------------------|--------|--------|-------|----------------------|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT |
| <u>MANHOLES:</u> | | <p>ASSUME THE STANDARD PRECAST TYPE STRUCTURE. THE MANHOLES WILL BE EXPOSED BY THE TWO TOP LEVEL ^{EXCAVATION} OPERATIONS. THE CONCRETE CURB AND SLAB OPERATION TYPE CREW CAN DEMOLISH IN SECTIONS & THE STINER CRANE LIFT OUT & HAUL TO OFF SITE DISPOSAL SURREE PILE.</p> | | | | | | | | | | | |
| <p>DEMO 6-7 PER DAY — ALLOW 1-WEEK</p> | | | | | | | | | | | | | |
| FOREMAN | 40 HR | | 32 ⁰⁰ | | | | | | 32 ⁰⁰ | | | | 1280 ⁰⁰ |
| COMPRESSOR | 40 HR | | 30 ⁰⁰ | | 12 ⁵⁰ | | 14 ⁵⁰ | | 57 ⁰⁰ | | | | 2280 ⁰⁰ |
| AIR (2-BREAKERS) | 80 HR | | 28 ⁰⁰ | | 5 ⁵⁰ | | 50 | | 34 ⁰⁰ | | | | 2720 ⁰⁰ |
| STINER CRANE | 16 HR | | 30 ⁰⁰ | | 19 ⁵⁰ | | 14 ⁰⁰ | | 63 ⁰⁰ | | | | 1018 ⁰⁰ |
| TRUCK | 16 HRS | | 28 ⁰⁰ | | 12 ⁵⁰ | | 17 ⁰⁰ | | 57 ⁰⁰ | | | | 920 ⁰⁰ |
| | | | | | | | | | | | | | 8218 ⁰⁰ ✓ |

KELLOGG CORPORATION
DIRECT COST ESTIMATE

Sheet 4 of 6 Estm DDC Ckd ITEM.....

Plan Sheet No..... Bid Quantity.....

Spec. Ref..... Take-off Quantity.....

Item Desc. DEMOLITION

JOB SCR TD DATE 3-18-83
WESTERN AVE. STATION.

FORM E240R HOECKEL'S 336481

| DESCRIPTION | QUANTITY | DIR. LABOR | | REP. LABOR | | MAT'L | | SUB-BID | | E.O.E. | | TOTAL | |
|-----------------------|--|------------|--------|------------|--------|-------|--------|---------|--------|--------|--------|-------|----------------|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT |
| <u>SIGNS</u> | <u>ASSUME SMALL</u> | | | | | | | | | | | | <u>\$ 250</u> |
| | <u>SUCH AS STREET SIGNS</u> | | | | | | | | | | | | <u>OK</u> |
| <u>PARKING METERS</u> | <u>ASSUME REMOVAL & HAUL TO</u> | | | | | | | | | | | | |
| | <u>STORAGE BY CITY</u> | | | | | | | | | | | | |
| | <u>PAVING BREAKER CREW CAN GAO OUT.</u> | | | | | | | | | | | | <u>\$ 950</u> |
| | | | | | | | | | | | | | <u>OK</u> |
| <u>FIRE HYDRANTS</u> | <u>REMOVAL BY CITY FIRE DEPT.</u> | | | | | | | | | | | | |
| | <u>DISCONNECT & HAUL TO STORAGE.</u> | | | | | | | | | | | | |
| | <u>NOTE:</u> | | | | | | | | | | | | |
| | <u>THESE WILL PROBABLY BE</u> | | | | | | | | | | | | |
| | <u>REQUIRED TO REMAIN IN OPERATION</u> | | | | | | | | | | | | |
| | <u>AND THEREFORE BE A UTILITY</u> | | | | | | | | | | | | |
| | <u>RELOCATION ITEM</u> | | | | | | | | | | | | |
| | <u>FOR REMOVAL ONLY - SHOULD</u> | | | | | | | | | | | | <u>\$ 1500</u> |
| | <u>BE OK - SAY ONE DAY FOR</u> | | | | | | | | | | | | |
| | <u>OPERATION - \$1500 OK</u> | | | | | | | | | | | | |

-173-

KELLOGG CORPORATION
DIRECT COST ESTIMATE

Sheet 5 of 6 Estm DPL Ckd ✓ ITEM.....

Plan Sheet No..... Bid Quantity.....

JOB SCRIP DATE 3-18-83

Spec. Ref..... Take-off Quantity.....

WESTERN AVE STATION

Item Desc. DEMOLITION

FORM E240R HOECKEL'S 336481

| DESCRIPTION | QUANTITY | DIR. LABOR | | REP. LABOR | | MAT'L | | SUB-BID | | E.O.E. | | TOTAL | |
|--|----------|------------|------------------|------------|------------------|-------|------------------|---------|------------------|--------|--------|-------------|---------|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT |
| <p><u>MASONRY BUILDING.</u> FROM DWG IT APPEARS THAT THIRTY DRUG STORE IS TO BE DEMOLISHED ESTIMATE 150 X 150 SINGLE LEVEL BLDG - TOTAL CLEAN UP 2-WKS TRUCKS ON MID 1ST WEEK</p> | | | | | | | | | | | | | |
| <p><u>DEMO SPRED.</u> 3 MAN CREW</p> | | | | | | | | | | | | | |
| FOREMAN | 80 | HR | 35 ⁰⁰ | | | | | | 35 ⁰⁰ | | | | 2800 ✓ |
| CRANE (HEAD ACHE) | 80 | HR | 91 ⁰⁰ | | 72 ⁰⁰ | | 38 ⁰⁰ | | 201 ⁻ | | | | 16080 ✓ |
| DOZER / LOADER | 80 | HR | 30 | | 44 ⁰⁰ | | 31 ⁰⁰ | | 105 ⁻ | | | | 8400 ✓ |
| TRUCK - DEMO BIN (2) | 120 | HR | 28 | | 15 ⁰⁰ | | 18 ⁰⁰ | | 61 ⁻ | | | | 7320 ✓ |
| LABOR - DUST MAN | 80 | HR | 26 ⁰⁰ | | | | | | 26 ⁻ | | | | 2080 ✓ |
| LABORERS (2) | 160 | HR | 26 ⁰⁰ | | | | | | 26 ⁻ | | | | 4160 ✓ |
| PICK UP. | 80 | HR. | | | 27 ⁰⁰ | | 3 ⁰⁰ | | 5 ⁰⁰ | | | | 470 ✓ |
| DUST WATER - FIRE HYDR. Hook up | | | | | | | | | | | | | 500 ✓ |
| ADD A 600 CFM COMP. & PAVE BREAKER FOR SECONDARY BREAK UP. | | | | | | | | | | | | | |
| COMPR. | 80 | | 30 ⁰⁰ | | 9 ⁰⁰ | | 11 ⁰⁰ | | 50 ⁰⁰ | | | | 4040 ✓ |
| AIR HAMMER | 80 | | 28 ⁰⁰ | | 5 ⁵⁰ | | 5 ⁰⁰ | | 34 ⁰⁰ | | | | 2720 ✓ |
| | | | | | | | | | | | | \$ 48,570 ✓ | |

-174-

KELLOGG CORPORATION
DIRECT COST ESTIMATE

Sheet 6 of 6 Estm DDK Ckd V ITEM

Plan Sheet No. Bid Quantity

Spec. Ref. Take-off Quantity

Item Desc. DEMOLITION

JOB 5 CRTD. DATE 3-18-83

WESTERN AVE STATION

FORM E240R HOECKEL'S 336481

| DESCRIPTION | QUANTITY | DIR. LABOR | | REP. LABOR | | MAT'L | | SUB-BID | | E.O.E. | | TOTAL | |
|--|-----------|------------|--------|------------|--------|-------|--------|---------|--------|--------|--------|-------|--------|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT |
| <u>CANOPY</u> | | | | | | | | | | | | | |
| <p>PROBABLY THE MARQUIS IN FRONT OF THE WILTERN THEATER</p> <p>NOTE: STORED OR REPLACED ?</p> <p>DMJM SOUNDS ADEQUATE \$ 36400</p> | | | | | | | | | | | | | |
| <u>HAUL AWAY</u> | 3835 C.Y. | | | | | | | | | | | | |
| <p>FROM EXCESS MUCK REMOVAL WORK SHEET.</p> | | | | | | | | | | | | | |
| | 3835 | | \$ | @ | 6.67 | | | | | | | \$ | 25,580 |

STATION SHELL CONSTRUCTION - DEPTH REDUCTION

SUMMARY

**KELLOGG CORPORATION
DIRECT COST ESTIMATE**

JOB SCRTD

DATE 3-30-83

Sheet 0 of Estm DD Ckd ITEM

Plan Sheet No. Bid Quantity

Spec. Ref. Take-off Quantity

Item Desc. DEPTH REDUCTION

FORM E240E HOECKEL'S 847869

DEPTH REDUCTIONS:

DEPTH REDUCTIONS WERE TAKEN AT THE FOLLOWING STATIONS:

DMJM PBQD - REDUCTIONS

| DESCRIPTION | QUANTITY | DIR. LABOR UNIT AMOUNT | EQUIPM'T COST UNIT AMOUNT | DIR. MAT'L UNIT AMOUNT | PM/SUB UNIT AMOUNT | E.O.E. UNIT AMOUNT | TOTAL UNIT AMOUNT |
|----------------|----------|------------------------|---------------------------|------------------------|--------------------|--------------------|-------------------|
| # ② 1ST & HILL | 8' | | | @ 460,000 | | | \$ 3,680,000 |
| ③ 5TH & HILL | 7' | | | @ 460,000 | | | 3,220,000 |
| ④ ALVARADO | 6' | | | @ 460,000 | | | 2,760,000 |
| ⑤ VERMONT | 2' | | | @ 460,000 | | | 920,000 |
| ⑦ NORMANDIE | 8' | | | @ 460,000 | | | 3,680,000 |

31 FT.

DMJM PBQD TOTAL REDUCTION SAVINGS: \$ 14,260,000 (INCL. MARK-UPS)

K.C.

DIRECT

SHEET 2
3

91,000
145,000

\$ 460,000 ÷ 1.155 = 398,268 w/o MARKUPS (SAY \$400,000 K)

\$ 236,000 / FT.

VARIANCE = (400,000 - 236,000) × 31 FEET = \$ 5,084,000 (ADD)

KELLOGG CORPORATION
DIRECT COST ESTIMATE

JOB SCRIP DATE 3-30-83

Sheet 1 of 3 Estm AK Ckd N ITEM.....
Plan Sheet No..... Bid Quantity.....
Spec. Ref..... Take-off Quantity.....
Item Desc DEPTH REDUCTIONS

FORM E240E HOFFKEL'S 34788D

| DESCRIPTION | QUANTITY | DIR. LABOR | | EQUIPMT COST | | DIR. MAT'L | | PM/SUB | | E.O.E. | | TOTAL | |
|---------------------------|----------|-----------------------------------|--------|--------------|--------|------------|--------|--------|--------|--------|--------|-------|--------|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT |
| <u>DEPTH REDUCTIONS :</u> | | | | | | | | | | | | | |
| | | <u>ITEMS THAT VARY WITH DEPTH</u> | | | | | | | | | | | |
| | | <u>REDUCTIONS :</u> | | | | | | | | | | | |
| | | <u>DIRECT :</u> | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |

KELLOGG CORPORATION
DIRECT COST ESTIMATE

Sheet 2 of 3 Estm DL Ckd ITEM
Plan Sheet No. _____ Bid Quantity _____
Spec. Ref. _____ Take-off Quantity _____
Item Desc. DEPTH REDUCTION

JOB. _____ DATE 3-30-83

FORM E240E HOECKEL'S 347880

| DESCRIPTION | QUANTITY | DIR. LABOR | | EQUIPM'T COST | | DIR. MAT'L | | PM/SUB | | E.O.E. | | TOTAL | | |
|-------------------------------|----------|------------|--------|---------------|--------|------------|--------|--------|--------|--------|--------|-------|--------|--|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | |
| <u>DEPTH REDUCTION CONT'D</u> | | | | | | | | | | | | | | |
| EXCAV PER FOOT | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | |
| | | | | | | | | | | | | | | |

-178-

DEPTH REDUCTION CONT'D

$640 \times 66.75 / 27 = 1582 \text{ C.Y.}$

UNIT COST FROM MARK ET. CALC SHEET 6^{45} FOR 80,000 CY

$6^{45} \times 1582 =$ **\$10,200**

SOLDER PILE LAG: $640 + 640 + 66.75 + 66.75 = 1414 \text{ D'}$

U.C. FOR ST. SUPP WORK SIM $1414 \text{ D' @ SAY } 32''$ **\$45,250**

BACKFILL (REDUCE 1 FT AS EXCAV) 1582 CY

$1582 \times 15^{45} =$ **\$25,000**

MUCK DISPOSAL 1582 C.Y.

FRONT WORK SHEET $1582 @ 6^{65} =$ **\$10,550**

TOTAL SHEET - **\$91,000**

KELLOGG CORPORATION
DIRECT COST ESTIMATE

JOB SCR70 DATE 3-30-83

Sheet 3 of 3 Estm. DD Ckd. Y ITEM
Plan Sheet No. _____ Bid Quantity _____
Spec. Ref. _____ Take-off Quantity _____
Item Desc. DEPTH REDUCTION

FORM E240E HOECKEL'S 347860

| DESCRIPTION | QUANTITY | DIR. LABOR | | EQUIPM'T COST | | DIR. MAT'L | | PM/SUB | | E.O.E. | | TOTAL | |
|--|----------|------------|--------|---------------|--------|------------|--------|--------|--------|--------|--------|-------|--------|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT |
| <p><i>DEPTH REDUCTION :</i></p> <p><i>DMJM PBAD DEPTH REDUCTION CALCS</i> <i>SHOW STEEL TO REDUCE IN SIZE</i> <i>LESS THAN .5 PERCENT PER FT.</i></p> <p><i>LACING NO CHANGE :</i> <i>\$1,500,000 / 65 = CALL \$25,000 / FT</i></p> <p><i>REDUCE OVERALL WT SAY .7%</i> <i>(GENEROUS) = \$100,000</i></p> <p><i>CONCRETE REDUCTION</i></p> <p><i>FORMS NIL CHANGE</i> <i>CONCR 1%</i> <i>REBAR 1%</i> <i>FINISH - CURE NIL</i></p> <p><i>MISC: TO DEWATER-TRAFFIC -</i> <i>SUPPORT-DISRUPTION - SAY \$10,000</i></p> <p><i>TOTAL SH. \$145,000</i></p> | | | | | | | | | | | | | |

-179-

STATION SHELL CONSTRUCTION - PARKING STRUCTURE DEDUCTION

DPL

PARKING DEDUCT.
(DUPLICATED)

BEVERLY

4,108,000

UNIVERSAL

11,042,000

15,150,000

STATION SHELL CONSTRUCTION - MOBILIZATION DEDUCTION

SCRIP

1223

3-29-83

DOL

MOB. DEDUCT

STA

1 UNION 434800

2 1ST 619150

3 STU 802950

4 7TH 547400

5 ALV 255000

6 VER 318900

7 NOR 476950

8 WEST 446600

9 LB 472800

10 FAIR 983850

11 BEV 328900

12 SM 0

13 SUN 474500

14 H. 469700

15 UNIV 415900

16 NH 476950

7,524,356

KC 1223 SCRTO/METRO RAIL
STATION ARCHITECTURAL FINISHES SUMMARY

AWJ/GHM
3/28/83

| | | 1 | 2 | 3 | 4 | 5 | 6 |
|----|--|----------------|--------------|---------------|------------------|------------|---------------|
| | | AREA (TAMS) | UNIT TAMS | PRICES ICC | ESTIMATE TAMS | COST KC | NET CHANGE |
| 1 | UNION | 30,144 | 62.19 | 65.08 | 1,874,655 | 1,961,772 | 87,117 |
| 2 | 1ST/HILL | 39,800 | 51.94 | 54.55 | 2,067,212 | 2,171,090 | 103,878 |
| 3 | 5TH/HILL | 50,800 | 51.94 | 54.55 | 2,638,552 | 2,771,440 | 132,888 |
| 4 | 7TH/FLOWER | 36,125 | 62.19 | 65.08 | 2,246,614 | 2,351,015 | 104,401 |
| 5 | * ALVARADO/WILSHIRE | 22,240 | 73.43 | 76.32 | 1,633,083 | 1,697,357 | 64,274 |
| 6 | * VERMONT/WILSHIRE | 27,840 | 71.17 | 74.06 | 1,981,373 | 2,061,830 | 80,457 |
| 7 | NORMANDIE/WILSHIRE | 22,950 | 62.19 | 65.08 | 1,427,261 | 1,493,586 | 66,325 |
| 8 | WESTERN/WILSHIRE | 23,140 | 62.19 | 65.08 | 1,439,077 | 1,505,951 | 66,874 |
| 9 | LEBREA/WILSHIRE | 24,024 | 62.19 | 65.08 | 1,494,053 | 1,563,482 | 69,429 |
| 10 | FAIRFAX/WILSHIRE | 61,700 | 51.94 | 54.55 | 3,204,698 | 3,345,735 | 141,037 |
| 11 | * BEVERLY/WILSHIRE | 25,880 | 71.85 | 74.74 | 1,859,478 | 1,934,271 | 74,793 |
| 12 | SANTA MONICA | 22,550 | 62.19 | 65.08 | 1,402,385 | 1,467,554 | 65,169 |
| 13 | LEBREA/SUNSET | 24,300 | 62.19 | 65.08 | 1,511,217 | 1,581,444 | 70,227 |
| 14 | * HOLLYWOOD/CAH. | 22,650 | 73.23 | 76.12 | 1,658,660 | 1,724,118 | 65,458 |
| 15 | * UNIVERSAL CITY | 25,200 | 72.11 | 75.00 | 1,817,172 | 1,890,000 | 72,828 |
| 16 | NO. HOLLYWOOD | 25,400 | 62.19 | 65.08 | 1,579,626 | 1,653,032 | 73,406 |
| 17 | | | | | | | |
| 18 | TOTALS | | | | 29,835,116 | 31,193,377 | 1,358,261 |
| 19 | | | | | | | |
| 20 | | | | | | | |
| 21 | | | | | | | |
| 22 | | | | | | | |
| 23 | | | | | | | |
| 24 | | | | | | | |
| 25 | * UNIT PRICES INCLUDE ADDITIONAL \$250,000 FOR | | | | | | |
| 26 | HEADHOUSE COSTS. | | | | | | |
| 27 | | | | | | | |
| 28 | | | | | | | |
| 29 | | | | | | | |
| 30 | | | | | | | |
| 31 | | | | | | | |
| 32 | | | | | | | |
| 33 | | | | | | | |
| 34 | | | | | | | |
| 35 | | | | | | | |
| 36 | | | | | | | |
| 37 | | | | | | | |
| 38 | | | | | | | |
| 39 | | | | | | | |
| 40 | | | | | | | |

KC1223 SCRTD/METRO RAIL
 COMPARATIVE SUMMARY (WESTERN)

AWJ/GHM
 3/28/83

| ITEM | QUANTITY | | UNIT | | PRICES | | ESTIMATE | | COST | |
|----------------------|---------------------------------------|---------------------|---------|-----------------------|-----------|-----------|----------|----|------|---------|
| | TAMS | KC | TAMS | KC | TAMS | KC | TAMS | KC | TAMS | KC |
| | | | #/UNIT | #/UNIT | (#) | (#) | | | (#) | (#) |
| 1 FLOORING | 24,850 SF | 27,586 SF | 9/SF | 7.46/SF | 223,650 | 205,814 | | | | |
| 2 CMU WALLS | 21,220 SF | 18,230 SF | 4/SF | 6.57/SF | 84,880 | 119,771 | | | | |
| 3 WALL TREATMENT | 16,704 " | 29,592 SF | 8/SF | 8.09/SF | 133,632 | 239,400 | | | | |
| 4 CEILING TREATMENT | 28,700 " | 38,144 SF | 3/SF | 1.42/SF | 86,100 | 54,164 | | | | |
| 5 SIGNS + GRAPHICS | - | - | L.S. | L.S. | 200,000 | 200,000 | | | | |
| 6 MAPPING | - | - | L.S. | L.S. | 50,000 | 50,000 | | | | |
| 7 ARTWORK | - | - | L.S. | L.S. | 150,000 | 150,000 | | | | |
| * 8 MODULE EQUIPMENT | - | - | L.S. | L.S. | 15,000 | 10,724 | | | | |
| 9 HARDWARE | - | - | L.S. | L.S. | 156,000 | 125,784 | | | | |
| 10 GRANITE | | | | | | | | | | |
| PLATFORM EDGE | 900 LF | 900 LF | 35/LF | 52 | 31,500 | 46,800 | | | | |
| 11 STAIRS - GRANITE | 1992 LF | 684 FT ³ | 35/LF | 75.29/FT ³ | 69,720 | 51,498 | | | | |
| 12 STAIRS - CONCRETE | - | 320 NLF | - | 19.32/NLF | - | 6,182 | | | | |
| 13 CUSTODIAL ROOM | - | - | L.S. | L.S. | 20,000 | 20,000 | | | | |
| 14 STAFF ROOM | - | - | L.S. | L.S. | 15,000 | 15,000 | | | | |
| * 15 RESTROOMS | - | - | L.S. | L.S. | 15,000 | 8,108 | | | | |
| 16 ACOUSTICAL PANEL | 22,275 SF | 22,275 SF | 8.20/SF | 8.20/SF | 182,655 | 182,655 | | | | |
| 17 GYPSUM BOARD | 3,000 | 3,000 SF | .50/SF | 1.40/SF | 1,500 | 4,200 | | | | |
| 18 PAINTING | 3,000 SF | 3,000 SF | 2/SF | .27/SF | 6,000 | 810 | | | | |
| 19 LANDSCAPE | - | - | - | L.S. | - | 15,000 | | | | |
| TOTALS | | | | | 1,439,137 | 1,505,910 | | | | |
| NET CHANGE | | | | | | | | | | +66,773 |
| * PLUMBING | FIXTURES INCLUDED IN MECHANICAL COSTS | | | | | | | | | |
| ASSUME | TAMS SQUARE FOOTAGE OF 23,140 IS | | | | | | | | | |
| CORRECT. | THEREFORE UNIT PRICE: | | | | | | | | | |
| TAMS | $1,439,137 \div 23,140 = \$62.19/SF$ | | | | | | | | | |
| KC | $1,505,910 \div 23,140 = \$65.08/SF$ | | | | | | | | | |

KC 1223 SCRTD / METRO RAIL
 COMPARATIVE SUMMARY (5TH + HILL)

AWJ/GHM
 3/28/83

| | ITEM | QUANTITY | | UNIT PRICES | | ESTIMATE COST | | |
|----|--|-----------|-----------|--------------|------------|---------------|-----------|--|
| | | TAMS | KC | TAMS \$/UNIT | KC \$/UNIT | TAMS \$ | KC \$ | |
| 1 | 1. FLOORING | 54,027 SF | 64,818 SF | 9/SF | 7.46/SF | 400,243 | 483,542 | |
| 2 | 2. CMU WALLS | 28,293 SF | 24,246 SF | 4/SF | 6.57/SF | 113,172 | 159,296 | |
| 3 | 3. WALL TREATMENT | 25,513 SF | 30,721 SF | 8/SF | 8.09/SF | 204,104 | 248,533 | |
| 4 | 4. CEILING TREATMENT | 51,005 SF | 94,503 SF | 3/SF | 1.42/SF | 153,015 | 134,194 | |
| 5 | 5. SIGNS + GRAPHICS | — | — | L.S. | L.S. | 300,000 | 300,000 | |
| 6 | 6. MAPPING | — | — | L.S. | L.S. | 75,000 | 75,000 | |
| 7 | 7. ARTWORK | — | — | L.S. | L.S. | 200,000 | 200,000 | |
| 8 | 8. MODULAR EQUIP. | — | — | L.S. | L.S. | 30,000 | 30,000 | |
| 9 | 9. HARDWARE | — | — | L.S. | L.S. | 312,000 | 312,000 | |
| 10 | 10. GRANITE FLT. EDGE | 1800 LF | 1800 LF | 35/LF | 52/LF | 63,000 | 93,600 | |
| 11 | 11. STAIRS - GRANITE | 5760 LF | 2,736 SF | 35/LF | 75.29/SF | 201,600 | 205,993 | |
| 12 | 12. STAIRS - CONCRETE | — | 640 NLF | — | 19.82/NLF | — | 12,365 | |
| 13 | 13. CUSTODIAL ROOM | — | — | L.S. | L.S. | 30,000 | 30,000 | |
| 14 | 14. STAFF ROOM | — | — | L.S. | L.S. | 20,000 | 20,000 | |
| 15 | * 15. REST ROOMS | — | — | L.S. | L.S. | 25,000 | 16,216 | |
| 16 | 16. ACOUSTICAL PANEL | 50,005 SF | 50,005 SF | 8.20/SF | 8.20/SF | 410,697 | 410,697 | |
| 17 | 17. GYPSUM WALLS | 6,000 SF | 6,000 SF | .50/SF | 1.40/SF | 3,000 | 8,400 | |
| 18 | 18. PAINTING | 6,000 SF | 6,000 SF | 2/SF | .27/SF | 12,000 | 1,620 | |
| 19 | 19. LANDSCAPE | — | — | — | L.S. | — | 30,000 - | |
| 21 | TOTALS | | | | | 2,638,831 | 2,771,456 | |
| 22 | NET CHANGE | | | | | | +132,625 | |
| 25 | * PLUMBING FIXTURES INCLUDED IN MECHANICAL COSTS | | | | | | | |
| 28 | ASSUME TAMS SQUARE FOOTAGE OF 50,800 IS CORRECT, THEREFORE UNIT PRICE IS: | | | | | | | |
| 31 | TAMS $2,638,831 \div 50,800 = \$51.94/SF$ | | | | | | | |
| 33 | KC $2,771,456 \div 50,800 = \$54.55/SF$ | | | | | | | |

| | | 1 | 2 | 3 | 4 | 5 | 6 |
|------|---|----------|------|-------|--------|----------|---------|
| | | QUANTITY | UNIT | UNIT | PRICES | ESTIMATE | COSTS |
| | | (TAMS) | | TAMS | KC | TAMS | KC |
| ITEM | | | | | | | |
| 1 | 1. CMU WALLS | 4,650 | SF | 4.00 | 6.57 | 19,600 | 30,550 |
| 2 | 2. CANOPY | 5,500 | SF | 5.85 | 5.97 | 32,175 | 32,835 |
| 3 | 3. FENCING | 1,200 | LF | 16.00 | 16.00 | 19,200 | 19,200 |
| 4 | 4. WALL TILE | 4,650 | SF | 8.00 | 8.09 | 37,200 | 37,620 |
| 5 | 5. FLOORING | 8,250 | SF | 9.00 | 7.46 | 74,250 | 61,545 |
| 6 | 6. BENCHES | | L.S | — | — | 2,000 | 2,000 |
| 7 | 7. LIGHTING | 5,500 | SF | 3.00 | 3.00 | 16,500 | 16,500 |
| 9 | TOTALS | | | | | 199,925 | 200,250 |
| 10 | NET CHANGE | | | | | | + 325 |
| 15 | TAMS REVISED ESTIMATE (12/6/82) shows | | | | | | |
| 16 | a 25% increase. Therefore, assuming | | | | | | |
| 17 | that is correct: | | | | | | |
| 19 | $200,250 \times 1.25 = \$250,000$ | | | | | | |
| 22 | FOR STATIONS AT ALVARADO, VERMONT, BEVERLY, | | | | | | |
| 23 | HOLLYWOOD, + UNIVERSAL | | | | | | |

KC 1223 SCRTD/METRO RAIL
 CHECK OF FINISHED AREA VS. GROSS AREA

3/28/82
 AJW/GJM

| | 1 | 2 | 3 | 4 | 5 | 6 | |
|----|--------------------|------|----------------------|--------------|--------------------------------|---------------------------------|-----|
| | STATIONS | TYPE | FINISH SF. (TAMS) | GROSS LENGTH | STATION AREA X WIDTH = AREA | FACTOR: A FINISH/ A GROSS | |
| 1 | UNION | S/L | 30,144 | 690 | 67 | 42,880 | .7 |
| 2 | 1ST/HILL | O/U | 39,800 | 631 | 63 | 39,753 | 1.0 |
| 3 | 5TH/HILL | O/U | 50,800 | 631 | 63 | 39,753 | 1.3 |
| 4 | 7TH/FLOWER | S/L | 36,125 | 740 | 63 | 46,620 | .8 |
| 5 | ALVARADO/WILSHIRE | S/L | 22,240 | 450 | 63 | 28,350 | .8 |
| 6 | VERMONT/WILSHIRE | S/L | 27,840 | 567 | 67 | 37,989 | .7 |
| 7 | NORMANDIE/WILSHIRE | S/L | 22,950 | 672 | 65 | 43,680 | .5 |
| 8 | WESTERN/WILSHIRE | S/L | 23,140 | 660 | 65 | 42,900 | .5 |
| 9 | LEBREA/WILSHIRE | S/L | 24,024 | 660 | 65 | 42,900 | .6 |
| 10 | FAIRFAR/WILSHIRE | O/U | 61,700 | 935 | 65 | 60,775 | 1.0 |
| 11 | BEVERLY/WILSHIRE | S/L | 25,880 | 685 | 63 | 43,155 | .6 |
| 12 | SANTA MONICA | S/L | 22,550 | 680 | 65 | 44,200 | .5 |
| 13 | LEBREA/SUNSET | S/L | 24,300 | 690 | 65 | 44,850 | .5 |
| 14 | HOLLYWOOD/CATUENGA | S/L | 22,650 | 635 | 65 | 41,275 | .5 |
| 15 | UNIVERSAL CITY | S/L | 25,200 | 630 | 65 | 40,950 | .6 |
| 16 | NO. HOLLYWOOD | S/L | 25,400 | 672 | 65 | 43,680 | .6 |
| 17 | | | | | | | |
| 18 | | | | | | | |
| 19 | | | | | | | |
| 20 | | | | | | | |
| 21 | | | | | | | |
| 22 | | | | | | | |
| 23 | | | | | | | |
| 24 | | | | | | | |
| 25 | | | | | | | |
| 26 | | | | | | | |
| 27 | | | | | | | |
| 28 | | | | | | | |
| 29 | | | | | | | |
| 30 | | | | | | | |
| 31 | | | | | | | |
| 32 | | | | | | | |
| 33 | | | | | | | |
| 34 | | | | | | | |
| 35 | | | | | | | |
| 36 | | | | | | | |
| 37 | | | | | | | |
| 38 | | | | | | | |
| 39 | | | | | | | |
| 40 | | | | | | | |

KELLOGG CORPORATION
DIRECT COST ESTIMATE

Item Analysis

JOB KC1223

DATE 3/23/83

DCE. 2-82-2500 HOECKELS 844125

Sheet 1 of 3 Estm. GMM Ckd. _____ ITEM _____
Plan Sheet No. _____ Bid Quantity _____
Spec. Ref. _____ Take-off Quantity _____
Item Desc. WESTERN STATION UNIT COSTS

1. QUARRY TILE

ASSUME LIGHT SANDBLASTING AND CLEANING CONCRETE PERFORMED
BY STATION SHELL WORK.

| | |
|------------------------|---------|
| 6" x 6" x 1/2" MUD SET | 4.55/SF |
| EPOXY GROUT + MORTAR | 2.03 " |
| COLORS | .15 " |
| ABRASIVE SURFACE | .41 |
| WAX COATING | .32 |
| TOTAL | 7.46/SF |

2. CONCRETE MASONRY UNIT WALLS

DUE TO EARTHQUAKE ZONE, ASSUMED SOLID, REINFORCED
8" THICK --- \$6.57/SF

3. WALL TREATMENT

| | |
|------------------------------|---------|
| TILE 4 1/2" x 4 1/2" MUD SET | 5.78 |
| EPOXY GROUT | .93 |
| PORTLAND CEMENT MORTAR | 1.38 |
| TOTAL | 8.09/SF |

4. CEILING TREATMENT

| | |
|----------------|------|
| MINERAL FIBER | 1.26 |
| CEILING PRIMER | .06 |
| CEILING CEMENT | .10 |
| TOTAL | 1.42 |

KELLOGG CORPORATION
DIRECT COST ESTIMATE

Item Analysis

JOB KC 1223

DATE 3/23/83

DCE. 2-82-2800 HOECKELS 844128

Sheet 2 of 3 Estm. GHM Ckd. _____ ITEM _____
Plan Sheet No. _____ Bid Quantity _____
Spec. Ref. _____ Take-off Quantity _____
Item Desc. WESTERN STATION UNIT COSTS

- | | | |
|---|--------|-----------|
| 5. SIGNS + GRAPHICS | L.S. | \$200,000 |
| 6. MAPPING | L.S. | \$50,000 |
| 7. ARTWORK | L.S. | \$150,000 |
| 8. MODULE EQUIPMENT | | |
| A. BENCHES | \$542 | ea |
| B. FIRE EXTINGUISHERS | \$342 | ea |
| C. EYE WASH | \$320 | ea |
| D. WATER FOUNTAIN | \$918 | ea |
| 9. HARDWARE | | |
| A. 5'x5' ALUMINIUM DBLE LEAF | \$1311 | ea |
| B. 4'x4' ALUMINIUM DBLE LEAF | \$926 | ea |
| C. SECURITY GATES ROLL-UP (12x12) MOTORIZED | \$2706 | ea |
| D. METAL RAILINGS | \$200 | LF |
| E. SECURITY GATE | \$500 | ea |
| F. GRATES | \$25 | SF |

KELLOGG CORPORATION
DIRECT COST ESTIMATE

Item Analysis

JOB KC 1223

DATE 3/23/83

DCE. 2-82-2500 HOECKELS 344125

Sheet 3 of 3 Estm. GHM Ckd. _____ ITEM _____
Plan Sheet No. _____ Bid Quantity _____
Spec. Ref. _____ Take-off Quantity _____
Item Desc. WESTERN STATION UNIT COSTS

10. GRANITE PLATFORM EDGE $1.5 \text{ SF/LF} \Rightarrow \$34.65/\text{SF} \times 1.5 \text{ SF/LF} = \$52/\text{LF}$
11. STAIRS A. GRANITE $\$75.29/\text{CF}$
B. CONCRETE $\$19.32/\text{NLF}$
12. CUSTODIAL ROOM L.S. $\$20,000$
13. STAFF ROOM L.S. $\$15,000$
14. TOILETS
- A. WOMEN
- PARTITIONS SS FLOOR MOUNTED $\$692 \text{ ea}$
- SINKS 366 ea
- WATER CLOSETS 619 ea
- ACCESSORIES L.S. 732 ea
- B MEN
- SAME EXCEPT FOR
- ACCESSORIES 456 ea
- URINALS 517 ea
15. ACCOUSTICAL PANELS TAMS ESTIMATE REASONABLE $\$8.20/\text{SF}$
16. GYPSUM WALL BOARD (INCLUDES FURRING) (FINISHED) $\$1.40/\text{SF}$
17. PAINTING PRIMER + 2 COATS $.27/\text{SF}$
18. LANDSCAPING ASSUME L.S. $\$15,000$

KELLOGG CORPORATION
DIRECT COST ESTIMATE

Item Analysis

JOB KC 1223

DATE 3/22/83

DCE. 2-82-2500 HOKCKELS 344125

Sheet 1 of 6 Estm GHM Ckd..... ITEM.....
Plan Sheet No. GP-A16 Bid Quantity.....
Spec. Ref..... Take-off Quantity.....
Item Desc. WESTERN STATION

1. QUARRY TILE

| | | | |
|-----------------|--------------|---------------|-----------------------|
| A. PLATFORM - | 450' x 32' = | 14,400 Φ | TAMS: 14,400 Φ |
| B.1. MEZZANINE | 140' x 55' = | 7,700 Φ | } TAMS: 10,450 Φ |
| 2. ENTRANCES #1 | 18' x 180' = | 3,240 | |
| 3. ENTRANCES #2 | 28' x 38' = | 1,064 Φ | |
| | 18' x 45' = | 810 | |
| 4. SUBTOTAL | | 12,814 | |
| C. BATHROOMS | 25' x 15' = | 375 Φ | |
| D. TOTAL | | 27,589 Φ | TAMS: 24,850 Φ |

QUANTITY CALCULATIONS ABOVE ASSUMED THAT ALL PUBLIC AREAS HAD QUARRY TILE, INCLUDING BATHROOM AND BOTH ENTRANCES. ALL ANCILLIARY AREAS ASSUMED TO HAVE CONCRETE FINISHED FLOORING

2 CONCRETE MASONRY WALLS

| | | |
|-------------|-----------------|--------------|
| A PLATFORM | | |
| 1. EAST END | 25' x 12' 6" = | 313 Φ |
| | 155' x 16' 4" = | 2,532 |
| SUBTOTAL | | 2,845 Φ |

KELLOGG CORPORATION
DIRECT COST ESTIMATE

Item Analysis

JOB..... DATE.....

DCE. 2.82.2500 HOECKELS 344125

Sheet 2 of 6 Estm G#M Ckd..... ITEM.....
Plan Sheet No. GP-A16 Bid Quantity.....
Spec. Ref..... Take-off Quantity.....
Item Desc. WESTERN STATION

2. CONCRETE MASONRY WALLS

A PLATFORM (CONT.) 2845 Φ
2. WEST END 2845 Φ
B. MEZZANINE
1. EAST END 16'6" x 550 = 9,075
2 WEST END 16'6" x 210 = 3,465

C. TOTAL 18,230 IAMS: 21,220 Φ

ASSUMED ALL PARTITION WALLS ARE C.M.U.

3. WALL TREATMENT

A. PLATFORM (SIDES) 2(450) x 12'-6" = 11,250
(ENDS) 2(25) x 12'-6" = 625
B. MEZZANINE (SIDES) 2(165) x 16'-6" = 5,445
SHORT SIDES OF MEZZANINE 4(40) x 5 = 800
SIDES OF ESCALATOR 2(40) x 5 = 400
BATHROOMS + END WALLS 2 x 27 x 16 + 2 x 16 x 56 = 3,656
C. ENTRANCE #1 2(180) x 16 = 5,760
ENTRANCE #2 2(83) x 16 = 2,656
D. TOTAL 29,592 DMJM 16,704

ASSUMED THAT TILE WALLS CONTINUOUS FROM ENTRANCE THRU STATION. TREATED WALL @ TRACTION POWER SUBSTATION AS VERTICAL WALL. BATHROOMS WERE ALSO CONSIDERED AS TILE WALLS.

KELLOGG CORPORATION
DIRECT COST ESTIMATE

Item Analysis

JOB KC 1223 DATE _____

Sheet 3 of 6 Estm GHM Ckd _____ ITEM _____
Plan Sheet No. GP-A16 Bid Quantity _____
Spec. Ref. _____ Take-off Quantity _____
Item Desc. WESTERN STATION

DCE. 2-82-2800 HOECKELS 344128

4. CEILING TREATMENT

| | | |
|-----------|--|--------------|
| PLATFORM | $310' \times 56' = 17,360$ | |
| MEZZANINE | $300' \times 56' + 400\phi = 16,800 + 400 = 17,200 \phi$ | |
| ENTRANCES | $140' \times 18' + 28' \times 38' = 2520 + 1064 = 3,584$ | |
| TOTAL | 38,144' | TAMB: 14,400 |

CEILING TREATMENT ASSUMED THRU OUT PUBLIC AREAS.

KELLOGG CORPORATION
DIRECT COST ESTIMATE

Item Analysis

JOB KC1223

DATE 3/22/03

DCE 2-82-2500 HOECKELS 344128

Sheet 4 of 6 Estm.....Ckd.....ITEM.....
Plan Sheet No. GP-A16 Bid Quantity.....
Spec. Ref.....Take-off Quantity.....
Item Desc. WESTERN STATION

5. SIGNAGE + GRAPHICS LUMP SUM \$200,000
THE TAMS FIGURE OF \$200,000 SEEMS ADEQUATE
6. MAPPING LUMP SUM \$50,000
THE TAMS FIGURE OF \$50,000 SEEMS ADEQUATE.
7. ARTWORK LUMP SUM \$150,000
THE TAMS FIGURE OF \$150,000 SEEMS ADEQUATE.
8. MODULE EQUIPMENT
- A. BENCHES
INFERRED FROM PLAN 16 BENCHES
 - B. FIRE EXTINGUISHERS
6 1 1/2" STANDPIPES (UBC)
 - C. EYE WASH
1
 - D. WATER FOUNTAIN
2 HANDICAPPED ACCESSIBLE

KELLOGG CORPORATION
DIRECT COST ESTIMATE

Item Analysis

JOB KC 1223

DATE 3/23/83

DCE. 2-92-2500 HOECKELS 244125

Sheet 5 of 6 Estm. G.M. Ckd. _____ ITEM _____
Plan Sheet No. G.P.-A16 Bid Quantity _____
Spec. Ref. _____ Take-off Quantity _____
Item Desc. WESTERN STATION TAKE-OFF

9. HARDWARE

A. DOORS

1. ALUMINIUM DOUBLE LEAF 5'x5' : ASSUME TAMS TAKE-OFF
OF 6 CORRECT

2. ALUMINIUM DOUBLE LEAF 4'x4' : ASSUME TAMS TAKE-OFF
OF 19 CORRECT

B. SECURITY GATES (ROLL DOWN) - ASSUME TAMS TAKE-OFF
OF 4 CORRECT

C. STAIR RAILING - 150' LF - TAMS: 150 LF

D. GATES TO END OF PLATFORM 4. TAMS: 4

E. GRATES 300 SF - ASSUME TAMS TAKE-OFF CORRECT

F. MISCELLANEOUS ORNAMENTAL METALS:

LUMP SUM \$50,000 LACK OF DETAILED
DESIGN; HAVE TO ASSUME TAMS TAKE-OFF
CORRECT

10. GRANITE PLATFORM EDGE 450 x 2 = 900 LF. TAMS: 900 LF

11. STAIRS

A. GRANITE: ENTRANCES (2) : $2 \times 35 \times 6' \times 12 = 420 \text{ ft}^3$
TO PLATFORM $2 \times 22 \times 12 \times 6' = 264 \text{ ft}^3$

B. CONCRETE: EMERGENCY STAIRS
 $2 \times 20 \times 8 = 320 \text{ NOSE LF.}$

KELLOGG CORPORATION
DIRECT COST ESTIMATE

Item Analysis

JOB KC 1223 DATE 3/23/83

Sheet 6 of 6 Estm. Ckd. ITEM
Plan Sheet No. GP-A16 Bid Quantity
Spec. Ref. Take-off Quantity
Item Desc. WESTERN STATION TAKE-OFF

DCE. 2-82-2500 HOECKELS 344125

12. CUSTODIAL ROOM - ASSUME TAMS ESTIMATE OF \$20,000
CORRECT, IF NOT HIGH
13. STAFF ROOM - ASSUME TAMS ESTIMATE OF \$15,000 CORRECT,
IF NOT HIGH
14. TOILETS
- | | | | |
|-----------|--------------|---|--------------------|
| A. WOMENS | PARTITIONS | 6 |] SEEMS REASONABLE |
| | SINK | 3 | |
| | WATER CLOSET | 6 | |
| | ACCESSORIES | | |
- B. MEN (SAME AS WOMEN EXCEPT 2 URINALS IN PLACE OF 2WC.)
15. ACCOUSTICAL PANELS ASSUME TAMS ESTIMATE OF 22,275 Φ
CORRECT
16. GYPSUM BOARD 3,000 Φ ASSUME TAMS ESTIMATE
CORRECT
17. PAINTING 3,000 Φ ASSUME TAMS ESTIMATE
CORRECT
18. LANDSCAPING LS \$15,000 SEEMS REASONABLE FOR URBAN
SETTING

KELLOGG CORPORATION
DIRECT COST ESTIMATE

Item Analysis

JOB KC 1223 - ARCHITECTURAL FINISHES DATE 3/23/83

DCE. 2-82-2500 HORCKELS 344125

Sheet 1 of 2 Estm GAM Ckd..... ITEM.....
Plan Sheet No..... Bid Quantity.....
Spec. Ref..... Take-off Quantity.....
Item Desc 5TH + HILL - QUANTITIES

1. FLOORING

ASSUME TAMS ESTIMATE CORRECT EXCEPT ADD 4 ENTRANCES
+ BATHROOMS.

TAMS : 54,027
BATHROOM: WESTERN X 1.5 = 563
(4) ENTRANCES: (2) X WESTERN = 10,228
TOTAL = 64,818 SF

2. CMU WALLS

1.33 X WESTERN
1.33 X 18,230 = 24,246 SF

3. WALL TREATMENT

WESTERN + LOWER PLATFORM ENDS
29,592 + 1129 = 30,721 SF

4. CEILING TREATMENT

TAMS USED WESTERN + LOWER PLATFORM AS SQUARE FOOTAGE. KC
DOES NOT AGREE.

LOWER PLATFORM 450 X 58'-6" = 26,325 SF
UPPER PLATFORM 340 X 58'-6" = 19,890
MEZZANINE 700 X 58'-6" = 40,950
2X WESTERN ENTRANCES 2 X 3,584 = 7,168
TOTAL 94,503

KELLOGG CORPORATION
DIRECT COST ESTIMATE

Item Analysis

JOB KC-1223 ARCHITECTURAL FINISH. DATE 3/29/83

DCE. 2-82-2500 HOECKELS 344125

Sheet 2 of 2 Estm. GMM Ckd. _____ ITEM _____
Plan Sheet No. _____ Bid Quantity _____
Spec. Ref. _____ Take-off Quantity _____
Item Desc. 5TH + HILL - QUANTITIES

| | | | | | |
|-----|-----------------------|---------------------------------|------|-------|------------|
| 5. | SIGN + GRAPHICS | \$300,000 | L.S. | SEEMS | REASONABLE |
| 6. | MAPPING | \$75,000 | L.S. | " | " |
| 7. | ARTWORK | \$200,000 | L.S. | " | " |
| 8. | MODULAR EQUIPMENT | \$30,000 | L.S. | " | " |
| 9. | HARDWARE | \$312,000 | L.S. | " | " |
| 10. | GRANITE PLATFORM EDGE | 4 x 450 = 1,800 LF | | | |
| 11. | STAIRS | | | | |
| | A. GRANITE | 4 x WESTERN | | | |
| | | 4 x 684 FT ³ = 2,736 | | | |
| | B. CONCRETE | 2 x WESTERN | | | |
| | | 2 x 320 NLF = 640 NLF | | | |
| 12. | CUSTODIAL ROOM | \$30,000 | L.S. | SEEMS | HIGH |
| 13. | STAFF ROOM | \$20,000 | LS | " | " |
| 14. | RESTROOM | 2 x WESTERN | L.S. | | |
| | | 2 x \$8,108 = 16,216 | LS. | | |
| 15. | ACCOUSTICAL PANELS | | | | |
| | ACCEPT TAMS | 50,085 SF | | | |
| 16. | GYP SUM WALL BOARD | | | | |
| | ACCEPT TAMS | 6,000 SF. | | | |
| 17. | PAINTING | | | | |
| | ACCEPT TAMS | 6,000 SF | | | |
| 18. | LANDSCAPING | | | | |
| | NOT PRESENT IN TAMS | \$30,000 | LS. | | |




Southern California Rapid Transit District Metro Rail Project DESIGN UNITS

PHASE 1

- A100 - CENTRAL YARD & SHOPS, INCLUDING YARD LEAD TRACK FROM UNHDN STATION
- A135 - UNION STATION
- A140 - TUNNEL SEGMENT BETWEEN UNION STATION & 7TH / FLOWER STATION, INCLUDING CIVIC CENTER & 5TH / HILL STATIONS
- A165 - 7TH / FLOWER STATION
- A170 - TUNNEL SEGMENT FROM 7TH / FLOWER TO WILSHIRE / VERMONT, INCLUDING THE STATION AT WILSHIRE / ALVARADO
- A195 - WILSHIRE / VERMONT STATION

PHASE 2

- A220 - TUNNEL SEGMENT BETWEEN WILSHIRE / VERMONT & WILSHIRE / LA BREA, INCLUDING THE WILSHIRE / NORMANDIE & WILSHIRE / WESTERN STATIONS
- A245 - WILSHIRE / LA BREA STATION AND POCKET TRACK
- A250 - TUNNEL SEGMENT FROM WILSHIRE / LA BREA TO FAIRFAX / BEVERLY, INCLUDING THE WILSHIRE / FAIRFAX STATION
- A275 - FAIRFAX / BEVERLY STATION
- A310 - TUNNEL SEGMENT FROM FAIRFAX / BEVERLY TO HOLLYWOOD / CAHUENGA, INCLUDING THE FAIRFAX / SANTA MONICA & LA BREA / SUNSET STATIONS
- A350 - HOLLYWOOD / CAHUENGA STATION AND POCKET TRACK
- A410 - TUNNEL SEGMENT FROM HOLLYWOOD / CAHUENGA TO UNIVERSAL CITY STATION
- A425 - UNIVERSAL CITY STATION
- A430 - TUNNEL SEGMENT BETWEEN UNIVERSAL CITY STATION & NORTH HOLLYWOOD STATION
- A445 - NORTH HOLLYWOOD STATION & END LINE STORAGE TRACK



LEGEND

- METRO RAIL ALIGNMENT
- METRO RAIL STATIONS
- X - Crossover
- ▽ Traction Power Substations
- * "requiring separate bldg"
- Separate vent shaft

SUMMARY

**KELLOGG CORPORATION
DIRECT COST ESTIMATE**

JOB SCRIPD DATE 3-24-82

Sheet 0 of Estm 202 Ckd ✓ ITEM.....
 Plan Sheet No..... Bid Quantity.....
 Spec. Ref..... Take-off Quantity.....
 Item Desc. CROSS OVER

FORM E240E HOECKEL'S 347860

| DESCRIPTION | QUANTITY | DIR. LABOR | | EQUIP'T COST | | DIR. MAT'L | | PM/SUB | | E.O.E. | | TOTAL | |
|----------------------|----------|------------|--------|--------------|--------|------------|--------|--------|--------|--------|--------|-------|--------------|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT |
| <u>CROSS OVER</u> | | | | | | | | | | | | | |
| SOLDIER / LAG - | | | | | | | | | | | | | 1,575,000 |
| STREET DECK | | | | | | | | | | | | | 354,000 |
| SOG | | | | | | | | | | | | | 799,000 |
| ROOF DECK | | | | | | | | | | | | | 578,000 |
| PART PART WALLS | | | | | | | | | | | | | 267,000 |
| EXTERIOR WALLS | | | | | | | | | | | | | 774,000 |
| DEWATERING | | | | | | | | | | | | | ELSEWHERE |
| EXCAVATION | | | | | | | | | | | | | 430,000 |
| COMP. BACKFILL | | | | | | | | | | | | | 315,000 |
| EXCESS MUCK DISPOSAL | | | | | | | | | | | | | 301,000 |
| | | | | | | | | | | | | | \$ 5,393,000 |

5,393,000 / 460 = \$ 11,723 / FT

DMJM \$ 11,000

CLOSE - BUT THERE'S HAS MARK UPS.

ALLOWING FOR MISC SITE RESTORATION ETC. USE \$ 12,000

AT FAIRFAX USE \$ 14,000 / FT (DUE TO DEPTH)

-199-

SUMMARY CONTD

KELLOGG CORPORATION
DIRECT COST ESTIMATE

Sheet 0 of 02 Estm. DDL Ckd. ITEM.....
Plan Sheet No. Bid Quantity.....
Spec. Ref. Take-off Quantity.....
Item Desc. CROSS OVER.....

JOB. SCR TD DATE 3-24-83

FORM E240E HOECKEL'S 347860

| DESCRIPTION | QUANTITY | DIR. LABOR | | EQUIPM'T COST | | DIR. MAT'L | | PM/SUB | | E.O.E. | | TOTAL | |
|--|----------|------------|--------|---------------|--------|------------|--------|--------|--------|--------|--------|-------|--------|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT |
| <u>CROSS OVER CONTD</u> | | | | | | | | | | | | | |
| <u>KC Est (ALL X-OVERS EXCEPT FAIRFAX)</u> | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |

$$2760 \times 12000 = 33,120,000$$

$$460 \times 14000 = 6,440,000$$

$$39,560,000$$

DMJM - PBOU EST :

$$3320 \times 11,000 \text{ (LESS INDIRECTS)}$$

SAY 9600 DIRECT

$$\therefore 3320 \times 9600 = 31,872,000$$

$$CALL \underline{7,700,000} \quad \# \quad \underline{7,688,000}$$

-200-

KELLOGG CORPORATION
DIRECT COST ESTIMATE

JOB SCRTD DATE 3-24-83

Sheet 1 of 5 Estm DDL Ckd ✓ ITEM

Plan Sheet No. Bid Quantity

Spec. Ref. Take-off Quantity

Item Desc. CROSSOVERS

FORM E240E HOECKEL'S 347860

| DESCRIPTION | QUANTITY | DIR. LABOR | | EQUIPM'T COST | | DIR. MAT'L | | PM/SUB | | E.O.E. | | TOTAL | |
|-------------------|----------|--|------------------|---------------|--------|------------|--------|---------|--------|--------|--------|-------|----------------------|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT |
| <u>CROSSOVERS</u> | | LOCATED IN ESTIMATE # ON THE SCHEMATIC DIAGRAM TO BE IN REACHES 2-5(2EA)-8(2EA)-10-14 TOTAL 7 CROSSOVERS @ 460' EA = 3220' | | | | | | | | | | | |
| | | CUTS: | | | | | | | | | | | |
| | | REACH | STATION | | | | | - CUT - | | | | | |
| | | 2 | UNION | | | | | 35' | | | | | |
| | | 5 | ALVARADO | | | | | ? | | | | | |
| | | 5 | VERMONT | | | | | 46 | | | | | |
| | | 8 | FAIRFAX | | | | | 84 | | | | | |
| | | 8 | BEVERLY | | | | | 42 | | | | | |
| | | 10 | LA BREA - SUNSET | | | | | 55 | | | | | |
| | | 14 | NO HOLLYWOOD | | | | | 64 | | | | | |
| | | | | | | | | | | | | | SPECIAL AVE CALL 50' |

KELLOGG CORPORATION
DIRECT COST ESTIMATE

JOB SCRIP DATE 3-24-85

Sheet 2 of 5 Estm DD Ckd V ITEM.....
 Plan Sheet No..... Bid Quantity.....
 Spec. Ref..... Take-off Quantity.....
 Item Desc CROSS OVERS

FORM E240E HOECKEL'S 347860

| DESCRIPTION | QUANTITY | DIR. LABOR | | EQUIPMT COST | | DIR. MAT'L | | PM/SUB | | E.O.E. | | TOTAL | |
|-------------------|--------------|------------|--------|--------------|--------|------------|--------|--------|--------|--------|--------|-------|--------|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT |
| <u>CROSSOVERS</u> | <u>CONTD</u> | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |

KELLOGG CORPORATION
DIRECT COST ESTIMATE

JOB SCRIPT DATE 3-24-83

Sheet 3 of 5 Estm DD Ckd..... ITEM.....
Plan Sheet No..... Bid Quantity.....
Spec. Ref..... Take-off Quantity.....
Item Desc. CROSS OVER

FORM E240E HOECKEL'S 347860

| DESCRIPTION | QUANTITY | DIR. LABOR | | EQUIPM'T COST | | DIR. MAT'L | | PM/SUB | | E.O.E. | | TOTAL | |
|------------------------|----------------------------|------------|--------|---------------|--------|------------|--------|--------|------------------|--------|--------|-------|-----------|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT |
| <u>CROSSOVER CONTD</u> | | | | | | | | | | | | | |
| <u>SOLD PILE LAG</u> | (65 + 65 + 460 + 460) 50 = | | | | | | | | | | | | |
| | @ 52500 D' | | | | | | | | 30 ⁰⁰ | | | | 1,575,000 |
| <u>STREET DECKING</u> | 65 x 460 = | | | | | | | | | | | | |
| | 30000 D' | | | | | | | | 1180 | | | | 354,000 |
| <u>EXCAVATION</u> | | | | | | | | | | | | | |
| TOP 3' | 3400 CY | | | | | | | | 21 ⁰⁰ | | | | 71400 |
| NEX 5' | 5670 CY | | | | | | | | 10 ⁰⁰ | | | | 56700 |
| BULK | 46500 CY | | | | | | | | 650 | | | | 302200 |

-203-

KELLOGG CORPORATION
DIRECT COST ESTIMATE

JOB SCRTD DATE 3-24-83

Sheet 4 of 5 Estm OK Ckd ✓ ITEM.....

Plan Sheet No..... Bid Quantity.....

Spec. Ref..... Take-off Quantity.....

Item Desc. CROSS OVER

FORM E240E HOECKEL'S 347880

| DESCRIPTION | QUANTITY | DIR. LABOR | | EQUIP'T COST | | DIR. MAT'L | | PM/SUB | | E.O.E. | | TOTAL | |
|--------------------------|--------------------|------------|--------|--------------|--------|------------|--------|------------------|--------|--------|--------|-------|-----------|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT |
| <u>CROSS OVER CONT'D</u> | | | | | | | | | | | | \$ | |
| <u>SLAB ON GRADE</u> | 5500 CY. (08 5700) | | | | | | | 70 ⁰⁰ | | | | | 399 000 |
| REBAR | 1000 000 # | | | | | | | 38 | | | | | 380 000 |
| FINISH / CURE | LS | | | | | | | | | | | | 20 000 |
| | | | | | | | | | | | | | 799 000 ✓ |
| <u>ROOF DECK</u> | 3000 CY (3400) | | | | | | | 70 ⁰⁰ | | | | | 210 000 |
| REBAR | 600 000 # | | | | | | | 38 | | | | | 228 000 |
| FORMS | 26000 sq' | | | | | | | 5 ⁰⁰ | | | | | 130 000 |
| FINISH / CURE | LS | | | | | | | | | | | | 10 000 |
| | | | | | | | | | | | | | 578 000 ✓ |
| <u>EXTERIOR WALLS</u> | 2700 CY (3000) | | | | | | | 78 ⁰⁰ | | | | | 234 000 |
| REBAR | 540 000 # | | | | | | | 38 | | | | | 205 000 |
| FORMS | 50 000 sq' | | | | | | | 6 ⁵⁰ | | | | | 325 000 |
| FINISH / CURE | LS | | | | | | | | | | | | 10 000 |
| | | | | | | | | | | | | | 774 000 ✓ |
| <u>PART PART WALLS</u> | 800 (900) | | | | | | | 82 ⁰⁰ | | | | | 74 000 |
| REBAR | 160 000 # | | | | | | | 38 | | | | | 61 000 |
| FORMS | 22 000 sq' | | | | | | | 6 ⁰⁰ | | | | | 132 000 |
| CURE (FORMED) | NIL | | | | | | | | | | | | 267 000 ✓ |

-204-

KELLOGG CORPORATION
DIRECT COST ESTIMATE

JOB SCRIPD DATE 3-24-83

Sheet 5 of 5 Estm. DM Ckd. ✓ ITEM.....

Plan Sheet No..... Bid Quantity.....

Spec. Ref..... Take-off Quantity.....

Item Desc. CROSS OVER

FORM E240E HOECKEL'S 347860

| DESCRIPTION | QUANTITY | DIR. LABOR | | EQUIPMT COST | | DIR. MAT'L | | PM/SUB | | E.O.E. | | TOTAL | |
|-----------------------------|-----------------|------------|--------|--------------|--------|------------|--------|--------|--------|--------|-------------|-------|----------------|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT |
| <u>CROSS OVER CONT'D</u> | | | | | | | | | | | | | |
| <u>COMPACTED BACKFILL</u> | <u>20000 CY</u> | | | | | | | | | | <u>1575</u> | | <u>315,000</u> |
| <u>EXCESS MUCK DISPOSAL</u> | <u>45000 CY</u> | | | | | | | | | | <u>670</u> | | <u>301000</u> |

KELLOGG CORPORATION
DIRECT COST ESTIMATE

Sheet 0 of Estm DDL Ckd K ITEM

Plan Sheet No. Bid Quantity

JOB SCRIPD DATE 3-23-83 Spec. Ref. Take-off Quantity

Item Desc. POCKET TRACK

FORM E240E HOECKEL'S 347860

| DESCRIPTION | QUANTITY | DIR. LABOR | | EQUIP'T COST | | DIR. MAT'L | | PM/SUB | | E.O.E. | | TOTAL | |
|----------------------|----------|------------|-----------------|--------------|--------|------------|---------|--------|--------|--------|--------|-------|------------|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT |
| <u>POCKET TRACKS</u> | | | | | | | | | | | | | |
| KC ESTIMATE | | | | | | | | | | | | | |
| | | | # 12,500 / FT | | | | DIRRECT | | | | | | |
| | | | 12,500 × 2260 = | | | | | | | | | # | 28,250,000 |
| DIAM PQQD EST. | | | # 11,000 / FT | | | | ALL IN | | | | | | |
| CONVERT TO DIRRECT | | | | | | | | | | | | | |
| | | | 9600 × 2260 = | | | | | | | | | # | 21,696,000 |
| | | | # | | | | | | | | | | |
| | | | CALL 6,500,000 | | | | | | | | | # | 6,554,000 |

KELLOGG CORPORATION
DIRECT COST ESTIMATE

Sheet 1 of 1 Estm. DDL Ckd. ITEM.....

Plan Sheet No..... Bid Quantity.....

JOB SCRIP DATE 3-23-83

Spec. Ref..... Take-off Quantity.....

Item Desc. POCKET TRACK

FORM E240E HOECKEL'S 347880

| DESCRIPTION | QUANTITY | DIR. LABOR | | EQUIPM'T COST | | DIR. MAT'L | | PM/SUB | | E.O.E. | | TOTAL | |
|----------------------|----------|--|--------|------------------|--------|------------|--------|--------|--------|--------|--------|-------|--------|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT |
| <u>POCKET TRACKS</u> | | | | | | | | | | | | | |
| | | <p>LOCATED IN ESTIMATE # ON THE SCHEMATIC DIAGRAM TO BE REACHES 6 & 11 TOTAL @ 1010 & 1250 FT EACH FOR TOTAL OF 2260 FT.</p> | | | | | | | | | | | |
| | | <p>CUTS:</p> | | | | | | | | | | | |
| | | REACH | | STATION | | | | | | | | | |
| | | 6 | | LA BREA WILSHIRE | | | | 575' | | | | | |
| | | 11 | | HOLLYWOOD | | | | 55' | | | | | |
| | | <p>SLIGHTLY DEEPER THAN CROSS OVER AVERAGE</p> | | | | | | | | | | | |
| | | <p>CUTS - USE 12,500 DIRECT COST.</p> | | | | | | | | | | | |

-207-

**KELLOGG CORPORATION
DIRECT COST ESTIMATE**

Sheet 1 of 1 Estm DM Ckd ✓ ITEM.....

Plan Sheet No..... Bid Quantity.....

JOB SCRTP DATE 3-23-83

Spec. Ref..... Take-off Quantity.....

Item Desc TAIL TRACK (N. HOLLYWOOD)

FORM E2406 HOECKEL'S 947589

| DESCRIPTION | QUANTITY | DIR. LABOR | | EQUIPM'T COST | | DIR. MAT'L | | PM/SUB | | E.O.E. | | TOTAL | |
|-------------------|----------|---|--------|---------------|--------|------------|--------|--------|--------|--------|--------|----------------------------|--------|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT |
| <u>TAIL TRACK</u> | | | | | | | | | | | | | |
| | | <p>LOCATED AT NORTH END OF LINE FROM STATION 1069 +50 TO 1057 <u>54</u> TOTAL CALL 1200 LF.</p> | | | | | | | | | | | |
| | | <p>CUT :</p> <p>ADJACENT TO NORTH HOLLYWOOD STATION WHICH IS 64 FT DEEP ∴ USE \$ 13000 / FT</p> <p style="text-align: right;">13000 @ 1200 = 15,600,000</p> | | | | | | | | | | | |
| | | <p>AS THIS WILL SERVE AS NORTH SHOP AND MAINT AREA - ALLOW FOR ELEC / MECH & SOME SHOP EQUIP</p> <p style="text-align: right;">4,400,000</p> | | | | | | | | | | | |
| | | | | | | | | | | | | <p>Calc. \$ 20,000,000</p> | |

SUMMARY

KELLOGG CORPORATION
DIRECT COST ESTIMATE

JOB SCRIP DATE 3-30-83

Sheet 0 of Estm DL Ckd ITEM

Plan Sheet No. Bid Quantity

Spec. Ref. Take-off Quantity

Item Desc. REACH 1

DUAL TRACK C/C

FORM E240E HOECKEL'S 347860

| DESCRIPTION | QUANTITY | DIR. LABOR | | EQUIPM'T COST | | DIR. MAT'L | | PM/SUB | | E.O.E. | | TOTAL | |
|-------------------------------------|----------------|------------|---------------------|---------------|------------------|------------|--------|-----------------|--------|--------|--------|-------|----------------------|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT |
| <u>REACH 1 DUAL TRACK</u> | | | | | | | | | | | | | |
| <u>DUAL TRACK TWIN TUBE C/C</u> | <u>792 FT.</u> | <u>@</u> | <u>45 FT ME CUT</u> | | | | | <u>\$ 11000</u> | | | | | <u>8,712,000</u> |
| <u>DUAL TRACK SINGE C-C.</u> | <u>945 FT</u> | <u>@</u> | <u>30 FT</u> | | | | | <u>\$ 7000</u> | | | | | <u>6,615,000</u> |
| | | | | | | | | | | | | | <u>\$ 15,327,000</u> |
| <u>REACH 1 DMM PGD</u> | | | <u>EST</u> | | <u>1,155,000</u> | | | | | | | | <u>8158000</u> |
| | | | | | <u>8267000</u> | | | | | | | | |
| | | | | | <u>9,422,000</u> | | | | | | | | |
| <u>RET UCAI</u> | | | | | <u>8158000</u> | | | | | | | | |
| <u>TO DIRECT COST</u> | | | | | | | | | | | | | <u>\$ 7,169,000</u> |

-209-

KELLOGG CORPORATION
DIRECT COST ESTIMATE

JOB SCRTD DATE 3-30-83

Sheet 1 of 1 Estm ML Ckd ITEM

Plan Sheet No. _____ Bid Quantity _____

Spec. Ref. _____ Take-off Quantity _____

Item Desc. REACH 1 QUANTITIES

DUAL TRACK

FORM E240E HOECKEL'S 347860

| DESCRIPTION | QUANTITY | DIR. LABOR | | EQUIPM'T COST | | DIR. MAT'L | | PM/SUB | | E.O.E. | | TOTAL | |
|---|----------|------------|--------|---------------|--------|------------|--------|--------|--------|--------|--------|-------|--------|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT |
| <u>REACH 1 DUAL TRACK :</u> | | | | | | | | | | | | | |
| <p>K C TAKE OFF</p> <p>OVERALL STATION LENGTH 640 FT SCHEMATIC SHOWS 450 FT WHICH IS PLATFORM.</p> <p>∴ 95 FT EACH WAY THEN END OF STATION IS 102+12.42</p> <p>102+12.42 TO THE EL MONTE EXTENSION BULKHEAD (94+20) IS 792.42 CALL <u>792</u></p> <p>EL MONTE BULKHEAD TO PORTAL 94+20 → 84+75 = 945 FT.</p> <p>DUAL TRACK TWIN TUBE 792 FT WITH AVE 45 FT CUT</p> <p>DUAL TRACK C/C 945 FT WITH AVE 30 FT CUT.</p> | | | | | | | | | | | | | |

SUMMARY

KELLOGG CORPORATION
DIRECT COST ESTIMATE

Sheet 0 of 0 Estm DR Ckd K ITEM.....
 Plan Sheet No..... Bid Quantity.....
 Spec. Ref..... Take-off Quantity.....
 Item Desc. DOWNTOWN VENT STRUCTURE

JOB SCRTD DATE 3-21-83

FORM E240E HOECKEL'S 347860

| DESCRIPTION | QUANTITY | DIR. LABOR | | EQUIP'T COST | | DIR. MAT'L | | PM/SUB | | E.O.E. | | TOTAL | |
|--|----------|------------|--------|--------------|--------|------------|--------|--------|--------|--------|--------|-------|------------|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT |
| <u>DOWNTOWN VENT STRUCTURE (SOFT GROUND)</u> | | | | | | | | | | | | | |
| <u>STRUCTURE ONLY - DIRECT COSTS</u> | | | | | | | | | | | | | |
| KC ESTIMATE TOTALS SH. 1 THRU 4 = | | | | | | | | | | | | \$ | 902,000 |
| DMJM EST | | | | | | | | | | | | | |
| AS PRESENTED | | | | | | | | | | | | | |
| DEMO | | | | | | | | | | | | | |
| SITE WORK | | | | | | | | | | | | | |
| TRAFFIC MAINT. | | | | | | | | | | | | | |
| EARTHWORK | | | | | | | | | | | | | |
| SHORING | | | | | | | | | | | | | |
| CONCRETE | | | | | | | | | | | | | |
| WATERPROOF | | | | | | | | | | | | | |
| SUBTOTAL | | | | | | | | | | | | | \$ 902,000 |
| UTILITIES | | | | | | | | | | | | | |
| ARCH FINISHES | | | | | | | | | | | | | |
| MECH / ELEC | | | | | | | | | | | | | |
| MOB | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |

-211-

ELSEWHERE
 SHOULD BE MINIMAL
 ELSEWHERE
 ELSEWHERE

KELLOGG CORPORATION
DIRECT COST ESTIMATE

Sheet 0 of 02 Estm. DD Ckd. K ITEM.....
Plan Sheet No..... Bid Quantity.....
Spec. Ref..... Take-off Quantity.....
Item Desc. DOWNTOWN VENT STR

JOB SCRTD DATE 3-21-83

FORM E240E HOCKEL'S 347860

| DESCRIPTION | QUANTITY | DIR. LABOR | | EQUIP'T COST | | DIR. MAT'L | | PM/SUB | | E.O.E. | | TOTAL | |
|--------------------------------------|----------|------------|--------------|--------------|--------|------------|--------|--------|--------|--------|--------|-------|--------|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT |
| <u>DOWNTOWN VENT STRUCTURE CONTD</u> | | | | | | | | | | | | | |
| <u>STRUCTURE ONLY DIRECT COSTS</u> | | | | | | | | | | | | | |
| <u>DMJM EST. CORRECTED FOR MATN.</u> | | | | | | | | | | | | | |
| DEMO | | | 50,000 | | | | | | | | | | |
| SITE WORK | | | 43,000 | | | | | | | | | | |
| TRAFFIC MAINT. | | | 12,000 | | | | | | | | | | |
| EARTHWORK | | | 108,000 | | | | | | | | | | |
| SHORING | | | 626,000 | | | | | | | | | | |
| CONCRETE | | | 514,000 | | | | | | | | | | |
| WATERPROOF | | | 28,000 | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | \$ 1,318,000 | | | | | | | | | | |
| KC EST | | | 907,000 | | | | | | | | | | |
| | | | \$ 416,000 | | | | | | | | | | |
| 3 SHAFTS | | | 416,000 | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |

NOTE: STR ONLY
LESS ARCH FINISH
MECH-ELECT.

#

CALL 1,250,000

KELLOGG CORPORATION
DIRECT COST ESTIMATE

JOB SCRIPD DATE 3-21-83

Sheet 2 of 4 Estm. DDC. Ckd. ITEM.....
Plan Sheet No..... Bid Quantity.....
Spec. Ref..... Take-off Quantity.....
Item Desc. DOWN TOWN VENT SHAFTS

FORM E240R HOECKEL'S 335481

| DESCRIPTION | QUANTITY | DIR. LABOR | | REP. LABOR | | MAT'L | | SUB-BID | | E.O.E. | | TOTAL | |
|----------------------------|--|------------|--------|---|--------|-------------------|--------|------------------------|--------|--------|--------|-------|-------------------------------------|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT |
| <u>III EARTHWORK</u> | <u>AT 30' DEEP X 100' TO ROADSIDE X 40' = 4500 CY @ Most</u> | | | | | | | | | | | | |
| <u>MACH. EXCAV.</u> | <u>4000 CY</u> | | | | | | | <u>5⁰⁰</u> | | | | | <u>20000</u> |
| <u>HAND EXCAV</u> | <u>200 CY</u> | | | | | | | <u>24⁰⁰</u> | | | | | <u>4800</u> |
| <u>CONV. IMPORT</u> | <u>500 CY</u> | | | <u>WHY HERE ?</u> | | <u>ALLOW same</u> | | <u>15⁰⁰</u> | | | | | <u>7500</u> |
| <u>DISPOSAL</u> | | | | | | | | | | | | | |
| <u>DISP. EXCESS</u> | <u>4200 CY</u> | | | | | | | <u>6⁵⁰</u> | | | | | <u>27300</u> |
| <u>IV SHORING -</u> | | | | | | | | | | | | | |
| <u>SOLDIER / LAG</u> | <u>15000 L'</u> | | | <u>(SHALLOW - UNIT DOWN)</u> | | | | <u>20⁰⁰</u> | | | | | <u>300,000</u> |
| | | | | | | | | | | | | | <u>* NOTE: DRUM EXTENSION BUST.</u> |
| <u>DECKING</u> | <u>3895 L'</u> | | | <u>SPAN WAY DOWN SAY -</u> | | | | <u>8⁰⁰</u> | | | | | <u>31,160</u> |
| <u>DEWATERING</u> | <u>6 Mo</u> | | | <u>DOWN TO GRADE - NO MORE THAN 6 -</u> | | | | | | | | | <u>30000</u> |
| <u>WALKWAY DECK</u> | | | | <u>STRONG BACKED PLY WOOD.</u> | | | | | | | | | <u>2000</u> |
| <u>STEEL SHEET (WHERE)</u> | | | | <u>ALLOW</u> | | | | | | | | | <u>5000</u> |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | <u>Total SHEET 428,000</u> |

-214-

KELLOGG CORPORATION
DIRECT COST ESTIMATE

JOB SCRTP DATE 3-21-83

Sheet 3 of 4 Estm..... Ckd ✓ ITEM.....
Plan Sheet No..... Bid Quantity.....
Spec. Ref..... Take-off Quantity.....
Item Desc DOWNTOWN VENT SCAFFS -

FORM E240R HOECKEL'S 936481

| DESCRIPTION | QUANTITY | DIR. LABOR | | REP. LABOR | | MAT'L | | SUB-BID | | E.O.E. | | TOTAL | |
|---------------------|-----------------|------------|--------|------------------|-----------|-------|--------|---------|------------------|--------|--------|--------------|---------|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT |
| ✓ CONCRETE : | | | | | | | | | | | | | |
| FORMWORK | | | | | | | | | | | | | |
| EX. WALLS | 4000 \square' | | | | | | | | 6 ⁰⁰ | | | | 24,000 |
| INTER. WALLS | 6000 \square' | | | WHERE | SO MANY ? | | | | 6 ⁰⁰ | | | | 36,000 |
| ROOF. | 5000 \square' | | | ? | | | | | 7 ⁰⁰ | | | | 35,000 |
| CONCRETE | | | | | | | | | | | | | |
| S.O.G. | 410 CY. | | | | | | | | 70 ⁰⁰ | | | | 28,700 |
| EXT. WALLS | 450 CY. | | | | | | | | 80 ⁰⁰ | | | | 36,000 |
| INT. WALLS | 118 CY. | | | | | | | | 90 ⁰⁰ | | | | 10,600 |
| ROOF SLAB | 615 CY. | | | MUST BE 5' THICK | | | | | 80 ⁰⁰ | | | | 49,200 |
| REBAR | | | | | | | | | | | | | |
| SOG @ 100 # | 41000 # | | | | | | | | 0 ⁴⁰ | | | | 16,400- |
| EX WALL @ 200 # | 90000 # | | | | | | | | 0 ⁴⁰ | | | | 36,000 |
| INT WALL @ 80 # | 9500 # | | | | | | | | 0 ⁴⁰ | | | | 3,800 |
| ROOF @ 300 # | 184500 # | | | | | | | | 0 ³⁵ | | | ? | 64,575 |
| FINISH & CURE | L.S. | | | | | | | | | | | | 5000 |
| | | | | | | | | | | | | TOTAL SHEET | |
| | | | | | | | | | | | | \$ 345,000 ✓ | |

-215-

KELLOGG CORPORATION
DIRECT COST ESTIMATE

JOB SCRIP DATE 3-21-83

Sheet 4 of 4 Estm DDC Ckd ✓ ITEM.....
Plan Sheet No..... Bid Quantity.....
Spec. Ref..... Take-off Quantity.....
Item Desc DOWNTOWN VENT SHAFT

FORM E240R HOECKEL'S 335481

| DESCRIPTION | QUANTITY | DIR. LABOR | | REP. LABOR | | MAT'L | | SUB-BID | | E.O.E. | | TOTAL | |
|---|----------|------------|--------|------------|--------|-------|--------|---------|--------|--------|--------|-------|-------------|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT |
| <u>VII</u> WATERPROOFING | | | | | | | | | | | | | \$ |
| 5/16" BENT. PANELS ^{WALL} 6048 sq' | | | | | | | | 100 | | | | | 6000 |
| 5/16" " " ^{Roof} 5576 sq' | | | | | | | | 100 | | | | | 5500 |
| WATER STOP JOINT PACK 2560 sq' | | | | | | | | 500 | | | | | 4000 |
| | | | | | | | | | | | | | 12000 |
| <u>VII</u> UTILITY SUPPORTS. THIS ITEM DUPLICATED IN \$25,000,000 | | | | | | | | | | | | | - |
| <u>VIII</u> ARCH FINISHES - NO. NOT A PAY AREA - ALLOW SOME PAINT OR BUSH HAMMER OF VENT STR. | | | | | | | | | | | | | 10,000 |
| <u>IX</u> MECHANICAL | | | | | | | | | | | | | - |
| <u>X</u> ELECTRICAL | | | | | | | | | | | | | 50,000 |
| NOTE: STRUCTURE ONLY. ALLOW FOR HOISTING EQUIP. | | | | | | | | | | | | | |
| TOTAL SHEET | | | | | | | | | | | | | \$ 88,000 ✓ |

-216-

KELLOGG CORPORATION
DIRECT COST ESTIMATE

Sheet 01 of 02 Estm DRL Ckd K ITEM.....
 Plan Sheet No..... Bid Quantity.....
 Spec. Ref..... Take-off Quantity.....
 Item Desc. VENT SHAFT MIN

JOB SCRIPD DATE 3-21-83

FORM E240E HOECKEL'S 347860

| DESCRIPTION | QUANTITY | DIR. LABOR | | EQUIPM'T COST | | DIR. MAT'L | | PM/SUB | | E.O.E. | | TOTAL | |
|-----------------------------|-----------------|------------|--------|---------------|---------------------------|-------------|--------|-----------------|--------|-----------------------|--------|----------|---------------------|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT |
| <u>MOUNTAIN VENT SHAFTS</u> | | | | | | | | | | | | | |
| | | | | <u>TWO</u> | | <u>EACH</u> | | <u>IN MIN</u> | | <u>(Pack)</u> | | | |
| | | | | | | | | | | | | <u>#</u> | |
| <u>TOTAL SHEETS</u> | <u>1 THRU 5</u> | | | | | | | <u>(KC EST)</u> | | | | | <u>3,144,000</u> |
| <u>DMJM EST</u> | | | | | | | | | | | | | |
| | | | | | | | | | | | | | <u>AS PRESENTED</u> |
| | | | | | | | | | | | | | <u>#</u> |
| <u>SITE WORK</u> | | | | | <u>250,000</u> | | | | | | | | |
| <u>EARTHWORK</u> | | | | | <u>- 0 -</u> | | | | | <u>(NOT EXTENDED)</u> | | | |
| <u>SHORING</u> | | | | | <u>100,000</u> | | | | | | | | |
| <u>CONCRETE</u> | | | | | <u>1,684,000</u> | | | | | | | | |
| <u>STR. STEEL / IRON</u> | | | | | <u>54,100</u> | | | | | | | | |
| <u>SPECIAL HOIST</u> | | | | | <u>800,000</u> | | | | | | | | |
| <u>CONSTR VENT SYSTEM</u> | | | | | <u>400,000</u> | | | | | | | | |
| <u>FINISHES</u> | | | | | <u>11,000</u> | | | | | | | | |
| <u>ELEC - MECH</u> | | | | | <u>-</u> | | | | | <u>ELSEWHERE</u> | | | |
| | | | | | | | | | | | | <u>#</u> | |
| <u>DIRECT STRUCTURAL</u> | | | | | <u>3,299,000</u> | | | | | | | | <u>3,299,000</u> |
| | | | | | | | | | | | | | <u>#</u> |
| | | | | | | | | | | | | | <u>155,000</u> |
| <u>TWO SHAFTS</u> | | | | | | | | | | | | | <u>#</u> |
| | | | | | <u>155,000 x 2 = CALL</u> | | | | | | | | <u>300,000</u> |
| | | | | | <u>DMJM EXCEEDS KC</u> | | | | | | | | <u>300,000</u> |

-217-

KELLOGG CORPORATION
DIRECT COST ESTIMATE

Sheet 02 of 02 Estm 02 Ckd _____ ITEM _____
Plan Sheet No. _____ Bid Quantity _____
Spec. Ref. _____ Take-off Quantity _____
Item Desc. VENT SHAFT - Mtn -

JOB SCRTD DATE 3-21-83

FORM E240E HOECKEL'S 347880

| DESCRIPTION | QUANTITY | DIR. LABOR | | EQUIP'T COST | | DIR. MAT'L | | PM/SUB | | E.O.E. | | TOTAL | |
|--------------------------------------|----------|------------|---------------------|--------------|--------|------------|--------|--------|--------|--------|--------|-------|---------------------------|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT |
| <u>MOUNTAIN VENT SHAFT CONTD</u> | | | | | | | | | | | | | |
| <u>DMJM Est. CORRECTED FOR MATH.</u> | | | | | | | | | | | | | |
| <u>SITE WORK</u> | | | <u>250 000</u> | | | | | | | | | | |
| <u>EARTH WORK</u> | | | <u>660 000</u> | | | | | | | | | | |
| <u>SHORING</u> | | | <u>100 000</u> | | | | | | | | | | |
| <u>CONCRETE</u> | | | <u>1684 000</u> | | | | | | | | | | |
| <u>STR STEEL</u> | | | <u>54 000</u> | | | | | | | | | | |
| <u>SP. HOIST</u> | | | <u>800 000</u> | | | | | | | | | | |
| <u>CONSTR VENT</u> | | | <u>400 000</u> | | | | | | | | | | |
| <u>FINISHES</u> | | | <u>11 000</u> | | | | | | | | | | |
| <u>DMJM —</u> | | | <u>\$ 3,959,000</u> | | | | | | | | | | |
| <u>KC Est</u> | | | <u>3,144 000</u> | | | | | | | | | | |
| | | | <u>\$ 815 000</u> | | | | | | | | | | <u>EACH</u> |
| <u>TWO SHAFTS</u> | | | <u>\$ 1,630,000</u> | | | | | | | | | | <u>+ MOB \$ 2,000,000</u> |

NOTE DMJM LEFT MOBILIZATION OUT OF THIS ONE. 400,000 ±

-218-

KELLOGG CORPORATION
DIRECT COST ESTIMATE

Sheet 1 of 5 Estm DPL Ckd _____ ITEM _____

Plan Sheet No. _____ Bid Quantity _____

JOB SCRTP DATE 3-21-83

Spec. Ref. _____ Take-off Quantity _____

Item Desc. VENT SHAFT MTN

FORM E240E HOECKEL'S 347880

| DESCRIPTION | QUANTITY | DIR. LABOR | | EQUIPM'T COST | | DIR. MAT'L | | PM/SUB | | E.O.E. | | TOTAL | |
|---|-------------|------------|--------|---------------|--------|------------|--------|--------|--------|--------|--------|-------|--|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT |
| <u>MOONTHAIN VENT SHAFTS :</u> | | | | | | | | | | | | | |
| | | | | | | | | | | | | | <u>TWO EACH IN MTN</u> |
| | | | | | | | | | | | | | <u>AREA - SELECT AREA WHERE DAYLIGHT SHOOTING - BLASTING PERMITTED. WORK 2-85 OR 1-10- MAT THE SHOTS AND ONCE UNDER WAY BLASTING IS OF NIL EFFECT.</u> |
| | | | | | | | | | | | | | <u>\$</u> |
| <u>I SITEWORK</u> | <u>L.S.</u> | | | | | | | | | | | | <u>ROADS - REHAB ETC</u> |
| | | | | | | | | | | | | | <u>150,000</u> |
| <u>II EARTHWORK :</u> | | | | | | | | | | | | | <u>ASSUME 300 LF @ 24' O.D.</u> |
| | | | | | | | | | | | | | <u>$\frac{24^2 \pi}{4} \times \frac{300}{27} = 5000$ CY BLAST</u> |
| | | | | | | | | | | | | | <u>ASSUME 3# / CY - POWDER CAPS</u> |
| <u>EXCAVATION</u> | | | | | | | | | | | | | <u>(SEE BACK UP SHEETS-X)</u> |
| <u>BUILD BASEMENT</u> | | | | | | | | | | | | | <u>920,000</u> |
| <u>BACKFILL</u> | | | | | | | | | | | | | <u>1620 CY @ 4.00</u> |
| <u>DRIFT OUT SIDE TUNNELS OVER HEADINGS</u> | | | | | | | | | | | | | <u>540 CY @ 5.00</u> |
| | | | | | | | | | | | | | <u>80' @ 500</u> |
| | | | | | | | | | | | | | <u>40,000</u> |
| | | | | | | | | | | | | | <u># 1,112,000</u> |

-219-

KELLOGG CORPORATION
DIRECT COST ESTIMATE

JOB SCRTD DATE 3-21-83

Sheet 2 of 5 Estm DD Ckd. ITEM

Plan Sheet No. Bid Quantity

Spec. Ref. Take-off Quantity

Item Desc. VENT SHAFT MIN

FORM E240E HOECKEL'S 347860

| DESCRIPTION | QUANTITY | DIR. LABOR | | EQUIPMT COST | | DIR. MAT'L | | PM/SUB | | E.O.E. | | TOTAL | |
|------------------------------|----------------|---|--------|--------------|-----------------|------------|--------|--------|--------|--------|--------|-------|------------------|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT |
| <u>II EARTHWORK (CONT'D)</u> | | | | | | | | | | | | | |
| <u>DISP. EXCESS ROCK -</u> | | <u>DOUBT IF WE CAN LEAVE ANY OF THIS ON TOP. EPA - GET RID OF ALL #</u> | | | | | | | | | | | |
| | <u>6000 CY</u> | | | | <u>@ 10.00</u> | | | | | | | | <u>60,000</u> |
| <u>III SHORING -</u> | | | | | | | | | | | | | |
| | | <u>ASSUME ROCK FAIRLY COMP. - THEN USE 20% RIBS - WITH ROCK BOLT & MAIN STRAPS.</u> | | | | | | | | | | | |
| | | | | | <u>80,000 #</u> | | | | | | | | <u>50,000</u> |
| | | | | | | | | | | | | | <u>25,000</u> |
| | | | | | | | | | | | | | <u># 135,000</u> |

-220-

KELLOGG CORPORATION
DIRECT COST ESTIMATE

Sheet 3 of 5 Estm OP-Ckd ITEM.....
Plan Sheet No..... Bid Quantity.....
Spec. Ref..... Take-off Quantity.....
Item Desc. VENT STRUCTURE MTN

JOB SCRIPD DATE 3-21-83

FORM E240E HOECKEL'S 347860

| DESCRIPTION | QUANTITY | DIR. LABOR | | EQUIP'T COST | | DIR. MAT'L | | PM/SUB | | E.O.E. | | TOTAL | |
|--------------------|----------|------------|--------|--------------|---------------|------------|--------|-------------------|--------|--------|--------|-------------------|------------|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT |
| IV CONCRETE | | | | | | | | | | | | | |
| FORMWORK. | | | | | | | | | | | | | |
| SLIP FORM | 18850 D' | | | 110 | X 300 | 20-11 | X 200 | 10 ⁰⁰ | | | | | 188000 |
| PART WALL | 12000 D' | | | | | | | 8 ⁰⁰ | | | | | 96000 |
| SIDE TUNNELS | 2100 D' | | | | | | | 6 ⁰⁰ | | | | | 12000 |
| BUILD. BASE | 8000 D' | | | | | | | 5 ⁰⁰ | | | | | 40000 |
| BUILD. PART. | 2500 D' | | | | | | | 4 ⁰⁰ | | | | | 10000 |
| SLAB ROOF | 1000 D' | | | | | | | 8 ⁰⁰ | | | | | 8000 |
| CONCRETE | | | | | | | | | | | | | |
| SHAFT WALLS | 1400 CY | | | 21 | 11 X 300 X 2' | 1466 | | 250 ⁰⁰ | | | | | \$ 350,000 |
| SHAFT PART WALL | 220 CY | | | | | | | 200 ⁰⁰ | | | | | 44,000 |
| SIDE TUNNEL | 186 CY | | | | UNDERGROUND | | | 500 ⁻ | | | | | 93,000 |
| SOG | 30 CY | | | | | | | 100 ⁻ | | | | | 3000 |
| BLDG BASE WALL | 300 CY | | | | | | | 200 ⁻ | | | | | 60000 |
| BLDG PART WALL | 100 | | | | | | | 200 ⁻ | | | | | 20000 |
| ROOF | 80 | | | | | | | 200 ⁻ | | | | | 16000 |
| | | | | | | | | | | | | \$ 940,000 | |

KELLOGG CORPORATION
DIRECT COST ESTIMATE

Sheet 4 of 5 Estm DDL Ckd ✓ ITEM.....
Plan Sheet No..... Bid Quantity.....
Spec. Ref..... Take-off Quantity.....
Item Desc. VENT. STRUCTURE MTN

JOB SCRTD DATE 3-21-83

FORM E249E HOECKEL'S 347880

| DESCRIPTION | QUANTITY | DIR. LABOR | | EQUIPM'T COST | | DIR. MAT'L | | PM/SUB | | E.O.E. | | TOTAL | |
|--------------------------------|---------------|------------|--------|---------------|--------|------------|--------|--------------------|--------|--------|--------|--------------------|-----------------|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT |
| <u>IV CONCRETE</u> | <u>CONT'D</u> | | | | | | | | | | | | |
| <u>REBAR</u> | | | | | | | | | | | | | |
| <u>SHAFT WALLS - 0 - ?</u> | | | | | | | | | | | | | |
| <u>SHAFT PART WALL 26640 #</u> | | | | | | | | <u>060</u> | | | | | <u>16000</u> |
| <u>SIDE TUNNEL - 0 -</u> | | | | | | | | | | | | | |
| <u>BLOG WALLS 60000 #</u> | | | | | | | | <u>060</u> | | | | | <u>36000</u> |
| <u>BLOG PART. 11000 #</u> | | | | | | | | <u>060</u> | | | | | <u>6600</u> |
| <u>ROOF SLAB 11500 #</u> | | | | | | | | <u>060</u> | | | | | <u>7000</u> |
| <u>S.O.G. 2700 #</u> | | | | | | | | <u>060</u> | | | | | <u>2000</u> |
| | | | | | | | | | | | | | |
| | | | | | | | | <u>TOTAL REBAR</u> | | | | | <u>68,000</u> |
| <u>FINISH / CURE</u> | <u>JOB</u> | | | <u>L.S.</u> | | | | | | | | | <u>15,000</u> |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | <u>TOTAL SHEET</u> | <u>\$83,000</u> |

-222-

KELLOGG CORPORATION
DIRECT COST ESTIMATE

JOB SCRTD DATE 3-21-83

Sheet 5 of 5 Estm DD Ckd X ITEM.....

Plan Sheet No..... Bid Quantity.....

Spec. Ref..... Take-off Quantity.....

Item Desc. VENT STRUCTURE - MTN

FORM E240E HOECKEL'S 347860

| DESCRIPTION | QUANTITY | DIR. LABOR | | EQUIP'T COST | | DIR. MAT'L | | PM/SUB | | E.O.E. | | TOTAL | |
|---|----------|------------|--------|--------------|--------|------------|--------|--------|----------|--------|--------|-------|------------------------------|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT |
| <u>V</u> STR. STEEL & MISC. IRON - ACCESS LADDER W/ LANDINGS FAN SUPPORT FAN RM GRATE | 300 LF | | | | | | | | | | | | 38,000 5,000 14,000 |
| <u>VI</u> SPECIAL HOIST HEADGEAR ... | | | | | | | | | NOT INCL | | | | 800,000 |
| | | | | | | | | | | | | | 400,000 |
| <u>VII</u> CONSTRUCT VENT SYSTEM ? THOUGHT THATS WHAT IS ABOVE | | | | | | | | | (DMJM) | | | | 400,000 |
| <u>VIII</u> MECHANICAL <u>IX</u> ? <u>X</u> ELECTRICAL <u>XI</u> FINISHES | | | | | | | | | | | | | 672,000 504,000 11,000 |
| | | | | | | | | | | | | | \$ 868,000 |

-223-

NOTE: STRUCTURE ONLY

KELLOGG CORPORATION
DIRECT COST ESTIMATE

Sheet X-1 of _____ Estm PKL Ckd _____ ITEM _____

Plan Sheet No. _____ Bid Quantity _____

JOB SCRTO DATE 3-21-83

Spec. Ref. _____ Take-off Quantity _____

Item Desc. SINK SHAFT - 300' 24" dia

FORM E240E HOEGKEL'S 947860

DEPEON FOR

| DESCRIPTION | QUANTITY | DIR. LABOR | | EQUIP'T COST | | DIR. MAT'L | | PM/SUB | | E.O.E. | | TOTAL | |
|--|---------------|------------|------------------|--------------|------------------|------------|------------------------|--------|--------|--------|-------------------|-------|--|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT |
| EXCAVATE SINK SHAFT ON 8 HR SHFT BASIS | 300 LF. | | | | | | | | | | | | |
| | | | | | | | | | | | | | 5000 CY BULK TO 7000 C.Y. - INCL. OVER BREAK - UP TO SPEED 2 WIK. WITH HALF CREW. |
| FOREMAN | 2 EA. | | 34 ⁰⁰ | | | | | | | | 34 ⁰⁰ | | 68 ⁰⁰ |
| MINERS | 5 EA | | 30 ⁰⁰ | | | | | | | | 30 ⁰⁰ | | 150 ⁰⁰ |
| AIR TRACKS | 3 EA | | | | 15 ⁰⁰ | | 6 ⁰⁰ | | | | 21 ⁰⁰ | | 63 ⁰⁰ |
| COMPRESSOR | 2 EA | | 28 ⁰⁰ | | 15 ⁰⁰ | | 17 ⁰⁰ | | | | 60 ⁰⁰ | | 121 ⁰⁰ |
| C TENDERS | 5 EA | | 26 ⁰⁰ | | - | | - | | | | 26 ⁰⁰ | | 130 ⁰⁰ |
| POWDERMAN | 1 EA | | 32 ⁰⁰ | | - | | - | | | | 32 ⁰⁰ | | 32 ⁰⁰ |
| DOZER - D6- | 1 EA. | | 30 ⁰⁰ | | 16 ⁷⁵ | | 13 ²⁵ | | | | 60 ⁰⁰ | | 60 ⁰⁰ |
| CRANE - | 1 EA | | 60 ⁰⁰ | | 95 ⁰⁰ | | 48 ⁰⁰ (1/2) | | | | 179 ⁵⁰ | | 179 ⁵⁰ |
| DOZE TO STOCK. | 1 EA | | 30 ⁰⁰ | | 16 ⁷⁵ | | 13 ²⁵ (1/2) | | | | 53 ⁵⁰ | | 53 ⁵⁰ |
| LABOR TOP | 2 EA | | 26 ⁰⁰ | | - | | - | | | | 26 ⁰⁰ | | 52 ⁰⁰ |
| DRILL DOCTOR | 1 EA | | 30 ⁰⁰ | | - | | - | | | | 30 ⁰⁰ | | 30 ⁰⁰ |
| | | | | | | | | | | | | | \$ 939 ⁰⁰ |
| UP TO SPEED | 80 HR @ 470 | | | | | | | | | | | | = 37600 |
| SINK SHAFT @ 3' / hr. | 100 x 8 x 939 | | | | | | | | | | | | = 751,200 |
| | | | | | | | | | | | | | \$ 788,800 |

-224-

KELLOGG CORPORATION
DIRECT COST ESTIMATE

Sheet X 7 of Estm RR Ckd ITEM.....

Plan Sheet No..... Bid Quantity.....

JOB SCRTD DATE 3-21-83 Spec. Ref..... Take-off Quantity.....

Item Desc. SINK SHAFT

FORM E240E HOECKEL'S 347880

| DESCRIPTION | QUANTITY | DIR. LABOR | | EQUIP'T COST | | DIR. MAT'L | | PM/SUB | | E.O.E. | | TOTAL | | |
|---|----------|------------|--------|--------------|--------|------------|--------|--------|--------|--------|--------|-------|--------|--|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | |
| SINK SHAFT (ONE ONLY) | | | | | | | | | | | | | | |
| POWDER PRIMERS - STEEL BITS | | | | | | | | | 788 | 800 | | | | |
| DEVELOP - POWDER PRIMER DELICATE LA AREA. ESCORTED TRANSPORTATION. | | | | | | | | | 45 | 000 | | | | |
| TEMP. ROCK BOCTING DURING SINKING | | | | | | | | | 20 | 000 | | | | |
| Misc. | | | | | | | | | 40 | 000 | | | | |
| | | | | | | | | | 25 | 000 | | | | |
| | | | | | | | | | \$ | | | | | |
| | | | | | | | | | CALL | | 920 | | 000 | |

DMJM/PBQD

Revised 12/30/82

METRO RAIL PROJECT

JOB No. WBS-14-A1E

SHEET No.

TUNNEL VENT SYSTEM

DESIGNED BY

DATE 30 DEC 1982

Note: Cost includes 15.5% Mark up - U.S. Cont.

APPROVED

Cost = \$000,000

| REACH No. | MECHANICAL (ONLY) | | | | Line Vent Mech | Line Vent Struct, Arch & Elect. |
|---|-------------------|----------------------|---------------------|---------------------|----------------|---------------------------------|
| | O-U Station | Single Level Station | O.U. Station X-over | S.L. Station X-over | | |
| 1 | | (1) 1.74 | | | (1) 0.57 | (1) 2.7 |
| 2 | (2) 6.94 | | (1) 0.88 | | | |
| 3 | | (1) 1.74 | | | | |
| 4 | | (1) 1.74 | | | | |
| 5 | | (2) 3.48 | | (2) 0.36 | | |
| 6 | | (1) 1.74 | | (1) 0.18 | | |
| 7 | | (1) 1.74 | | | | |
| 8 | (1) 3.47 | | (1) 0.38 | (1) 0.18 | | |
| 9 | | (1) 1.74 | | | | |
| 10 | | (2) 3.48 | | (1) 0.18 | (1) 0.57 | (1) 2.7 |
| 11 | | (1) 1.74 | | (1) 0.18 | | |
| 12 | | | | | (2T) 1.00 | (2T) 10.4 |
| 13 | | (1) 1.74 | | | | |
| 14 | | (1) 1.74 | | (1) 0.18 | (1) 0.57 | (1) 2.7 |
| | 10.4 | 22.7 | 0.8 | 1.3 | 2.7 | 18.4 |
| <p>Note: Mech Cost - see Memo from from K. McGrath.</p> | | | | | | |
| <u>TOTAL VENT SYSTEM</u> | | | | | | <u>56.3</u> |

KC 1223 SQRTO/METRO RAIL UTILITIES

3/21/83 JEK

UTIL. SUPPORT (NOT IN ESTIMATE)

| STATION DESIGNATION | STATION LENGTH | OTHER CUT/CUT & COVER LENGTH | \$ IN ESTIMATE FOR UTILITY SUPPORT | UNIT COST FOR UTILITY SUPPORT (1) | \$ OMITTED FROM EST. FOR UTIL. SUPPORT (2) | \$ IN ESTIMATE FOR UTILITY RELOCATION | UNIT COST FOR UTILITY RESTORE (3) | \$ OMITTED FROM EST. FOR UTIL. REST. (4) | ADD PRG. TELEPHONE @ \$420/LF | ADD DWP POWER @ \$470/LF | 5 | |
|--------------------------|----------------|------------------------------|------------------------------------|-----------------------------------|--|---------------------------------------|-----------------------------------|--|-------------------------------|--------------------------|--------------------|---------------|
| | | | | | | | | | | | ADD PRG. TELEPHONE | ADD DWP POWER |
| UNION STATION | 640 | 2077 | 517600 | 809 | 1540000 | 0 | 0 | | 161470000 | 6536000 | | |
| 15 TH & HILL | 631 | 460 | 773550 | 1226 | 372000 | 396500 | 628 | 289000 | 193000 | 216000 | | |
| 5 TH & HILL | 631 | | 1003650 | 1591 | | 599960 | 350 | | | | | |
| 7 TH & FLOWER | 740 | | 654250 | 885 | | 1283160 | 1734 | | | | | |
| ALVARADO/WILSHIRE | 490 | 320 | 73800 | 151 | 139000 | 40040 | 86 | 55000 | 336000 | 432000 | | |
| VERMONT/WILSHIRE | 367 | | 379600 | 670 | | 261860 | 462 | | | | | |
| NORMANDIE/WILSHIRE | 672 | | 567500 | 845 | | 1932660 | 2281 | | | | | |
| WESTERN/WILSHIRE | 660 | | 558300 | 846 | | 1514720 | 2295 | | | | | |
| LA BREA/WILSHIRE | 660 | 1010 | 562850 | 853 | 562000 | 494800 | 750 | 732000 | 424000 | 475000 | | |
| FAIRFAX/WILSHIRE | 785 | | 1186300 | 1267 | | 407720 | 434 | | | | | |
| BEVERLY/FAIRFAX | 485 | 920 | 239500 | 390 | 322000 | 13400 | 20 | 18000 | 366000 | 432000 | | |
| SANTA MONICA/FAIRFAX | 680 | | 201800 | 299 | | 485400 | 713 | | | | | |
| LA BREA/SUNSET | 690 | 460 | 364900 | 519 | 377000 | 1162100 | 1684 | 775000 | 193000 | 216000 | | |
| HOLLYWOOD/CAHUENGA | 635 | 1250 | 286400 | 451 | 564000 | 1067400 | 200 | 250000 | 525000 | 585000 | | |
| UNIVERSAL CITY | 630 | | 103000 | 163 | | NAT ESTIMATED | | | | | | |
| NORTH HOLLYWOOD | 672 | 1360 | 567000 | 845 | 1149600 | NAT ESTIMATED (435 1600) | | 2,176,000 | 571,000 | 639,000 | | |
| | 10618 | 6380 | | | 5,627,000 | | | 4,354,000 | 3,156,000 | 3,533,000 | | |
| | | | | | | | | 11,043,000 | | | | |

- 1 COL 3 + COL 1
- 2 COL 2 + COL 4
- 3 COL 6 + COL 1
- 4 COL 7 + COL 2
- 5 5,000,000 ÷ 10618 LF
- 6 1/2 UNIT COST USED

7 AMOUNT SHOWN EXCLUDES SURFACE RESTORATION COSTS WHICH WERE DUPLICATED IN ESTIMATE

TOTAL TO BE ADDED 16,670,000

-227-

DMJM/PBQD-UNDERPINNING ESTIMATE RECAP

| REACH | UNDEEPINNING DESCRIPTION | TAB: "REACH G1-G17" | TAB: "UNDERPINNING STATIONS X-OVER" | TAB: "STATION SHELL" | ESTIMATE SUMMARY MATRIX | LF STATION CUT | LF OTHER CUT | ADDITIONAL UNDEEPINNING \$ | | | | | | |
|-------|--------------------------------|---------------------|-------------------------------------|----------------------|-------------------------|----------------|--------------|----------------------------|------------------------|--|--|--|--|--|
| 1 | FREEMWAY / L.A. RIVER | 2000000 | | | 2000000 | | | | | | | | | |
| 2 | UNION STATION | 0 | | | | | | | | | | | | |
| 3 | RAILROAD TRACKS | 0 | | | | | | 960000 | (3 TRACKS @ \$320,000) | | | | | |
| 4 | BRIDGE | 250000 | | | 300000 | | | | | | | | | |
| 5 | 1 ST HILL STATION | 1000000 | 1000000 | | 1000000 | 631 | 460 | 730000 | | | | | | |
| 6 | 5 TH HILL STATION | 7500000 | 7500000 | | 8500000 | | | | | | | | | |
| 7 | 7 TH FLOWER STATION | 3230000 | 3230000 | | 3200000 | | | | | | | | | |
| 8 | ALVARADO/WILSHIRE STATION | 120000 | 120000 | | 100000 | 490 | 920 | 220000 | | | | | | |
| 9 | X-OVER @ VERM/WILS STA. | 80000 | | 80000 | 100000 | | | | | | | | | |
| 10 | VERMONT/WILSHIRE STATION | 0 | | | | | | | | | | | | |
| 11 | NORMANDIE/WILSHIRE STA. | 2700000 | 2700000 | | 2700000 | | | | | | | | | |
| 12 | WESTERN/WILSHIRE STA. | 1000000 | 1000000 | | 1000000 | | | | | | | | | |
| 13 | LA BREA/WILSHIRE STA | 800000 | 800000 | | 800000 | 660 | 1010 | 700000 | | | | | | |
| 14 | X-OVER @ FAIRFAX/WILS. STA. | 1200000 | | 1000000 | 1000000 | | | | | | | | | |
| 15 | FAIRFAX/WILSHIRE STATION | 500000 | 500000 | | 500000 | | | | | | | | | |
| 16 | BEVERLY/FAIRFAX STATION | 0 | | 700000 | 700000 | | | | | | | | | |
| 17 | X-OVER | 670000 | | 150000 | 700000 | | | | | | | | | |
| 18 | SANTA MONICA/FAIRFAX STA. | 510000 | 510000 | | 1000000 | | | | | | | | | |
| 19 | LA BREA/SUNSET STA. | 510000 | 510000 | | | | | | | | | | | |
| 20 | HOLLYWOOD/CANUENSA STA | 315000 | 315000 | | 300000 | | | | | | | | | |
| 21 | POCKET TRACK | 160000 | | 160000 | 200000 | | | | | | | | | |
| 22 | BLUFFSIDE BRIDGE | 3000000 | | | 5100000 | | | | | | | | | |
| 23 | UNIVERSAL CITY STATION | 0 | | | | | | | | | | | | |
| 24 | RAILROAD TRACKS | 0 | | | | | | 250000 | (2 TRACKS @ \$125,000) | | | | | |
| 25 | X-OVER | 600000 | | 550000 | 600000 | | | | | | | | | |
| 26 | NORTH HOLLYWOOD STA | 0 | | | | | | | | | | | | |
| 27 | | | | | | | | | | | | | | |
| 28 | | 44365000 | | | 4007000 | 44500000 | | | 2930450 | | | | | |
| 29 | | | | | | | | | | | | | | |
| 30 | | | | | | | | | | | | | | |
| 31 | | | | | | | | | | | | | | |
| 32 | | | | | | | | | | | | | | |
| 33 | | | | | | | | | | | | | | |
| 34 | | | | | | | | | | | | | | |
| 35 | | | | | | | | | | | | | | |
| 36 | | | | | | | | | | | | | | |
| 37 | | | | | | | | | | | | | | |
| 38 | | | | | | | | | | | | | | |
| 39 | | | | | | | | | | | | | | |
| 40 | | | | | | | | | | | | | | |

-228-

SUMMARY

**KELLOGG CORPORATION
DIRECT COST ESTIMATE**

JOB SCRPTD DATE 3 26 83

Sheet 0 of Estm DPL Ckd. ITEM
 Plan Sheet No. Bid Quantity 1 TRACK SPAN
 Spec. Ref. Take-off Quantity
 Item Desc. UNDERPIN RR

FORM E240E HOECKEL'S 347860

| DESCRIPTION | QUANTITY | DIR. LABOR | | EQUIPM'T COST | | DIR. MAT'L | | PM/SUB | | E.O.E. | | TOTAL | |
|-----------------------------------|----------|------------|--------|---------------|--------|------------|--------|--------|--------|--------|--------|-------|------------------------|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT |
| <i>SUMMARY UNDERPIN RAIL ROAD</i> | | | | | | | | | | | | | |
| <i>SHEET # 1</i> | | | | | | | | | | | | | <i>- 0 -</i> |
| <i>SHEET # 2</i> | | | | | | | | | | | | | <i>8740-</i> |
| <i>SHEET # 3</i> | | | | | | | | | | | | | <i>11500</i> |
| <i>SHEET # 4</i> | | | | | | | | | | | | | <i>10930-</i> |
| <i>SHEET # 5</i> | | | | | | | | | | | | | <i>11270-</i> |
| <i>SHEET # 6</i> | | | | | | | | | | | | | <i>21323-</i> |
| <i>SHEET # 7</i> | | | | | | | | | | | | | <i>5000</i> |
| <i>SHEET # 8</i> | | | | | | | | | | | | | <i>43000</i> |
| <i>SHEET # 9</i> | | | | | | | | | | | | | <i>5000</i> |
| | | | | | | | | | | | | | <i>CALL \$ 117,000</i> |

*CALL UNION STATION
\$ 120,000 EACH*

*CALL NO HOLLYWOOD
\$ 125,000 EACH*

-229-

KELLOGG CORPORATION
DIRECT COST ESTIMATE

JOB SCRTD

DATE 3-26-83

Sheet 1 of Estm D.O.A. Ckd..... ITEM.....

Plan Sheet No..... Bid Quantity 1 TRACK SPAC

Spec. Ref..... Take-off Quantity.....

Item Desc. UNDERPIN R.R.

FORM E249E HOECKEL'S 347860

| DESCRIPTION | QUANTITY | DIR. LABOR | | EQUIPMT COST | | DIR. MAT'L | | PM/SUB | | E.O.E. | | TOTAL | |
|---|----------|------------|--------|--------------|--------|------------|--------|--------|--------|--------|--------|-------|--------|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT |
| <p><u>UNDERPIN RAILROADS:</u> THERE ARE TWO LOCATIONS THAT MIGHT REQUIRE UNDERPINNING FOR RAILROADS. THE SANTA FE YARDS IN THE UNION STATION AREA AND THE DOUBLE TRACK AREA OVER THE NORTH HOLLYWOOD STATION. REGARDLESS PRIOR PERMITS IT IS A GOOD POSSIBILITY THAT "X" NUMBER OF TRACKS MAY BE REQUIRED TO BE KEPT OPEN FOR RAIL TRAFFIC. THIS IS AN ESTIMATE FOR UNDERPIN COSTS PER TRACK (2 RAIL)</p> | | | | | | | | | | | | | |

KELLOGG CORPORATION
DIRECT COST ESTIMATE

JOB SCRTD DATE 3-26-83

Sheet 7 of Estm. DDK Ckd. ITEM
Plan Sheet No. Bid Quantity 1 TRACK SPAN
Spec. Ref. Take-off Quantity
Item Desc. UNDERPIN RR

FORM E249E HOECKEL'S 347860

DEP OR FOR

| DESCRIPTION | QUANTITY | DIR. LABOR | | EQUIPM'T COST | | DIR. MAT'L | | PM/SUB | | E.O.E. | | TOTAL | |
|--|----------|------------|------------------|---------------|----------------------------|------------|-----------------------|--------|--------|--------|-------------------------|-------------|-------------------|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT |
| <u>UNDERPIN RAILROAD</u> | | | | | | | | | | | | | |
| <u>ASSUME AN OUTAGE OF ONE WEEK</u> | | | | | | | | | | | | | |
| <u>TO ERECT AND UNDERPINNING STRUCTURE</u> | | | | | | | | | | | | | |
| <u>FOR EACH STATION / TRACK SPAN.</u> | | | | | | | | | | | | | |
| <u>REMOVE TRACK :</u> | | | | | | | | | | | | | |
| FOREMAN | 10 HRS. | | 35 ⁰⁰ | | | | | | | | 35 ⁰⁰ | | 350 |
| CRANE | 10 HRS. | | 91 ⁰⁰ | | 72 ⁰⁰ | | 38 ⁰⁰ | | | | 201 ⁰⁰ | | 2010 |
| LOW BOY TR. | 10 HR. | | 30 ⁰⁰ | | Lo ³⁰⁰ Boy RENT | | | | | | 30 ⁰⁰ + Rent | | 600 |
| LOADER. | 10 HR. | | 30 ⁰⁰ | | 16 ⁰⁰ | | 13 ⁰⁰ | | | | 59 ⁰⁰ | | 590 |
| 8 LABORERS | 100 HRS. | | 26 ⁰⁰ | | | | | | | | 26 ⁰⁰ | | 2600 |
| SMALL CRANE | 10 HR. | | 32 ⁰⁰ | | 19 ⁵⁰ | | 14 ¹⁰ | | | | 65 ⁶⁰ | | 660 |
| WELDER TORCH | 10 HR. | | 30 ⁰⁰ | | 3 ²⁰ | | 6 ⁰⁰ | | | | 39 ²⁰ | | 390 |
| SPECIAL TOOLS | | | | | | | | | | | | | 500 ⁰⁰ |
| R. R. INSPECTOR | | | | | | | | | | | | | 500 ⁰⁰ |
| | 36 | | | | | | 15 ⁰⁰ AVE. | | | | | | 540 |
| | | | | | | | | | | | | TOTAL SHEET | 8740 |

-231-

KELLOGG CORPORATION
DIRECT COST ESTIMATE

JOB SCRTP DATE 3-26-80

Sheet 3 of Estm DDL Ckd ITEM
Plan Sheet No. Bid Quantity 1-TRACK SPAN
Spec. Ref. Take-off Quantity
Item Desc. UNDER PIN R.R.

FORM E240E HOECKEL'S 347880

| DESCRIPTION | QUANTITY | DIR. LABOR | | EQUIPM'T COST | | DIR. MAT'L | | PM/SUB | | E.O.E. | | TOTAL | |
|---|---------------|------------|--------|---------------|--------|------------|--------|-------------------------|--------|--------|--------|--------------------|-------------------------------|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT |
| <u>UNDER PIN RAILROAD</u> | | | | | | | | | | | | | |
| <u>PRE DRILL HOLES: ACCOMPLISHED BY STATION PILE DRILLING - (SEE WORK UP ON STATIONS)</u> | | | | | | | | | | | | | |
| <u>THIS RATE IS 4 PILES / SHIFT HOWEVER</u> | | | | | | | | | | | | | |
| <u>AS THIS EXACT SCHEDULING DOUBTFUL</u> | | | | | | | | | | | | | |
| <u>ALL 1/2 DAYS -</u> | | | | | | | | | | | | | |
| <u>DRILL PILING:</u> | | | | | | | | | | | | | |
| <u>FROM SHEET 4</u> | <u>12 HRS</u> | | | | | | | <u>390⁰⁰</u> | | | | | <u>\$ 4700⁰⁰</u> |
| <u>SOLDIER PILE/LAM.</u> | | | | | | | | | | | | | |
| <u>SEAT STICK PILE:</u> | <u>12 HRS</u> | | | | | | | <u>564⁹⁰</u> | | | | | <u>\$ 6800⁰⁰</u> |
| <u>FROM SHEET 5</u> | | | | | | | | | | | | | |
| | | | | | | | | | | | | <u>TOTAL SHEET</u> | <u>\$ 11,500⁰⁰</u> |

-232-

KELLOGG CORPORATION
DIRECT COST ESTIMATE

JOB SCRTP DATE 3-26-83

Sheet 4 of Estm DDL Ckd K ITEM.....
Plan Sheet No..... Bid Quantity 1 TRACK SPAN
Spec. Ref..... Take-off Quantity.....
Item Desc UNDERPIN RAIL ROAD
DEP AN FOG

FORM E240E HOECKEL'S 347860

| DESCRIPTION | QUANTITY | DIR. LABOR | | EQUIP'MT COST | | DIR. MAT'L | | PM/SUB | | E.O.E. | | TOTAL | |
|--|--------------------------|------------|------------------|---------------|------------------|------------|------------------|--------|-------------------|--------|--------|---------------------|-------------------|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT |
| <p><u>UNDER PIN RAILROAD</u></p> <p>CARRYING BEAM TO BE BUILT UP DEEP I BEAMS - THESE TO BE FULLY BUILT UP, WELDED, ASSEMBLED AND STORED ADJECENT TO SITE PRIOR TO OUTRACK:</p> <p>MAKE UP BEAMS :</p> | | | | | | | | | | | | | |
| FOREMAN | 24 HRS | | 33 ⁰⁰ | | | | | | 33 ⁰⁰ | | | | 792 ⁰⁰ |
| CRANE (OFFLOAD) | 8 HRS | | 91 ⁰⁰ | | 72 ⁰⁰ | | 38 ⁰⁰ | | 201 ⁰⁰ | | | | 1608 ⁻ |
| WELDERS (4) | 96 HR | | 30 | | 32 ⁰⁰ | | 6 ⁰⁰ | | 39 ²⁰ | | | | 3763 ⁻ |
| LABORERS | 48 HR | | 26 ⁻ | | | | | | 26 ⁻ | | | | 1248 ⁻ |
| FLATRACK | 24 HR | | 28 ⁻ | | 7 ⁰⁰ | | 44 ⁰⁰ | | 39 ⁴⁰ | | | | 946 ⁻ |
| STINGER ON-OFF | 24 HR. | | 32 ⁰⁰ | | 19 ⁵⁰ | | 14 ⁰⁰ | | 65 ⁶⁰ | | | | 1575 ⁻ |
| Misc SUPPLY | (LAYDOWN AREA - WELD -) | | | | | | | | | | | 1000 | |
| TOTAL SHEET - | | | | | | | | | | | | 10932 ⁰⁰ | |

KELLOGG CORPORATION
DIRECT COST ESTIMATE

Sheet 5 of Estm ML Ckd V ITEM.....
Plan Sheet No. Bid Quantity 1 TRACK SPAN
Spec. Ref. Take-off Quantity.....
Item Desc. UNDERPIN RAIL ROAD

JOB SCRTD DATE 3-26-83

FORM E240E HOECKEL'S 947860

DEP-01 FOG

| DESCRIPTION | QUANTITY | DIR. LABOR | | EQUIPMT COST | | DIR. MAT'L | | PM/SUB | | E.O.E. | | TOTAL | |
|-------------------------------|-----------------|------------|------------------------|------------------------|------------------------|------------|--------|-------------------------------|------------------------|--------|--------|-------|---|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT |
| <u>UNDERPIN RAIL ROAD</u> | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| | | | | | | | | | | | | | |
| <u>ERECT STRUCTURE:</u> | | | | | | | | | | | | | |
| <u>FOREMAN</u> | <u>16 HRS</u> | | <u>35-</u> | | | | | | <u>35⁰⁰</u> | | | | <u>560-</u> |
| <u>CRANE</u> | <u>16 HRS</u> | | <u>91⁰⁰</u> | <u>72⁰⁰</u> | <u>38⁰⁰</u> | | | <u>201⁰⁰</u> | | | | | <u>3216-</u> |
| <u>STINGER CRANE</u> | <u>16 HRS</u> | | <u>32⁰⁰</u> | <u>19⁵⁰</u> | <u>14⁰⁰</u> | | | <u>65⁶⁰</u> | | | | | <u>1050-</u> |
| <u>LO BOY</u> | <u>16 HRS</u> | | <u>30-</u> | | <u>(RENT 200)</u> | | | <u>30⁰⁰ + RENT</u> | | | | | <u>1080-</u> |
| <u>FLATRACK</u> | <u>16 HRS</u> | | <u>28-</u> | <u>7⁰⁰</u> | <u>4⁴⁰</u> | | | <u>39⁴⁰</u> | | | | | <u>630-</u> |
| <u>IRON WORKERS</u> | <u>3 48 HRS</u> | | <u>30-</u> | | | | | <u>30⁰⁰</u> | | | | | <u>1440-</u> |
| <u>WELDER</u> | <u>2 32 HR</u> | | <u>30-</u> | <u>3⁰⁰</u> | <u>6⁰⁰</u> | | | <u>30⁰⁰</u> | | | | | <u>960-</u> |
| <u>LABORERS</u> | <u>2 32 HRS</u> | | <u>26-</u> | | | | | <u>26⁰⁰</u> | | | | | <u>832-</u> |
| <u>MISC - SMALL TOOLS ETC</u> | | | | | | | | | | | | | <u>500-</u> |
| <u>RR INSP.</u> | | | | | | | | | | | | | <u>1000-</u> |
| | | | | | | | | | | | | | <u>TOTAL SHEET - \$ 11,268⁰⁰</u> |

-234-

KELLOGG CORPORATION
DIRECT COST ESTIMATE

JOB SCRIPD DATE 3-26-83

Sheet 6 of Estm. DDL Ckd. V ITEM
Plan Sheet No. Bid Quantity 1-TRACK SPAN
Spec. Ref. Take-off Quantity
Item Desc. UNDERPIN RAIL ROAD

DEP ON POG

FORM E240E HOECKEL'S 347860

| DESCRIPTION | QUANTITY | DIR. LABOR | | EQUIP'M'T COST | | DIR. MAT'L | | PM/SUB | | E.O.E. | | TOTAL | |
|---------------------------|--------------------|------------|------------------------|---|------------------------|------------|------------------------|--------|-------------------------|--------|---------------|-------|------------------------------|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT |
| <u>UNDERPIN RAIL ROAD</u> | | | | | | | | | | | | | |
| | | | | <u>RELAY RAIL - LOAD OUT IN LOW BOY FROM STORAGE AND ASSEMBLE:</u> | | | | | | | | | |
| | | | | <u>OVERTIME WORK - AS ONE WEEK OUTAGE SLIP - PROBABLY CATCH THE WEEK END.</u> | | | | | | | | | |
| <u>RELAY RAIL :</u> | | | | | | | | | | | | | |
| <u>FOREMAN</u> | <u>16 HR</u> | | <u>53-</u> | | | | | | <u>53⁰⁰</u> | | | | <u>848-</u> |
| <u>CRANE</u> | <u>16 HR</u> | | <u>137-</u> | | <u>72⁰⁰</u> | | <u>38⁰⁰</u> | | <u>247⁰⁰</u> | | | | <u>3950-</u> |
| <u>LO BOY</u> | <u>16 HR</u> | | <u>48-</u> | | | | <u>300 RENT</u> | | <u>48⁰⁰</u> | | <u>+ RENT</u> | | <u>1368-</u> |
| <u>LOADER</u> | <u>16 HR</u> | | <u>45-</u> | | <u>16⁰⁰</u> | | <u>13⁰⁰</u> | | <u>74⁰⁰</u> | | | | <u>1184-</u> |
| <u>8 LABORERS</u> | <u>17.5 HR</u> | | <u>39-</u> | | | | | | <u>39⁰⁰</u> | | | | <u>4992-</u> |
| <u>SMALL CRANE</u> | <u>16 HR</u> | | <u>48-</u> | | <u>19⁵⁰</u> | | <u>14⁰⁰</u> | | <u>67⁵⁰</u> | | | | <u>1080-</u> |
| <u>IRON WORKER</u> | <u>32 HR</u> | | <u>45⁰⁰</u> | | | | | | <u>45⁰⁰</u> | | | | <u>1440-</u> |
| <u>FLAT RACIE</u> | <u>16 HR</u> | | <u>42-</u> | | <u>7⁰⁰</u> | | <u>44⁰⁰</u> | | <u>53⁴⁰</u> | | | | <u>854-</u> |
| <u>DUMP TRUCK</u> | <u>16 HR</u> | | <u>48-</u> | | <u>12⁵⁰</u> | | <u>17⁰⁰</u> | | <u>77⁵⁰</u> | | | | <u>1240-</u> |
| <u>WELDERS</u> | <u>16 HR</u> | | <u>45-</u> | | <u>32⁰⁰</u> | | <u>6⁰⁰</u> | | <u>54²⁰</u> | | | | <u>867-</u> |
| <u>SPECIAL TOOLS</u> | <u>(TIE RAMMER</u> | | | | | | <u>- OPER)</u> | | | | | | <u>2500</u> |
| <u>R/R INSPECTOR</u> | | | | | | | | | | | | | <u>1000-</u> |
| | | | | | | | | | | | | | <u>TOTAL SHEET \$ 21,323</u> |

KELLOGG CORPORATION
DIRECT COST ESTIMATE

JOB SCRTD DATE 3-26-83

Sheet 9 of 10 Estm DDK Ckd _____ ITEM _____
Plan Sheet No. _____ Bid Quantity _____
Spec. Ref. _____ Take-off Quantity _____
Item Desc. UNDERPIN RAILROAD

FORM E240E HOECKEL'S 347860

| DESCRIPTION | QUANTITY | DIR. LABOR | | EQUIP'T COST | | DIR. MAT'L | | PM/SUB | | E.O.E. | | TOTAL | |
|---|----------|------------|--------|--------------|--------|------------|--------|--------|--------|--------|--------|-------|--------|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT |
| <p>UNDERPIN RAIL ROAD: THE RAILROAD WILL REQUIRE THAT A TEST TRAIN (PROBABLY A YARD SWITCH ENGINE & SEVERAL CARS) MAKE A HALF DAY'S TEST RUNS OVER TRACK PLUS ADJUSTMENT.</p> | | | | | | | | | | | | | |
| START UP - TEST - ADJUSTMENT | | | | | | | | 5AY | | | | 5000 | |
| <p>NOTE THE NO HOLLYWOOD CROSSING WILL REQUIRE SPECIAL DECKING & TIES & FASTENER & SWITCH TIE IN. PROBABLY \$5000 MORE</p> | | | | | | | | | | | | | |

TRAFFIC MAINTENANCE

DMJM/PBQD SUMMARY

KC 1223 SCRTD/METRO RAIL

3/21/83

JEK

| STATION DESIGNATION | 6' CHAIN LINK FENCING | | | MISC. | TOTAL TRAFFIC MAINT \$ |
|--------------------------|-----------------------|-----------------|-------|-------|------------------------|
| | LF | \$/LF | \$ | \$ | |
| UNION STATION | 1500 | 6 | 9000 | 6000 | 15000 |
| 1 ST & HILL | 1550 | 5 ⁷⁵ | 8900 | 32750 | 41650 |
| 5 TH & HILL | 1700 | 5 ⁷⁵ | 9800 | 39200 | 49000 |
| 7 TH & FLOWER | 1860 | 5 ⁷⁵ | 10700 | 42900 | 53600 |
| ALVARADO / WILSHIRE | 1140 | 5 ⁷⁵ | 6600 | 4400 | 11000 |
| VERMONT / WILSHIRE | 2140 | 5 ⁷⁵ | 12300 | 2700 | 15000 |
| NORMANDIE / WILSHIRE | 1540 | 6 | 9250 | 6150 | 15400 |
| WESTERN / WILSHIRE | 1760 | 5 ⁷⁵ | 10150 | 6850 | 17000 |
| LA BREA / WILSHIRE | 1560 | 6 | 9350 | 6250 | 15600 |
| FAIRFAX / WILSHIRE | 2160 | 6 | 13000 | 8700 | 21700 |
| BEVERLY / FAIRFAX | 1610 | 6 | 9650 | 6450 | 16100 |
| SANTA MONICA / FAIRFAX | 1660 | 6 | 10000 | 6600 | 16600 |
| LA BREA / SUNSET | 2250 | 6 | 13500 | 5600 | 19100 |
| HOLLYWOOD / CAHUENGA | 2240 | 6 | 13450 | 5550 | 19000 |
| UNIVERSAL CITY | 3700 | 6 | 22200 | 7800 | 30000 |
| NORTH HOLLYWOOD | 1540 | 6 | 9250 | 6150 | 15400 |
| | | | | TOTAL | 371150 |

APPROXIMATION ESTIMATE
TRAFFIC MAINTENANCE
KL 1223 SERTD/METRO RAIL

3/21/83
JEK

DIVISION?
ON STREET CUT?
AN/IN BYWEGE

| STATION DESIGNATION | LENGTH | | | DIVISION? | ON STREET CUT? | AN/IN BYWEGE | DURATION (WEEKS) | SET-UP / TEAR DOWN CREW HOURS | MAINT. CREW HOURS / WEEK | TOTAL CREW HOURS | LABOR & EQUIPMENT COSTS | 6' CHAIN LINK FENCE | | SIGNS & BARRICADES ALLOW \$ | TEMP PAVE. & STRIPING ALLOW \$ | TOTAL MAT'L / SUBC. COST \$ |
|---|--------|-----------|-------|-----------|----------------|--------------|------------------|-------------------------------|--------------------------|------------------|-------------------------|---------------------|-------|-----------------------------|--------------------------------|-----------------------------|
| | STA. | OTHER CUT | TOTAL | | | | | | | | | LP | \$ | | | |
| UNION STATION | 640 | 2277 | 2917 | N | N | N | 116 | 50 | 8 | 1008 | 201600 | 6800 | 40800 | 40000 | 15000 | 95800 |
| 1ST & HILL | 631 | 460 | 1091 | Y | Y | N | 116 | 240 | 15 | 1380 | 396000 | 2600 | 15600 | 100000 | 30000 | 105600 |
| 5TH & HILL | 631 | - | 631 | Y | Y | N | 121 | 160 | 15 | 1875 | 393000 | 1700 | 10000 | 70000 | 20000 | 100800 |
| 7TH & FLOWER | 740 | - | 740 | Y | Y | N | 180 | 160 | 15 | 2110 | 422000 | 1800 | 11200 | 75000 | 25000 | 111200 |
| ALVARADO / WILSHIRE | 440 | 920 | 1410 | N | N | N | 130 | 120 | 8 | 1160 | 232000 | 3280 | 19700 | 30000 | 12000 | 61700 |
| VERMONT / WILSHIRE | 567 | - | 567 | N | N | N | 133 | 80 | 8 | 1146 | 239300 | 2100 | 12800 | 20000 | 10000 | 42800 |
| NORMANDIE / WILSHIRE | 672 | - | 672 | Y | Y | Y | 156 | 160 | 40 | 6400 | 1280000 | 1500 | 9200 | 75000 | 28000 | 109200 |
| WESTERN / WILSHIRE | 660 | - | 660 | Y | Y | Y | 150 | 120 | 40 | 6000 | 1200000 | 1700 | 10600 | 75000 | 25000 | 110600 |
| LA BREA / WILSHIRE | 660 | 1010 | 1670 | Y | Y | Y | 136 | 320 | 40 | 5760 | 1152000 | 3900 | 23400 | 100000 | 30000 | 163400 |
| FAIRFAX / WILSHIRE | 935 | - | 935 | Y | Y | Y | 147 | 240 | 40 | 6120 | 1204000 | 2100 | 13000 | 100000 | 30000 | 143000 |
| BEVERLY / FAIRFAX | 685 | 920 | 1605 | N | N | N | 108 | 80 | 8 | 944 | 188800 | 3700 | 22200 | 30000 | 12000 | 60800 |
| SANTA MONICA / FAIRFAX | 680 | - | 680 | N | Y | Y | 136 | 120 | 40 | 5480 | 1096000 | 1600 | 10000 | 75000 | 25000 | 110000 |
| LA BREA / SUNSET | 690 | 460 | 1150 | Y | Y | Y | 131 | 240 | 40 | 4280 | 1256000 | 5300 | 19900 | 80000 | 30000 | 123900 |
| HOLLYWOOD / CANTUENGA | 685 | 1260 | 1945 | N | N | N | 126 | 240 | 16 | 2256 | 451200 | 5100 | 30400 | 80000 | 25000 | 158600 |
| UNIVERSAL CITY | 630 | - | 630 | N | N | N | 112 | 80 | 8 | 976 | 195200 | 3700 | 22200 | 20000 | 10000 | 52200 |
| NORTH HOLLYWOOD | 672 | 1360 | 2032 | N | Y | N | 121 | 280 | 40 | 5120 | 1024000 | 4700 | 28200 | 180000 | 30000 | 158200 |
| * CREW: 1 PMN @ 35 ⁰⁰ = 35 ⁰⁰ | | | | | | | | | | | | | | | | |
| 4 LAB @ 26 ⁰⁰ = 104 ⁰⁰ | | | | | | | | | | | | | | | | |
| 1 BM/PEL @ 50 ⁰⁰ = 50 ⁰⁰ | | | | | | | | | | | | | | | | |
| EQUIPMENT ALLOW 31 ⁰⁰ | | | | | | | | | | | | | | | | |
| TOTAL \$ 202 ⁰⁰ / CREW HOUR | | | | | | | | | | | | | | | | |
| | | | | | | | | | | | | 1080,000 | | TOTAL MAT'L & SUB CONTRACT | 1,703,500 | |
| | | | | | | | | | | | | | | TOTAL LABOR & EQUIP | 12,821,000 | |
| | | | | | | | | | | | | | | GRAND TOTAL | 12,504,500 | |

-240-

KC1223 SCRTD/METRO RAIL
DEWATERING

3/21/83
JEK

| STATION DESIGNATION | SUMMARY OF DGM/POOD EST. | | | KC ESTIMATE | | MONTHLY \$ | TOTAL \$ | | | | | | | | | | | | | |
|----------------------|--------------------------|-------|---------------|-------------|-------|------------|----------------|--|--|--|--|--|--|--|--|--|--|--|--|--|
| | MONTHS | \$/MO | \$ | LS | \$/MO | | | | | | | | | | | | | | | |
| UNION STATION | 16 | 2650 | 42400 | 20000 | 12000 | 192000 | 212000 | | | | | | | | | | | | | |
| 1ST & HILL | 16 | | 42400 | | | 192000 | 212000 | | | | | | | | | | | | | |
| 5TH & HILL | 21 | | 58300 | | | 252000 | 272000 | | | | | | | | | | | | | |
| 7TH & FLOWER | 18 | | 47700 | | | 216000 | 236000 | | | | | | | | | | | | | |
| ALVARADO/WILSHIRE | 13 | | 34450 | | | 152000 | 176000 | | | | | | | | | | | | | |
| VERMONT/WILSHIRE | 16 | | 42400 | | | 192000 | 212000 | | | | | | | | | | | | | |
| NORMANDIE/WILSHIRE | 22 | | 58300 | | | 264000 | 284000 | | | | | | | | | | | | | |
| WESTERN/WILSHIRE | 18 | | 47700 | | | 216000 | 236000 | | | | | | | | | | | | | |
| LA BREA/WILSHIRE | 22 | | 58300 | | | 264000 | 284000 | | | | | | | | | | | | | |
| FAIRFAX/WILSHIRE | 27 | | 71950 | | | 324000 | 344000 | | | | | | | | | | | | | |
| BEVERLY/FAIRFAX | 23 | | 60900 | | | 276000 | 296000 | | | | | | | | | | | | | |
| SANTA MONICA/FAIRFAX | 19 | | 50350 | | | 228000 | 248000 | | | | | | | | | | | | | |
| LA BREA/SUNSET | 21 | | 58300 | | | 252000 | 272000 | | | | | | | | | | | | | |
| HOLLYWOOD/CANUENGA | 18 | | 47700 | | | 216000 | 236000 | | | | | | | | | | | | | |
| UNIVERSAL CITY | 19 | | 50350 | | | 228000 | 248000 | | | | | | | | | | | | | |
| NORTH HOLLYWOOD | 22 | | 58300 | | | 264000 | 284000 | | | | | | | | | | | | | |
| | | | <u>824150</u> | | | | <u>4052000</u> | | | | | | | | | | | | | |

-241-

KELLOGG CORPORATION
DIRECT COST ESTIMATE

JOB SCR TD DATE 3-16-83

WESTERN STATION

Sheet 1 of 7 Estm DOL Ckd 1 ITEM.....
 Plan Sheet No..... Bid Quantity.....
 Spec. Ref..... Take-off Quantity 16 MONTHS.....
 Item Desc DEWATERING.....

FORM E240R HOECKEL'S 336481

| DESCRIPTION | QUANTITY | DIR. LABOR | | REP. LABOR | | MAT'L | | SUB-BID | | E.O.E. | | TOTAL | |
|---|----------|------------|--------|------------|--------|-------|--------|---------|--------|--------|--------|-------|--------|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT |
| <p>THE CONCEPTONAL PREGIMINARY ESTIMATE PROVIDED A DEWATERING ESTIMIAE OF 16 MONTHS AT \$2650 PER MONTH.</p> <p>REGARDLESS THE NATURE OR EXTENT THAT THE GEOTECHNICAL DATA REPORTS THE ABSENCE OF GROUND WATER A PRUDENT BIDDER SHOULD ALLOW AT LEAST FOR CONTROL OF SURFACE RUN OFF, FROM RAIN OR CONSTRUCTION WATER, AS WELL AS SOME SUBSURFACE WATER IN THE FORM OF PERCHED OR TRAPPED WATER.</p> <p>GEOTECHNICAL REPORTS INDICATE THAT GROUND WATER IS BELOW GRADE IN THIS AREA THEREFORE AN EXTENSIVE WELL POINT OR DEEP WELL SYSTEM WOULD PROBABLY NOT BE REQUIRED, HOWEVER THIS TYPE OF ESTIMATE SHOULD ALLOW SOME PROVISION FOR A LOCAL, SUMP AND TRENCHING TYPE OF DEWATERING OPERATION AS PERCHED WATER IS REPORTED TO EXIST.</p> <p>THE 16 MONTH PERIOD FOR DEWATERING SHOULD COVER THE SPAN OF REQUIRED OPERATIONS.</p> | | | | | | | | | | | | | |

-242-

KELLOGG CORPORATION
DIRECT COST ESTIMATE

Sheet 2 of 2 Estm DD/Ckd ITEM ✓
 Plan Sheet No. _____ Bid Quantity _____
 Spec. Ref. _____ Take-off Quantity 16 MONTHS
 Item Desc. DEWATERING

JOB SCRTD DATE 3-16-83

WESTERN STATION

FORM E240R HOECKEL'S 336481

DEP. & OH FOR

| DESCRIPTION | QUANTITY | DIR. LABOR | | REP. LABOR | | MAT'L | | SUB-BID | | E.O.E. | | TOTAL | |
|---|-----------------------------------|------------|---------|------------------|--------|-------|--------|---------|--------|--------|--------|-------------------|----------|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT |
| PROVIDE A SPREAD OF PORTABLE, MOBILE PUMPS OPERATING ONLY ON PART TIME BASIS, SINGLE SHIFT WITH SOME OVERTIME ALLOW. | | | | | | | | | | | | | |
| FOREMAN | (COVERED BY GEN. CONSTR. FOREMAN) | | | | | | | | | | | | |
| PUMPMAN | 16 Mo | | \$ 7000 | | | | | | | | | | 112000 ✓ |
| PUMPMAN OT. | | | | | | | | | | | | | |
| LABORERS | 10 Mo | | \$ 6000 | | | | | | | | | | 60,000 ✓ |
| (ON & OFF) | | | | | | | | | | | | | |
| PUMPS 4" (2) | 32 Mo | | | OPERATE 25% TIME | 400 - | | 80° | 12800 | | 2560 | | | 15360 ✓ |
| PUMPS 3" (1) | 16 Mo | | | 25% TIME | 350 - | | 55° | 5600 | | 880 | | | 6480 ✓ |
| STILLING BASINS | | | | | | | | | | | | | |
| SUMPS - CMP - | | | | | | | | | | | | | |
| MANIFOLDS | | | | | | | | | | | | | |
| HOSES | | | | | | | | | | | | | 20000 ✓ |
| | | | | | | | | | | | | CALL \$ 213,840 ✓ | |

-243-

KELLOGG CORPORATION
DIRECT COST ESTIMATE

Item Analysis

Sheet 1 of 1 Estm Aug Ckd..... ITEM.....

Plan Sheet No..... Bid Quantity.....

Spec. Ref..... Take-off Quantity.....

Item Desc. TRACKWORK SUMMARY

JOB. SURT/ME DATE 3/31/83

DCE. 15 5.00.2500 HOECKEL'S 334896

TRACKWORK SUMMARY - DIRECT COST

AREA

DMJM/
PBQD

KC

Δ

① MAIN YARD

② RAILROAD - BALLASTED

\$ 5,344,000

\$ 3,026,600

< \$ 2,317,400 >

③ TRANSIT - BALLASTED

\$ 8,162,500

7,190,000

< \$ 972,500 >

④ TRANSIT - DIRECT FIX.

\$ 487,920

267,500

< \$ 220,420 >

SUBTOTAL

\$ 13,994,420

\$ 10,484,100

< \$ 3,510,320 >

② REACH 1 TO 14

\$ 39,067,698

\$ 28,202,500

< \$ 10,865,198 >

③ NORTH HOLLYWOOD
TAIL TRACK

\$ 606,000

\$ 630,000

\$ 24,000

TOTAL TRACKWORK.

\$ 53,668,118

\$ 39,316,600

< \$ 14,351,518 >

KELLOGG CORPORATION
DIRECT COST ESTIMATE

Item Analysis

Sheet 1 of 2 Estm Aug Ckd.....ITEM.....
Plan Sheet No.....Bid Quantity.....
Spec. Ref.....Take-off Quantity.....
Item Desc. TRACKWORK - YARD

JOB SCRTD/ME DATE 3/31/83

DCE. 15 5-80 2500 HOECKEL'S 334596

TRACKWORK PRICING - YARD

USE SCRTD TAKEOFF w/ KC UNIT PRICES (DIRECT COST ONLY)

① BALLASTED @ GRADE - RAILROAD

| | | | | |
|---------------------|-----------|---------------------------|---|--------------|
| RELOCATE TRACK | 1620 LF | @ \$ 30 ⁰⁰ /LF | = | 48 600 |
| NEW TRACK | 32,900 LF | @ \$ 70 ⁰⁰ /LF | = | 2,303,000 |
| NEW No. 8 SWITCHES | 5 EA | @ \$ 30,000/EA | = | 150,000 |
| NEW No. 10 SWITCHES | 15 EA | @ \$ 35,000/EA | = | 525,000 |
| | | SUBTOTAL | = | \$ 3,026,600 |

OMJM/PBQD DIRECT COST = 5,344,000

∴ DEDUCT \$ 2,317,400

② BALLASTED @ GRADE - TRANSIT.

| | | | | |
|----------------------------|-----------|---------------------------|---|-----------|
| TRANSIT TRACK | 45,000 LF | @ \$ 85 ⁰⁰ /LF | = | 3,825,000 |
| PIT TRACKS | 1,500 LF | @ 150 ⁰⁰ /LF | = | 225,000 |
| No. 8 SWITCHES | 54 EA | @ 30,000/EA | = | 1,620,000 |
| No 8 DBL X-OVER (SCISSORS) | 7 EA | @ 180,000/EA | = | 1,260,000 |
| No 8 SINGLE X-OVER | 4 EA | @ 65,000/EA | = | 260,000 |
| | | SUBTOTAL | = | 7,190,000 |

OMJM/PBQD DIRECT COST = 8,162,500

∴ DEDUCT \$ 972,500

-245-

KELLOGG CORPORATION
DIRECT COST ESTIMATE

Item Analysis

JOB SUERO/ME DATE 3/31/83

DCE. 15 5-80.2500 HOECKEL'S 334596

Sheet 2 of 2 Estm. Am Ckd. _____ ITEM _____
Plan Sheet No. _____ Bid Quantity _____
Spec. Ref. _____ Take-off Quantity _____
Item Desc. TRACKWORK - YARD

③ TRANSIT TRACK - DIRECT FIXATION - YARD.
TRANSIT TRACK 2140 LF @ 125⁰⁰/LF = \$ 267,500
DMJM/PBQD "DIRECT COST" * = 487,920
∴ DEDUCT \$ 220,420

* MARK-UPS ADDED TWICE
SO DIRECT COST IN
THIS CASE = \$ 228/LF

TOTAL DEDUCT MAIN YARD = \$ 3,510,320

KELLOGG CORPORATION
DIRECT COST ESTIMATE

Item Analysis

JOB SCPTD/MR DATE 3/31/93

Sheet 1 of 2 Estm any Ckd..... ITEM.....

Plan Sheet No..... Bid Quantity.....

Spec. Ref..... Take-off Quantity.....

Item Desc. TRACK WORK - REACH 1-14

DCE. 15 5-90-2500 HOECKEL'S 334596

TRANSIT TRACK - REACH No. 1 TO 14 QUANTITIES FROM SYSTEM TAKEOFF APPENDIX A

BALLASTED AT GRADE (NO QUANTITY FOR THIS ITEM)
SCHEMATIC SHOWS ALL C&C.
@ YARD END.

DIRECT FIXATION: 199,140 @ \$125⁰⁰/FT = \$24,892,500

ADD FOR NO 10 DOUBLE SCISSORS X-OVERS
7 ea @ \$300,000/EA 2,100,000

ADD FOR QUAD C&C NO. 10 SCISSORS X-OVER
PLUS TWO ADDITIONAL SWITCHES
ADJACENT TO THIS X-OVER
(BTWN MAIN YARD & UNION STA)
1 X-OVER @ \$300,000/EA 300,000
2 SWITCHES @ 65,000/EA 130,000

ADD 6 SWITCHES (CONCRETE) FOR EACH
POCKET TRACK (2 ea) = 12 TOTAL
12 SWITCHES @ 65,000/EA 780,000

KC TOTAL DIRECT = \$28,202,500

-247-

KELLOGG CORPORATION
DIRECT COST ESTIMATE

Item Analysis

JOB SCRIPD/MR DATE 3/31/83

Sheet 2 of 2 Estm. Quj Ckd. _____ ITEM _____
Plan Sheet No. _____ Bid Quantity _____
Spec. Ref. _____ Take-off Quantity _____
Item Desc. TRACKWORK - REACH 1-14

DCE. 15 5-80-2500 HOECKEL'S 334598

$$\text{DMJM/PBQD DIRECT COST} = 45,123,192 \div 1.155 = 39,067,698 \text{ (MARK-UP)}$$
$$\therefore \text{DEDUCT} = \underline{\underline{\$10,865,198}}$$

NOTE: DMJM/PBQD DIRECT COST
FOR DIRECT FIXATION
TRACK (WITH ALLOWANCE
FOR X-OVERLS & SWITCHES)
IS \$228/LF $\div 1.155 = \$197/TF$

KC'S DIRECT COST
PRICE FOR DIRECT
FIXATION TRACK ONLY = 125/TF

} $\Delta = \$72^{00}/TF$

KELLOGG CORPORATION
DIRECT COST ESTIMATE

Item Analysis

Sheet 1 of 1 Estm. any Ckd. _____ ITEM _____

Plan Sheet No. _____ Bid Quantity _____

Spec. Ref. _____ Take-off Quantity _____

Item Desc. TRACKWORK - N. HOLLYWOOD T.T.

JOB SCRTD/NE DATE 3/31/83

DCE. 15 5 80-2500 HOECKEL'S 334598

TRACKWORK - N. HOLLYWOOD TATC TRACK.

DIRECT FIXATION TRACK ~ 3480 LF @ 125⁰⁰/FT = \$ 435,000

CONCRETE SWITCHES ~ 3 EACH @ \$ 65,000 \$ 195,000

KC TOTAL DIRECT COST = \$ 630,000

OMTM/PBQD DIRECT COST = 700,000 ÷ 1.155 = 606,000

∴ ADD = \$ 24,000

3/31/83

DWJ

SCPTD/MR
ESTIMATE CHECK
QUANTITY CHECK - TRACK WORK

| | 1 | 2 | 3 | 4 | 5 |
|----|---|-----|-----|----------|--------|
| | DWG | DWG | DWG | KC | QNTY/ |
| | 013 | 014 | 015 | TOTAL | PBQD |
| | | | | | TOTAL |
| 1 | <u>RAILROAD TRACK - YARD - BALLASTED AT GRADE</u> | | | | |
| 2 | | | | | |
| 3 | No 10 SWITCH | 4 | - | 9 | 13 |
| 4 | No 8 SWITCH | 1 | - | 7 | 8 |
| 5 | TOTAL | | | 21 | 20 |
| 6 | | | | | |
| 7 | NEW TRACK | | | 27,000 ± | 32,900 |
| 8 | | | | | |
| 9 | RELOCATE TRACK | | | ? | 1600 |
| 10 | | | | | |
| 11 | | | | | |
| 12 | | | | | |
| 13 | <u>TRANSIT TRACK - YARD - BALLASTED AT GRADE</u> | | | | |
| 14 | | | | | |
| 15 | No 8 DBL X-OVER | 5 | 2 | - | 7 |
| 16 | No 8 SING. X-OVER | - | - | 2 | 4 |
| 17 | No 8 SWITCH | 12 | 34 | 11 | 57 |
| 18 | | | | | |
| 19 | TRANSIT TRACK | | | 35,000 ± | 45,000 |
| 20 | | | | | |
| 21 | PIT TRACK | | | ? | 1500 |
| 22 | | | | | |
| 23 | | | | | |
| 24 | | | | | |
| 25 | <u>TRANSIT TRACK - DIRECT FIXATION - YARD</u> | | | | |
| 26 | TRACK | | | ? | 2140 |
| 27 | | | | | |
| 28 | | | | | |
| 29 | | | | | |
| 30 | | | | | |
| 31 | | | | | |
| 32 | | | | | |
| 33 | | | | | |
| 34 | | | | | |
| 35 | | | | | |
| 36 | | | | | |
| 37 | | | | | |
| 38 | | | | | |
| 39 | | | | | |
| 40 | | | | | |

KELLOGG CORPORATION
DIRECT COST ESTIMATE

Item Analysis

JOB SCRTD/ME DATE 3/30/83

Sheet 1 of 6 Estm. Am Ckd. ITEM.....
Plan Sheet No. Bid Quantity.....
Spec. Ref. Take-off Quantity.....
Item Desc. TRACKWORK

DCE 15 5-80-2500 HOECKEL'S 334598

UNIT PRICES: (WITHOUT MARK-UPS ⇒ DIRECT COST)

① RAILROAD TRACK: NEW 115# RAIL, TIMBER TIES, SAWAST

1982 DODGE GUIDE : \$122⁵⁰/LF
RAILROAD BUILDERS : 65⁰⁰/LF

SCRTD DATA: (UNIT PRICE BK)

| | |
|------------------------|---------------------------|
| MEANS | 62 ⁶⁶ /LF |
| DODGE | 124 ⁸⁵ /LF |
| LSI | 46 ³⁸ /LF |
| SHARP & WELCHS (QUOTE) | \$60-70 ⁰⁰ /LF |
| PACIFIC RR CONTR " | 60-65 ⁶⁰ /LF |
| BOSTON ESCALATED PRICE | \$125 ⁰⁰ /LF |
| BALTIMORE | 57 ⁰¹ /LF |

USE: \$70⁰⁰/LF

② No. 8. TURNOUT (SWITCH) RAILROAD

RAILROAD BUILDERS = \$20-25,000/ea
BOSTON ESCALATED PRICE = \$50,000/ea
BALTIMORE EST = \$27,800/ea

USE = \$35,000/EA

③ No 10. TURNOUT (SWITCH) RAILROAD.

RAILROAD BUILDERS = \$25-30,000/EA
1982 DODGE GUIDE = \$27,845/EA

USE: \$35,000/EA

KELLOGG CORPORATION
DIRECT COST ESTIMATE

Item Analysis

JOB SUETO/MR DATE 3/30/82

Sheet 2 of 6 Estm By Ckd. ITEM.....
Plan Sheet No. Bid Quantity.....
Spec. Ref. Take-off Quantity.....
Item Desc. TRACKWORK

DCE 15 5-80-2500 HOECKEL'S 334598

- ④ RELOCATE TRACK - RAILROAD
ASSUME NEW BALLAST - REUSE ALL ELSE
RAILROAD BUILDERS QUOTE = \$20⁰⁰/LF USE \$30⁰⁰/LF
- ⑤ TRANSIT TRACK - NEW 115# CUR, CONC. TIES, BALLAST
1982 OODGE GUIDE \$93.61/LF
CONCRETE VS. TIMBER TIES ADDS 15⁰⁰±/LF USE \$85⁰⁰/LF
BALTIMORE (MAINLINE) EST = \$72⁵⁰
- ⑥ NO. 8 SINGLE X-OVER - BALLASTED
USE 2x NO. 8 TURNOUT + \$5,000 2x 30,000 + 5,000 = \$65,000/EA
- ⑦ NO. 8 OBL X-OVER - BALLASTED USE \$130,000/EA
- ⑧ NO. 8 OBL X-OVER (SCISSORS) BALLASTED
\$130,000 + 50,000 (FURNISH) USE \$180,000/EA.

KELLOGG CORPORATION
DIRECT COST ESTIMATE

Item Analysis

Sheet 3 of 6 Estm. by Ckd. _____ ITEM. _____
Plan Sheet No. _____ Bid Quantity _____
Spec. Ref. _____ Take-off Quantity _____
Item Desc. TRACK WORK

JOB scrap/mc. DATE 3/30/83

DCE. 15 5.80-2500 HOECKEL'S 334896

② DIRECT FIXATION TRACK.

① BALTIMORE PRICE $\$104^{83}/LF$ (1975 ESCALATED TO 1982)
(DIRECT COST ONLY)

② DENVER RTD ESTIMATE (9/75) = $60^{00}/LF$. (DIRECT COST)
ESCALATE 65% = $\$79^{00}/LF$

③ RE-ESTIMATE USING DENVER RTD DETAIL EST.

| | | |
|---|---|---------------------|
| 115# RAIS ($\$460/TON$) | = | \$17.65 |
| SHOP WELD ($75^{00}/ea/30'ran$) | = | \$3.85 |
| FREIGHT | | \$2.40 |
| FIELD WELD & X-RAYS | | \$1.00 |
| TRACK SECONDARY POUR (CONC?) | | 5.50 |
| DIRECT FASTENER ($\$24 \times 1.6 ESCL$) | | \$38.40 |
| INSTALLATION LABOR ($\$20 \times 1.7 ESCL$) | | 34.00 |
| | | <u>\$102.80/LF.</u> |

KELLOGG CORPORATION
DIRECT COST ESTIMATE

Sheet 4 of 6 Estm. July Ckd. _____ ITEM _____
 Plan Sheet No. _____ Bid Quantity _____
 Spec. Ref. _____ Take-off Quantity _____
 Item Desc. TRACK WORK

Item Analysis

JOB SCTD/ML DATE 3/30/83

DCE. 15 5-80-2500 HOECKEL'S 334586

Ⓐ DRAVO COSTS ON BART (1970) (JOB 5018) OAKLAND TO FREMONT

FURNISH RAIL \$194⁰⁰/TON USE \$460/TON ⇒ \$18⁰⁰/LF

| CONCRETED TRACK (CWE) | AERIAL | ENR ESCL INDEX 1970-1982 | |
|-----------------------|-----------------|--------------------------|----------------------|
| LABOR | 6 ⁶⁵ | x 2.26 | 15 ⁰⁰ /LF |
| PERM. MATRS | 8 ⁷³ | 2.98 | 26 ⁰⁰ |
| EQUIP | 1 ⁴¹ | 2.98 | 4 ⁰⁰ |
| SUPPLIES | 2 ⁶⁸ | 2.98 | 8 ⁰⁰ |
| SUBS | 2 ⁴⁰ | 2.40 | 6 ⁰⁰ |

(AERIAL) Σ = \$77⁰⁰/LF.

Ⓑ DRAVO BID ON BART 1970 - JOB 5039 OAKLAND - SF.

FURNISH RAIL \$214⁰⁰/TON USE 460/TON = \$18⁰⁰/LF

| CONCRETED TRACK (CWE TUNNEL) | ACT 6327 | (40 ⁰⁰ /LF BID) | |
|------------------------------|----------|----------------------------|------------------|
| LABOR | 10.18 | x 2.26 | 23 ⁰⁰ |
| PERM MATR | 15.50 | x 2.98 | 46 ⁰⁰ |
| SUPPLIES | 3.10 | x 2.98 | 9 ⁰⁰ |
| SUBS | 3.43 | x 2.40 | 8 ⁰⁰ |
| EQUIP | | | 8 ⁰⁰ |

(ALLOW) (TUNNEL) \$112⁰⁰/LF.

KELLOGG CORPORATION
DIRECT COST ESTIMATE

Item Analysis

JOB SORTD/MR DATE 3/30/83

Sheet 5 of 6 Estm. Aug Ckd. _____ ITEM _____
Plan Sheet No. _____ Bid Quantity _____
Spec. Ref. _____ Take-off Quantity _____
Item Desc. TRACKWORK

DCE. 15 5-80.2500 HOECKEL'S 334896

USE FOR DIRECT FIXATION TRACK \$ 125⁰⁰/LF
(DIRECT COST)

⑩ NO. 10 DOUBLE SCISSORS CROSSOVER - CONCRETED

① A BALLASTED NO 10 X-OVER ~ \$ 35,000/EA
x 4 = \$ 140,000
ADD FOR CROSSING PIECE = 50,000
\$ 190,000/EA BALLASTED

"BALLASTED" LABOR DEDUCT = \$ 4,000
(4 T.O.S + X-ING) x 5 <20,000>

ADD FOR CONC. TRACK LABOR \$ 15,000 x 5 \$ 75,000

CONCRETE VS BALLAST
25,000
\$ 270,000

-255-

KELLOGG CORPORATION
DIRECT COST ESTIMATE

Item Analysis

Sheet 6 of 6 Estm July Ckd. ITEM.....
 Plan Sheet No. Bid Quantity.....
 Spec. Ref. Take-off Quantity.....
 Item Desc. TRACKWORK.

JOB SURT/ MR DATE 3/30/83

DCE, 15 5-80-2500 HOECKEL'S 334598

⑥ BALTIMORE ESTIMATE

NO 8 TURNOUT - DIRECT FIXATION = 32 400
x 9 ea

129 600
 + CROSSING DIAMOND (D.F.) 24 800

\$ 154 400

⑦ DRAND BART COSTS (S.F. SEGMENT)
 NO 10 SCISSORS X-OVER. (2M) ACT # 6340/6391
 BID \$ 135,000 / EA.

| | | <u>EXCL. RATE</u> | |
|--------------------|-----------|-------------------|-------------------|
| ACTUAL COST: LABOR | \$ 65,700 | 2.26 | 148 000. |
| P.M. | 65,000 | 2.98 | 194,000 |
| SUPPLIES | 3,700 | 2.98 | 11,000 |
| SUBS | -0- | - | - |
| EQUIP | 2500 | 2.98 | 8,000 |
| | | TOTAL | <u>\$ 361,000</u> |

\$ 150,000 ÷ \$ 20⁰⁰/MH = \$ 7500 MH ÷ 8 = 937.5 MAN DAYS ÷ 20 MAN CREW = 47 DAYS
 = 2 MOS +.

USE \$ 300,000 / EACH.

-256-

To FILE

Date 3/28/83

From *Amj.*

Subject SCRTD/MR *g/*

TRACKWORK

GEORGE STANSKE -

TRACK EXPERT w/ DMJM

(213) 381-3663 EXT 426

① DIRECT FIXATION -

② RESILIENTLY SUPPORTED - VERY COST.

400/RF

③ FLOATING SLAB - VIB & NOISE.

CBS TELEVISION STUDIO.

(NEAR BLDG FOUNDATIONS) ^{CRITICAL} POTENTIAL ROTURE DEN
(LA BREA TAR PITS - COUNTY MUSEUM.)

④ PARTIAL ACOUSTICAL CONTROL

CONC TIES IN RUBBER BOOT.
IMBED IN CONC. 2ND POUR.

DIRECT FIX ^{OR.} w/ MORE RUBBER.

TIMBER TIES - PREFERENCE FOR
EMBEDDED SWITCHES.

1/83 EST
BASED ON DIRECT FIXATION.

TRANSIT - 115# RE MAIN LINE & YARD (CUR)

RE - 115# - YARD (RE WILL PROBABLY WANT CUR)

TIES - CONC

RE - TIMBER.

To

Date 3/28/83

From

Subject

g2

PRICES:

2) RESILIENT - SLIGHTLY MORE THAN DIRECT FIXATION
\$200/LF - SUPPLIER OF SYSTEM
SALT QUANTITY ^{THIS} TOO LOW

3) MORTARS SLAB ~ \$400/LF

To FILE

Date 3/30/83

From *anj*

Subject SURETY/MR.

RAILROAD BUILDERS INC.
4039 S. SANTE FE DRIVE (DENVER)
761-1993 (STEVE MCCORMICK)

RR TRACKS { \$70⁰⁰/LF - BID
115# RAIL NEW { 65⁰⁰/LF - w/o M.U. (CWR, #2-3/FT OVER JOINTED,
B T.O. \$20, -25-000 w/o M.U. (~20% LABOR)
10 T.O. 25-30K

TIMBER TIE \$15-30 WOOD TIE 18-24" SP.
CONC TIE 2x \$50-60 CONC TIE.

115# @ MILL \$460/TON [39' FEET STD.
WELD 75⁰⁰/EA. 78' FEET "

NO 8 OBL CROSS-OVER: 4x
"X" + \$50,000

FIXATION FASTENER - ?

RELOCATE \$20⁰⁰/FT NEW BALLAST -
REUSE ALL ELSE

ALPHA #4 OR #5 RR BALLAST.
ASTM CONC ROCK.

To *MLC*

Date *3/25/83*

From *AWJ*

Subject *SURTID/MR*

**TRACKWORK COSTS: 1982 DODGE GUIDE.
RAILROAD RAIL SYSTEMS:**

(Pg 115-116) SINGLE TRACK/LF.

| | <u>L</u> | <u>M</u> | <u>E</u> | <u>T.</u> |
|---------------------|----------------|---------------|-------------|---------------|
| PLACE BALLAST | .27 | 9.60 | .24 | 10.11 |
| PLACE TIES (TIMBER) | .93 | 9.40 | 1.19 | 11.52 |
| PLACE RAIL (CUR) | 1.79 | 99.00 | 1.47 | 102.26 |
| $\Sigma =$ | 2.99 | 118.00 | 2.90 | 123.89 |
| L.A. ADJUST | x 1.32 | x 0.98 | — | — |
| TOTAL | \$ 3.95 | 115.64 | 2.90 | 122.49 |

| | | | | |
|--------------------|--------------|---------------|--------------|------------------|
| <u># 10 SWITCH</u> | 2,750 | 24,650 | 57.00 | 27,457 |
| L.A. ADJUST | x 1.32 | x 0.98 | — | — |
| <u>TOTAL</u> | <u>3,630</u> | <u>24,158</u> | <u>57.00</u> | <u>\$ 27,845</u> |

To *FILE*

Date *3/25/83*

From *AWJ*

Subject *SCRTD/MR.*

TRACKWORK UNITS

1982 DODGE GUIDE

RAPID TRANSIT RAIL SYSTEMS - (HEAVY RAIL)
(Pg 115) SINGLE TRACK / LF

| | <u>L</u> | <u>M</u> | <u>E</u> | <u>TOTAL</u> |
|--------------------|----------|----------|----------|--------------|
| PLACE BALLAST | .27 | 9.60 | .24 | 10.11 |
| CONC TIES - PLACE | .93 | 13.60 | 1.19 | 15.72 |
| RAIL (CUR) - PLACE | 1.58 | 65.80 | 1.29 | 68.67 |

$\Sigma =$ 2.78 89.00 2.72 94.50

LOS ANGELES
ADJUST INDSP: $\times 1.32$ $\times 0.98$ — —

TOTAL 3.67 87.22 2.72 \$ 93.61/LF

SWITCH # 12/EA \$ 2,375 30,900 20.00 \$ 33,295

L.A. ADJUST $\times 1.32$ $\times 0.98$ — —

TOTAL = \$ 3,135 30,282 20.00 \$ 33,437

DMJM/PBQD

SC2TD ME RAIL PROJECT
TRACK WORK

JOB No.

SHEET No. 1 OF 7

DESIGNED BY

DATE 5 JAN 1982

APPROVED

JB

TRACK COSTS ARE BASED ON THREE (3) PRIMARY SOURCES:

- 1) KAISER ENGINEERS BID PRICES FOR BOSTON METRO AND RAIL TRACK WORK, AND . . .
- 2) COST WORK UP FROM PBQD TRACK EXPERT GEORGE STANEKE, AND . . .
- 3) R.S. MEANS & COMPANY.

THE WORK IN BOSTON WAS BID AND LET IN MARCH 1981.
THREE LABOR TRADES ARE MOST GENERALLY USED:

COMMON LABOR
IRONWORKER
EQUIPMENT OPERATOR

THE MARCH '81 BOSTON RATE FOR COMMON LABOR WAS \$14.05/HR.
LOS ANGELES DECEMBER RATE FOR COMMON LABOR IS \$18.13/HR.
THE DIFFERENCE IS +29%.

IRONWORKERS' DIFFERENCE IS +15%

EQUIPMENT OPERATORS DIFFERENCE IS +15%

AN ANALYSIS OF BOSTON WORK SHOWS THAT:

| | | |
|--------------------|-----|------------------------|
| LABOR COMPRISES | 9% | OF THE TOTAL JOB VALUE |
| EQUIPMENT | 3% | " " " " |
| PERM MATERIALS | 53% | " " " " |
| CONCRETE MATERIALS | 17% | " " " " |
| SUB CONTRACTS | 4% | " " " " |

CONCLUSION: EVEN THOUGH LABOR RATES ARE DIFFERENT BY 15% TO 30% THE TOTAL LABOR SHARE OF THE COST PIE DOES NOT HAVE SIGNIFICANT IMPACT. MATERIALS IN THE PRESENT DEPRESSED MARKET HAVE NOT CHANGED TO ANY DEGREE.

DMJM/PBQD

SURTH M. 2015
 TRACK WORK COSTS

JOB No.

SHEET No. 2 OF 7

DESIGNED BY

DATE 1 JUN 1983

APPROVED

JB

A COMPOUNDING OF A 30% INCREASE IN LABOR AND
 A 10% INCREASE IN ALL OTHER SEGMENTS OF WORK
 PRODUCES A NET TOTAL INCREASE OF 12%.

THIS 12% WAS USED TO FACTOR THE BOSTON COSTS TO
 PRESENT DAY LOS ANGELES COSTS.

RAILROAD TRACK No. 5a AT \$110⁰⁰/LF + 12% = 123.20 USE \$125⁰⁰ LF
 No. 8 TURN OUT No. 16a AT \$39,000 + 12% = \$44,000 USE \$50,000
 No. 8 DBL X OVER No. 17a AT \$201,000 + 12% = \$225,120 USE \$225,000/EA
 No. 8 SING. X OVER No. 18a AT \$89,000 + 12% = \$99,680 USE \$100,000/EA

TRANSIT TRACK

| | |
|---|--------------------|
| BASE COST OF FASTNER @ 24" SPACING | 60- |
| MATERIAL COST ON CONCRETE | 10- |
| LABOR @ 5 HRS TRACK FOOT @ 22 ⁰⁰ /HR | <u>110</u> |
| SUBTOTAL | \$ 180- |
| RAIL COST | 17- |
| OVERHEAD & PROFIT @ 15.5% | <u>31-</u> |
| | \$ <u>228-</u> USE |



CONSTRUCTION COST ESTIMATE

DATE 17 AUG. 1982

NAME METRA RAIL PROJECT LOCATION LOS ANGELES, CA.
 SUBJECT CONVERSION - BALTIMORE RAIL COST TO 1982 L.A.
 JOB NO. WBS-14-AAE PHASE STUDY PAGE 1 OF 2

| Item | Description | Quantity | Unit | Unit Cost | Estimated Cost | Totals |
|------|-------------|----------|------|-----------|----------------|--------|
|------|-------------|----------|------|-----------|----------------|--------|

MEANS - 1982 COST GUIDE

PAGE 65 (27) R.R. TRACK

COSTS.

LF TRACK COST = L = 13.55 M = 35.60 (BARE)
MARK UP = 18.11% (50% O.H. + P.)

% RATIO: L = $\frac{13.55}{49.15} = 0.2757$

M = $\frac{35.60}{49.15} = 0.7243$

CITY COST INDEXES - MEANS PAGE 375 & 378

USE 5 - METALS FOR MATERIAL

L.A. 82 = $\frac{111.8}{98.7} = 1.13273$

BALT. 82 = 98.7

USE 2 - SITEWORK FOR LABOR

LA 82 = $\frac{111.4}{91.7} = 1.2148$

BALT 82 = 91.7

RATIO x CITY INDEX

LABOR = $0.2757 \times 1.2148 = 0.3349$

MATERIAL = $0.7243 \times 1.13273 = 0.8209$

1.1553 LA/BALT. FACTOR
DIRECT COST

LA/BALT DC FACTOR x MARKUP =

118.11 x 1.1553

= 1.3645 LA/BALT $\frac{82}{79}$ SUB FACTOR

$\frac{\$16,031,076 (79 JULY)}{12,534,071 (75 DEC)} = 1.279$

1.279 x 1.3645 = 1.7542 CONVERSION FACTOR TO EQUATE DEC/75

Amounts Forwarded

BALT PRICES TO 1982 LA PRICES

DIRECT COST ONLY

To MCE

Date 3/25/83

From AWJ

Subject SCRTD/MR.

I. TRACKWORK - ITEMS & UNITS

- 1) RAILROAD TRACK - BALLASTED, AT GRADE
 - a) RELOCATE TRACK \$ 50⁰⁰/LF
 - b) NEW TRACK \$ 125/LF
 - c) NEW No. 8 SWITCHES \$ 50,000/EA
 - d) NEW No. 10 SWITCHES \$ 60,000/EA

- 2) TRANSIT TRACK - BALLASTED, AT GRADE
 - a) TRANSIT TRACK \$ 75⁰⁰/LF
 - b) PIT TRACKS \$ 75⁰⁰/LF
 - c) No. 8 SWITCHES \$ 50,000/EA
 - d) NO. 8 OBL X-OVER \$ 225,000/EA
 - e) NO. 8 SINGLE X-OVER \$ 100,000/EA

- 3) DIRECT FIXATION
 - a) TRANSIT \$ 228⁰⁰/LF

II. TRACKWORK - GROSS CHECK (MATH/QTY'S)

TOTAL TF REACH 1-19 = 198,714 TF (FROM LENGTH ANALYSIS)
 LESS BALLASTED AT GRD = 1,200 TF

 \$ 197,514
 x \$ 228⁰⁰/TF

 \$ 45,033,192
 BALLASTED 1200 LFE @ 75⁰⁰ = 90,000
 \$ 45,123,192
 MAIN YARD 16,300,000
 TAIL TRACK 2900 LFE @ 228⁰⁰ = 661,200

 62,084,392 ✓
 = TF TOTAL

TRACKWORK
 SERTD ESTIMATE CHECK
 RECAP OF TRACKWORK EST.

3/25/83
 AWJ

| | 1 | 2 | 3 | 4 | 5 | |
|---|--|--------------------------|----------------------|-----------------------------|----------------|--|
| | QTY (SERTD) | UNIT PRICE (SERTD) | \$ (SERTD) | ROUNDED TOTAL (SERTD) | | |
| RAILROAD TRACK BALLASTED AT GRADE - YARD | | | | | | |
| 1 | RELOCATE TRACK | 1620LF | 50 ⁰⁰ | 81,000 | | |
| 2 | NEW TRACK | 32,900LF | 125 ⁰⁰ | 4,112,500 | | |
| 3 | NEW No. 8 SWITCHES | 5 EA | 50,000 ⁰⁰ | 250,000 | | |
| 4 | NEW No. 10 SWITCHES | 15 EA | 60,000 ⁰⁰ | 900,000 | | |
| 5 | | | | 856,500 | | |
| 6 | OH+P & BONDERS | | | 6,200,000 | \$6.2M | |
| 7 | | | | | | |
| 8 | | | | | | |
| 9 | | | | | | |
| 10 | | | | | | |
| 11 | | | | | | |
| 12 | | | | | | |
| 13 | | | | | | |
| 14 | | | | | | |
| 15 | TRANSIT TRACK - BALLASTED AT GRADE - YARD | | | | | |
| 16 | TRANSIT TRACK | 45,000LF | 75 ⁰⁰ | 3,375,000 | | |
| 17 | PIT TRACKS | 1500LF | 75 ⁰⁰ | 112,500 | | |
| 18 | No. 8 SWITCHES | 59 EA | 50,000 | 2,700,000 | | |
| 19 | No. 8 DBL X-OVER | 7 EA | 225,000 | 1,575,000 | | |
| 20 | No 8 SING X-OVER | 4 EA | 100,000 | 400,000 | | |
| 21 | | | | 1,337,500 | | |
| 22 | OH+P+BOND | | | 9,500,000 | \$9.5M | |
| 23 | | | | | | |
| 24 | | | | | | |
| 25 | TRANSIT TRACK - DIRECT FIXATION - YARD | | | | | |
| 26 | TRANSIT TRACK | 2,190LF | 228 ⁰⁰ | 487,920 | | |
| 27 | OH+P+BOND | | | 112,080 | | |
| 28 | | | | 600,000 | \$0.6M | |
| 29 | | | | | | |
| 30 | TRANSIT TRACK - REACH 1 TO 14 | | | | | |
| 31 | BALLASTED - AT GRADE | 1200LF | 75 ⁰⁰ | 90,000 | | |
| 32 | DIRECT FIXED | 137,541LF | 228 ⁰⁰ | 45,033,192 | | |
| 33 | | | | 45,123,192 | \$45.3M | |
| 34 | | | | | | |
| 35 | TAIL TRACK - N. HOLLYWOOD | | | | | |
| 36 | DIRECT FIXATION | 2900LF | 228 ⁰⁰ | 661,000 | \$0.7M | |
| 37 | | | | | | |
| 38 | | | | | | |
| 39 | | | | | | |
| 40 | | | | | | |
| | TOTAL | | | | \$62.3M | |

NOT USED

SUMMARY

**KELLOGG CORPORATION
DIRECT COST ESTIMATE**

JOB SCRTD DATE 3-24-83

Sheet 0 of Estm. 002 Ckd. ITEM.....
 Plan Sheet No. Bid Quantity.....
 Spec. Ref. Take-off Quantity.....
 Item Desc. MAIN YARD

FORM E240E HOECKEL'S 947960

| DESCRIPTION | QUANTITY | DIR. LABOR | | EQUIPM'T COST | | DIR. MAT'L | | PM/SUB | | E.O.E. | | TOTAL | |
|-----------------------------|----------|---|--------|---------------|--------|------------|--------|--------|--------|--------|--------|-------|---------------------|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT |
| <u>MAIN YARD : EXCLUDES</u> | | <u>BUILDINGS & TRACK WORK (NRA)</u> | | | | | | | | | | | |
| | | <u>BY OTHERS IN KC</u> | | | | | | | | | | | |
| <u>DEMOLITION</u> | | | | | | | | | | | | | <u>2,120,000</u> |
| <u>SITE PREP</u> | | | | | | | | | | | | | <u>770,000</u> |
| <u>STRUCTURAL</u> | | | | | | | | | | | | | <u>2,796,000</u> |
| <u>ROADS & PAVING</u> | | | | | | | | | | | | | <u>818,000</u> |
| <u>FENCING</u> | | | | | | | | | | | | | <u>196,000</u> |
| <u>LIGHTING</u> | | | | | | | | | | | | | <u>625,000</u> |
| | | | | | | | | | | | | | <u>\$ 7,325,000</u> |

-270-

KELLOGG CORPORATION
 DIRECT COST ESTIMATE

Sheet 1 of 6 Estm DDL Ckd ITEM
 Plan Sheet No. _____ Bid Quantity _____
 Spec. Ref. _____ Take-off Quantity _____
 Item Desc. MAIN YARD

JOB SCRIPT DATE 3-24-83

FORM F249E HOECKEL'S 347860

| DESCRIPTION | QUANTITY | DIR. LABOR | | EQUIPMT COST | | DIR. MAT'L | | PM/SUB | | E.O.E. | | TOTAL | | |
|--|--------------|------------|--------|--|--------|------------|--------|------------------|--------------------|---------------------|--------|-----------------|-----------|--|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | |
| <u>MAIN YARD EXCLUDES BUILDINGS & TRACK WORK (NEW)</u> | | | | | | | | | | | | | | |
| <u>DEMOLITION</u> | | | | | | | | | | | | | | |
| REMOVE RR TRACK | 94175 LF | | | } ALLOWS FOR HAUL TO STORAGE FOR ANY RELAY VALUE | | | | 12 ⁰⁰ | | | | 1,130,000 | | |
| REMOVE YARD SWs. | 91 EA | | | | | | | | 1000 ⁰⁰ | | | | 91,000 | |
| REMOVE MAIN LINE SW | 1 EA. | | | | | | | | 1500 ⁰⁰ | | | | 1,500 | |
| REM. RETAIN WALLS | 1054 CY | | | | | | | | | 46 ⁰⁰ | | | 42,200 | |
| REM. INV. BLDGS. | 3,258750 CF. | | | | | | | | | 0 ¹⁷ | | | 554,000 | |
| REM. CR. & CONC SILOS | 6 EA. | | | | | | | | | 5000 ⁰⁰ | | | 30,000 | |
| REM. GAS STA & EQUIP LS. | | | | | | | | | | 20000 ⁰⁰ | | | 20,000 | |
| REM. CONC/ASP PAVE | 436,500 SF | | | | | | | | | | | 30 | 131,000 | |
| OFF SITE DISPOSAL | 20,000 CY | | | | | | | | | | | 6 ⁰⁰ | 120,000 | |
| | | | | | | | | | | CALL | | | 2,120,000 | |

-271-

KELLOGG CORPORATION
DIRECT COST ESTIMATE

JOB SCRTD DATE 3-24-83

Sheet 7 of 6 Estm DR Ckd K ITEM.....

Plan Sheet No..... Bid Quantity.....

Spec. Ref..... Take-off Quantity.....

Item Desc. MAIN YARD

FORM E240E HOECKEL'S 847880

| DESCRIPTION | QUANTITY | DIR. LABOR | | EQUIP'T COST | | DIR. MAT'L | | PM/SUB | | E.O.E. | | TOTAL | |
|-------------------------|-----------|------------|--------|--------------|--------|------------|--------|--------|--------|--------|--------|-------|-------------|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT |
| <u>MAIN YARD CONTD</u> | | | | | | | | | | | | | |
| <u>SITE PREPARATION</u> | | | | | | | | | | | | | |
| CLEAR/GRUB | 13 AC | | | | | | | 2000 | - | | | | 26000 |
| MACH EXCAV | 107000 CY | | | | | | | 200 | | | | | 214000 |
| ROUGH GRADE | 45000 CY | | | | | | | 50 | | | | | 23000 |
| FINE GRADE | 45000 CY | | | | | | | 100 | | | | | 45000 |
| SOLD. PILE/LAG | 13300 SF | | | | | | | 2500 | | | | | 332500 |
| SHEET PILE | 5300 L' | | | | | | | 1500 | | | | | 80000 |
| DISP. /OFF SITE | L.S. | | | | | | | | | | | | 50000 |
| | | | | | | | | | | | | | \$ 770000 ✓ |

-272-

KELLOGG CORPORATION
 DIRECT COST ESTIMATE

JOB SCRTO

DATE 3-24-83

Sheet 3 of 6 Estm DRL Ckd / ITEM.....

Plan Sheet No..... Bid Quantity.....

Spec. Ref..... Take-off Quantity.....

Item Desc. MAIN YARD

FORM E249E HOECKEL'S 847880

| DESCRIPTION | QUANTITY | DIR. LABOR | | EQUIPMT COST | | DIR. MAT'L | | PM/SUB | | E.O.E. | | TOTAL | |
|--|----------------|--|--------|--------------|--------|------------|--------|--------|--------|--------|--------|-------|---------------------|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT |
| <u>MAIN YARD CONTD</u> | | | | | | | | | | | | | |
| <u>STRUCTURAL</u> | | <p><u>DESIGN / DRAWINGS AVAILABLE</u></p> <p><u>INDICATE THIS WORK TO BE</u></p> <p><u>PRIMARILY RELOCATION OF ONE</u></p> <p><u>FIRST STREET BENT (SERIES OF PILE)</u></p> <p><u>AND PORTAL STRUCTURE AT NEW</u></p> <p><u>SANTA FE CONNECTION.</u></p> | | | | | | | | | | | |
| <u>RECONSTR 1ST ST BRIDGE LS.</u> | | <p><u>IF BENT ONLY - TOO MUCH</u></p> <p><u>HOWEVER - COULD BE</u></p> <p><u>EXTENSIVE - STAY WITH</u></p> | | | | | | | | | | | |
| <u>PORTAL WALLS</u> | <u>4240 CY</u> | <p><u>SA - LOT OF CONCRETE</u></p> <p><u>FOR PORTAL</u></p> | | | | | | | | | | | |
| | | | | | | | | | | | | | <u>1,100,000</u> |
| | | | | | | | | | | | | | <u>1,696,000</u> |
| | | | | | | | | | | | | | <u>\$ 2,796,000</u> |

-273-

KELLOGG CORPORATION
DIRECT COST ESTIMATE

JOB SLRTP DATE 3-24-83

Sheet 4 of 6 Estm 120L Ckd..... ITEM.....

Plan Sheet No..... Bid Quantity.....

Spec. Ref..... Take-off Quantity.....

Item Desc MAIN YARD

FORM E210E HOECKEL'S 347890

| DESCRIPTION | QUANTITY | DIR. LABOR | | EQUIPM'T COST | | DIR. MAT'L | | PM/SUB | | E.O.E. | | TOTAL | |
|--|----------|--|--------|---------------|--------|------------|--------|-----------------|--------|--------|--------|------------|---------|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT |
| <u>MAIN YARD Cont'd</u> | | | | | | | | | | | | | |
| <u>ROADS & PAVEMENT</u> | | | | | | | | | | | | | |
| NOTE: SHEET #3 DIMJM TAKE OFF | | | | | | | | | | | | | |
| ASPH. HEAVY DUTY | } | ASSUMED TO BE 8" BASE 3" CONCR WITH | | | | | | | | | | | |
| ASPH. LIGHT DUTY | | A 1 1/2" OVERLAY & 6" BASE WITH 4" ASPH. | | | | | | | | | | | |
| ALL FINISHED & STRIPED. W-24, 20, 16, 10 | | | | | | | | | | | | | |
| 115,160 / 20 = 6000 FT - 342340 / 20 = 17000 | | | | | | | | | | | | | |
| ASPH. Hvy DUTY | 115,160 | | | | | | | 2 ²⁵ | | | | | 259,000 |
| ASPH LT. DUTY | 342,340 | | | | | | | 1 ⁵⁰ | | | | | 514,000 |
| CONCR. CURB 8' | 4200 FT. | | | | | | | 6 ⁰⁰ | | | | | 25,000 |
| MISC. ALLOW SOME REFLECTORS / SIGNS / GUARD RAIL | | | | | | | | | | | | | 20,000 |
| | | | | | | | | | | | | \$ 818,000 | |

-274-

KELLOGG CORPORATION
DIRECT COST ESTIMATE

Sheet 5 of 6 Estm DPL Ckd V ITEM.....

Plan Sheet No..... Bid Quantity.....

JOB SCRIPD DATE 3-24-83

Spec. Ref..... Take-off Quantity.....

Item Desc. MAIN YARD

FORM E240E HOECKEL'S 347880

| DESCRIPTION | QUANTITY | DIR. LABOR | | EQUIPMT COST | | DIR. MAT'L | | PM/SUB | | E.O.E. | | TOTAL | |
|-------------------------|----------|------------|--------|--------------|--------|------------|--------|--------|--------------------|--------|--------|-------------------|--------|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT |
| <u>MAIN YARD CONT'D</u> | | | | | | | | | | | | | |
| <u>FENCE WORK</u> | | | | | | | | | | | | | |
| <u>W/ BARB WIRE</u> | | | | | | | | | | | | | |
| 7' CL W 3 STR. | 12900 LF | | | | | | | | 12 ⁵⁰ | | | | 161250 |
| 16' GATES | 1 EA | | | | | | | | 800 ⁰⁰ | | | | 800 |
| 20' GATES | 3 EA | | | | | | | | 1000 ⁰⁰ | | | | 3000 |
| 24' GATES | 2 EA | | | | | | | | 1200 ⁰⁰ | | | | 2400 |
| <u>W/O BARB WIRE</u> | | | | | | | | | | | | | |
| 6' CL | 1700 LF | | | | | | | | 10 ⁰⁰ | | | | 17000 |
| 20 | 2 EA | | | | | | | | 1000 ⁰⁰ | | | | 2000 |
| 24 | 2 EA | | | | | | | | 1200 ⁰⁰ | | | | 2400 |
| 30 | 1 EA | | | | | | | | 1800 ⁰⁰ | | | | 1800 |
| <u>SIGNING - Misc</u> | | | | | | | | | | | | 5000 | |
| | | | | | | | | | | | | <u>\$ 196,000</u> | |

-275-

KELLOGG CORPORATION
DIRECT COST ESTIMATE

Sheet 6 of 6 Estm. PRE Ckd. ✓ ITEM.....

Plan Sheet No..... Bid Quantity.....

JOB SCRIP DATE 3-24-83 Spec. Ref..... Take-off Quantity.....

Item Desc. MAIN YARD

FORM E240E HOECKEL'S 347860

| DESCRIPTION | QUANTITY | DIR. LABOR | | EQUIP'M'T COST | | DIR. MAT'L | | PM/SUB | | E.O.E. | | TOTAL | |
|---|--------------|------------|--------|----------------|--------|------------|--------|--------|--------|--------|--------|-------|-------------------|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT |
| <u>MAIN YARD CONT'D</u> | | | | | | | | | | | | | |
| <u>LIGHTING</u> | | | | | | | | | | | | | |
| <p><u>DMJM WORK SHEET Y-43 (#28)</u> <u>RELATES LIGHTING REQUIREMENTS</u> <u>HOWEVER SHOULD BE ALLOWANCE</u> <u>FOR LOCAL POWER SUBSTATION / SW YD</u> <u>& TRANSMISSION / DISTRIBUTION</u></p> | | | | | | | | | | | | | |
| <u>LIGHTING STANDARD</u> | <u>25 EA</u> | | | | | | | | | | | | <u>500,000</u> |
| <u>SUB / SW YD</u> | <u>25</u> | | | | | | | | | | | | <u>50000</u> |
| <u>TRANS / DISTR.</u> | <u>25.</u> | | | | | | | | | | | | <u>75000</u> |
| | | | | | | | | | | | | | <u>\$ 625,000</u> |

-276-

NOT USED

COMPARISON OF ELECTRICAL/MECHANICAL COSTS - BUILDINGS

| DESCRIPTION | TOTAL COST (incl. O&P) | COST/SF | PLUMBING | COST/SF | HVAC | COST/SF | FIRE PROTECTION | COST/SF | ELECTRICAL | COST/SF |
|--|------------------------|----------|----------|---------|---------|---------|-----------------|---------|------------|---------|
| MAIN SHOP BUILDING | 44.35 M | 88.82 * | - | - | - | - | - | - | - | - |
| MAINT. OF WAY BUILDING | 8.0 M | 89.81 * | - | - | - | - | - | - | - | - |
| TRANSPORTATION BLDG | 1.69 M | 122.18 | 12,000 | 732 | 153,000 | 925 | - | 175,000 | 10.32 | - |
| CAR CLEANER BLDG | 0.32 M | 99.42 | 28,000 | 732 | 25,000 | 688 | - | 41,000 | 10.62 | - |
| TEST BUILDING | 0.89 M | 131.14 | 33,000 | 422 | 14,000 | 214 | 190,000 | 234 | 72,000 | 10.32 |
| CAR WASHER | 0.56 M | 144.44 * | - | - | - | - | - | - | - | - |
| TRACTION POWER | 0.46 M | 64.51 | 17,000 | 240 | 8,000 | 112 | - | 40,000 | 8.42 | - |
| CONTROL BUILDING | 1.5 M | 150.00 | - | - | - | - | - | - | - | - |
| CHANGES REQUIRED MECHANICAL/ELECTRICAL BUDGETS | | | | | | | | | | |
| CONTROL BUILDING ADD. | | | 128,000 | | | | | | | |
| * INCLUDES MECHANICAL/ELECTRICAL COSTS | | | | | | | | | | |

-278-

KELLOGG CORPORATION
DIRECT COST ESTIMATE

JOB SCRTP. DATE 3-24-88

Sheet 1 of 2 Estm DR Ckd ITEM

Plan Sheet No. Bid Quantity

Spec. Ref. Take-off Quantity

Item Desc. PARKING

FORM E240E HOECKEL'S 347860

| DESCRIPTION | QUANTITY | DIR. LABOR | | EQUIP'T COST | | DIR. MAT'L | | PM/SUB | | E.O.E. | | TOTAL | |
|---|----------|------------|--------|--------------|--------|------------|--------|--------|--------|--------|--------|-------|--------|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT |
| <u>SURFACE (AT GRADE) PARKING.</u> | | | | | | | | | | | | | |
| <p>ASSUME: AREA RUNS 200 TO 300 FT PER CAR WITH THRUWAYS - SAY 250 FT AVE.</p> <p>SELECTED SITES WILL REQUIRE:</p> <ul style="list-style-type: none"> • DEMOLITION • SITE GRADING / LEVELING. • PRE COMPACTION • BASE COURSE • ASPHALT • STRIPING • FENCING • BUMPERS - SOME - • LIGHTING - ? • LANDSCAPING. / IRRIGATION <p>AT GRADE PARKING LOTS ARE SHOWN TO BE LOCATED AT</p> <ul style="list-style-type: none"> • REACH 8 FAIRFAX / WILSHIRE • REACH 13 UNIVERSITY CITY. | | | | | | | | | | | | | |

-279-

KELLOGG CORPORATION
DIRECT COST ESTIMATE

Sheet 2 of 2 Estm. DD Ckd. ITEM.....

Plan Sheet No..... Bid Quantity.....

JOB SCRIPT DATE 3-24-83 Spec. Ref..... Take-off Quantity.....

Item Desc. PARKING

FORM E240E HOECKEL'S 347860

| DESCRIPTION | QUANTITY | DIR. LABOR | | EQUIPM'T COST | | DIR. MAT'L | | PM/SUB | | E.O.E. | | TOTAL | | |
|--|---|------------|--------|---------------|--------|------------|--------|--------|--------|--------|--------|-------|--------|---------------------|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | |
| <u>SURFACE (AT GRADE) PARKING CONT'D</u> | | | | | | | | | | | | | | |
| | <u>DMJM INDICATES AT EACH SITE THAT 80 - 90,000 SQ' OR 2 ACRES EACH OF AREA TO BE USED.</u> | | | | | | | | | | | | | |
| <u>SITE GRADING & PRECOMPACTON</u> | | | | | | | | | | | | | \$ | 20,000 |
| <u>BASE PLUS ASPH SURFACE</u> | <u>85,000 SQ'</u> | | | | | | | | | | | | \$ | 51,000 |
| <u>STRIPING</u> | <u>300 - 400 CARS</u> | | | | | | | | | | | | | 3,000 |
| <u>BUMPERS</u> | | | | | | | | | | | | | | 10,000 |
| <u>CURBS / PLANTERS / LANDSCAPING</u> | | | | | | | | | | | | | | 30,000 |
| <u>FENCING - PERIMETER</u> | | | | | | | | | | | | | | 12,000 |
| <u>DEMOLITION</u> | | | | | | | | | | | | | | 20,000 |
| <u>LIGHTING</u> | | | | | | | | | | | | | | 50,000 |
| | | | | | | | | | | | | | | 200,000 (BALL PARK) |
| | | | | | | | | | | | | | \$ | 196,000 |

-280-

KELLOGG CORPORATION
DIRECT COST ESTIMATE

JOB SCRIP

DATE 3-24-83

Sheet 1 of 2 Estm OK Ckd ✓ ITEM.....

Plan Sheet No..... Bid Quantity.....

Spec. Ref..... Take-off Quantity.....

Item Desc. PARKING

FORM E240E HOECKEL'S 347889

| DESCRIPTION | QUANTITY | DIR. LABOR | | EQUIPM'T COST | | DIR. MAT'L | | PM/SUB | | E.O.E. | | TOTAL | | | | |
|--|----------|------------|--------|---------------|--------|------------|--------|--------|--------|--------|--------|-------|--------|--------------------|------|-----|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | | | |
| <u>PARKING GARAGES -</u> | | | | | | | | | | | | | | | | |
| CONCEPTUAL PRELIMINARY ESTIMATE AND THE SCHEMATIC DIAGRAM SHOW PARKING STRUCTURES AT REACHES 1 - 8 - 9 - 13 - 14. | | | | | | | | | | | | | | | | |
| REACH 1 | | | | | | | | | | | | | | UNION STATION | 2250 | CAR |
| REACH 8 | | | | | | | | | | | | | | FAIRFAX / WILSHIRE | 1000 | CAR |
| REACH 9 | | | | | | | | | | | | | | BEVERLY / FAIRFAX | 1000 | CAR |
| REACH 13 | | | | | | | | | | | | | | UNIVERSAL CITY | 2000 | CAR |
| REACH 14 | | | | | | | | | | | | | | NO. HOLLYWOOD. | 2500 | CAR |

KELLOGG CORPORATION
DIRECT COST ESTIMATE

Sheet 7 of 7 Estm DDL Ckd ITEM
 Plan Sheet No. _____ Bid Quantity _____
 Spec. Ref. _____ Take-off Quantity _____
 Item Desc. PARKING

JOB SCRTD DATE 3-24-83

FORM E240E HOEGKEL'S 347880

| DESCRIPTION | QUANTITY | DIR. LABOR | | EQUIP'T COST | | DIR. MAT'L | | PM/SUB | | E.O.E. | | TOTAL | |
|--|-----------|------------|--------|--------------|--------|---------------|--------|--------|--------|--------|--------|-------------------|----------|
| | | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT | UNIT | AMOUNT |
| <u>PARKING GARAGE CONT'D</u> | | | | | | | | | | | | | |
| <p><u>PARKING STRUCTURES (LESS LAND PURCHASE)</u> <u>RANGE FROM 3500 - 6500 / CAR SPACE.</u> <u># 5,000 - / CAR SPACE A FAIR ESTIMATE.</u> <u>FOR OPEN TYPE MINUS AVAC.</u></p> | | | | | | | | | | | | | |
| <u>REACH</u> | <u>1</u> | | | <u>2250</u> | | <u>@ 5000</u> | | | | | | <u>11,250,000</u> | <u>✓</u> |
| | <u>8</u> | | | <u>1000</u> | | <u>5000</u> | | | | | | <u>5,000,000</u> | <u>✓</u> |
| | <u>9</u> | | | <u>1000</u> | | <u>5000</u> | | | | | | <u>5,000,000</u> | <u>✓</u> |
| | <u>13</u> | | | <u>2000</u> | | <u>5000</u> | | | | | | <u>10,000,000</u> | <u>✓</u> |
| | <u>14</u> | | | <u>2500</u> | | <u>5000</u> | | | | | | <u>17,500,000</u> | <u>✓</u> |
| | | | | | | | | | | | | <u>OK.</u> | |

-282-

To FILE

Date 3/29/93

From Awf

Subject SCRTD/ME

CONTINGENCES (ALLOWANCE FOR CHANGE ORDERS - POST BID)

VALUE OF POTENTIAL CHANGE ORDERS WILL VARY WITH THE RISK OF THE WORK AND THE KNOWLEDGE OF CONDITIONS UPON WHICH THE DESIGN IS BASED. UNDERGROUND WORK WILL CARRY HIGHEST CONTINGENCY AND BUILDING WORK THE LOWEST.

USE SAME % OF WORK TYPE BREAKDOWN AS DEVELOPED FOR PREPAT ANALYSIS. (APPENDIX T)

WEIGHTED AVERAGE

| | | | |
|-----------------------|-------------------|----------|------------------|
| \$ 395 M | UNDERGROUND @ 15% | CONTING. | = \$ 59.25 M |
| 80 M | BUILDINGS @ 5% | " | = 4.00 |
| 980 M | HEAVY CONST @ 10% | " | = 98.00 |
| <u>Σ = \$ 1,455 M</u> | | | <u>\$ 161.25</u> |

WEIGHTED AVE = $\frac{161.25}{1,455} = .1108 \approx \underline{\underline{11\%}}$

To *Paul*

Date *3/29/83*

From *Amj*

Subject *SURTD/MR*

PROFIT ANALYSIS

CONTRACTOR'S PROFIT TO BE BASED ON TYPE OF WORK.

| <u>PROFIT %</u> | <u>WORK TYPE</u> | <u>\$ IN CURRENT EST</u> |
|-----------------|-------------------------------|---------------------------|
| 20-30% | UNDERGROUND HIGH RISK | \$ 395 M (27% OF WORK) |
| 6-7% | BUILDING TYPE (LOW RISK) | \$ 80 M (5% OF WORK) |
| 10-12% | TYPICAL HEAVY CONSTRUCTION | \$ 980 M (67% OF WORK) |

WEIGHTED AVERAGE

$$\begin{aligned} & \$ 395 \text{ M @ } 25\% \text{ PROFIT} = \$ 98.75 \text{ M} \\ & \quad 80 \text{ M @ } 6\frac{1}{2}\% = 5.20 \text{ M} \\ & \quad 980 \text{ M @ } 11\% = 107.80 \text{ M} \\ & \hline \Sigma = \$ 1,455 \text{ M} & \quad \quad \quad \hline & \quad \quad \quad \$ 211.75 \text{ M} \end{aligned}$$

$$\begin{aligned} \text{WEIGHTED PROFIT AVE} &= \frac{\$ 211.75}{1,455} = .1455 \\ \text{USE } \underline{15\%} & \quad \quad \quad -284- \end{aligned}$$

NOT USED

APPENDIX V - AGENCY COSTS

NOT USED

NOT USED


NOT USED

To **KC 1223 SCRTD FILES**

Date **3-17-83**

From **JEK**

Subject **CONSTRUCTION CONTRACT
STAGING - PAGE 1 OF 2**




To **KC 1223 SCRTO/MR FILES**

Date **3-17-83**

From **JEK**

Subject **CONSTRUCTION CONTRACT
STAGING - PAGE 2 OF 2**



To


Date

From

Subject



MAIN YARD All Surface

REACH ① All Cut & Cover including Union Station less outbound cross-over ②.



REACH ③ All Cut & Cover including Seventh & Flower Station

REACH ④ All Cut & Cover including Alvarado Station but excluding inbound cross-over ⑤




To

Date


From

Subject


REACH (7) All cut & cover including LaBrea-Wilshire Station but excluding inbound pocket track (6).



REACH (9) All cut & cover including Beverly & Fairfax Station but excluding inbound crossover (8).



REACH (11) All cut & cover including Hollywood & Cahuenga Station and out bound pocket tracks.



To

Date

From

Subject

REACH (13) All cut & cover including Universal City Station.

