
Airport Metro Connector Board Meeting April, 2015




Crenshaw/LAX Accommodations

Accommodations

- > Placement of turn-back and tail track at 96th St Station
- > Special track work and turn outs
- > Bridge and wall modifications
- > Grade crossing at Arbor Vitae


> PLATFORMS NOT PART OF CRENSHAW/LAX ACCOMMODATIONS






Base Design vs Ultimate Design

Base Design




Ultimate Design – Eastside Alignment



4/10/2015

Metro Existing & Proposed ROW



Option 1 - Cross Section A-A

PROPOSED LIMIT OF EXISTING CURRENT/PROPOSED CURRENT EXISTING PROPOSED ROW **Ç SB TRK G NB TRK** ROW **ÇNB, TRK** PERMANENT R/W TAKE PROPOSED LIMIT OF TEMPORARY CONSTRUCTION EASEMENT (TCE) 31.16 33.12 24.00' 4.56' 4.56 24.00 4.56' 4.56 24.00 POTENTIAL FUTURE 24 -11 L1 PLATFORM (TYP.) 11 EXISTING ++ 11 GROUND 0000 0000 0000 0000 0 70 25 24 5' TO 5'TO 7 UNDERDRAIN (TYP) ×. OCS DUCTBANK SCGC GAS LINE 8 " COLA SANITARY SEWER LINE 4" TO 12" SCGC GAS LINE SCGC 9.50' GAS LINE 16.00 22.50' 25.32' NOT TO SCALE LEGEND Metro Existing ROW **Temporary Construction Easement** Proposed ROW 30 ' Gas Line

OVERLAY OF CURRENT CRENSHAW/LAX PROJECT WORK AND 96TH ST STATION ACCOMMODATION

4/10/2015

Eastside Alignment

Option 1: Install Crenshaw/LAX Baseline/Relocate Later

Property Acquisition, Relocate Utilities, Relocate Baseline, Build Ultimate Track Configuration

Estimated Cost to Relocate Baseline: Under Evaluation (May)

Option 2: Delay Crenshaw/LAX

Property Acquisition, Relocate Utilities, Build Ultimate Track Configuration (Up to a 2-year delay)

Estimated Cost of Delay: Under Evaluation (May)




Option 1 vs Option 2

Pros	Cons
 No Delay to 	Relocation of
Crenshaw	Baseline
	required
	Cost of
	relocating
	Baseline
	Reconstruction
	of Baseline and
	construction of
	ultimate while
	under operation
	Requires
	property (sliver)
Metro	acquisition

Option 2: Delay Crenshaw	
Pros	Cons
 No relocation of baseline required 	 Up to 2-Years delay to Crenshaw schedule
	 Cost of Delay
	 Impacts to TIFIA?

7

Possible Option 3 (Westside Alternative)



Possible Option Westside: Primarily on Metro ROW (minimal takes)

Outstanding items still under review: Utility Conflicts, Track Alignment, Design Criteria Compliant, Safety Standards, Property Requirements, Yard Circulation, Cost, Schedule

