

LOS ANGELES COUNTY METROPOLITAN TRANSPORTATION AUTHORITY


REGIONAL TRANSIT ALTERNATIVES ANALYSIS

STUDY RESULTS

Presented by Booz-Allen & Hamilton Inc.

MTA


November 6, 1998



.,

Introduction

MILESTONES 1, 2 AND 3 ARE COMPLETE



-2-

HE 24574 4491 .L675 R738 NOV. 1 2 1998

Introduction

THE PURPOSE OF THIS BRIEFING IS TO PROVIDE TECHNICAL INFORMATION TO SUPPORT FUTURE BOARD DECISIONS REGARDING THE REGIONAL TRANSIT ALTERNATIVES ANALYSIS

- Study progress to date
- Financial outlook update
- A framework for policy decision making and recommendations of MTA management:
 - system investment priorities
 - allocations to non-transit programs
 - allocations to operate existing services at a reliable standard
 - related municipal operator allocations
 - addressing financial risk
 - countywide bus service expansion
 - process for future investment decisions
- Analysis of RTAA investment alternatives, including corridor specific alternatives, capital and operating cost, actions and schedule to implement, capacities, ridership and performance measures

THIS BRIEFING PROVIDES INFORMATION AND RECOMMENDATIONS – POLICY DECISIONS ARE NEEDED AND BOARD ACTION REQUESTED

Introduction

THE INCLUSIVE RTAA PROCESS HAS ENTAILED A NUMBER OF MEETINGS AND CONSULTATIONS WITH STAKEHOLDERS

1

NO. MTGS.	OUTREACH TO DATE	
4	Board Staff Meetings	
4	Ad Hoc Meetings of Elected Officials	
2	Community Outreach Meetings	
2	Citizen's Advisory Committee Meetings	
1	Transportation Business Advisory Council	
2	Bus Riders Union Meetings	
1	Local Transportation System Subcommittee	
1	Technical Advisory Committee	
2	Peer Reviews	
1	General Managers Meeting	
1	Meeting with California Transportation Commission representatives	

ADDITIONAL STAKEHOLDER MEETINGS ARE SCHEDULED

COMMITTED FUNDING FOR SUSPENDED PROJECTS (\$ millions)

	New Starts	CMAQ	STIP	Prop C	TOTAL
FY99 – FY04					
Eastside Mid-City Transit Capital	\$60	\$51 \$4	\$65 \$40 <u>\$46</u>		\$176 \$44 <u>\$46</u>
Subtotal	<u>\$60</u>	<u>\$55</u>	<u>\$151</u>		<u>\$266</u>
Pasadena Suspended Fund Unexpended Fun Pasadena Subtotal TOTAL, FY99-FY04		\$55	\$258 <u>\$22</u> <u>\$280</u> \$431	\$88 <u>\$1</u> <u>\$89</u> \$89	\$346 <u>\$23</u> <u>\$369</u> \$635
FY05 – FY10 Eastside and/or Mid-City	<u>\$360</u>				<u>\$360</u>
FY99 – FY10 TOTAL	\$420	\$55	\$431	\$89	\$995

Financial Update

THE STIP MUST BE AMENDED TO REPROGRAM FUNDS CURRENTLY COMMITTED FOR SUSPENDED PROJECTS

- Under the terms of the Memorandum of Understanding with the California Transportation Commission, the MTA must present a STIP amendment to the CTC by December 1, 1998

 or place at risk \$151 million in STIP funds associated with the Eastside, Mid-City, and new transit capital
- The Schiff Bill requires the MTA to transfer previously programmed capital funds to the new Pasadena Blue Line JPA, provide vehicles, and operate the resulting system

REVENUE UPDATE (\$ millions)

REVENUE SOURCE	FY99-FY04	<u>FY05-FY10</u>	<u>FY99-FY10</u>
Federal	\$3,115.5	\$3,194.7	\$6,310.2
State	\$3,369.3	\$2,581.6	\$5,950.9
Local	\$10,184.9	\$11,112.5	\$21,297.4
Farebox	<u>\$1,975.1</u>	<u>\$2,460.2</u>	<u>\$4,435.3</u>
UPDATED REVENUE ESTIMATE	\$18,644.8	\$19,349.0	\$37,993.8

Financial Update

REVENUE PROJECTIONS ARE BASED ON CRITICAL ASSUMPTIONS AND ACTUAL RESULTS COULD VARY SIGNIFICANTLY FROM PROJECTIONS

- Federal funds are assumed to continue and to increase:
 - MTA will receive annual federal appropriations from TEA-21 at 90% of authorized levels, equal to the expected national average authorization level
 - MTA will gain \$60 million every year through 2010 in federal discretionary New Starts funds, and the money will be provided in a timely manner
 - TEA-21 represents a new federal funding base allocations under the next federal transportation funding act will keep pace with the 1.4% average annual growth in the Highway Trust Fund
- State funds would also continue to increase:
 - State STIP funds will remain at the levels provided by the current STIP
 - Non-STIP State programs funded with gas tax sources (e.g., STA) will grow from current levels at the 1.4% rate in the Highway Trust Fund
 - Sales tax-funded State programs will also grow from current levels at the projected rate of change in the CPI -- approximately 42 percent from FY00 through FY10
- Economic forecasts for local funding sources (i.e., Prop A, Prop C and TDA) also assume continuous growth in both the current and future STIP periods – at 27% and 34% respectively
- Fare revenues include annual increases by the MTA Board of Directors to keep pace with inflation, as permitted by the Consent Decree

FY99-FY04 FUNDING COMMITMENTS DETAIL (\$ millions)

1		OPERATING					· · · · · · · · · · · · · · · · · · ·	
	BUS	HIGHWAY (1)	TRANSIT	BUS		HIGHWAY (1)	TRANSIT	TOTAL
COMMITTED PROJECTS - MTA								
Bus Operations	3,819.1							3,819.1
BSIP	53.7							53.7
Bus Purchases Baseline				465.5				465.5
Accelerated Bus Purchases				251.7				251.7
Other Bus Capital				533.5				533.5
Bus Operations Expansion (Consent Decree)	289.3							289.3
Fare Structure Costs	50.3							50.3
Red Line			403.4				791.8	1,195.2
Blue Line (Long Beach)			265.2					265.2
Blue Line (Pasadena)			66.0				48.3	114.3
Green Line			146.6				24.9	171.4
Other Rail Costs (2)							109.3	109.3
Red Line Segment 2 Station Enhancements						X	22.9	22.9
Rail Rehab. & Replacement							82.8	82.8
L.A. Rail Car Transit Capital (3)							82.5 32.3	82.5 32.3
Capital Reservation - Section 5309 Rail Mod.	·					8	40.5	40.5
Metrolink			167.3				50.4	217.7
Rail & Bus Debt Service	135.1		1,436.7				50.4	1,571.7
Hwy. Ops. (SHOPP, Safe, Incid. Management)		1,279.5						1,279.5
Hwy. Projects (Capital-Call For Projects)					1,927.7	2,125.4		2,125.4
Other Hwy. (Alameda Corr. & Local Agency projects)					1,143.1	1,255.0		1,255.0
Hwy. Debt Service		581.8						581.8
COMMITTED PROJECTS - REGIONAL								
Bus Operations, (Muni)	1,225.0							1,225.0
BSIP: Expansion/Service Improvement (Muni)	22.2							22.2
ADA/Paratransit	355.9							355.9
Bus Purchases Baseline (Muni)				432.8				432.8
Accelerated Bus Purchases	31.7			44.7				44.7
Muni Prop. C 5% Security Funds (Calderon Bill) TSE, Base Bus	61.5							31.7 61.5
Incentive Program/Service Expansion	61.6							61.6
Immediate Needs	34.0							34.0
Other Eligible Operators	45.0							45.0
TOTAL COMMITMENTS	6,184.6	1,861.4	2,485.1	1,728.3	3,070.8	3,380.4	1,285.7	16,925.5
TOTAL SUSPENDED RAIL PROJECTS								634.9
TOTAL COMMITMENTS + SUSPENDED RAIL								17,560.4
UNCOMMITTED FUNDS								1,084.4
TOTAL FUNDS								\$18,644.8

NOTES: (1) Highway dollars include funds that MTA passes through, not maintenance and construction costs which the MTA does not program

(2) Includes Long Beach Blue Line improvements, radio retrofit, MOW facility, Hollywood Blvd. construction mitigation

(3) Call for Projects funding for STIP TCI element

Financial Update

COST PROJECTIONS ARE ALSO ESTIMATED AND WILL CHANGE AS DECISIONS ARE MADE AND THE MTA CONTINUES TO OPERATE

- The projected \$144 million operating deficit in FY00-FY04 has not been resolved. It is assumed to be addressed through cost savings, not by accessing additional revenue
- Cost estimates assume that the MTA operates more effectively to contain costs to the expected rate of change in the CPI: 19.3% for FY99-FY04 and 18.9% for FY05-FY99. The following major cost drivers can impact this assumption:
 - Labor agreements
 - Fuel prices
 - Parts and materials
 - Health care benefits
 - Liability costs
- Operating costs assume no impact from new technologies and conversion to a CNG fleet
- Consent Decree costs include current interpretations of Consent Decree requirements. There is risk that these could change if new decisions are made by the Special Master
- Recent and projected ridership growth on ADA-mandated paratransit services provided by ASI indicate a potential shortfall of approximately \$15 million per year beginning in FY00
- Ridership growth is projected and considered in cost projections, but could change

Financial Update

BECAUSE REVENUES ARE PROJECTIONS, THERE IS AN INHERENT RISK THAT MTA WILL COMMIT TO DELIVERING MORE THAN FUNDING SUPPORTS – THERE ARE TWO COMMON APPROACHES TO REDUCING THESE RISKS

- Some transit operators establish a depreciation reserve, or sinking fund, which can be used to reduce revenue risk. Several policy considerations include:
 - Depreciation reserves may be limited to local fund investments in capital
 - Money in the sinking fund is unavailable for improvements today
 - Reserve balances may become targets of other agencies and interests
- A second approach is to establish clear priorities for funding, indicating the order of investments and specifying that delivery of the list will speed up or slow down in direct relationship to available revenues. Several benefits of this approach include:
 - All monies are fully leveraged
 - Delivery schedules focus on the order of projects
 - Continuous monitoring and communications manages risk effectively

MTA MANAGEMENT RECOMMENDS ESTABLISHMENT OF PRIORITIES CONVEYING THE ORDER OF PROJECTS/PROGRAMS TO BE DELIVERED

AVAILABLE FUNDS (\$ millions)

	FY99 - FY04	FY05 - FY10	FY99 - FY10
Revenue Available			
Federal	\$3,115.5	\$3,194.7	\$6,310.2
State	3,369.3	2,581.6	5,950.9
Local	10,184.9	11,112.5	21,297.4
Fare Revenues	1,975.1	2,460.2	4,435.3
Total Available	\$18,644.8	\$19,349.0	\$37,993.8
Commitments:	Ĩ.		
Suspended Projects	(\$266.1)	(\$360.0)	(\$626.1)
Pasadena Blue Line			
Capital (1)	(368.8)	0.0	(\$368.8)
Rail Cars	(45.0)	0.0	(\$45.0)
Operations	(64.2)	(217.8)	(\$282.0)
Accelerated Bus Procurement	(265.0)	0.0	(\$265.0)
Other Commitments	(16,551.3)	(15,211.7)	(31,763.0)
Total Committed (2)	(\$17,560.4)	(\$15,789.5)	(\$33,349.9)
NET AVAILABLE	\$1,084.4	\$3,559.5	\$4,643.9
Plus: SUSPENDED PROJECTS	\$266.1	\$360.0	\$626.1
TOTAL AVAILABLE	\$1,350.5	\$3,919.5	\$5,270.0

NOTES:

(1) A question has been raised as to the intent of the Schiff bill: Is the funding reserved for the Pasadena Blue Line or is the project expected to compete with other corridors in the RTAA

(2) Projected \$144 million deficit (FY00-FY04) is not included in committed funding

Financial Update

INCLUDING THE SUSPENDED PROJECTS, THE MTA IS EXPECTED TO HAVE APPROXIMATELY \$1.4 BILLION AVAILABLE BETWEEN FY99 AND FY04

- This estimate reflects recent changes to estimated revenues and commitments. It does not include funds to cover the \$144 million operating deficit projected over the FY00-FY03 timeframe, since it is assumed that the MTA will resolve the deficit through internal cost savings
- Another \$3.9 billion is expected to be available during the second planning period, yielding a total of \$5.2 billion through the 12-year timeframe of this study
- Note that these revenue estimates are based on numerous assumptions and there is significant risk that actual revenues may fall short of these amounts
- In addition to alternatives considered by the RTAA, several non-RTAA programs have a call on these funds

H²

Policy Decisions

THIS DOCUMENT PROVIDES RTAA AND MTA MANAGEMENT RECOMMENDATIONS REGARDING BOARD DECISIONS AND ACTIONS

- System investment priorities
- Non-transit program allocations
- Allocations to improve current bus system reliability and integration
- Related municipal operator allocations
- Managing financial risk
- Countywide bus service expansion
- Process for finalizing corridor investments

.

Policy Decisions

THE RTAA AND MTA MANAGEMENT RECOMMEND THE BOARD OF DIRECTORS ADOPT A CLEAR SET OF PRIORITIES FOR COUNTYWIDE TRANSIT INVESTMENT

- The first priority and call on funds is to operate and maintain the transportation infrastructure and network in place today
- The second priority for revenue allocation is to improve the current countywide transit system in terms of reliability and service connectivity from a passenger perspective
- Transit system expansion is the third priority, and would only occur after current operations and improvements to reliability and connectivity are adequately funded. The MTA Board of Directors may further wish to define priorities within the expansion category considering new services:
 - Countywide (e.g., rapid bus)
 - Eastside
 - Mid-City
 - San Fernando Valley

THESE PRIORITIES SHOULD GUIDE FUTURE ALLOCATION AND INVESTMENT DECISIONS

FUNDING FOR NON-RTAA PROJECTS (\$ millions)

	FY99-FY04	FY05-FY10	FY99-FY10
CALL FOR PROJECTS		2	
Constant Funding Approach	\$493.6	\$1,412.4	\$1,906.0
Revenue Growth Approach	\$558.7 (1)	\$2,012.3 (2)	\$2,571.0 (2)
i i		ž	
STORM DAMAGE PROGRAM	\$50.0 (1)	\$0.0	\$50.0 (1)
SOUNDWALL PROGRAM	\$34.8 (1)	\$76.4 (1)	\$111.2 (1)
FUNDING RANGE	\$578.4 -	\$1,488.8 -	\$2,067.2 -
-	\$643.5 (1)	\$2,088.7 (2)	\$2,732.2 (2)

NOTE:

(1) Recommended by RTAA and MTA Management

(2) To be addressed in the context of the Long Range Plan

Policy Decisions

THE TIP CALL FOR PROJECTS HAS HISTORICALLY BEEN FUNDED BY THE MTA; ADDITIONAL PROGRAMS MAY ALSO HAVE A CALL ON THE AVAILABLE FUNDING

- MTA has funded the call for projects at an average of \$235 million annually. Maintaining the same level of funding would require another \$494 million for FY02-FY04 and \$1.4 billion for FY05-FY10
- Another approach, recommended by MTA Management, to determine call funding is to examine revenue growth by fund source typically used in the call, which would require \$558.7 million for FY02-FY04:
 - Local funds (44% of the total) are assumed to grow 4.8% in FY03 and 5.0% per year thereafter
 - State funds (35% of the total) grow at the 1.4% rate of growth in the Highway Trust Fund
 - Federal funds (21% of the total) grow commensurate with CMAQ and RSTP funds under TEA-21, and at the Highway Trust Fund rate thereafter
- SB1477 would have provided \$79 million for El Nino storm damage rehabilitation in Los Angeles County. As a consequence of the governor's veto, MTA retains \$50 million under SB45. The veto message instructs MTA to work with the CTC and Caltrans to fund these needs. CTC guidelines are being developed – MTA management recommends funding at \$50 million over two years using a formula allocation approach
- The MTA Board of Directors has acknowledged that soundwalls are a regional transportation issue and has committed to seeking funding. With the veto of AB1686, the MTA should participate in funding May 1989 list retrofits using the call for projects process.
 Management recommends that MTA assume half of Caltrans' current cost estimates
 -- \$35 million in the current planning period and \$76 million in FY05-FY10. This does not include funding for more recent soundwall needs

Regional Transit Alternatives Analysis

MTA BUS SYSTEM IMPROVEMENTS TO RELIABILITY AND CONNECTIVITY (\$ millions)

ESTIMATED	COMMITTED	ADD'L. FUNDING
COST	FUNDING	REQUIRED
\$500.0	\$500.0	\$00
\$592.3	\$592.3	\$0.0
<u>225.0</u>	<u>225.0</u>	0.0
\$817.3	\$817.3	\$0.0
\$75.8	\$37.0	\$38.8
50.0	35.0	15.0
<u>27.8</u>	<u>0.0</u>	<u>27.8</u>
\$970.9	\$889.3	\$81.6
	<u>COST</u> \$592.3 <u>225.0</u> \$817.3 \$75.8 50.0 <u>27.8</u>	COST FUNDING \$592.3 \$592.3 225.0 225.0 \$817.3 \$817.3 \$75.8 \$37.0 50.0 35.0 27.8 0.0

NOTES:

(1) Includes 2,095 CNG buses and fueling facilities, spare parts, applicable sales taxes, shipping and delivery charges, remote outside cameras, fire suppression, headsigns, air conditioning, maintenance diagnostic hardware and software, force account, computer hardware upgrade required to support smart system components; also includes global positioning systems (GPS), automated voice enunciators for 1,657 buses and automated passenger counters for 25% of the fleet

1.

- (2) Assumes 2,599 buses, including 161 expansion buses for the Consent Decree, unless otherwise noted
- (3) Includes GPS retrofits required on 941 buses; assumes 2/3 of fleet is outfitted with passenger counters

Policy Decisions

MTA HAS ALREADY COMMITTED SOME FUNDS TO IMPROVING RELIABILITY AND CONNECTIVITY OF THE CURRENT COUNTYWIDE TRANSIT SYSTEM IN FY99-FY04

- The Board-approved Accelerated Bus Procurement will reduce fleet age and improve the reliability of the buses in service
- Some technology improvements are already funded additional needs are identified that will enhance the MTA's ability to operate the bus system at a reliable standard:
 - Universal Fare System (UFS): \$37 million are currently committed to replace existing cash fareboxes. Another \$38.8 million would permit the addition of the farecard technology that would permit seamless, coordinated inter-modal and inter-agency travel in L.A. County and faster boarding times
 - Radio System: \$35 million are currently committed to replace the existing radio system. An additional \$15 million are required to replace and upgrade the entire radio system and for the central control facility
 - GPS and APC Retrofits: The Global Positioning System enables real-time dispatching in response to actual events. In conjunction with the GPS, the APC system will enable improved response to actual conditions, as well as improved ridership data for planning. Approximately \$27.8 million are needed to retrofit GPS on 941 buses and to provide passenger counters on two-thirds of the fleet

THE RTAA AND MTA MANAGEMENT RECOMMEND AN ADDITIONAL \$81.6 MILLION BE ALLOCATED IN FY99-FY04 TO TECHNOLOGY WHICH IMPROVES ON-STREET OPERATIONS

FY99-FY04 COUNTY-WIDE RELIABILITY AND CONNECTIVITY PROJECTS (\$ millions)

.

4	ESTIMATED <u>COST</u>	COMMITTED <u>FUNDING</u>	ADD'L. FUNDING <u>REQUIRED</u>
FUNDING TO IMPROVE RELIABILITY	\$40.0	\$40.0	\$0.0
FUNDING RELATED TO UNIVERSAL FARE SYSTEM	\$17.5	\$0.0	\$17.5
FUNDING TO IMPROVE RELIABILITY/ INTEGRATION	<u>\$14.0</u>	<u>\$0.0</u>	<u>\$14.0</u>
TOTAL COUNTY-WIDE TRANSIT ALLOCATION	\$71.5	\$40.0	\$31.5

=__

Policy Decisions

MTA HAS COMMITTED \$40 MILLION TO MUNICIPAL OPERATORS – ADDITIONAL ALLOCATIONS ARE WARRANTED

- The \$40 million currently committed are intended to improve operations and reliability of the current countywide bus transit system. These funds were committed at the time funding was provided for the Accelerated Bus Procurement
- An additional \$31.5 million could fund improvements that would further integrate the county-wide transit system:
 - \$17.5 million is needed to extend the Universal Fare System to the municipal operators, ASI, and Metrolink
 - In addition, \$14 million should be added to provide funding to municipal operators to further improve transit integration in the County related to a municipal operators' share from other MTA bus technology
- The RTAA and MTA management recommend a process for allocating these funds be developed in consultation with municipal operators. The current intent would be to provide municipal operators significant flexibility in using these discretionary funds to meet regional objectives of high bus service reliability and improved countywide connectivity. Operators would need to demonstrate that proposed uses meet these countywide objectives
- Another option is to restrict the use of Universal Fare System funds to UFS implementation

THE RTAA AND MTA MANAGEMENT RECOMMEND AN ADDITIONAL \$31.5 MILLION BE ALLOCATED TO MUNICIPAL OPERATORS FOR PROJECTS TO IMPROVE RELIABILITY AND CONNECTIVITY

AVAILABLE FUNDS (\$ millions)

· · ·	FY99 - FY04	FY05 - FY10	FY99 - FY10
NET AVAILABLE	\$1,084.4	\$3,559.5	\$4,643.9
RECOMMENDATIONS:			
Non-Transit Projects			
Call for Projects	(\$558.7)	(\$2,012.3)	(\$2,571.0)
Storm Damage Rehabilitation	(\$50.0)	\$0.0	(\$50.0)
Soundwall Rehabilitation	(\$34.8)	(\$76.4)	(\$111.2)
Subtotal - Non-Transit	(\$643.5)	(\$2,088.7)	(\$2,732.2)
Reliability and Connectivity Projects			
MTA Universal Fare System	(\$38.8)	\$0.0	(\$38.8)
MTA Bus Technology	(\$42.8)	\$0.0	(\$42.8)
Subtotal - Reliability and Connectivity	(\$81.6)	\$0.0	(\$81.6)
Municipal Operator Call for Projects	(\$31.5)	\$0.0	(\$31.5)
TOTAL RECOMMENDATIONS	(\$756.6)	(\$2,088.7)	(\$2,845.3)
AVAILABLE FOR SYSTEM EXPANSION	\$327.8	\$1,470.8	\$1,798.6
Plus: SUSPENDED PROJECTS	\$266.1	\$360.0	\$626.1
TOTAL AVAILABLE	\$593.9	\$1,830.8	\$2,424.7

NOTE: This table begins with the "Net Available" funding shown on the facer to page 8

Policy Decisions

RTAA AND MTA MANAGEMENT RECOMMEND THAT THE MTA BOARD COMMIT AN ADDITIONAL \$757 MILLION, AS NOTED ABOVE, IN FY99-FY04

- \$643.5 million would be committed to non-RTAA projects, including:
 - \$558.7 million for the Call for Projects
 - \$50.0 million for storm damage rehabilitation
 - \$34.8 million for soundwall rehabilitation
- \$81.6 million would be programmed for MTA reliability and connectivity projects, including:
 - \$38.8 million for the Universal Fare System
 - \$42.8 million for other bus technology projects
- \$31.5 million would fund a county-wide municipal operator call for projects

INCLUDING SUSPENDED PROJECTS FUNDING, \$594 MILLION COULD REMAIN AVAILABLE TO SUPPORT SYSTEM EXPANSION

Considerations for Transit System Expansion

A NUMBER OF FACTORS MAKE FULL IMPLEMENTATION OF ADDITIONAL FIXED GUIDEWAY PROJECTS UNLIKELY DURING THE FY 2004 STIP PERIOD

- The current MTA fixed guideway implementation commitments include expansion of the Red Line to Universal City, capacity expansion of the Long Beach Blue Line (e.g., platform extensions and vehicles) and allocation of additional capital funds to MetroLink. These fixed guideway projects are fully funded and will be completed in the FY04 period
- The transfer of funds to the Pasadena Blue Line Joint Powers Authority (JPA) comes with the expectation that the JPA will develop a fully funded project and implement an additional fixed guideway facility during the FY04 period
- The only additional project that is ready to move to construction in the near term is the Red Line extension to First/Lorena (a supplemental EIS may be required), but funding is not available for its construction
- Given the passage of Proposition A, federal and state funding would be needed to support construction of the suspended subway project using matching state funds. Federal new starts monies are fully committed to the North Hollywood Red Line Extension through FY 2003
- Use of federal monies requires a full funding grant agreement; state monies need also be assigned to fully funded projects. Given the degree of uncertainty in funding beyond FY04, it will be easier to gain such agreements as we get closer to fund availability and reduce uncertainties

ESTIMATED TIME TO CONSTRUCTION


CORRIDOR	ESTIMATED DURATION OF PLANNING AND ENVIRONMENTAL PROCESS
Eastside (Excluding Suspended Project)	32 to 62 Months
Mid Cities/Westside	35 to 62 Months
San Fernando Valley	38 Months

Considerations for System Expansion

ALL OTHER FIXED GUIDEWAY EXPANSION ALTERNATIVES REQUIRE SIGNIFICANT ADDITIONAL PLANNING AND ENVIRONMENTAL WORK TO DEVELOP THE FINAL PROJECT

- On the Eastside, if any fixed guideway project other than the suspended subway alignment, or modifications thereof, is pursued, significant planning and environmental work is required to fully define the alternative, involve the public and comply with funding and legal mandates
- In the mid-cities the planning work on the suspended corridor is not yet complete. In addition, a federal prohibition to deep bore tunnelling west of Crenshaw represents another hurdle. Alternative alignments and modes (e.g., exposition right of way) require substantial planning, community involvement and environmental work to define a fixed guideway project for implementation
- The San Fernando Valley fixed guideway system is still fairly early in the planning process. The administrative environmental document recently completed identifies alternatives for the Burbank/Chandler corridor, but has not completed analysis or public processes required before selecting a locally preferred alternative
- The time required for the planning and environmental process associated with implementing these fixed guideway alternatives is approximately 3 years or more
- It would be precipitous to decide on an alternative and funding commitments without the benefit of knowing the locally preferred alternative and project requirements – all to be determined through the structured planning process

PLANNING AND ENVIRONMENTAL TIMELINE



124-100.00

Task

Progress

Milestone

Summary

Reaching Project Implementation

THE PLANNING PROCESS FOR FEDERAL ENVIRONMENTAL CLEARANCE NECESSARY TO SECURE FEDERAL FUNDING REQUIRES A NUMBER OF STEPS

- The process to arrive at project implementation follows four sequential phases Alternatives Analysis, Draft EIS, Final EIS and the development of the Record of Decision (ROD). The entire process typically requires at least 46 months
- An Alternatives Analysis examines a broad corridor and its transportation needs and narrows the number of options to carry through environmental analysis through a detailed evaluation. A typical alternatives analysis requires 21 months of analysis and includes close coordination with affected government and community groups in identifying and evaluating alternatives
- The Draft Environmental Impact Statement measures the environmental performance of the short list of alternatives. The Federal Transit Administration (FTA), the public, and the Board review the process and note issues to resolve. The Draft EIS typically requires 9 months to prepare. The review process adds a minimum of another 6 months
- The Final Environmental Impact Statement addresses comments generated during review of the Draft EIS and suggests methods to mitigate environmental impacts. The development of the Final EIS requires 4 months
- Preliminary engineering activities often occur concurrent with the development of the Draft and Final EIS. The design level is generally about 30% by the adoption of the Final EIS

.

·

Reaching Project Implementation

THE PLANNING PROCESS FOR FEDERAL ENVIRONMENTAL CLEARANCE NECESSARY TO SECURE FEDERAL FUNDING REQUIRES A NUMBER OF STEPS (CONTINUED)

- A Record of Decision (ROD) can be obtained 6 months after all environmental clearances have been obtained. After the ROD, financial plans and final designs can be developed and then construction can proceed
- If the project does not involve federal funds the process can be shortened by 3 to 9 months

IT IS IMPORTANT THAT THE PLANNING PROCESS FOR ANY PROJECT FOLLOW THE FUNDING CASH FLOWS SO AS NOT TO JEOPARDIZE THE SHELF LIFE OF ANY OF THESE DOCUMENTS

ALTERNATIVES	CONSIDERATIONS
Bus Transitway	Funding
Light Rail	Implementation Time Frame
Heavy Rail	Capital Costs
	Operating Costs
	Performance Measures
At-Grade	Regional Benefit
Elevated	Corridor Benefit Serve Transit
Subway	Dependent
	Capacity
	Ridership

-

.

Considerations for System Expansion

THE MTA SHOULD CONTINUE PLANNING, ENVIRONMENTAL AND COMMUNITY WORK IN ALL THREE CORRIDORS – FEDERAL FUNDING IS AVAILABLE AND COMMITTED TO THE EASTSIDE AND MID-CITIES PLANNING EFFORTS

- The RTAA examined a wide range of alternative fixed guideway alternatives within each suspended corridor, and planning efforts can take advantage of this work
- Additional alternatives are possible, and should also be considered in the corridor planning process
- Different modal choices were identified within the RTAA for both regionwide and corridor specific alternatives:
 - Rapid Bus
 - Bus Transitways
 - Light Rail
 - Heavy Rail
 - Alternative transit technologies (e.g., DMU's)
- In the context of each of these modal choices a number of alignment alternatives were considered for each of the corridor options:
 - At-grade running in dedicated right-of-way
 - At-grade running in mixed flow traffic
 - Elevated
 - Subway

, . -

Fixed Guideway Alternatives

THE APPENDIX CONTAINS DETAILED INFORMATION AND ANALYSIS WHICH CAN SUPPORT THE NEXT STEPS IN CORRIDOR PLANNING

- Detailed summaries of the alternatives carried forward into final evaluation for the Eastside, Westside and San Fernando Valley corridors:
 - Alignment descriptions and characteristics
 - Strengths and weaknesses of each alternative
 - Implementation schedule
 - Performance characteristics and costs
- A description of the process and measurements used to evaluate each alternative, along with a summary of the data used to calculate each performance goal:
 - Description of process used
 - Definition of the performance measures used
 - Evaluation of alternatives in the context of the performance measures
 - Summary of the performance goal evaluation
 - Detailed support data for the performance measures
- A summary of the capital costs and operating costs using both historical MTA costs and experience of other U.S. transit agencies:
 - Discussion of the costing methodology and alternative approache s
 - Summary of the capital and operating costs by alternative
 - Detailed cost back up

Recommendation

THE RAPID BUS ALTERNATIVE IS A FAVORABLE NEAR TERM OPTION BASED ON A LARGE NUMBER OF FACTORS AND INFLUENCES

- MTA Board of Directors, management, employees and community groups want improvements to bus service for greater quality, reliability and speed
- The City of Los Angeles is completing a study to increase bus speeds in city traffic and have indicated they are willing to participate in upgrades to the signal systems and bus stops
- The MOU with the CTC calls for immediate short term improvements to communities with suspended or deferred projects in addition to longer term infrastructure improvements
- The Consent Decree mandates that the MTA develop a five-year plan for new bus services
- Rapid bus provides a means to improve transit service in heavily used corridors within a short time frame

RAPID BUS IS THE ONLY INVESTMENT THAT CAN BE UP AND RUNNING BY FY2000

•••


Policy Decisions

THE RTAA AND MTA MANAGEMENT RECOMMEND COUNTYWIDE BUS SYSTEM ENHANCEMENTS AS THE FIRST EXPANSION PRIORITY

- MTA should implement countywide rapid bus network intended to provide high quality, high speed service through a combination of limited stop service and signal priority
- Rapid bus includes: vehicles with a different look from other buses in the fleet (e.g., gold standard); vehicles with additional technology components (e.g., signal preemption); diamond lane operation during peak hours; joint use transit centers at key locations
- Criteria for selection of priority rapid bus routes should include:
 - Transit dependent corridors
 - Major high speed transit connections
 - Priority community service due to suspended or deferred rail projects
- Implementation is possible in the very near term:
 - Initiate 3 demonstration lines over the next 12 months and monitor their performance through FY2001
 - Expand reasonable countywide network in accordance with a long range plan
 - Could serve to focus ridership on potential future fixed guideway corridors

THE EXACT ROUTE STRUCTURE OF AN EXPANDED RAPID BUS NETWORK CAN BE DETERMINED THROUGH A MORE THOROUGH AND INCLUSIVE PLANNING PROCESS

POTENTIAL **EXPANDED RAPID BUS NETWORK**



Rapid Bus

A COUNTYWIDE RAPID BUS ALTERNATIVE IS BEING CONSIDERED TO ENHANCE REGIONAL BUS SERVICE. THE FEATURES OF THIS ALTERNATIVE INCLUDE LIMITED STOP, SIGNAL PRIORITIZATION AND PEAK HOUR DEDICATED LANES WHERE AVAILABLE

• A potential rapid bus network could include the following routes...

	Rapid Bus	Limits	No. Buses	Stops	New Transit Centers
1.	Garvey Ave.	El Monte Busway – LACBD	13	16	
2.	Chavez / Venice	Monterey Park – Santa Monica	30	48	1
3.	Atlantic Blvd.	Pasadena – Artesia Blue Line Station	16	19	
4.	Colorado Blvd.	Pasadena – Hollywood	15	26	
5.	Whittier / Wilshire	City of Commerce – Santa Monica	43	47	1
6.	Florence Blvd.	Los Angeles International Airport – Whittier	16	31	1
7.	Long Beach Blvd.	LACBD – Long Beach	20	38	
8.	San Fernando Rd.	LACBD – Sylmar Transit Center	15	30	
9.	Van Nuys Blvd.	Sylmar Transit Center – Westwood/UCLA	14	19	1
10.	Roscoe Blvd.	Red Line North Hollywood Station – Warner Center	12	15	E.
11.	Ventura Blvd.	Red Line Universal City Station – Warner Center Branch Line to Cal State Northridge Via Reseda Blvd.	14	19	1
12.	Santa Monica Blvd.	LACBD – Santa Monica	27	31	1
13.	Western Ave.	Hollywood - Green Line Imperial/Wilmington Station	14	20	
14.	Vermont Ave.	Hollywood – Green Line Vermont Ave. Station	19	17	
15.	Crenshaw Blvd.	Hollywood – South Bay Galleria Transit Center	10	33	
16.	Hawthorne Blvd.	LACBD – South Bay Galleria Transit Center	14	26	

. · · · · ·

. .

. . .

.

.

Rapid Bus

THE RAPID BUS SERVICE IMPLEMENTATION INCLUDES A NUMBER OF UNIQUE FEATURES

- Approximately 300 buses could be used as part of the ultimate regional program. This includes a service expansion of approximately 200 buses with the remainder of the service coming from the conversion of local service along these corridors to Rapid Bus
- The initiation of this service can be done through a number of demonstration projects:
 - Service within the corridors with suspended or deferr ed projects
 - Transit Dependent Corridors
- The buses used for this service should have a different color scheme and look to differentiate them from the current service offerings (e.g., gold, low floor buses)
- This program is being initiated throughout the region and should be implemented by MTA and the Municipal operators in cooperation with cities and the county
- Discussions with the City of Los Angeles Department of Transportation have indicated that the City will implement the signal priority/synchronization and bus stop enhancement components of this service within the City of Los Angeles jurisdiction. Other cities might also be interested
- Six transit centers could be constructed to enhance the system:
 - Utilize right-of-way previously acquired by the MTA
 - Will not preclude construction of rail stations in the future
 - Maximize commercial and joint development opportunities

.


Rapid Bus

THE COUNTYWIDE RAPID BUS EXPANSION HAS THE FOLLOWING STRENGTHS AND WEAKNESSES

 STRENGTHS Offers regional mobility solution Two thirds of the rapid bus corridors serve transit dependant populations and destinations Can be quickly implemented Relatively low cost Serves high demand corridors Transit centers improve modal connectivity and puts right-of-way purchased in suspended rail corridors to productive use Serves to focus transit demands to support future fixed guideway systems Applicable to all county operators Readily recognizable as a different service offering 	 WEAKNESSES Providing dedicated Peak Hour Lanes reduces the number of travel lanes and leads to increased congestion Not having dedicated right-of-way slows operations relative to an exclusive facility Bus service may not provide as significant economic redevelopment opportunities as rail lines Some elements of the community indicate strong support for rail projects
---	---

THE DEMONSTRATION PROGRAM WILL BE DESIGNED TO MAXIMIZE SYSTEM PERFORMANCE AND DEMONSTRATE DIFFERENT APPROACHES

EXPANDED RAPID BUS NETWORK



The use of buses acquired as part of the accelerated procurement program allows the first phase to be implemented within 12 months.

Rapid Bus

THE IMPLEMENTATION OF THE COUNTYWIDE RAPID BUS SYSTEM CAN FOLLOW A PHASED PROCESS THROUGH FY 2005

- Determine Priority Corridors for demonstration projects (e.g., Suspended / Deferred Project Corridors, Transit Dependent)
- Coordinate Priority Signal Program with City of Los Angeles Department of Transportation
- Design Corridor Facilities
- Procure Buses
- Construct Facilities
- Implement Service
- Monitor Program Performance

Rapid Bus...Demonstration Corridors

INITIATING THREE DEMONSTRATION CORRIDORS ALLOWS FOR THE SHORTEST TERM IMPLEMENTATION PERIOD AND PROVIDES A PROCESS TO EVALUATE THE RAPID BUS PROGRAM AND TECHNOLOGY ALTERNATIVES

- The demonstration corridor should be selected based on three important criteria:
 - Serve corridors with suspended or deferred projects
 - Serve transit dependent areas
 - Provide the greatest regional connectivity
- These demonstration projects should include different technological approaches to ascertain through system performance the most cost effective approach:
 - Signal synchronization versus signal priority
 - Low floor vehicles versus standard buses
 - Mixed flow lanes versus peak hour dedicated lanes
- The performance of the rapid bus demonstration system should be evaluated regularly and the best approach selected prior to implementation of Phase II
- Once Phase II service is implemented and following completion of the 30 month demonstration project, the demonstration lines will be rolled into the Phase II service plan

IN THE NEAR FUTURE, MANAGEMENT WILL RECOMMEND TO THE BOARD THE THREE LINES SCHEDULED FOR RAPID BUS IMPLEMENTATION, IN CONSULTATION WITH OTHER STAKEHOLDERS

IMPLEMENTATION COSTS

		FY04		F۱	/10	TOTAL	
		Cap. Costs Ops. Costs		Cap. Costs Ops. Costs		Cap. Costs	Ops. Costs
	Phase	(\$M)	(\$M)	(\$M)	(\$M)	(\$M)	(\$M)
1	(Demonstration)	36.3	24.6	0	0	36.3	24.6
П		111.5	94.7	0	308.2	111.5	226.0
Ш		0	0	118.9	170.6	118.9	170.6
	Total	147.8	119.3	118.9	478.8	266.7	598.1
	Aggregate Total	26	7.1	59	7.7	864	4.8

Rapid Bus

PRELIMINARY EVALUATION OF THE COUNTYWIDE RAPID BUS ALTERNATIVES HAS YIELDED THE FOLLOWING INFORMATION

No. Buses	No. Stops	No. Transit Facilities	Headways (Min.)	Route Miles	Daily Ridership	Peak Hour Capacity	Ultimate Peak Hour Capacity	Capital Cost(\$M)	Annual Operating Cost(\$M)
200	435	6	Varies	340	126,570	N/A	N/A	221.4	60.0

- The implementation of this program is assumed to follow a three phased approach; Phase 1 is anticipated to operate midway through FY2000 through FY2001, Phase 2 operates midway through FY2003 and Phase 3 operates midway through FY2005
- Under this implementation scheme and inflating the capital and operating costs which are in 1998 dollars results in additional commitments through the 2010 planning horizon:
 - \$147.8 million in capital and \$119.3 million in operating costs through FY2004
 - \$118.9 million in capital and \$478.8 million in operating costs from FY05 to FY10
- These commitments could be applied to the total available dollars summarized on page 14F

AVAILABLE	FY99 – FY04 (\$ millions)	FY05 – FY10 (\$ millions)	FY99 – FY10 (\$ millions)
TOTAL AVAILABLE	\$ 593.9	\$1830.8	\$2424.7
LESS RAPID BUS COSTS	\$ 267.1	\$ 597.7	\$ 864.8
NET REMAINING	\$ 326.8	\$1233.1	\$1559.9

MTA MANAGEMENT RECOMMENDS THE INITIATION OF THE RAPID BUS PROGRAM AT A COST OF \$267.1 MILLION THROUGH FY04 AND \$597.7 MILLION THROUGH FY10

FUNDS TO BE REPLACED (\$ millions)

TAL ABAOUNT TO

PREVIOUS FUNDING SOURCES

	New Starts	CMAQ	<u>STIP</u>	BE REPLENISHED
Eastside Mid-City	\$60	\$51 \$4	\$65 \$40	\$176 \$44
TOTAL				\$220

Policy Decisions

FUNDS REPROGRAMMED FROM THE SUSPENDED CORRIDORS SHOULD BE REPLENISHED AS FUNDS BECOME AVAILABLE IN THE FY04 PLANNING PERIOD

- Of the funds to be reprogrammed in the STIP amendment, \$220 million are associated with projects that were suspended (i.e., Eastside and Mid-Cities). Note that an additional \$46 million of suspended monies was committed to transit capital projects which are undefined
- The RTAA and MTA Management recommend that these funds be replaced by reserving \$220 million of the available funds remaining in the FY04 period to fixed guideway uses in these corridors
- The exact use of the funds toward a project need not be decided at this time. The corridor planning process recommended by the RTAA will result in identification of a locally preferred option in each corridor, including full funding requirements, before money is available to be expended on these fixed guideway investments
- After the planning process is complete, and the future funding picture becomes clearer, the MTA Board of Directors should act to fully fund recommended fixed guideway investments as allowed by financial resource availability
- Of the \$326 million remaining after funding the rapid bus program, reserving \$220 million for fixed guideway projects to be defined for the Eastside and Mid-City corridors would leave a balance of \$106 million uncommitted and available
- MTA is not required to commit the remaining \$106 million in projected funds given risk in projections and the need to have flexibility to meet planning study recommendations, the RTAA recommends the MTA not commit these residual monies at this time

	FY99 - FY04	FY05 - FY10	FY99 - FY10
NET AVAILABLE	\$1,084.4	\$3,559.5	\$4,643.9
RECOMMENDATIONS:			
Non-Transit Projects			
Call for Projects	(\$558.7)	(\$2,012.3)	(\$2,571.0)
Storm Damage Rehabilitation	(\$50.0)	\$0.0	(\$50.0)
Soundwall Rehabilitation	(\$34.8)	(\$76.4)	(\$111.2)
Subtotal - Non-Transit	(\$643.5)	(\$2,088.7)	(\$2,732.2)
Reliability and Connectivity Projects			
MTA Universal Fare System	(\$38.8)	\$0.0	(\$38.8)
MTA Bus Technology	(\$42.8)	\$0.0	(\$42.8)
Subtotal - Reliability and Connectivity	(\$81.6)	\$0.0	(\$81.6)
Municipal Operator Call for Projects	(\$31.5)	\$0.0	(\$31.5)
TOTAL RECOMMENDATIONS	(\$756.6)	(\$2,088.7)	(\$2,845.3)
AVAILABLE FOR SYSTEM EXPANSION	\$327.8	\$1,470.8	\$1,798.6
Plus: SUSPENDED PROJECTS	\$266.1	\$360.0	\$626.1
TOTAL AVAILABLE	\$593.9	\$1,830.8	\$2,424.7
Less: Rapid Bus Demonstration	(\$60.9)	\$0.0	(\$60.9)
Less: Rapid Bus Phase II & III	(\$206.2)	(\$597.7)	(\$803.9)
Less: Eastside/Mid-City Reserve	(\$220.0)	\$0.0	(\$220.0)
NET AVAILABLE	\$106.8	\$1,233.1	\$1,339.9

.

Color of Money

THE FINAL "COLOR OF MONEY" WILL BE DONE AFTER THE BOARD OF DIRECTORS MAKES DECISIONS AT THIS MEETING

- RTAA and MTA Management recommendations could be implemented within the available funding
- Available CMAQ funds could be used to operate rapid bus for the first three years sufficient uncommitted funds are available for this purpose
- If anything unexpected should occur, it is possible to "swap" uncommitted funds for sources that are currently committed, to make eligible funding available
- Booz-Allen believes, with a high degree of confidence, that MTA can accomplish management's recommendations with the available funds

		<u>(\$ millions)</u>
	Call for Projects	\$558.7
-	Storm Damage Program	\$50.0
-	Soundwall Program	\$34.8
-	MTA Bus Technology	\$81.6
-	Municipal Operators	\$31.5
	Rapid Bus	\$267.1

 Prop A, which passed on November 3, 1998, disallows use of local sales tax monies for subway planning, design, engineering, or construction

PROPOSED DECISION PROCESS -- FY04 INVESTMENT DECISIONS

TOPIC	IMMEDIATE POLICY	FUTURE POLICY	INPUT PROCESS
	DECISIONS	DECISIONS	
1. System priorities	Maintain, improve reliability	Individual corridor priorities	Corridor planning process
	and connectivity, expand		
2. TIP Call for Projects	Funding mark	Specific projects to be	Call and call evaluation
funding	(recommendation: growth	funded	results
	share \$558.7M)		
3. Storm damage funding	Funding mark	Funding allocation	Consult with cities, county
	(recommendation: revenue	formula/process	and Caltrans
	retained \$50M)		
4. Soundwall funding	Funding mark	Project selection process	Consult with legislative
	(recommendation: \$34.8M)	and specific projects	representatives,
			communities, cities, county
			and Caltrans
5. Universal Fare System	Funding commitment	Implementation schedule,	Internal review, consult with
(UFS)	(recommendation: \$38.8M)	contract award	Muni operators
6. Radio system (GPS)	Funding commitment	Implementation schedule,	Internal review
	(recommendation: \$15.0M)	contract award	
7. GPS and APC	Funding commitment	Implementation schedule,	Internal review
	(recommendation: \$27.8M)	contract award	

THE MTA BOARD OF DIRECTORS HAS A NUMBER OF IMMEDIATE AND FUTURE POLICY DECISIONS WHICH WILL DETERMINE INVESTMENTS OVER THE FY99 TO FY04 PERIOD

ΤΟΡΙϹ	IMMEDIATE POLICY DECISIONS	FUTURE POLICY DECISIONS	INPUT PROCESS
 Muni allocation – Universal Fare System 	Funding mark (recommendation: \$17.5M)	Allocation process	Consult with Muni operators, ASI and Metrolink
 Muni allocation – reliability and connectivity 	Funding mark (recommendation: \$14M)	Allocation, reporting and review process	Consult with Muni operators
10.Fixed guideway planning	Funding commitment of \$8M to Eastside and mid-cities, \$0.3M to Eastside transit center	Corridor project selection, schedule for implementation, contract awards	Commence inclusive planning process
11.Rapid bus demonstration	Funding commitment of \$60.9M	Route selection, transit center location, final design, contract awards	Consult with cities, Muni operators, communities, BRU, CAC
12.Rapid bus expansion	Funding commitment of \$803.9M (capital and operating)	Route selection, transit center locations, final design, contract awards, schedule	Consult with riders, cities, Muni operators, communities, BRU and CAC
13.Fixed guideway expansion planning countywide	Begin countywide system planning process (20 year plan)	Systemwide fixed guideway 20 year plan and priorities	Planning process and financial results
14.Replace funds for suspended projects	Statement of intent to replace funds with future revenues	Fully-funded projects and additional funds required	Corridor planning process

w7 .

Next Steps

IN ORDER TO SUBMIT THE STIP AMENDMENT TO THE CTC BY DECEMBER 1, 1998, CRITICAL STEPS MUST BE COMPLETED OVER THE NEXT 2 WEEKS

- The MTA board must make the decisions summarized on the previous page
- Instruct staff to modify the STIP
- Review and adopt the STIP amendment
- MTA management must present the STIP amendment to the CTC on December 1

.

DRAFT

RTAA STUDY RESULTS APPENDICES

,

APPENDIX 1 FUNDING

INTENTIONALLY LEFT BLANK

.

REVENUE UPDATE

(\$ millions)

	FY99-FY04	FY05-FY10	FY99-FY10
ESTIMATED REVENUES, MILESTONE 1	\$18,454.3	\$19,199.0	\$37,653.3
Adjustments: – Unexpended Pasadena Blue Line funds – Additional New Starts funding – Revised STIP fund estimate	\$22.6 \$8.3 \$152.1	\$150.0	\$22.6 \$8.3
 Audit adjustment to financial model 	\$7.5	\$150.0	\$302.1 \$7.5
UPDATED REVENUE ESTIMATE	\$18,644.8	\$19,349.0	\$37,993.8

THROUGHOUT THE RTAA PROCESS, REVENUE PROJECTIONS HAVE BEEN REVISED AND UPDATED AS ADDITIONAL INFORMATION BECAME AVAILABLE

- The Milestone 1 "best estimate" of \$18,454.3 million is based on assumptions of continuing economic growth, as reiterated on page six of this document
- Four adjustments have been made to the Milestone 1 revenue estimates:
 - Less has been expended on the Pasadena Blue Line than originally estimated, thereby increasing available revenue by \$22.6 million. However, all of these funds are committed by the Schiff Bill to the JPA
 - The recent Federal appropriation provides \$8.3 million more in New Starts funds than previously anticipated. Of this amount, \$8 million are committed to Red Line planning for East Side and Mid-Cities; \$0.3 million is available for an East Side Transit Center
 - Caltrans recently revised the STIP fund estimate, increasing the amount available to Los Angeles County by \$152.1 million
 - The recent audit of the MTA's financial model identified \$7.5 million that had been committed twice, making that much more available for programming
- As a result of these adjustments, revenue projections for the FY99-FY04 planning horizon total \$18,644.8 million

COMMITMENTS UPDATE (\$ millions)

F	FY99-FY04	FY05-FY10	FY99-FY10
ESTIMATED COMMITMENTS, MILESTONE 1	\$17,135.1	\$16,738.4	\$33,873.5
Adjustments: — Commitments overstated in Milestone 1	(\$2.1)	(\$1,256.7)	(\$1,258.8)
 Pasadena Blue Line rail cars 	45.0	(+ ,, ,, _ , , , , , , , , , , , , , ,	45.0
 Pasadena Blue Line operating costs 	64.2	217.8	282.0
 Accelerated Bus Procurement 	265.0	9	265.0
 Revised STIP funding estimate 	(24.0)		(24.0)
 Model adjustments (Red Line/Blue Line) 	(22.5)		(22.5)
 ASI expansion 	75.0	90.0	165.0
 Additional New Starts funding 	8.3		8.3
 TSM backfill 	9.0		9.0
 Audit adjustment to financial model 	7.4		7.4
UPDATED COMMITMENT ESTIMATE	\$17,560.4	\$15,789.5	\$33,349.9

F

1

COSTS HAVE ALSO BEEN UPDATED TO INCORPORATE MORE CURRENT INFORMATION

- Commitments were overstated in the Milestone 1 report, primarily for the FY05-FY10 period. The Milestone 1 report noted this discrepancy and attributed it to the difficulty of following provisions in the MTA's financial model for financing debt
- The cost of 18 additional rail cars needed for the Pasadena Blue Line is estimated to be \$45 million
- Operating costs for the Pasadena Blue Line are added and assume that service would begin in July 2002
- The Accelerated Bus Procurement was adopted by the Board and funded at \$265 million
- Funds previously identified as committed in anticipation of the Caltrans STIP funds revision are now treated as uncommitted, reducing commitments by \$24 million
- An adjustment to the financial model was necessary to reduce an overstated commitment to the Red Line by \$22.5 million
- Recent and projected ridership growth on ADA-mandated paratransit services provided by ASI indicate a potential shortfall of approximately \$15 million per year, beginning in FY00
- Recently appropriated New Starts funds have been committed to bus facilities and Red Line planning (\$8.3 million)
- The need to provide the match for back-year projects (matched by the State before SB45 was enacted) was recognized, resulting in additional commitments of \$9 million
- The audit of the MTA financial model identified additional committed revenue (\$7.4 million)

n La constante de la constante de

APPENDIX 2 SUMMARY OF ALTERNATIVES

• • • • • • •

ELEVEN TRANSIT ALTERNATIVES IN FOUR CORRIDORS WERE ANALYZED IN THE FINAL EVALUATION OF THE REGIONAL TRANSIT ALTERNATIVES ANALYSIS STUDY

- Each corridor contained heavy rail, light rail, and bus transitway alternatives
- Four Alternatives were analyzed for The Eastside
 - Heavy Rail Subway Extension to First/Lorena (Suspended Project)
 - Heavy Rail Subway Extension to Chavez/Soto
 - Light Rail Extension to Whittier / Atlantic
 - Bus Transitway to Whittier / Atlantic
- Four Alternatives were analyzed for The Westside
 - Heavy Rail Extension to Pico/San Vicente (Suspended Project)
 - Heavy Rail subway extension to Fairfax via Wilshire Boulevard
 - Light Rail to downtown Santa Monica via Exposition right-of-way
 - Bus Transitway to downtown Santa Monica via Exposition right-of-way
- Three alternatives were analyzed for The San Fernando Valley
 - Heavy rail extension to the I-405 (Deferred Project)
 - Light Rail/DMU alternative from the North Hollywood Station to Warner Center
 - Bus Transitway from Red Line North Hollywood Station to Warner Center

SUMMARY OF EASTSIDE CORRIDOR ALTERNATIVES

Alternative	Alignment	Mode	Grade	No. of Stations	No. of Stations with Park and Ride Lots	Route Length (miles)	One-Way Travel Time (minutes)	Average Speed (mph)	Peak Headway (minutes)	Off-Peak Headway (minutes)
Heavy Rail to First / Lorena — Suspended Project	Union Station to First / Lorena	Heavy Rail	Subway	4	None	3.7	7.6	29.2	4.25	5.0
Heavy Rail to Chavez / Soto — Revised Alignment without Little Tokyo Station	Union Station to Chavez/ Soto	Heavy Rail	Subway	2	None	1.9	3.6	31.7	4.25	5.0
	Union Station to Whittier / Atlantic	Light Rail	At-Grade with one aerial section	7	None	5.9	26.5	13.4	5.0	12.0
Bus Transitway to Whittier / Atlantic	Gateway Plaza to Whittier / Atlantic	Bus	At-Grade	7	None	5.9	26.5	13.4	3.4	8.0

i


Eastside Corridor Alternatives

FOUR ALTERNATIVES WERE TAKEN THROUGH THOROUGH ANALYSIS FOR THE EASTSIDE CORRIDOR

- Red Line Subway Extension to First/Lorena (Suspended Project)
- Red Line Subway Extension to Chavez/Soto
- Light Rail Extension to Whittier / Atlantic
- Bus Transitway to Whittier / Atlantic

ì





-3F

THE SUSPENDED PROJECT TO THE EASTSIDE PROVIDES A HEAVY RAIL SUBWAY ALIGNMENT INTO THE HEART OF EAST LOS ANGELES

• The characteristics of the alignment include...


Alignment Limits: Union Station to First/Lorena Station Locations: Little Tokyo/Arts District First/Boyle Chavez/Soto First/Lorena

No. Vehicles: None, extension of Red Line and utilizes existing fleet

							Planned Peak-	Maximum Build-Out
				One-Way	Peak	Off-Peak	Hour Capacity	Peak-Hour Capacity
	Consist	Route	Speed	Time	Headway	Headway	(Passengers per	(Passengers Per
Vehicles	Length	Miles	(MPH)	(Min)	(Min)	(Min)	Hour)	Hour)
Not Required	4	3.2	25.9	7.4	4.25	5	31,350	53,294

Sti	Strengths		Weaknesses					
1.	Serves demand travel corridor	1.	I. High Cost					
2.	Strong Community Support							
3.	Minimal Community Impacts							
4.	Design is nearly complete							
5.	Utilizes existing Red Line Vehicles							
6.	Utilizes Existing Maintenance Facility		i					
7.	Expands the Red Line network and Improves regional connectivity							
8.	Portion of Right-of-Way Purchased							

EASTSIDE CORRIDOR – MODIFIED ALIGNMENT TO CHAVEZ / SOTO



4F

Eastside Corridor Alternatives Descriptions – Modified Alignment to Chavez / Soto

THE CHAVEZ/SOTO HEAVY RAIL SUBWAY ALIGNMENT TO THE EASTSIDE MODIFIES THE SUSPENDED PROJECT BY ELIMINATING TWO STATIONS AND REDUCING THE LENGTH OF TUNNEL CONSTRUCTION

• The characteristics of the alignment include...


Alignment Limits: Union Station to Chavez/Soto Station Locations: First/Boyle Chavez/Soto

No. Vehicles: None, extension of Red Line and utilizes existing Fleet

							Planned Peak-	Maximum Build-Out
			8	One-Way	Peak	Off-Peak	Hour Capacity	Peak-Hour Capacity
	Consist	Route	Speed	Time	Headway	Headway	(Passengers per	(Passengers Per
Vehicles	Length	Miles	(MPH)	(Min)	(Min)	(Min)	Hour)	Hour)
Not Required	4	1.9	31.3	3.6	4.25	5	18,418	31,310

Str	engths	We	aknesses
1.	Serves demand travel corridor	1.	High Cost
2.	Strong Community Support	2.	Limited Corridor Penetration
3.	Minimal Community Impacts	3.	No Little Tokyo Connection
4.	Utilizes existing Red Line Vehicles	4.	Requires Modification to EIR
5.	Utilizes Existing Maintenance Facility	5.	Requires Redesign
6.	Expands the Red Line network and Improves regional		
	connectivity		1
7.	Portion of Right-of-Way Purchased		
8.	Lower Cost than Suspended Project		

EASTSIDE CORRIDOR – LIGHT RAIL



THE LIGHT RAIL ALIGNMENT IS AN EXTENSION OF THE PASADENA BLUE LINE AND **PROVIDES AN AT-GRADE ALTERNATIVE TO SERVE THE TRAVEL MARKET NEEDS OF THE** EASTSIDE CORRIDOR


• The characteristics of the alignment include...

Alignment Limits:	Union Station to Atlantic Blvd.				
Station Locations:	Little Tokyo, First/Boyle, First/Soto, First/Indiana				
	Whittier/Rowan, Whittier/Arizona, Whittier/Atlantic				
No. Vehicles:	34				

No. Vehicles:

			14				Planned Peak-	Maximum Build-Out
				One-Way	Peak	Off-Peak	Hour Capacity	Peak-Hour Capacity
	Consist	Route	Speed	Time	Headway	Headway	(Passengers per	(Passengers Per
Vehicles	Length	Miles	(MPH)	(Min)	(Min)	(Min)	Hour)	Hour)
34	2	5.9	13.4	26.5	5.0	12.0	5,453	10,224

Strengths	Weaknesses
1. Meets Travel Market Demands	1. Dedicated Right-of-Way Requires Reduction in the number of Travel Lanes
2. Lower Costs	2. Station Construction Requires Significant Right-of-Way Purchase and
3. Deepest Penetration Through Eastside	Condemnation of Residential/Business Property
4. Expands Pasadena Blue Line Network	3. Mixed Flow Alternative Significantly Reduces System Speed and Significantly
5. Can Provide Connection to Little Tokyo if	Impacts Street Congestion
Chavez/Soto Subway Alternative is Preferred	4. Requires Modification or New EIR
	5. System Design Must Be Done
	6. Requires Transfer to Travel West
	7. Requires New Maintenance Facility



EASTSIDE CORRIDOR – BUS TRANSITWAY

-9F

THE BUS TRANSITWAY FOLLOWS THE SAME ALIGNMENT AS THE LIGHT RAIL ALTERNATIVE AND PROVIDES BUS SERVICE TO SERVE THE TRAVEL MARKET NEEDS OF THE EASTSIDE CORRIDOR

The characteristics of the alignment include... •

Alignment Limits:	Union Station to Atlantic Blvd.			
Station Locations:	Little Tokyo, First/Boyle, First/Soto, First/Indiana			
	Whittier/Rowan, Whittier/Arizona, Whittier/Atlantic			
No. Vehicles:	34			

INO. VEHICLES:

							Planned Peak-	Maximum Build-Out
				One-Way	Peak	Off-Peak	Hour Capacity	Peak-Hour Capacity
	Consist	Route	Speed	Time	Headway	Headway	(Passengers per	(Passengers Per
Vehicles	Length	Miles	(MPH)	(Min)	(Min)	(Min)	Hour)	Hour)
34	2	5.9	13.4	26.5	5.0	12.0	1,996	6,732

Strengths	Weaknesses			
1. Meets Travel Market Demands	1. Dedicated Lane Requires Reduction in the number of Travel			
2. Lowest Cost	Lanes			
3. Deepest Penetration Through Eastside	2. Requires Transfer to Travel West			
4. Less Community Disruption than Light Rail Alternative	3. Dedicated Lane Limits Parking			
	-			

î.

...

EACH OF THE ALTERNATIVES SELECTED FOR FINAL EVALUATION IN THE EASTSIDE CORRIDOR ARE AT DIFFERENT STAGES IN THE PLANNING AND DESIGN PROCESS

- The suspended project to First and Lorena is for all intents and purposes ready to go, but adequate funding is not available to build this segment of subway
- The other projects in this corridor are at different st ages in the planning process and must pass a number of steps prior to implementation

				ST	EPS TO IM	PLEMENTA	TION	17 N. 18	- 40 h	1	
			es Analysis			FTA,				•	
Alternative	Scope & Purpose (3 mo.)	Develop & Screen Alternatives (5 mo.)	Detailed Alternative Definition (10 mo.)	Evaluate Alternatives (3 mo.)	Prepare Draft EIS (9 mo.)	Public, & Board Review (6 mo.)	Prepare Final EIS (4 mo.)	Develop ROD (6 mo.)	Final Design (12 mo.)	Bid (4 mo.)	Total Months to Construction
Heavy Rail Subway: Union Station to First / Lorena (Suspended Project)	Complete	Complete	Complete	Complete	Complete	Complete	Complete	Complete	95% 3 mo.	4 mo.	7 mo.
Heavy Rail Subway: Union Station to Chavez / Soto	Complete	Complete	Complete	Complete	65% 3 mo.	0% 6 mo.	0% 4 mo.	0% 6 mo.	50% 9 mo.	4 mo.	32 mo.
Light Rail At-Grade: Union Station to Atlantic / Whittier	0% 3 mo.	0% 5 mo.	0% 10 mo.	0% 3 mo.	0% 9 mo.	0% 6 mo.	0% 4 mo.	0% 6 mo.	0% 12 mo.	4 mo.	62 mo.
Bus Transitway At-Grade: Gateway Plaza to Atlantic / Whitter	0% 3 mo.	0% 5 mo.	0% 10 mo.	0% 3 mo.	0% 9 mo.	0% 6 mo.	0% 4 mo.	0% 6 mo.	0% 12 mo.	4 mo.	62 mo.

NO PROJECT IN THE EASTSIDE CORRIDOR IS READY TO GO AND ADDITIONAL PLANNING OR FUNDING IS NEEDED IN THE FY04 PERIOD PRIOR TO IMPLEMENTATION

IMPLEMENTATION TIMEFRAME FOR SUSPENDED PROJECT TO FIRST / LORENA

			MOI	NTH	S															-			
PROJECT PHASE		Months to Complete		6	1	2	18	 24	3	10	36	 42	48	 54	60	 66	72	2	78		34	90	
Alternatives Analysis	100%																						
Draft EIS	100%																						
Final EIS	100%																						
Preliminary Engineering	100%																						
Procurement Strategy / ROD	100%																				-		
Final Design / Engineering	95%	3 - 4						 _						 							1		
Right-of-Way Acquisition	80%	6										1		1									
Contractor Bid	0%	4																			1		-
Construction and Testing	0%	36 - 42		Τ							-												
Total Time to Completion		45 - 52																					

1

THE SUSPENDED PROJECT TO THE EASTSIDE COULD CONTINUE WITH ONLY FINAL DESIGN ELEMENTS AND CONSTRUCTION REMAINING

- All environmental documents for the full Suspended Project are complete
- Five percent of the design and engineering work remains
- Completion of construction to First and Lorena and the revenue testing period is estimated to require an additional 3 to 3 ½ years

i

IMPLEMENTATION TIME FRAME FOR MODIFIED ALIGNMENT TO CHAVEZ / SOTO

PROJECT PHASE		Months to Complete	MON	6	12	2	18		24	30	0	36		42	48	54	60	66	72	78	8	4	90	
Alternatives Analysis	100%			Τ																				Τ
Draft EIS	65%	3	-						-							 		 		 	+			
DEIS Review	0%	6					-+									 		 		 	+			+
Final EIS	0%	4										-+												-
Preliminary Engineering	65%	12											-								1			+
Procurement Strategy / ROD	0%	6														-					-			+
Final Design / Engineering	50%	9																 		 	1			-
Right-of-Way Acquisition	90%	6		-	-			T								 				 				-
Contractor Bid	0%	4		-					1-			-+				 		 		 	-			
Construction and Testing	0%	36							-				4								1			+
Total Time to Completion		68										Τ	Τ				Π	Τ						


ì

Eastside Corridor Alternatives Timelines – Modified Alignment to Chavez / Soto

THE MODIFIED ALIGNMENT TO CHAVEZ / SOTO REQUIRES REVISIONS TO DESIGN FOR THE NEW TUNNEL ALIGNMENT. CONSTRUCTION TIME CAN DECREASE BUT ADDITIONAL ENVIRONMENTAL TIME TO PREPARE ENVIRONMENTAL DOCUMENTS IS REQUIRED

- The Modified Alignment to Chavez / Soto requires a reselection of the Locally Preferred Alternative. This process, which takes place normally during the development of the Draft EIS, is expected to take 9 months
- New tunnel designs must be completed for the shortened tunnel between Union Station and the station at First and Boyle. Although station designs for the First / Boyle and Chavez / Soto stations are nearly complete, they may require minor revisions. These design revisions and completion of the Final Environmental Impact Statement can occur as the Locally Preferred Alternative is being revised
- Right-of-way acquisition for the Modified Alignment is nearly complete and requires just an additional 6 months
- Construction for this shortened subway alternative can be complete in two years. Testing and final preparations are estimated to require up to an additional year

IMPLEMENTATION TIME FRAME FOR LIGHT RAIL EXTENSION TO WHITTIER / ATLANTIC



4

Eastside Corridor Alternatives Timelines – Light Rail Extension to Whittier / Atlantic

AN EXTENSION OF LIGHT RAIL TO THE EASTSIDE REQUIRES AN ENTIRELY NEW PROJECT DEVELOPMENT PROCESS

- Choosing a light rail option on the Eastside will require a new alternatives analysis process which can last approximately 21 months
- Development of a new Draft EIS and adoption of a Locally Preferred Alternative will require approximately 15 months
- Completion of the Final Environmental Impact Statement requires four additional months
- Construction and testing of an Eastside light rail alternative will require approximately three to four years. Additional time to mitigate impacts to street traffic and commercial businesses occurs within this time frame
- The construction process is complicated by the need to build a bridge over the existing US

 101 freeway. The need to maintain traffic flow requires an elongated construction schedule

IMPLEMENTATION TIME FRAME FOR BUS TRANSITWAY TO WHITTIER / ATLANTIC

			-	NTH	IS																						_
	Percent	Months to																									
PROJECT PHASE	Complete	Complete		6		12		18	2	4	30	36	42	2	48	54	4	60	66	6	72	7	8	84		90	
						Т		T	T			Т	T		Т			Т	T			T		Т	T	T	Т
Alternatives Analysis	0%	21																									
Draft EIS	0%	9																									T
DEIS Review	0%	6																									T
Final EIS / Prelim. Engineerir	0%	4																									T
Preliminary Engineering	0%	12																									T
Procurement Strategy / ROD	0%	6						1	1																		T
Final Design / Engineering	0%	12	ľ																			1				1	T
Right-of-Way Acquisition	0%	12					-		1						T	T											T
Contractor Bid	0%	4																									t
Construction	0%	24																Τ			-						T
Total Time to Completion		86																									

;

Eastside Corridor Alternatives Timelines – Bus Transitway to Whittier / Atlantic

THE DEVELOPMENT OF A BUSWAY TO THE EASTSIDE REQUIRES AN ENTIRELY NEW PROJECT DEVELOPMENT PROCESS

- Choosing a bus transitway option on the Eastside will require a new alternatives analysis process which can last approximately 21 months
- Development of a new Draft EIS and adoption of a Locally Preferred Alternative will require approximately 15 months
- Completion of the Final Environmental Impact Statement requires four additional months
- Construction of an Eastside bus transitway alternative will require approximately two years. Additional time to mitigate impacts to street traffic and commercial businesses may be necessary

....

SUMMARY RESULTS FOR EASTSIDE CORRIDOR ALTERNATIVES

Alternative	Capital Costs (\$M)	Operating Costs (\$M)	Estimated Ridership	Estimated Time Before Construction (months)	Mobility	Transit Dependence	Reliability	Community Impact	Cost Effectiveness
Heavy Rail Subway: Union Station to First / Lorena (Suspended Project)	922.6	10.5	10,400	7	•			•	•
Heavy Rail Subway: Union Station to Chavez / Soto	481.1	3.4	6,100	32					\bigcirc
Light Rail At-Grade: Union Station to Atlantic / Whittier	430.9	15.5	11,500	62					
Bus Transitway At- Grade: Gateway Plaza to Atlantic / Whitter	88.2	9.9	11,400	62					•

KEY		Most Favorable or High	>	0	Least Favorable or Low	
-----	--	---------------------------	---	---	---------------------------	--

ì

SUMMARY OF WESTSIDE CORRIDOR ALTERNATIVES

Alternative	Alignment	Mode	Grade	No. of Stations	No. of Stations with Park and Ride Lots	Route Length (miles)	One-Way Travel Time (minutes)	Average Speed (mph)	Peak Headway (minutes)	Off-Peak Headway (minutes)
Heavy Rail to Pico / San Vicente— Suspended Project, subway	Wilshire / Western to Pico San Vicente via Wilton and Arlington	Heavy Rail	Subway	2	1	2.1	2.8	45.0	8.5	10.0
Heavy Rail to Wilshire / Fairfax	Wilshire Boulevard subway or aerial to Fairfax	Heavy Rail	Subway or Aerial	3	None	3.0	4.4	29.2	8.5	10.0
Light Rail At-Grade Expo Right-of-Way: 7 th / Flower to 4 th / Colorado	7 th /Flower LACBD to Exposition via existing Long Beach Blue Line alignment, Exposition to 4 th / Colorado	Light Rail	At-Grade	16 (2 existing)	7	18	51	21.2	5.0	12.0
Bus Transitway At- Grade Expo Right-of-Way: Gateway Plaza to 4 th / Colorado	Union Station To 4 th / Colorado	Bus	At-Grade	24	6	18	57	19.5	5.0	12.0

ì

Westside Corridor Alternatives


FOUR ALTERNATIVES IN THE WESTSIDE CORRIDOR ADVANCED TO EVALUATION

- Red Line Extension to Pico/San Vicente (Suspended Project)
- Red Line subway extension to Fairfax via Wilshire Boulevard
- Light Rail to downtown Santa Monica via Exposition right-of-way
- Bus Transitway to downtown Santa Monica via Exposition right-of-way

THE PHYSICAL AND OPERATING CHARACTERISTICS OF EACH ALTERNATIVE ARE DEFINED FOR FURTHER ANALYSIS

1

WESTSIDE CORRIDOR – SUSPENDED PROJECT



.

Westside Corridor Alternatives Descriptions - Suspended Project

THE SUSPENDED PROJECT TO THE WESTSIDE EXTENDS EXISTING RED LINE SUBWAY SERVICE FURTHER INTO THE WILSHIRE DISTRICT

• The characteristics of the alignment include...

Alignment Limits:Wilshire/Western to Pico/San VicenteStation Locations:Olympic/ArlingtonPico/San Vicente


No. Vehicles: None, extension of Red Line and utilizes existing Fleet

• This is the locally preferred alternative and as such has a number of benefits which come at a high cost

Vehicles	Consist Length	Route Miles	Speed (MPH)	One-Way Time (Min)	Peak Headway (Min)	Off-Peak Headway (Min)	Planned Peak-Hour Capacity (Passengers per Hour)	Maximum Build- Out Peak-Hour Capacity (Passengers Per Hour)
Not Reqíd	4	2.2	33.8	3.9	4.25	5	8,621	18,320

Strengths	Weaknesses	
1. Serves Travel Demand Corridor	1. High Cost	
2. Minimal Community Impacts		
3. Strong Community Support		
4. Approved EIR		
5. Design is nearly Complete		
6. Extends Existing Red Line Service		
7. Utilizes Existing Maintenance Facility		
Utilizes Existing Red Line Fleet		

WESTSIDE CORRIDOR – WILSHIRE ALIGNMENT



THE WILSHIRE HEAVY RAIL SUBWAY ALIGNMENT EXTENDS RED LINE SERVICE DOWN WILSHIRE BOULEVARD TO FAIRFAX

• The characteristics of the alignment include...


Alignment Limits:	Wilshire/Western to Wilshire/Fairf ax
Station Locations:	Wilshire/Crenshaw
	Wilshire/La Brea
	Wilshire/Fairfax

No. Vehicles: None, extension of Red Line and utilizes existing Fleet

Vehicles	Consist Length	Route Miles	Speed (MPH)	One-Way Time (Min)	Peak Headway (Min)	Off-Peak Headway (Min)	Planned Peak- Hour Capacity (Passengers per Hour)	Maximum Build- Out Peak-Hour Capacity (Passengers Per
Not Reqíd	4	3.03	41.3	4.4	4.25	5	11,874	Hour) 25,232

Str	engths	We	eaknesses	
1.	Serves Travel Demand Corridor	1.	High Cost	
2.	Minimal Community Impacts	2.	Legislative Restriction will have to be Overturned	
3.	Extends Existing Red Line Service	3.	Requires Design	
4.	Utilizes Existing Maintenance Facility	1		
5.	Utilizes Existing Red Line Fleet		i	
6.	Provides Deepest Penetration into Westside of all Subway			
	Alternatives			

WESTSIDE CORRIDOR – EXPOSITION LIGHT RAIL



16F

Westside Corridor Alternatives Descriptions - Exposition Light Rail

THE EXPOSITION LIGHT RAIL ALIGNMENT BRANCHES OFF THE LONG BEACH BLUE LINE SERVICE AND UTILIZES EXISTING RIGHT-OF-WAY ALONG EXPOSITION BOULEVARD

• The characteristics of the alignment include...

Alignment Limits: 7th/Flower (L.A.) to 4th/Colorado (Santa Monica)

Station Locations: 2 Existing on Long Beach Blue Line Alignment


14 New Stations along Exposition (Locations To Be Determined)

No. Vehicles: 39

				5-			Planned Peak-	Maximum Build-Out
				One-Way	Peak	Off-Peak	Hour Capacity	Peak-Hour Capacity
	Consist	Route	Speed	Time (Min)	Headway	Headway	(Passengers per	(Passengers Per
Vehicles	Length	Miles	(MPH)		(Min)	(Min)	Hour)	Hour)
39	2	18	21.2	51	5	12	16,635	31,190

Str	engths	We	eaknesses
1.	Utilizes Existing Right-of-Way	1.	Some Community Opposition
2.	Serves Transit Dependent Corridor	2.	Does Not Serve Travel Demand Corridor of Suspended
3.	Provides Rail Access to Convention Center, Staples Center,		Project
	USC, Coliseum and Sports Arena	3.	Requires Environmental Process
4.	Extends Existing Blue Line Service	4.	Requires Design
5.	Expands Regional Connectivity	5.	At-Grade Alignment Poses Some Safety Considerations
6.	A Number of Branch Alternatives can Further expand		
	Regional Connectivity		

WESTSIDE CORRIDOR – EXPOSITION BUS TRANSITWAY



Westside Corridor Alternatives Descriptions - Exposition Bus Transitway

THE EXPOSITION BUS TRANSITWAY PROVIDES A BUS ALTERNATIVE TO ALONG THE EXISTING EXPOSITION RIGHT-OF-WAY

• The characteristics of the alignment include...

Alignment Limits:Union Station (L.A.) to 4th/Colorado (Santa Monica)Station Locations:24 New Stations (Locations To Be Determined)No. Vehicles:29

			2				Planned Peak-	Maximum Build-
				One-Way	Peak	Off-Peak	Hour Capacity	Out Peak-Hour
	Consist	Route	Speed	Time (Min)	Headway	Headway	(Passengers	Capacity
Vehicles	Length	Miles	(MPH)	a di seconda	(Min)	(Min)	per Hour)	(Passengers Per
			:				*	Hour)
29	N/A	18.5	21.2	51	5	12	6,090	20,538

Strengths	Weaknesses
 Utilizes Existing Right-of-Way Serves Transit Dependent Corridor Provides Transitway Access to Convention Center, Staples Center, USC, Coliseum and Sports Arena Low Cost Expands Regional Connectivity A Number of Branch Alternatives can Further expand 	 Some Community Opposition Does Not Serve Travel Demand Corridor of Suspended Project Requires Environmental Process Requires Design At-Grade Alignment Poses Some Safety Considerations Lower Capacities
Regional Connectivity	

. ...

Westside Corridor Alternatives – Project Timelines

ALL ALTERNATIVES WITHIN THE WESTSIDE CORRIDOR REQUIRE ADDITIONAL PLANNING

.

- No project in the Westside corridor is ready to move into construction at this time
- The suspended project must still go through a supplemental EIS process, as well as design prior to moving to construction

			÷	STE	PS TO IMP	PLEMENT	TION				4
		Alternativ	es Analysis			FTA,					
Alternative	Scope & Purpose (3 mo.)	Develop & Screen Alternatives (5 mo.)	Detailed Alternative Definition (10 mo.)	Evaluate Alternatives (3 mo.)	Prepare Draft EIS (9 mo.)	Public, & Board Review (6 mo.)	Prepare Final EIS (4 mo.)	Develop ROD (6 mo.)	Final Design (12 mo.)	Bid (4 mo.)	Total Months to Construction
Heavy Rail Subway:	Complete	Complete	Complete	Complete	65%	0%	0%		5%		
Wilshire / Western to Pico / San Vicente (Suspended Project)			1		3 mo.	6 mo.	4 mo.	6 mo.	12 mo.	4 mo.	35 mo.
Heavy Rail Subway:	0%	40%	40%	0%	65%	0%	0%		5%		
Wilshire / Western to Wilshire / Fairfax	3 mo.	3 mo.	6 mo.	3 mo.	3 mo.	6 mo.	4 mo.	6 mo.	12 mo.	4 mo.	50 mo.
Light Rail At-Grade	0%	0%	0%	0%	0%	0%	0%		0%		
Expo Right-of-Way: 7 th / Flower to 4 th / Colorado	3 mo.	5 mo.	10 mo.	3 mo.	9 mo.	6 mo.	4 mo.	6 mo.	12 mo.	4 mo.	62 mo.
Bus Transitway At-	0%	0%	0%	0%	0%	0%	0%		0%		
Grade Expo Right-of-Way: Gateway Plaza to 4 th / Colorado	3 mo.	5 mo.	10 mo.	3 mo.	9 mo.	6 mo.	4 mo.	6 mo.	12 mo.	4 mo.	62 mo.

NO PROJECT IN THE WESTSIDE CORRIDOR IS READY TO MOVE INTO CONSTRUCTION AND ADDITIONAL PLANNING MUST BE DONE DURING THE FY04 PERIOD

IMPLEMENTATION TIME FRAME FOR SUSPENDED PROJECT TO PICO / SAN VICENTE

			MON	THS						1 (D. Hand								an a		-		in sector of		
PROJECT PHASE	Complete	Complete		6	12	1	8	24	30)	36	42	4	8	54	60	66	72	7	8	84		90	
Alternatives Analysis	100%	0																						
Draft EIS	65%	3																						T
DEIS Review	0%	6																						Т
Final EIS	0%	4																						T
Preliminary Engineering	0%	12																					1	T
Procurement Strategy / ROD	0%	6																						T
Final Design / Engineering	5%	12							and an and								 1							1
Right-of-Way Acquisition	5%	24																						T
Contractor Bid	0%	4															-		-				1	1
Construction and Testing	0%	36 - 48										Π												T
Total Time to Completion		79 - 91																						

ì

Westside Corridor Alternatives Timelines – Suspended Project

THE IMPLEMENTATION OF THE SUSPENDED HEAVY RAIL PROJECT TO PICO / SAN VICENTE RESUMES A PARTIALLY COMPLETE ENVIRONMENTAL CLEARANCE PROCESS

- The completion of the last portion of the Draft Environmental Impact Statement will take approximately nine months
- Completion of the Final Environmental Impact Statement will require an additional four months
- Right-of-way acquisition begins once all engineering work is complete and falls within a two-year time frame
- Once enough real estate is acquired to begin station construction, construction of the project will likely require an additional three to four years

IMPLEMENTATION TIME FRAME FOR WILSHIRE SUBWAY

			Contraction of the local division of the loc	NTH	3					Contraction of the											-		11 - 11 - 11		
		Months to																							
PROJECT PHASE	Complete	Complete		6	1	2	18	1	24	30	:	36	42	48	}	54	60	6	6	72	7	78	84	ç	0
Alternatives Analysis	70%	15																							
Draft EIS	65%	9																							
DEIS Review	0%	6																							
Final EIS	0%	4																							
Preliminary Engineering	25%	12																							
Procurement Strategy / ROD	0%	6																							
Final Design / Engineering	5%	12																							
Right-of-Way Acquisition	30%	24																							
Contractor Bid	0%	4																							
Construction and Testing	0%	48 - 54															4 TO	4 1/2	YEAF	RS					
Total Time to Completion		104 - 110																							

1

i.

Westside Corridor Alternatives Timelines – Wilshire Alignment

IMPLEMENTATION OF THE WILSHIRE SUBWAY ALIGNMENT TO FAIRFAX AVENUE REQUIRES REVISIONS TO ALREADY COMPLETE ENVIRONMENTAL IMPACT STATEMENTS

- Environmental clearances for the Wils hire Subway Alignment were completed in 1987. Although environmental documents are complete, new conditions require that these documents be revised. A partial alternatives analysis should be done in order for this option to advance. Such a process may require approximately 15 months
- Completion of the Final Environmental Impact Statement requires an additional year
- Although nearly 20 percent of the required right-of-way is already owned by the MTA, the remaining right-of-way will require an additional two years to purchase
- Since a significant portion of the right-of-way is already owned by the MTA, construction can occur concurrent with the final purchases of right-of-way
- Construction of the full extension to Fairfax Avenue will take approximat ely three to four years. Testing will require an additional one-half to one year before revenue service can begin

IMPLEMENTATION TIMEFRAME FOR EXPOSITION LIGHT RAIL

STATE FUNDING PROCESS

Percent PROJECT PHASE Months to Complete 6 12 18 24 30 36 42 48 54 60 66 72 78 84 Alternatives Analysis 0% 21 1	90
Alternatives Analysis 0% 21 Draft EIS 0% 9 DEIS Review N/A Final EIS 0% 4 Preliminary Engineering 0% 12 Procurement Strategy 0% 6 Final Design / Engineering 0% 12 Procurement Strategy 0% 6 Contractor Bid 0% 4 Construction and Testing 0% 36 - 48 Total Time to Completion 92 - 98	90
Draft EIS 0% 9 1 <th1< th=""> <th1< th=""> <th1< th=""> <th1< t<="" th=""><th></th></th1<></th1<></th1<></th1<>	
Draft EIS 0% 9 1 <th1< th=""> <th1< th=""> <th1< th=""> <th1< t<="" th=""><th></th></th1<></th1<></th1<></th1<>	
DEIS Review N/A Final EIS 0% 4 Preliminary Engineering 0% 12 Procurement Strategy 0% 6 Final Design / Engineering 0% 12 Right-of-Way Acquisition 95% 12 Contractor Bid 0% 4 Construction and Testing 0% 36 - 48	
Final EIS 0% 4 Image: Construction and Testing 0% 12 Procurement Strategy 0% 6 Image: Construction and Testing 0% 12 Total Time to Completion 92 - 98 Image: Construction and Testing 92 - 98 Image: Construction and Testing 1mage: Construction and Te	
Preliminary Engineering 0% 12 Image: Construction and Testing 0% 12 Image: Construction and Testing Image: Construction and Testing 0% 36 - 48 Image: Construction and Testing Image: Construction and Testing 0% 36 - 48 Image: Construction and Testing Image: Construction and Testing 0% 36 - 48 Image: Construction and Testing	
Procurement Strategy 0% 6 Image: Construction of the second	
Final Design / Engineering 0% 12 Right-of-Way Acquisition 95% 12 Contractor Bid 0% 4 Construction and Testing 0% 36 - 48 Total Time to Completion 92 - 98	
Right-of-Way Acquisition 95% 12 Contractor Bid 0% 4 Construction and Testing 0% 36 - 48 Total Time to Completion 92 - 98	
Contractor Bid 0% 4 Construction and Testing 0% 36 - 48 Total Time to Completion 92 - 98	
Construction and Testing 0% 36 - 48 Total Time to Completion 92 - 98	
Total Time to Completion 92 - 98	
FEDERAL FUNDING PROCESS	
MONTHS	
Percent Months to	
PROJECT PHASE Complete 6 12 18 24 30 36 42 48 54 60 66 72 78 84	90
Alternatives Analysis 0% 21	
Draft EIS 0% 9	
DEIS Review 0% 6 .	
Final EIS 0% 4	
Preliminary Engineering 0% 12	
Procurement Strategy / ROD 0% 6	
Final Design / Engineering 0% 12	
Right-of-Way Acquisition 95% 12	
Contractor Bid 0% 4	
Construction and Testing 0% 36 - 48 3 TO 4 YEARS	

Westside Corridor Alternatives Timelines – Exposition Light Rail

IMPLEMENTATION OF THE LIGHT RAIL ON THE EXPOSITION RIGHT-OF-WAY REQUIRES AN ENTIRELY NEW ENVIRONMENTAL CLEARANCE PROCESS. THE TIME FRAME FOR COMPLETION DEPENDS ON THE SOURCE OF FUNDS

- Funding the Exposition Light Rail project entirely with local and state funds requires that the project satisfy the requirements of the California Environmental Quality Act. The state environmental clearance process can take three to nine months shorter than the federal one
- Funding the Exposition Light Rail project with partial federal funding requires the satisfaction of the federal environmental review process. This lengthens the project time frame by 9 months. The completion of environmental clearance is estimated at 33 months
- Construction of the project and completion of testing are estimated to require an additional three to four years

IMPLEMENTATION TIMEFRAME FOR EXPOSITION BUSWAY

STATE FUNDING PROCESS

PROJECT PHASE		Months to Complete	6	1	2	18	24	30	36		42	48	54		60	66	72	78	84	90	
							T		TT				TT		T		TT			TT	
Alternatives Analysis	0%	21																			
Draft EIS	0%	9																			
DEIS Review	N/A										1										
Final EIS	0%	4																			
Preliminary Engineering	0%	12																			
Procurement Strategy	0%	6																			
Final Design / Engineering	0%	12																			
Right-of-Way Acquisition	95%	12								1					ann Guanne						
Contractor Bid	0%	4																			
Construction	0%	24												4	-						
Total Time to Completion		80																			

FEDERAL FUNDING PROCESS

		Months to																				
PROJECT PHASE	Complete	Complete	6	12	18	24	3	0	36	4	2	48	54	1	60	66	72	2	78	84	90	
Alternatives Analysis	0%	21	 		 																	
Draft EIS	0%	9																				
DEIS Review	0%	6																				
Final EIS	0%	4																				
Preliminary Engineering	0%	12																				T
Procurement Strategy / ROD	0%	6									den mender		1									T
Final Design / Engineering	0%	12																				
Right-of-Way Acquisition	95%	12																				T
Contractor Bid	0%	4																				T
Construction and Testing	0%	24																				Τ
Total Time to Completion		86																				

1

Westside Corridor Alternatives Timelines – Exposition Bus Transitway

IMPLEMENTATION OF THE EXPOSITION BUSWAY MAY REQUIRE BETWEEN FIVE AND SIX YEARS

- The Exposition Busway could be funded entirely with local and state funds. This funding arrangement requires that the project satisfy the requirements of the California Environmental Quality Act only. The project would not be required to have federal environmental documents. The state environmental clearance process can take 24 months
- Funding the Exposition Busway project with partial federal funding requires the satisfaction of the federal environmental review process. This lengthens the project time frame by 9 months. The completion of environmental clearance is estimated at 33 months
- Busway construction can be completed within approximately 2 years

;

. .

WESTSIDE CORRIDOR ALTERNATIVES

Alternative	Capital Costs (\$M)	Operating Costs (\$M)	Estimated Ridership	Estimated Time Before Construction (months)	Mobility	Transit Dependence	Reliability	Community Impact	Cost Effectiveness
Heavy Rail Subway: Wilshire / Western to Pico / San Vicente (Suspended Project)	607.4	4.4	16,300	35	•	•	•	•	O
Heavy Rail Subway: Wilshire / Western to Wilshire / Fairfax	859.7	6.5	21,600	50					
Light Rail At-Grade Expo Right-of-Way: 7 th / Flower to 4 th / Colorado	930.8	21.2	36,600	62	•	J	•		
Bus Transitway At- Grade Expo Right-of-Way: Gateway Plaza to 4 th / Colorado	264.3	14.7	33,400	62	•				

KEY	Most Favorable	>	Least Favorable or
	or High		Low

.

×.

SUMMARY OF SAN FERNANDO VALLEY ALTERNATIVES

Alternative	Alignment	Mode	Grade	No. of Stations	No. of Stations with Park and Ride Lots	Route Length (miles)	One-Way Travel Time (minutes)	Average Speed (mph)	Peak Headway (minutes)	Off-Peak Headway (minutes)
Heavy Rail to I-405, subway / aerial combination	North Hollywood to I- 405 via Burbank / Chandler Right-of-Way	Heavy Rail	Subway / Aerial	4	4	5.6	9.5	35.3	8.5	10.0
Light Rail (or DMU) to Warner Center	North Hollywood to Warner Center via Burbank / Chandler Right-of-Way	Light Rail	At-Grade with Elevated Flyovers	12	10	13.7	24.8	33.1	5.0	12.0
Bus Transitway	North Hollywood to Warner Center via Burbank / Chandler Right-of-Way	Bus	At-Grade in Exclusive Right – of – Way	13	6	13.7	24.8	33.1	5.0	12.0

i.

San Fernando Valley Alternatives


THREE ALTERNATIVES IN THE SAN FERNANDO CORRIDOR ADVANCED TO FINAL EVALUATION

- Heavy rail extension to the I-405 (Deferred Project)
- Light Rail/DMU alternative from the North Hollywood Station to Warner Center
- Bus Transitway from Red Line North Hollywood Station to Warner Center

THE PHYSICAL AND OPERATING CHARACTERISTICS OF EACH ALTERNATIVE ARE DEFINED FOR FURTHER ANALYSIS

÷.

SAN FERNANDO VALLEY - DEFERRED PROJECT



.

THE DEFERRED PROJECT IN THE SAN FERNANDO VALLEY EXTENDS THE RED LINE NORTH HOLLYWOOD SEGMENT CURRENTLY UNDER CONSTRUCTION

• The characteristics of the alignment include...

Alignment Limits: North Hollywood Station to I-405

Station Locations: Van Nuys Boulevard

Valley College


Laurel Canyon

Sepulveda Boulevard

No. Vehicles: None, extension of Red Line and utilizes existing Fleet

								Maximum
				8				Build-Out
							Planned Peak-	Peak-Hour
					Peak	Off-Peak	Hour Capacity	Capacity
	Consist	Route	Speed	One-Way	Headway	Headway	(Passengers per	(Passengers
Vehicles	Length	Miles	(MPH)	Time (Min)	(Min)	(Min)	Hour)	Per Hour)
Not Req'd	6	5.6	35.4	9.5	4.25	5	32,917	46,633

Strengths	Weaknesses
1. Serves Travel Demand Corridor	1. High Cost
2. Minimal Community Impacts	2. Does Not Serve Warner Center
3. Extends Existing Red Line Service	3. Some Community Opposition
4. Utilizes Existing Maintenance Facility	
5. Utilizes Existing Red Line Fleet	1



SAN FERNANDO VALLEY - LIGHT RAIL

Booz-Allen & Ha Inc.

26F

nal Transit Alternatives Analysis


THIS ALTERNATIVE PROVIDES AN AT-GRADE LIGHT RAIL ALIGNMENT TO WARNER CENTER UTILIZING THE BURBANK/CHANDLER RIGHT-OF-WAY

• The characteristics of the alignment include...

Alignment Limits:North Hollywood Red Line Station to Warner CenterStation Locations:12 New Stations (Locations To Be Determined)No. Vehicles:33

							Planned Peak-	Maximum Build-Out
			8	One-Way	Peak	Off-Peak	Hour Capacity	Peak-Hour Capacity
	Consist	Route	Speed	Time (Min)	Headway	Headway	(Passengers per	(Passengers Per
Vehicles	Length	Miles	(MPH)		(Min)	(Min)	Hour)	Hour)
33	2	13.8	33.1	25	5	12	12,753	23,913

Stre	engths	W	eaknesses
1.	Utilizes Existing Right-of-Way	1.	Robbin's Bill prohibits at-grade alternative over a section of
2.	Serves Warner Center		proposed alignment
3.	Lower Cost than Subway	2.	Segment Operates Independently and Does Not Expand any
4.	Minimizes Community Impacts		Current System
5.	Could be Implemented using DMU Technology	3.	Requires Environmental Process
6.	A Number of Branch Alternatives can Further expand	4.	Requires Design
	Regional Connectivity	5.	At-Grade Alignment Poses Some Safety Considerations
		6.	Requires transfer to downtown L.A.
			•



SAN FERNANDO VALLEY - BUS TRANSITWAY

onal Transit Alternatives Analysis

Booz-Allen & H: n Inc.

27F

THIS TRANSITWAY ALTERNATIVE PROVIDES AN AT-GRADE BUS OPTION TO WARNER CENTER UTILIZING THE BURBANK/CHANDLER RIGHT-OF-WAY

• The characteristics of the alignment include...

Alignment Limits:North Hollywood Red Line Station to Warner CenterStation Locations:13 New Stations (Locations To Be Determined)No. Vehicles:22

								Maximum Build-
							Planned Peak-	Out Peak-Hour
					Peak	Off-Peak	Hour Capacity	Capacity
1	Consist	Route	Speed	One-Way	Headway	Headway	(Passengers per	(Passengers Per
Vehicles	Length	Miles	(MPH)	Time (Min)	(Min)	(Min)	Hour)	Hour)
22	N/A	13.8	33.1	25	5	12	4,669	15,746

Str	rengths	We	eaknesses
1.	Utilizes Existing Right-of-Way	1.	Robbin's Bill prohibits at-grade alternative over a section of proposed alignment
2.	Serves Warner Center	2.	Requires Environmental Process
3.	Lowest Cost Option	3.	Requires Design
4.	Minimizes Community Impacts	4.	At-Grade Alignment Poses Some Safety Considerations
1		5.	Lower Capacities
		6.	Requires Transfers

-

IN THE SAN FERNANDO CORRIDOR THE LOCALLY PREFERRED ALTERNATIVE STILL MUST BE SELECTED

- The three projects identified for final evaluation in the RTAA are at a point in the process where the Locally Preferred Alternative (LPA) is to be selected
- Once the LPA has been determined, the selected project can begin the process to construction

			and the second sec	STE	PS TO IMP	PLEMENTA	ATION		1 Charles		
		Alternativ	es Analysis			FTA,					
Alternative	Scope & Purpose (3 mo.)	Develop & Screen Alternatives (5 mo.)	Detailed Alternative Definition (10 mo.)	Alternative Evaluate Definition Alternatives		Public, & Board Review (6 mo.)	Prepare Final EIS (4 mo.)	Develop ROD (6 mo.)	Final Design (12 mo.)	Bid (4 mo.)	Total Months to Construction
Heavy Rail: North Hollywood Station to I-405	Complete	Complete	Complete	Complete	35% 6 mo.	0% 6 mo.	0% 4 mo.	6 mo.	0% 12 mo.	4 mo.	38 mo.
Light Rail At-Grade Burbank / Chandler Right-of-Way: North Hollywood Station to Warner Center	Complete	Complete	Complete	Complete	35% 6 mo.	0% 6 mo.	0% 4 mo.	6 mo.	0% 12 mo.	4 mo.	38 mo.
Bus Transitway At- Grade Burbank / Chandler Right-of-Way: North Hollywood Station to Warner Center	Complete	Complete	Complete	Complete	35% 6 mo.	0% 6 mo.	0% 4 mo.	6 mo.	0% 12 mo.	4 mo.	38 mo.

NO PROJECT IN THE SAN FERNANDO VALLEY CORRIDOR IS READY TO MOVE INTO CONSTRUCTION. THE LOCALLY PREFERRED ALTERNATIVE MUST BE DETERMINED AND THE PLANNING PROCESS COMPLETED PRIOR TO IMPLEMENTATION

IMPLEMENTATION TIMEFRAME FOR DEFERRED PROJECT --NORTH HOLLYWOOD TO I-405

			-	NTH	5							-													
		Months to																							
PROJECT PHASE	Complete	Complete		6		2	18	1	24	30	0	36	4	2	·48	54		60	66	72	78		84	9	0
						Г			Т			Т								Т			Т	Т	ГТ
Alternatives Analysis	100%																								
Draft EIS	65%	6																							
DEIS Review	0%	6																							
Final EIS	0%	4																							
Preliminary Engineering	0%	12			and an area																				
Procurement Strategy / ROD	0%	6				T																			
Final Design / Engineering	0%	12																							
Right-of-Way Acquisition	90%	12							Т					1											
Contractor Bid	0%	4				1																			
Construction and Testing	0%	36 - 42										Т					_								
Total Time to Completion		74 - 80				1																- 1			


.

1

THE IMPLEMENTATION OF THE DEFERRED HEAVY RAIL PROJECT TO I-405 RESUMES THE ENVIRONMENTAL CLEARANCE PROCESS

- The planning process for a San Fernando East-West rail line was deferred before the Locally Preferred Alternative was selected. An additional nine months is required to complete the Draft Environmental Impact Statement and select the Locally Preferred Alternative
- Completion of the Final Environmental Impact Statement requires four additional months
- Right-of-way acquisition begins once all engineering work is complete and falls within a one-year time frame. Most of the right-of-way along the Burbank / Chandler right-of-way is already owned by the MTA
- Completion of construction and testing will require approximately 3 to 3 ½ years

IMPLEMENTATION TIME FRAME FOR SAN FERNANDO VALLEY LIGHT RAIL



R al Transit Alternatives Analysis

.

1

THE IMPLEMENTATION OF LIGHT RAIL ON THE BURBANK / CHANDLER RIGHT-OF-WAY CAN USE WORK COMPLETED FROM THE DEFERRED PLANNING PROCESS

- Most of the environmental clearance work for the right-of-way between the North Hollywood station and the I-405 freeway is complete. A new environmental process must be initiated for the portion of the route west of the I-405 freeway
- An additional year is required to complete the Draft EIS and select the Locally Preferred Alternative
- Completion of the Final Environmental Impact Statement will require an additional four months
- Right-of-way acquisition begins once all engineering work is complete and falls within a one-year time frame. Most of the right-of-way along the Burbank / Chandler right-of-way is already owned by the MTA
- Completion of construction and testing will require approximately 3 to 4 years

IMPLEMENTATION TIME FRAME FOR SAN FERNANDO VALLEY BUSWAY

	Percent	Months to	MOI		5																				
PROJECT PHASE	Complete	Complete		6	1	2	18	1	24	30	3	36	42	2	48	54	6	0	66	72	7	78	84	90	
												Г													Τ
Alternatives Analysis	100%	0							_																
Draft EIS	35%	6																							
DEIS Review	0%	6																							T
Final EIS	0%	4			T																				
Preliminary Engineering	0%	12															1								T
Procurement Strategy / ROD	0%	6			Τ																				T
Final Design / Engineering	0%	12		-	-												1				-	1			
Right-of-Way Acquisition	90%	12			1				Т				1				1					1			1
Contractor Bid	0%	4			1			1	1																1
Construction	0%	24										Π													T
Total Time to Completion		62																							

i.

San Fernando Valley Alternatives Timelines – Bus Transitway

THE IMPLEMENTATION OF A BUSWAY ON THE BURBANK / CHANDLER RIGHT-OF-WAY TO WARNER CENTER CAN BORROW FROM WORK COMPLETED IN THE DEFERRED PLANNING PROCESS

- Most of the environmental clearance work for the right-of-way east of the I-405 freeway is complete. A new environmental process must be initiated for the portion of the route west of the I-405 freeway. An additional year is required to complete the Draft EIS and select the Locally Preferred Alternative
- Completion of the Final Environmental Impact Statement requires an additional four months
- Right-of-way acquisition begins once all engineering work is complete and falls within a one-year time frame. Most of the right-of-way along the Burbank / Chandler right-of-way is already owned by the MTA
- Completion of construction will require approximately 3 years

SUMMARY RESULTS FOR SAN FERNANDO CORRIDOR ALTERNATIVES

Alternative	Capital Costs (\$M)	Operating Costs (\$M)	Estimated Ridership	Estimated Time Before Construction (months)	Mobility	Transit Dependence	Reliability	Community Impact	Cost Effectiveness
Heavy Rail: North Hollywood Station to I-405	920.0	12.7	15,900	38					
Light Rail At-Grade Burbank / Chandler Right-of-Way: North Hollywood Station to Warner Center	1,126.1	22.6	23,400	38					
Bus Transitway At- Grade Burbank / Chandler Right-of-Way: North Hollywood Station to Warner Center	173.0	14.0	16,100	38					

KEY Most Favorable _____ Least Favorable or or High Low

L

÷.

ĩ

~ ~ ~

APPENDIX 3.1 EVALUATION OF ALTERNATIVES


** •

INTENTIONALLY LEFT BLANK

. ×*.-

. • • •

PERFORMANCE EVALUATION MAIN TASKS



4

Performance Evaluation Framework


PERFORMANCE EVALUATION FOR THE MTA ALTERNATIVES HAS NOW BEEN COMPLETED

- The Project teams utilized the "short list" of options developed for Milestone 2
- Project teams fleshed out each alternative in terms of individua I data fields necessary to calculate the performance measures, both quantitatively and qualitatively
- The MTA regional travel demand model constituted one of the key inputs for trip generation, vehicle delay and other mobility and environmental issues
- Input from community focus groups, government ad-hoc, peer review panels was incorporated throughout the process

Performance Evaluation Framework

.

THE EXISTING FRAMEWORK INCORPORATES EIGHT GOALS




OUTREACH INPUT TO EVALUATION GOALS

Performance Area	Average Ranking
Mobility/Accessibility	1.98
Transit Dependency	2.88
Reliability	2.92
Cost Effectiveness	3.74
Community Impacts	4.02
Economic	4.10
Safety	4.59
Environmental	4.61

Performance Evaluation Framework

EACH ALTERNATIVE IS PRESENTED BASED ON A TWO-TIER EVALUATION SYSTEM, REFLECTING EXTERNAL FEEDBACK RECEIVED (E.G., AD-HOC, PEER REVIEW) VIS-A-VIS THE RELATIVE IMPORTANCE OF EACH MEASUREMENT AREA




• *

Performance Evaluation Framework...Mobility

MOBILITY EVALUATION INCLUDES FOUR SEPARATE SERIES OF PERFORMANCE MEASURES

- **Market Size** corresponds to the total number of additional transit trips generated as a result of each alternative, compared to the base case for 2010. Total transit trips in the County are listed, as well as the alternative transit trip percentage of those total trips
- **Mobility Index** corresponds to the average person throughput for the county. The mobility index is presented compared to the base case and as percentage increase over the base case
- Vehicle Delay represents the total number of hours lost due to congestion for all Los Angeles County trip makers
- **Job Accessibility** is the percent of total employment that can be reached within one hour of transit travel time (including waiting, walking, and the travel time on the bus or rail system)

TRANSIT DEPENDENCE INDEX MAP Eastside Corridor - Heavy Rail Options



A3.1-5F

Performance Evaluation Framework...Transit Dependency

THE DEGREE OF TRANSIT DEPENDENCE FORMS A CRITICAL COMPONENT OF THE EVALUATION FRAMEWORK

- **Transit Dependence Index** This Index corresponds to a geographic superposition of three critical drivers to transit dependency: population density, income level, and low auto ownership. The overall Index is developed by comparing the alignments of each alternative with transit dependence "zones" and overall Origin-Destination patterns for the Community Statistical Area. The end result is a transit dependence Index which varies from "low" to "very high" for each alternative
- **Job Accessibility** The percent of total employment that can be reached within one hour of transit travel time for the transit dependent public (including waiting, walking, and the travel time on the bus or rail system)

COST EFFECTIVENESS AIMS TO ANSWER TWO QUESTIONS: HOW MUCH AND HOW EFFICIENTLY ARE THE DOLLARS SPENT

- **Project Costs** include capital and operating costs. Capital costs typically last only for the construction period, while operating and maintenance costs last for the entire life of the project
- **Cost Efficiency** is listed in terms of cost per trip and cost per passenger mile. The first measure addresses each trip made, the second incorporates also the length of each trip

Performance Evaluation Framework...Reliability

!

THE RELIABILITY MEASURE REFERS TO EXPECTED SERVICE RELIABILITY FROM ALTERNATIVES, BUT IT IS BASED ON PAST MTA EXPERIENCE

ALTERNATIVE	Model Notes		REL	IABILI	ГҮ	
	WOULD NOTES	Very Reliable	•	Reliable		Moderately Reliable
HR to First / Lorena	E-1 Suspended					
HR to Chavez/ Soto (Without Little Tokyo Station)	E-2 HRT)			
LR from Union Station to Whittier/Atlantic Blvd.	E-5 LRT					
Rapid Bus (Atlantic Blvd. / Santa Monica)	E-4 BusWay					

COMMUNITY IMPACTS ARE CRITICAL IN CONSIDERING ANY MAJOR ALTERNATIVE AND INCORPORATE TEN INDIVIDUAL ELEMENTS

COMMUNITY IMPACT		EXAMPLE
Impact on Property Values		Positive impact on property values due to new heavy rail line
Impact on Businesses		Positive impact due to neighborhood attractiveness
Impacts on Security		Reduced community security due to vagrants drawn by station
Impacts on Aesthetics		Reduce aesthetics due to elevated light rail line and associated
		catenary
Noise Impacts	⇒	Negligible surface impact with subterranean metro
Impacts on Traffic Lanes		Negative due to transforming a lane to a dedicated bus transitway
Community Response		Negative if despite environmental mitigation, significant components
		of the community are against the project
Household Relocations		Significant impact with light rail system construction
Community Facility Relocations		Negligible with subterranean metro
Historic Site Relocations		Probably significant even if only one or two facilities need relocation

Performance Evaluation Framework...Combined Tier 1 Measures

1

۲

1

COMBINED TIER ONE MEASURES CAN BE COMPARED WITHIN SEPARATE CORRIDORS OR ACROSS CORRIDORS AS NEEDED

	MOBLITY TRANSIT DEPENDENCE COST EFFECTIVENESS						0000000				
ALTERNATIVE	in crease In Market Share	In crease In Mobility In de x	Ve hicle Del ay	Job Accessibility	Transit Dependence In dex	In crease In Job Accessibility In de x	Magnitude of Project Costs	Cost Efficiency / Total Trips	Subsidy/ Trip	RELIABILITY	COMMUNITY IMPACT MATRIX
WESTSIDE											
HR to Pico / San Vicente	0	•		•		O		•	-		-
HR to Wilshire/ Fairfax	•	•	•	•	•	•	•	0	-		-
Blue Line Exposition Branch	•	O	O		•		•	O	-	•	-
Rapid Bus (Atlantic Bwd. / Santa Monica	•	0		•		•	O		-	•	
Bus Transitway Along Exposition ` Blvd.						-	-	-	-	•	-
	0	O Moderate	High	Very High]						

ADDITIONAL MEASURES CONSIDERED IN THE PROJECT WILL INCLUDE ECONOMIC IMPACTS, ENVIRONMENTAL EMISSIONS, AND SAFETY

ECONOMIC IMPACTS	ENVIRONMENTAL EMISSIONS	SAFETY
Jobs Supported - jobs supported by capital expenditures - jobs supported by operating expenditures	Auto Emissions - includes Reactive Organic Gases, hydrocarbons and nitrous oxides	Passenger Accidents/Boarding
Gross Area Product	Bus Emissions	Pedestrian Accidents/100,000 train miles (trains) Pedestrian Accidents/100,000 VMT (bus)
		Vehicle Accidents/100,000 train miles (trains) Vehicle Accidents/100,000 VMT (bus)

BOTH TIER 1 AND TIER 2 MEASURES ARE INCLUDED IN THE FINAL PROJECT EVALUATION MATRIX

Results...

PERFORMANCE EVALUATION RESULTS ARE PRESENTED IN THE NEXT THREE PAGES

- Top Down Summaries provide "Harvey Ball" results for each alternative, by study corridor (i.e., Eastside, Westside, San Fernando Valley)
- While the definitions of the harvey balls vary by performance measure (e.g., higher degree of safety versus lower degree of safety, higher mobility impact versus lower mobility impact), each alternative can consistently be compared based on a "most favorable", "least favorable" basis.
- The five performance measurement categories in Tier 1 are presented first, followed by the three categories in Tier 2.

DETAILED HARVEY BALL AND NUMERIC RESULTS PER ALTERNATIVE ARE PROVIDED IN APPENDIX 3.2

Results...Eastside Corridor

EASTSIDE CORRIDOR RESULTS INCLUDE...

TIER 1 MEASURES

Alternative	Model Note	Mobility	Transit Dependency	Reliability	Community Impacts	Cost Effectiveness
Heavy Rail to First/Lorena	E-1 Suspended	•				
Heavy Rail to Chavez/Soto (without Little Tokyo Station)	E-2 HRT					\bigcirc
Light Rail from Union Station to Whittier / Atlantic	E-5 LRT					
Bus Transitway from Union Station to Whittier / Atlantic	E-4 Transitway					•

TIER 2 MEASURES

Alternative	Model Note	Economic	Safety	Environmental
Heavy Rail to First/Lorena	E-1			
	Suspended			
Heavy Rail to Chavez/Soto (without Little	E-2 HRT			
Tokyo Station)				
Light Rail from Union Station to Whittier /	E-5 LRT			
Atlantic				
Bus Transitway from Union Station to	E-4			
Whittier / Atlantic	Transitway			

KEY

Most Favorable or High C Least Favorable or Low

Results...Westside Corridor

WESTSIDE CORRIDOR RESULTS INCLUDE...

TIER 1 MEASURES

.

Alternative	Model Note	Mobility	Transit	Reliability	Community	Cost
			Dependency		Impacts	Effectiveness
Heavy Rail to Pico/San	W-1					
Vicente	Suspended					
Heavy Rail to Wilshire/Fairfax	W-4 HRT					
Blue Line to Exposition Branch	W-3 LRT					
Bus Transitway along	W-2 Busway					
Exposition Branch						

TIER 2 MEASURES

Alternative	Model Note	Economic	Safety	Environmental
Heavy Rail to Pico/San Vicente	W-1			
	Suspended			5
Heavy Rail to Wilshire/Fairfax	W-4 HRT			
Blue Line to Exposition Branch	W-3 LRT			
Bus Transitway along Exposition Branch	W-2 Busway			

KEY

Most Favorable or High Least Favorable or Low		Most Favorable or High	\bigcirc	Least Favorable or Low
---	--	------------------------	------------	------------------------

Results...San Fernando Valley Corridor

SAN FERNANDO VALLEY CORRIDOR RESULTS INCLUDE...

TIER 1 MEASURES

1

Alternative	Model Note	Mobility	Transit	Reliability	Community	Cost
			Dependency		Impacts	Effectiveness
Heavy Rail to I-405 (Subway /	V-1 HRT					
Aerial combination)						
Light Rail (or DMU) to Warner	V-2 LRT					
Center						
Bus Transitway (North	V-3					. •
Hollywood to Warner Center)	transitway			-		

TIER 2 MEASURES

Alternative	Model Note	Economic	Safety	Environmental
Heavy Rail to I-405 (Subway / Aerial	V-1 HRT			
combination)				
Light Rail (or DMU) to Warner Center	V-2 LRT			
Bus Transitway (North Hollywood to	V-3			
Warner Center)	Transitway			

KEY ·

Most Favorable or High Least Favorable or Low

PERFORMANCE MEASURE EVALUATION RESULTS DETAIL APPENDIX 3.2

The Eastside Corridor

.

.

						MOE	BILITY				TR	ANSIT DEPEN	IDENCE		COST EFFECT	IVENESS		RELIABILITY
		Route		Market			Mobility Inde	x	Annual, Transit		Transit			Project U	Init Costs	Cost Eff	Iclency	
ALTERNATIVE	Model Notes	Miles	Additional Daily Transit Trips Generated	Daily Transit Trice	Percent of Total	Alternative Specific	Base 2010	Percent Change	Travel Time Decrease	Job Accessibility	Dependence Index	index Composition	Job Accessibility Index	Capital Costs / Mile (MTA)	O&M Costs / Mile (BAH)	Annualized Lifecycle Cost / Trip	Subeidy / Trip	Reliability per Mode
HR to First / Lorena	E-1 Suspended	3.62	1,715	883,619	0.19%	43.37	43.32	0.12%	3,432	16.29	3.3	50% Very High, 40% High, 10% Low	21.98	\$254,861,878	\$2,900,552.49	\$32,886	\$5,907	Very low to low
HR to Chave2/ Solo Without Little Tokyo Station)	E-2 HRT	1.92	349	882,253	0.04%	43.42	43.32	0.23%	1,552	16.26		70% Very High, 20% High, 10% Low	21.95	\$250,572,917	\$1,770,833 33	\$84,241	\$9,527	Very low to low
LR from Union Station to Whittier/Atlantic Street.	E-5 LRT	5.9	1,762	883,666	0.20%	43.40	43.32	0.18%	4,173	16.40	2.95	60% Very High, 15% High, 10% Low, 15% Very	22.10	\$73,033,898	\$1,677,966.10	\$15,551	\$5,403	Low
Bus Transitway (Union Station to Whittier Atlantic Blvd.)	E-4 Transitway	5.9	-2,282	879,622	-0.26%	43.24	43 32	-0 18%	1,266	16 20	2 95	Low 60% Very High, 15% High, 10% Low, 15% Very Low	21.90	\$14,525,424	\$1,067,796.61	N/A	N/A	Low

						MO	BILITY				TA	ANSIT DEPEN	NDENCE		COST EFFECT	IVENESS		RELIABILITY
		Route		Market			Mobility Inde	x	Annual, Transit		Transit			Project Unit Costs		Cost Efficiency		
ALTERNATIVE	Model Notes	Miles	Additional Daily Transit Trips Generated	Daily Transit	Percent of Total	Alternative Specific	Base 2010	Percent Change	Traund Time	Job Accessibility	Desendence	Work Destination	Job Accessibility Index	Capital Costs / Mile (MTA)	O&M Costs / Mile (BAH)	Annualized Lifecycle Cost / Trip	Subsidy / Trip	Reliability per Mode
IR to First / Lorena	E-1 Suspended	3.62			0	•	N/A	•		<u>(</u>			0	((_)	<u>()</u>	0	0	•
HR to Chavez/ Solo Without Little Tokyo Station)	E-2 HRT	1.92	0	0	0	•	N/A		0	0	•	•	()	(<u> </u>		0	<u>()</u>	•
R from Union Station to Whittler/Atlantic Street.	E-5 LRT	5.9	9	•	0		N/A		0		•	•	0			.	0	
Bus Transitway - (Union Station to Whittler Atlantic Blvd.)	E-4 Transitway	5.9	0	٢	\bigcirc	Ō	N/A	<u> () </u>	0	0	•		Ō		0	N/A	N/A	•

The Westside Corridor

,

						MC	BILITY				TF	ANSIT DEPEN	IDENCE		COST EFFECT	VENESS		RELIABILITY
		Route		Market			Mobility Inde	x	Annual Transi		Transit			Project Unit Costs		Cost Efficiency		
ALTERNATIVE	Model Note	Miles	Additional Daily Transit Trips Generated	LA County Daily Transit Trips	Percent of Total	Alternative Specific	Base 2010	Percent Change	Travel Time Decrease	Job Accessibility	Dependence Index	Index Composition	Job Accessibility Index	Capital Costs / Mile (MTA)	O&M Costs / Mile (BAH)	Annualized Lifecycle Cost / Trip	Subsidy / Trip	Reliability per Mode
HR to Pico / San Vincent	W-1 Suspended	2.56	1,925	883,829	0.22%	43.39	43.32	0.16%	6,858	16.34	1.35	15% Very High, 25% High, 60% Very Low	22.08	\$237,265,625	\$1,718,750	\$18,026	\$2,070	Very low to low
HR to Wilshire/ Fairfax	W-4 HRT	3.17	2,142	884,046	0.24%	43.38	43.32	0.14%	9,464	16.38	1.6	30% High, 70% Low	22.17	\$271,198,738	\$2,050,473	\$24,276	\$2,819	Very low to low
Blue Line Exposition Branch	W-3 LRT	18	3,395	885,299	0.38%	43.34	43.32	0.05%	15,145	16.33	1.9	30% Very High, 70% Low	22.12	\$54,861,111	\$1,177,778	\$17,791	\$6,029	Low
Exposition Busway	W-2 Busway	18.5	8,663	890,567	0.97%	43.33	43.32	0.02%	22,334	16.54	1.5	20% Very High, 70% Low, 10% Very Low	22.46	\$16,989,189	\$297,297	\$2,736	\$420	Low

										TR	ANSIT DEPEN	NDENCE		COST EFFECT	VENESS		RELIABILITY
1 1	Route		Market			Mobility Inde	x	Annual Transi		Transit			Project L	Jnit Costs	Cost E	fficiency	
Model Note	Miles	Additional Daily Transit Trips Generated			Alternative Specific	Base 2010	Percent Change	Travel Time Decrease	Job Accessibility	Dependence Index	Work Destination	Job Accessibility Index	Capital Costs / Mile (MTA)	O&M Costs / Mile (BAH)	Annualized Lifecycle Cost / Trip	Subsidy / Trip	Reliability per Mode
W-1 Suspended	2.56	•	•	, O	•	N/A	•	•	•	0	•	0	0	O	0	•	٠
W-4 HRT	3.17	•	•	•	•	N/A	•	•	0	•	•	0	0	O	0		٠
W-3 LRT	18	•	•	•	•	N/A	•	•	0	•	0	0	•	0	0	•	•
W-2 Busway	18.5				0	N/A	•	•		•		•		•		•	•
	W-4 HRT W-3 LRT	W-1 Suspended 2.56 W-4 HRT 3.17 W-3 LRT 18	Model Note Miles Additional Daily Transat Tripa Generated W-1 Suspended 2.56 W-4 HRT 3.17 W-3 LRT 18	Model Note Miles Additional Daly Transit Trip Generated L. County Daly Transit Trip W-1 Suspended W-1 Suspended 2.56 Image: County State	Model Note Route Miles Additional Daly Transk Trips Generated LA County Daly Transk Generated Percent of Total W-1 Suspended 2.56 Image: Constraint of the second of the seco	Model Note Route Miles Market Alternative Transk Trips Percent of Total Alternative Specific W-1 Suspended 2.56 Image: Constraint of the specific Image: Constraint of the specific Image: Constraint of the specific W-1 HRT 3.17 Image: Constraint of the specific Image: Constraint of the specific Image: Constraint of the specific W-3 LRT 18 Image: Constraint of the specific Image: Constraint of the specific Image: Constraint of the specific	Model Note Route Miles Additional Daly Transk Trips LA County Daly Transk Trips Percent of Total Atemative Specific Base 2010 W-1 Suspended 2.56 Image: Construction of the specific Image: Construction of the specific </td <td>Model Note Route Miles Market Mobility Index Additional Daily Transt Trips Cashy Daily Transt Trips Percent Trips Percent Change W-1 Suspended 2.58 Image: Cash Strips Image: Cash</td> <td>Model Note Route Miles Market Mobility Index Annual Transl Travel Travel Travel Travel Travel Dely Transl Trips Percent of Total Assenative Specific Base 2010 Percent Charge Percent Decrase W-1 Suspended 2.56 Image Imag</td> <td>Model Note Route Miles Market Mobility index Additional Daty Trans Trajo Market Mobility index Atternative Trajo Atternative Parcent of Total Base 2010 Parcent Change Annual. Trans Travel Time Decrease Job Accessibility W-1 Suspended 2.56 Image: Comparison of Comparison of Comparison of Comparison of Comparison of Comparison of Comparison of Comparison of Comparison of Comparison of Comparison of Comparison</td> <td>Model Note Route Miles Market Mobility Index Annual. Transi Charge Job Accessibility Transit Dependence Index W-1 Suspended 2.56 Image: Comparison of the compa</td> <td>Model Note Route Miles Market Mobility Index Annual. Transit Charge Job Transit Dependence Index Work Destination Model Note Miles Additional Daly Transit Trips Accessibility Transit Trips Percent of Trips Alernative Specific Base 2010 Percent Charge Transit Descrease Dob Accessibility Transit Dependence Index Dob Method Dob Accessibility Transit Dependence Index Work Destination W-1 Suspended 2.55 Image: Comparison of transit Trips Image: Compari</td> <td>Model Note Route Miles Market Mobility Index Annual. Tranal Travel Travel Trave</td> <td>Model Note Route Miles Market Mobility Index Annual. Tranal Travel Travel Trave</td> <td>Model Note Route Miles Market Mobility Index Annual. Transit Dependence Transit Dependence Work Market Job Accessibility Index Project Unit Costs Model Note Additional Daly Transit Generated Accounty Transit Trips Project Unit Costs Accessibility Index Job Accessibility Index Job Accessibility Index Job Accessibility Index Dependence (urin) Obm Accessibility Index Obm Accessibility Index Capital Costs / Mile (urin) Obm Accessibility Index Obm Accessibility Index Capital Costs / Mile (urin) Obm Accessibility Index Obm Accessibility Index</td> <td>Model Note Route Miles Market Mobility Index Annual. Transit Dependence Job Accessibility Transit Dependence Mork Destination Job Accessibility Project Unit Costa Costa Costa Model Note Miles Additional Daly Transit Generated Accounty Transit Generated Project Unit Costa Aternative Specific Base 2010 Percent Change Project Unit Costa Costa / Mile (MV) Costa / Mile (MV</td> <td>Model Note Route Miles Market Mobility Index Annual. Tranel Travel Travel Trav</td>	Model Note Route Miles Market Mobility Index Additional Daily Transt Trips Cashy Daily Transt Trips Percent Trips Percent Change W-1 Suspended 2.58 Image: Cash Strips Image: Cash	Model Note Route Miles Market Mobility Index Annual Transl Travel Travel Travel Travel Travel Dely Transl Trips Percent of Total Assenative Specific Base 2010 Percent Charge Percent Decrase W-1 Suspended 2.56 Image Imag	Model Note Route Miles Market Mobility index Additional Daty Trans Trajo Market Mobility index Atternative Trajo Atternative Parcent of Total Base 2010 Parcent Change Annual. Trans Travel Time Decrease Job Accessibility W-1 Suspended 2.56 Image: Comparison of Comparison of Comparison of Comparison of Comparison of Comparison of Comparison of Comparison of Comparison of Comparison of Comparison	Model Note Route Miles Market Mobility Index Annual. Transi Charge Job Accessibility Transit Dependence Index W-1 Suspended 2.56 Image: Comparison of the compa	Model Note Route Miles Market Mobility Index Annual. Transit Charge Job Transit Dependence Index Work Destination Model Note Miles Additional Daly Transit Trips Accessibility Transit Trips Percent of Trips Alernative Specific Base 2010 Percent Charge Transit Descrease Dob Accessibility Transit Dependence Index Dob Method Dob Accessibility Transit Dependence Index Work Destination W-1 Suspended 2.55 Image: Comparison of transit Trips Image: Compari	Model Note Route Miles Market Mobility Index Annual. Tranal Travel Travel Trave	Model Note Route Miles Market Mobility Index Annual. Tranal Travel Travel Trave	Model Note Route Miles Market Mobility Index Annual. Transit Dependence Transit Dependence Work Market Job Accessibility Index Project Unit Costs Model Note Additional Daly Transit Generated Accounty Transit Trips Project Unit Costs Accessibility Index Job Accessibility Index Job Accessibility Index Job Accessibility Index Dependence (urin) Obm Accessibility Index Obm Accessibility Index Capital Costs / Mile (urin) Obm Accessibility Index Obm Accessibility Index Capital Costs / Mile (urin) Obm Accessibility Index Obm Accessibility Index	Model Note Route Miles Market Mobility Index Annual. Transit Dependence Job Accessibility Transit Dependence Mork Destination Job Accessibility Project Unit Costa Costa Costa Model Note Miles Additional Daly Transit Generated Accounty Transit Generated Project Unit Costa Aternative Specific Base 2010 Percent Change Project Unit Costa Costa / Mile (MV) Costa / Mile (MV	Model Note Route Miles Market Mobility Index Annual. Tranel Travel Travel Trav


.

						MO	BILITY				TR	ANSIT DEPEN	DENCE		COST EFFECT	VENESS		RELIABILITY
	Model	Route		Market		Mobility Index			Annual, Transi		Transit			Project Unit Costs		Cost E	Miclency	
ALTERNATIVE	Notes	Miles	Additional Daily Transit Trips Generated	LA County Daily Transit Trips	Percent of Total	Alternative Specific	Base 2010	Percent Change	Travel Time Decrease	Job Accessibility	Dependence Index	Index Composition	Job Accessibility Index	Capital Costs / Mile (MTA)	O&M Costs / Mile (BAH)	Annualized Lifecycle Cost Trip	Subsidy / Trip	Reliability per Mode
HR to I - 405 (Subway / Aerial Combination)	V-1 HRT	6.01	7,389	889,293	0.83%	43.39	43.32	0.16%	10,043	16.32	1	100% Low	22.03	\$153,078,203	\$2,113,144.76	\$7,931	\$1,503	Very low to low
LR (or DMU) to Warner Center	V-2 LRT	13.8	(534)	881,370	-0.06%	43.32	.43.32	0.00%	8,330	16.15	1	100% Low	21.78	\$81,601,449	\$1,637,681.16	N/A	N/A	Low
Bus Transitway (N. Hollywood / Warner Center)	V-3 Transitway	14	3,969	885,873	0.45%	43.34	43.32	0.05%	7,732	16.23	1	100% Low	21.92	\$13,478,571	\$350,000.00	\$3,250	\$1,019	Low
Bus Transitway (N. Hollywood / Warner Center)	V-3 Transitway	14	3,969	885,673	0.45%	43.34	43.32	0.05%	7,732	16.23	1	100% Low	21.92	\$13,478,571	\$350,000.00	\$3,250	\$1,019	Le

The	San	Fernando	Valley	Corridor

						MO	BILITY				TR	ANSIT DEPEN	IDENCE		COST EFFECT	VENESS	T	RELIABILITY
	Model	Route		Market			Mobility Inde	x	Annual, Transi		Transit			Project U	Init Costs	Cost E	Miclency	
ALTERNATIVE	Notes	Miles	Additional Daily Transit Trips Generated	LA County Daily Transit Trips		Alternative Specific	Base 2010	Percent Change	Travel Time Decrease	Job Accessibility	Dependence Index	Work Destination	Job Accessibility Index	Capital Costs / Mile (MTA)	O&M Costs / Mile (BAH)	Annualized Lifecycle Cost Trip	Subsidy / Trip	Reliability per Mode
HR to I - 405 (Subway / Aerial Combination)	V-1 HRT	6.01		•	•	•	N/A	•	•	0	0	•	•	•	٢	•	•	•
LR (or DMU) to Warner Center	V-2 LRT	13.8	•	0	0	0	N/A	0	•	0	O	•	0	0	O	N/A	N/A	•
Bus Transitway (N. Hollywood / Warner Center)	V-3 Transitway	14	•		•	0	N/A			0	0	•	•				•	•

EASTSIDE CORRIDOR - SUSPENDED PROJECT



A3.2-4


Legend Very High High Moderate Low Other Metrorail - Existing or Under Construction Modified Alignment to Chavez / Soto

EASTSIDE CORRIDOR - MODIFIED ALIGNMENT TO CHAVEZ/SOTO

.

.

A3.2-5



EASTSIDE CORRIDOR - LIGHT RAIL ALIGNMENT


۲

1

EASTSIDE CORRIDOR - BUS TRANSITWAY

t


· · · ·



WESTSIDE CORRIDOR - HEAVY RAIL OPTIONS

.


t



WESTSIDE CORRIDOR - SUSPENDED PROJECT


1

i.




WESTSIDE CORRIDOR - WILSHIRE ALIGNMENT

,




WESTSIDE CORRIDOR - EXPOSITION LIGHT RAIL




WESTSIDE CORRIDOR - EXPO BUS TRANSITWAY


1

1






SAN FERNANDO VALLEY - DEFERRED PROJECT



SAN FERNANDO VALLEY - LIGHT RAIL

A3.2-14



SAN FERNANDO VALLEY - BUS TRANSITWAY

1 1 1

1

.

The Eastside Corridor

0								AL	TERM	ATIV	'ES								
GENERAL COMMUNITY	н	R to First / (Suspen		na		R to Cl hout L						Unio /Atlan				us Tra on To		ier/Atl	
IMPACTS	-5 Negative	0 No Effec	·		-5 Negative		0 Io Effect		+5 Positive	-5 Negative		0 No Effect		+5 Positive	-5 Negative		0 No Effect		+5 Positive
Impacts on Property Values				1					1					1			1		
Impacts on Businesses			1					1					1					1	
Impacts on Security		1					1					1					1		
Impacts on Aesthetics		:		1					1			1					1		
Noise Impacts		1					1				1						1		
Impacts on Traffic Lanes		1					1				1					1			
Community Response *				1					1		1					1			
* Where Applicable												(•						
		Posiive				Positi	ve				Sligh	nt Miti	gable	•			Neut	ral	

Q						AL.	TERM	ATIVE	S						
COMMUNITY IMPACTS ON RELOCATIONS	HF	to First / (Suspend			R to Chave nout Ltl. T		190		om Unio tier/Atlan				s Transiv n To Wh Biv	ittier/A	
	Minor		Maja	r Minor			Major	Minor	in goog		Major	Minor			Major
Household Relocations			1			1				1		1			
Community Facility Relocations	1				1					1		1			
Historic Site Relocations	1				1					1		1			

Neutral

Less Positive

Sligt Mitigable

Positive

The Westsdie Corridor

0						ALTER	ATIVE	ES							
GENERAL COMMUNITY IMPACTS	-6	to Pico / Sar (Suspend 0 No Eliet			o Wilshire / O No Effect	/ Fairfax +5 Positive	Blu -5 Negative	Br	e Exp anch e		-5	osition	Bus 1 0 No Effect		way +6
mpacts on Property Values			1			1				1				1	
mpacts on Businesses			1			1				1				1	
mpacts on Security		1			1				1				1		
mpacts on Aesthetics		1			1			1					1		
oise Impacts		1			1			1				1			
mpacts on Traffic Lanes		1			1				1				1		
ommunity Response *		1			1				1				1		
* Where Applicable		•			•			J)		
	F	ositive		P	ositive		N	eutral	I			Les	s Pos	sitive	

0				ALTER	ATIVE	ES			
COMMUNITY IMPACTS ON RELOCATIONS		Pico / San Vincent (Suspended)	HR	to Wilshire / Fairfax	Blu	e Line Exposition Branch		Exposition Busw	ay
	Minor	illajor		and the second se			Minor		Major
ousehold Relocations	1		1		1		1		maper
ommunity Facility Relocations	1		1		1		1		
istoric Site Relocations	1		1		1		1		
		•		•		•		•	
		Positive		Positive		Positive		Positive	

A3.2-17

4

1

The San Fernando Valley Corridor

0				AL	TERNA	TIVES	1				
GENERAL COMMUNITY	HR to	I-405 (aerial Comb	subway / o.)	LR (c	or DMU) t Cente	o Warner r	Bus T		tway (ner Ce		lly'd. /
IMPACTS	-5 Negative	0 No Effect	+5	-5 Negative	0 No Effec		-5 Negative		0 No Effect		+5 Positive
Impacts on Property Values			1			1				1	
Impacts on Businesses			1			1				1	
Impacts on Security		1			1				1		
Impacts on Aesthetics		1			1			1			
Noise Impacts		1			1			1			
Impacts on Traffic Lanes		1			Ĵ				1		
Community Response *		1			1				1		

• Where Applicable

-







Less Positive

Slight Mitigable

0

Neutral

0					1	LTE	RNA'	TIVES						
COMMUNITY IMPACTS ON RELOCATIONS	HR t	o I-40 aer	5 ial Co	way /	LF	•	MU) to Center	o Warne r	ər	Bus		itway ner Ce	(N. Hol enter)	ly'd./
KELOGAHONG	Minor			 Major	Minor				Major	Minor				Major
Household Relocations	1				1					1				
Community Facility Relocations		1				1					1			
Historic Site Relocations	1				1					1				

.

t

The Eastside Corridor

			ECON	OMIC		E	NVIRONMEN	IT		SAF	ETY	
	Model	Job	Jobs	Gross Area	Gross Area		Air Quality Index	1		Safety	Index	
ALTERNATIVE	Notes	Supported, Operating	Supported, Capital	Product, Operating (\$98Millions)	Product, Capital (\$98Millions)	Additional Transit Emissions	Non Transit Vehicular Emissions (kgs)	Percent of NTVE	Pass. Accidents per 100,000 Boardings	Pass. Accidents per 100,000 Hub/Train Miles	Traffic Accidents per 100,000 Hub/Train Miles	Safety Index
		!										
HR to First / Lorena	E-1 Suspended	311	22189	10.43	1099.74	N/A	242,992	N/A	0.08	0.00	1.33	Composite
						(stationary source)						
HR to Chavez/ Soto (Without Little Tokyo Station)	E-2 HRT	101	11,570	3.38	573.47	N/A	243,024	N/A	0.08	0.00	1.33	Composite
н.						(stationary source)						
LR to Little Tokyo	E-5 LRT	293	10,363	9.83	513.63	N/A	243,026	N/A	0.15	0.83	4.17	Composite
						(stationary source)						
Bus Transitway (Union Station to Whittier Atlantic Blvd.)	E-4 Transitway	186	2,061	6.26	102.15	5,725	243,031	2.36%	0.40	0.06	2.69	Composite

			ECON	OMIC		E	NVIRONMEN	IT		SAF	ETY	
	Model	Job	Jobs	Gross Area	Gross Area		Air Quality Index	1		Safety	/ Index	
ALTERNATIVE	Notes	Supported, Operating	Supported, Capital	Product, Operating	Product, Capital	Additional Transit Emissions	Non Transit Vehicular Emissions (kgs)	Percent of NTVE	Pass. Accidents per 100,000 Boardings	Pass. Accidents per 100,000 Hub/Train Miles	Traffic Accidents per 100,000 Hub/Train Miles	Safety Index
HR to First / Lorena	E-1 Suspended	•		•								
HR to Chavez/ Soto (Without Little Tokyo Station)	E-2 HRT	0		0								•
LR to Little Tokyo	E-5 LRT											
Bus Transitway (Union Station to Whittier Atlantic Blvd.)	E-4 Transitway		0		0				•		•	•

Regional Transit Alternatives Analysis

1

t

1

The Westside Corridor

			ECON	IOMIC		E	NVIRONMEN	IT		SAF	ETY	
			Jobs	Gross Area	Gross Area		Air Quality Index			Safety	Index	
ALTERNATIVE	Model Notes	Job Supported, Operating	Supported, Capital	Product, Operating (\$98Millions)	Product, Capital (\$98Millions)	Additional Transit Emissions	Non Transit Vehicular Emissions (kgs)	Percent of NTVE	Pass. Accidents per 100,000 Boardings	Pass. Accidents per 100,000 Hub/Train Miles	Traffic Accidents per 100,000 Hub/Train Miles	Safety Index
			ļ									
HR to Pico / San Vincent	W-1 Suspended	130	14,608	4.37	724.02	N/A	243,021	N/A	0.08	0.00	1.33	Composite
						(stationary source)						
HR to Wilsher / Fairfax	W-4 HRT	192	20,676	6.45	1024.76	N/A	243,023	N/A	0.08	0.00	1.33	Composite
						(stationary source)						
Blue Line Exposition Branch	W-3 LRT	627	23,749	21.05	1177.10	N/A	243,021	N/A	0.15	0.83	4.17	Composite
						(stationary source)						
Exposition Busway	W-2 Busway	163	7,559	5.46	374.65	5,638	243,005	2.32%	0.40	0.06	2.69	Composite

			ECON	IOMIC	×	E	NVIRONMEN	NT		SAF	ЕТҮ	
	No. do to to to to to to		Jobs	Gross Area	Gross Area		Air Quality Index	1		Safet	y Index	
ALTERNATIVE	Model Notes	Job Supported, Operating	Supported, Capital	Product, Operating	Product, Capital	Additional Transit Emissions	Non Transit Vehicular Emissions (kgs)	Percent of NTVE	Pass. Accidents per 100,000 Boardings	Pass. Accidents per 100,000 Hub/Train Miles	per 100,000	Safety Index
HR to Pico / San Vincent	W-1 Suspended											
HR to Wilsher / Fairfax	W-4 HRT					•						
Blue Line Exposition Branch	W-3 LRT											
Exposition Busway	W-2 Busway										•	

Safest

Safest

Safe

Safer

.

.

The San Fernando Valley Corridor

		ECON	IOMIC		E	NVIRONMEN	1T		SAF	ETY	
Model		lobs	Gross Area	Gross Area		Air Quality Index			Safety	/ Index	
Notes	Job Supported, Operating	Supported, Capital	Product, Operating (\$98Millions)	Product, Capital (\$98Millions)	Additional Transit Emissions	Non Transit Vehicular Emissions (kgs)	Percent of NTVE	Pass. Accidents per 100,000 Boardings	Pass. Accidents per 100,000 Hub/Train Miles	Traffic Accidents per 100,000 Hub/Train Miles	Safety Index
		!									
V-1 HRT	376	22126	12.61	1096.64	N/A	243,004	N/A	0.08	0.00	1.33	Composite
					(stationary source)						
V-2 LRT	669	27083	22.44	1342.31	N/A	243,026	N/A	0.15	0.83	4.17	Composite
					(stationary source)						
V-3 Busway	145	4538	4.87	224.93	5,622	242,980	2.31%	0.40	0.06	2.69	Composite
	V-1 HRT V-2 LRT	Notes Job Supported, Operating V-1 HRT 376 V-2 LRT 669 V-3 Bueway 1	Model NotesJob Supported, OperatingJobs Supported, CapitalV-1 HRT37622126V-1 HRT66927083V-2 LRT66927083V-3 Busway11	Notes Job Supported, Operating Job Supported, Supported, Capital Product, Operating (\$98Millions) V-1 HRT 376 22126 12.61 V-2 LRT 669 27083 22.44	Model NotesJob Supported, OperatingJobs Supported, CapitalGross Area Product, Operating (\$98Millions)Gross Area Product, Capital (\$98Millions)V-1 HRT3762212612.611096.64V-2 LRT6692708322.441342.31V-3 Busnay	Model Notes Jobs Supported, Operating Jobs Supported, Capital Gross Area Product, Operating (\$98Millions) Gross Area Product, Capital V-1 HRT 376 22126 12.61 1096.64 V-2 LRT 669 27083 22.44 1342.31 V-3 Busway V-3 Busway V-1 V-1 N/A	Model Notes Job Supported Operating Jobs Supported, Capital Gross Area Product, Operating (\$98Millions) Gross Area Product, Capital (\$98Millions) Air Quality Index Model Product, Capital (\$98Millions) V-1 HRT 376 22126 12.61 1096.64 N/A (stationary source) N/A 243,004 V-2 LRT 669 27083 22.44 1342.31 N/A (stationary source) 243,026	Model NotesJob Supported, OperatingJobs Supported, CapitalGross Area Product, Operating (\$98Millions)Gross Area Product, CapitalAir Quality IndexV<1 HRT	Model Notes Job Supported, Operating Jobs Supported, Capital Gross Area Product, Operating (\$98Millions) Gross Area 	Model Notes Job Supported, Operating Jobs Supported, Capital Gross Area Product, Operating (\$98Millions) Gross Area Product, Capital (\$98Millions) Air Quality Index Percent of NTVE Pass. Accidents per 100,000 Boardings Pass. Accidents per 100,000 Hub/Train Miles V-1 HRT 376 22126 12.61 1096.64 N/A (stationary source) N/A 0.08 0.00 V-2 LRT 669 27083 22.44 1342.31 N/A (stationary source) N/A 243,026 N/A 0.15 0.83 V-3 Busuary Courted Cour	Model Notes Jobs Supported, Operating Jobs Supported, Capital Gross Area Product, Operating (\$98Millions) Gross Area Product, Capital Gross Area Product, Operating (\$98Millions) Air Quality Index Percent of Emissions Pass. Accidents per 100,000 Boardings Pass. Accidents per 100,000 Boardings Pass. Accidents per 100,000 Pass. Accidents per 100,000

			ECON	IOMIC		E	NVIRONMEN	IT		SAF	ETY	
	Model		Jobs	Gross Area	Gross Area		Air Quality Index			Safety	/ Index	
ALTERNATIVE	Notes	Job Supported, Operating	Supported, Capital	Product, Operating	Product, Capital	Additional Transit Emissions	Non Transit Vehicular Emissions (kgs)	Percent of NTVE	Pass. Accidents per 100,000 Boardings	Pass. Accidents per 100,000 Hub/Train Miles	Traffic Accidents per 100,000 Hub/Train Miles	Safety Index
HR to I - 405 (Subway / Aerial Combination)	V-1 HRT	•		•				•				•
LR (or DMU) to Warner Center	V-2 LRT											0
(14. Hollywood 7 warrier Center)	V-3 Busway	•	•					•			•	•

Safest

Safe

Safer

APPENDIX 4 DETAILS OF COST ESTIMATES

INTENTIONALLY LEFT BLANK

CAPITAL COSTS WERE DEVELOPED FOR EACH ALTERNATIVE BASED ON THE ALIGNMENT DEFINITIONS PRODUCED BY THE ALTERNATIVES ANALYSIS TEAM

- Three sets of independent capital cost estimates were developed for each alternative:
 - 1. MTA Estimates --- Capital cost estimates based on MTA's current cost experience
 - 2. Independent Estimates Independent capital cost estimates based on the average capital cost experience of other US transit operators.
 - Best Estimate Capital Costs These cost estimates represent the lowest believed to be attainable by MTA and include alternate contracting and management approaches (e.g. Design-Build)
- This costing approach was designed to address concerns that MTA capital costs are frequently higher than industry averages
 - The MTA Estimates provide an upper bound to the cost of each alternative
 - The Independent Estimates provide lower bound cost ranges based on the actual cost and construction experience of other operators — these lower bound estimates may not be attainable by MTA given local cost levels, labor agreements, etc.
 - The Best Estimate Capital Costs utilize:
 - a) MTA unit costs when the MTA costs are at the lower bound, are not significantly different from the independent costs or are believed to be more realistic for local conditions
 - b) Independent costs where attainable by MTA and significantly lower than MTA costs
 - c) A combination of the MTA and Independent based (primarily for soft-costs) based on the level of cost savings believed to be attainable by MTA (e.g., through alternate contracting and management techniques)

Capital Cost Data Sources

THE CAPITAL UNIT COSTS USED TO ESTIMATE THE TOTAL COST OF EACH ALTERNATIVE WERE DERIVED FROM MTA RECORDS AND FROM NATIONAL CAPITAL COSTING EXPERIENCE

- MTA estimates of capital costs for each alternative utilized MTA's "Planning Level" cost estimates:
 - These costs are regularly adjusted to reflect MTA's actual cost experience
 - Level of detail coincides with the asset types definitio ns defined for this study
 - Costing structure includes MTA's overhead (soft) costs including start-up costs, insurance, design and project management costs and contingencies
- The Independent unit capital cost estimates were derived from Booz •Allen's national capital cost database:
 - Database captures unit capital costs from all light rail, heavy rail and Busway/HOV projects completed in the US over the past 20-year period
 - Level of detail coincides with the asset types definitions defined for this study (see above)
 - Database identifies over 400 capital cost line items
 - Provides detailed descriptions of project alignments, design philosophy and other characteristics
 - Identifies year of project construction
 - Includes right-of-way, environmental mitigation, demolitions, utility relocation
 - Includes all soft-costs (engineering & design, construction management, project management, insurance, testing and start-up, etc.)
- All National Database costs have been converted to a common \$1998 baseline using FTA's Transit Capital Cost Price Index developed by Booz •Allen & Hamilton Inc.

Capital Unit Costs

SAMPLE UNIT COSTS FOR SYSTEMS, STATIONS AND VEHICLES AS USED FOR THE MTA AND INDEPENDENT COST ESTIMATES

CATEGORY	SUB-CATEGORY	MTA COSTS			INDEPENDENT COSTS*		
		Units	Heavy Rail	Light Rail	Units	Heavy Rail	Light Rail
Guideway	At-Grade-Ballast Guideway	Route Feet	\$2,580	\$900	Route Feet	\$1,000	\$760
	At-Grade-In-Street Guideway	Route Feet	NA	Not Available	Route Feet	NA	\$2,460
	Aerial Structure Guideway	Route Feet	\$6,500	\$6500	Route Feet	\$6,125	\$3,750
	Elevated Fill Guideway	Route Feet	\$3,500	\$3,500	Route Feet	\$1,760	\$690
	Underground Guideway – Cut & Cover	Route Feet	\$12,000	\$8,500	Route Feet	\$12,200	\$12,200
	Underground Guideway - Tunnel	Route Feet	\$10,000	Not Available	Route Feet	\$10,300	\$10,300
	Open Trench Guideway	Route Feet	\$6,500	\$3,500	Route Feet	\$5,500	\$4,500
	Grade Crossing		NA	\$250,000	Each	NA	\$180,000
	Trackwork (Incl. Special Trackwork)	Route Feet	\$420 - \$575	\$420 - \$480	Track Feet	\$675	\$140 - \$260
Facilities	Building		\$2,000,000	\$25,000,000	Rev. Vehicle	\$7,700,000	\$650,000
	Storage Yard	Lump Sum	to	to	Track Feet	\$440	\$160
	Major Shops		\$50,000,000	\$35,000,000	Rev. Vehicle	\$157,000	\$42,000

DRAFT UNIT CAPITAL COSTS — Guideway and Facilities (\$1998)†

* National averages based on experience of other US transit operators

† Draft cost estimates — estimates currently under review

£ .

UNIT COSTS FOR SYSTEMS, STATIONS AND VEHICLES AS USED FOR THE MTA AND INDEPENDENT COST ESTIMATES

CATEGORY	SUB-CATEGORY		MTA COSTS		INDEPENDENT COSTS*				
		Units	Heavy Rail	Light Rail	Units	Heavy Rail	Light Rail		
Systems	Train Control	Route Feet	\$2,200	\$1,500	Route Feet	\$1080	\$485		
	Traction Power	Route Feet	\$258	\$296	Route Feet	\$660	\$370		
	Communications	Route Feet	\$1,500	\$230	Route Feet	\$180	\$83		
	Fare Collection	Station	\$750,000	\$240,000	Station	\$1,000,000	\$130,000		
Stations	At-Grade	Station	\$36,000,000	\$3,500,000	Station	\$18,000,000	\$1,135,000		
	Subway	Station	\$65,000,000	NA	Station	\$53,000,000	NA		
	Aerial	Station	\$30,000,000	\$7,500,000	Station	\$22,000,000	\$4,000,000		
	Open Trench Station	Station	\$35,000,000	\$28,700,000	Station	\$24,000,000	\$21,000,000		
	Retained Fill (Elevated) Station	Station	\$20,000,000	NA	Station	\$18,500,000	NA		
	Parking Lots	Space	\$3,161	\$3,000	Space	\$5,500	\$2,437		
	Parking Garages	Each	\$5,000,000	Not Available	Space	\$10,000	Not Available		
	Signage & Graphics	Station	\$1,500,000		Station	\$300,000	\$35,157		
Vehicles	Revenue Vehicles ("LA" Vehicle)	Rev. Vehicle	NA	\$3,200,000	Rev. Vehicle	NA	\$2,002,000		
	Revenue Vehicles (Low Floor LRT)	Rev. Vehicle	NA	\$2,400,000	Rev. Vehicle	NA			
Environmental	Hazardous Waste Handling	Route Feet	\$500-\$1,000	\$200	Route Feet	\$100	\$100		

DRAFT UNIT CAPITAL COSTS — Systems, Stations and Vehicles (\$1998)†

* National averages based on experience of other US transit operators

† Draft cost estimates — estimates currently under review

SOFT-COST AS A PERCENT OF HARD-COSTS AND CONTINGENCY FACTORS

CATEGORY	SUB-CATEGORY	Units	MTA	INDEPENDENT
Soft Cost Factors	Pre-Revenue Operations	Percent	2.5%	2.0%
	Owners Project Insurance	of	8.0%	6.5%
	Master Agreements	Total	2.5%	2.5%
	"Art for Transit" – Station Artwork	Hard	0.5%	NA
	Professional Services	Costs †	30%-45%	22% to 25%
Contingencies	Guideways & Structures	Percent	10% - 12%	10% - 12%
	Hazardous Waste Handling	of	10% - 12%	10% - 12%
	Stations	Total	12% - 17%	12% - 17%
	Yards, Systems and Vehicles	Cost	8% - 10%	8% - 10%
	Pre-Rev. Operations, Insurance	by	10%	10%
	Right-of-Way	Category ‡	10%	10%
	Professional Services		10%	10%

DRAFT UNIT CAPITAL COSTS — Soft Cost and Contingency Factors

* National averages based on experience of other US transit operators

† Total hard costs include costs for all guideway, trackwork, stations, systems, vehicles, facilities and other "hard" assets

‡ Ranges reflect the degree of completion/design (i.e., contingency factor declines as a project becomes more defined).

Approach to Development of Operating & Maintenance Costs

OPERATING AND MAINTENANCE (O&M) COSTS FOR EACH ALTERNATIVE HAVE BEEN DEVELOPED USING MTA'S EXISTING O&M COST MODEL

- O&M Model developed using MTA's detailed budget (approx. 700 line items)
- MTA's O&M model provided the flexibility required to analyze the cost impacts of independent changes in service levels for the Red Line, Blue Line, Green Line and bus system.
- Budget level detail permitted analysis of O&M cost impacts resulting from new technologies (e.g., new farebox systems)
- Model was recalibrated to the FY1 998 budget
- Analysis of the O&M costs for each alternative used input data derived from the alternative's operating plan and travel demand analysis

CAPITAL AND OPERATING COSTS RESULTS

A4-7

Alternative Capital and Operating Costs

.

1

	Model Notes		Alignment		BREAT	otal Cos	st	Co	st Per N	lile	
Planning Area		Alternative		Route Miles	MTA	Lower Bound	Best Est.	MTA	Lower Bound	Best Est.	Annual O&M Costs
Eastside	E1	Suspended Red Line	Union Station east to First/Lorena	3.62	\$922.6	\$739.9	\$794.9	\$254.9	\$204.4	\$219.6	\$10.5
	E2	Red Line 2 Station Extension	Union Station to Chavez / Soto	1.92	\$481.1	\$385.0	\$414.8	\$250.6	\$200.5	\$216.0	\$3.4
	E4*	Busway - At-Grade (with branching routes)	Union Station to Whittier & Atlantic	5.9	\$88.2	\$68.2	\$70.4	\$14.9	\$11.6	\$11.9	\$15.5
	E5*	Light Rail - At- Grade	Union Station to Whittier & Atlantic	5.9	\$430.9	\$351.3	\$371.0	\$73.0	\$59.5	\$62.9	\$9.9
	E6	Light Rail - At- Grade	Union Station south to Little Tokyo	0.4	\$63.4	\$41.8	\$53.1	\$151.0	\$99.5	\$126.4	\$0.2
Westside	W1	Suspended Red Line	Wilshire & Western to Pico & San Vicente	2.6	\$607.4	\$471.6	\$489.3	\$237.3	\$184.2	\$191.1	\$4.4
	W4	Subway Red Line	Below grade to Wilshire	3.17	\$859.7	\$684.0	\$733.6	\$271.2	\$215.8	\$231.4	\$6.5
	W2*	Busway	Exposition	18.5	\$264.3	\$316.1	\$231.1	\$14.3	\$17.1	\$12.5	\$14.7
	W3*	Light Rail	Exposition	18	\$930.8	\$739.2	\$842.9	\$51.7	\$41.1	\$46.8	\$21.2

CAPITAL AND OPERATING COSTS (Millions \$1998)

* Cost estimates for these options do not include extensive analysis of condemnation and/or mitigation requirements. Actual development costs may be higher.

				1	т	otal Cos		· · ·		lilo	
				Theorem 1.		T			st Per N		
Planning Area	Model	Alternative	Alignment	Route	MTA	Lower	Best	MTA	Lower	Best	Annual
	Notes			Miles		Bound	Est.		Bound	Est.	O&M
											Costs
San Fernando	V1	Red Line Extension	North Hollywood to	6.01	\$920.0	\$728 1	\$827.7	\$153.1	\$121.1	\$1377	\$12.7
Valley		to I-405	I-405 Sepulveda	0.01	\$520.0	<i>\$720.1</i>	\$027.7	\$150.1	φ121.1	\$107.7	ψ12.7
	V3*	Busway	Warner Center to	14	\$173.0	\$140.8	\$143.8	\$12.4	\$10.1	\$10.3	\$14.0
			North Hollywood		\$110.0	• • • • • • •	¢ 1 10.0	\$12.1	• .•.•	\$10.0	\$11.0
			Red Line Station								
	V2	Light Rail	Warner Center to	13.8	\$1 126	\$878.4	\$934 5	\$81.6	\$34.6	\$67.7	\$22.6
			North Hollywood	10.0	¢1,120	¢070.1	\$001.0	\$01.0	\$01.0	\$07.7	<i><u><u></u></u></i> <u><u><u></u></u><u></u><u><u></u></u><u></u><u><u></u></u><u></u><u></u><u></u><u></u><u></u><u></u><u></u><u></u><u></u></u>
			Red Line Station								
Systemwide Bus	B5	Expanded Rapid		338.5	\$221.4	\$199.2	\$206.9	\$0.7	\$0.6	\$0.6	\$80.6
		Bus Network		000.0	<i><i>v</i></i> <i>LLIII</i>	\$100.L	\$200.0	\$0.7	0.0	\$0.0	φ00.0
		(Includes Rapid									
		Bus Base Routes								18	
		plus additional									
		routes. Costs are in									
		addition to those									
		included in the high									
		technology option))									

CAPITAL AND OPERATING COSTS – Continued (Millions \$1998)

* Cost estimates for these options do not include extensive analysis of condemnation and/or mitigation requirements. Actual development costs may be higher.

Review of Capital Costs

DETAILED CAPITAL COSTS HAVE BEEN DEVELOPED FOR EACH OF THE PROJECT ALTERNATIVES

- For most capital items, MTA costs were not significantly different from the national average (when adjusted to LA price levels)
- Significant exceptions to this observation include the following asset types:
 - Stations
 - Vehicles
 - Communications
 - Signage and Graphics
 - Project Soft-Costs
- Each of these items offers the potential for project cost savings in the case of stations, vehicles and soft-costs, these savings may be significant:

Item	Potential Savings (% of asset cost)	Share of Total Project Cost
Stations	5% to 40%	10% to 15%
Vehicles	10% to 25%	10% to 15%
Soft-Costs	20% to 30%	30% to 45%

 The total cost savings attainable from these areas is captured by the "Best Estimates" Costs

BOOZ-ALLEN AND PEER-GROUP ANALYSIS IDENTIFIED BOTH STATION AND VEHICLE COSTS AS HIGHER THAN AVERAGE

Vehicles

- Vehicle costs might be reduced through the use of performance specification which facilitates the use of "off the shelf" technology
- Peer review team members identified MTA as having specification requirements which are considerably more strenuous than the industry average
- Given these requirements, MTA has paid per vehicle costs which are 10% to 25% higher than the industry average for similar vehicles

Stations

- Similarly, the peer review group suggested the station costs might be reduced by:
 - Creating a standardized station design
 - Utilizing less amenities than traditional MTA station facilities
 - Building smaller stations

Achieving Potential Cost Savings — Soft-Costs

A VARIETY OF OPTIONS EXIST TO REDUCE PROJECT SOFT COSTS

- "Learning by Doing" capital development costs tend to decline as agencies expand their rail networks
 - Decreased costs reflect reduced design needs and increased agency construction experience
 - Development costs for the Red Line extension to North Hollywood are less than that for the initial Red Line segment
 - Inflation adjusted capital costs for Washington Metro (WMATA) decreased by between 25% and 33% over the period 1974 and 1988 during which WMATA constructed 10 rail segments
- Design-Build
 - Use of turnkey contracting by US operators is yielding cost savings to sponsoring agencies
 - The highest cost savings originate from reductions in the time required to complete project development
 - The capital costing team will provide order of magnitude estimates of the potential cost savings

SAVINGS IDENTIFIED THROUGH THIS PROCESS WERE APPLIED TO "BEST ESTIMATE" COSTS

Learning by Doing...

PROJECT UNIT COSTS TEND TO DECLINE WHEN NEW SEGMENTS ARE ADDED TO AN EXISTING RAIL NETWORK (I.E., RELATIVE TO THE INITIAL NETWORK INVESTMENT)

- A variety of factors contribute to this cost decrease including:
 - Reduced design costs (components only need to be designed once)
 - Increased agency procurement, project and construction management experience
 - Supplier agreements (refined through successive procurement s)
 - One time costs (control center, admin, revenue counting)
- MTA may achieve similar reductions in cost savings by learning from past projects
 - Perform most construction management in-house using MTA staff
 - Limit contracting of construction managem ent duties to specialized areas such as geotechnical and advanced systems
 - Bid more engineering and design work on a competitive basis to greater number of small, specialty contractors

Design–Build (Turnkey)

USE OF DESIGN-BUILD CONTRACTING CAN REDUCE PROJECT CAPITAL COSTS BY 5% TO 10%¹ (HIGHER FOR DBOM – DESIGN/BUILD/OPERATE/MAINTAIN)

- Under a Design–Build contract, a single contractor completes the final design, construction, systems procurement and start-up/tasting of the full project
- D/B reduces costs through the following mechanisms:
 - Schedule compression and reduced price escalation
 - reduced funding constraints
 - elimination of task sequencing buffers
 - overlapping of sequential tasks (where possible)
 - Reduced construction management and administrative costs
 - shorter project duration
 - fewer contract interfaces to coordinate
 - Increased efficiencies of a single contractor
 - consolidated PM functions
 - pooling of risks (performance bonds, insurance)
 - more effective utilization of labor (reduced downtime and delay claims)
 - Reduced incentive for design and delay claims
 - leads to reduced contingency requirements

¹ Based on BAH research for FTA and 'Pasadena Turnkey Implementation Analysis" report prepared for MTA by BAH January, 1996.

ESTIMATED COST SAVINGS FROM A DESIGN-BUILD PROCUREMENT BY FUNCTION (AS A PERCENT OF TOTAL PROJECT CAPITAL COSTS)

		(PERCENT OF TOTAL	CAPITAL COSTS)
		Design-Build	DBOM
•	Reduced Escalation	2.75	2.75
•	Reduced Construction Management Costs	1.63	4.88
•	Reduced MTA Project Administration	0.75	0.75
•	Economies of Scale	1.3	1.38
•	Reduced Contingency	0.75	0.75
•	Added Consultant and Legal Support	<u>(1.00)</u>	(1.00)
	CAPITAL COST SAVINGS	6.25%	9.50%
•	O&M Cost Savings	0.00	11.88
	O&M AND CAPITAL COST SAV	INGS 6.25%	21.38%

THESE ESTIMATES OF D/B COST SAVINGS MAY BE CONSERVATIVE — MARYLAND MTA IS EXPECTING HIGHER OVERALL SAVINGS FOR ITS DESIGN-BUILD LRT EXTENSION PROJECTS

Review of O&M Costs

THE O&M COST MODEL'S INPUT, OUTPUT AND PARAMETER SETTINGS HAVE BEEN REVIEWED FOR REASONABILITY AND ACCURACY

- O&M costing team has verified the recalibrated of the MTA O&M model
- The O&M costing team has assessed the reasonability of the model's internal cost parameters (e.g., for fuel, wages, staffing rates, etc.) against industry standards
 - Model estimates are considered reasonable given the modes, network structure and service levels proposed
 - Confidence in the model's predictive accuracy
- The O&M costing team has verified the model parameter settings for each alternative to ensure they accurately reflect the alternative's service characteristics — including number of vehicles, revenue miles, service hours, unit costs and other input values
- The O&M team has assessed the reasonability of model output for each alternative
 - Model output is considered reasonable

CAPITAL COSTS DETAILS

....

VERSION DA	ATE:		11/6/98 10:59		CAPITAL C	COSTS BY ALT	ERNATIVE									
				1.			Capita		BEST	Cost p	er Mile	BEST	Annualized	Cap Cost	BEST	
Planning Area	Model Run Ranking	Model Notes	Alternative	Alignment	Characteristics	Route Miles	MTA	BOUND	BEST ESTIMATE	MTA	BAH	BEST ESTIMATE	MTA	BAH	BEST ESTIMATE	Annual Q&M Costs
Baseline	0	BASE	Baseline		Consent decree to 2006, 1973 + 100 buses, Pasadena light rail to Del Mar Station beginning service in June 2002		NA	NA		NA .	NA					NA
Eastside	1	E1	Suspended Red Line	Union Station east to First/Lorena	Tunnel Sections and Cut and Cover Stations	3.62	\$922.6	\$739.9	\$794.9	\$254.9	\$204.4	\$219.6	\$65.9	\$52.6	\$56.4	\$10.5
	3	E2	Red Line 2 Station Extension	Union Station to Chavez / Soto	Tunnel Sections and Cut and Cover Stations	1.92	\$481.1	\$385.0	\$414.8	\$250.6	\$200.5	\$216.0	\$34.4	\$27.4	\$29.4	\$3.4
	5	E4	Busway - At-Grade (with branching routes)	Union Station south along Alameda, eastward along First to Whittier & Atlantic	At-grade dedicated bus lanes in arterial highways	5.9	\$88.2	\$68.2	\$70.4	\$14.9	\$11.6	\$11.9	\$7.2	\$5.6	\$5.8	\$15.5
	5	E5	Light Rail - At-Grade	Union Station south along Alameda, First, Indiana, and Whittier to Whittier & Atlantic	At-grade in arterial highways	5.9	\$430.9	\$351.3	\$371.0	\$73.0	\$59.5	\$62.9	\$31.8	\$26.2	\$27.4	\$9.9
		E6	Light Rail - At-Grade	Union Station south to Little Tokyo	At-grade in arterial highways	0.4	\$63.4	\$41.8	\$53.1	\$151.0	\$99.5	\$126.4	\$4.7	\$3.2	\$3.9	\$0.2
Westside	1	W1	Suspended Red Line	Wilshire & Western to Pico & San Vicente with subway following Wilton and Arlington		2.6	\$607.4	\$471.6	\$489.3	\$237.3	\$184.2	\$191.1	\$43.4	\$33.5	\$34.7	\$4.4
	5	W4	Subway Red Line	Below grade along Wilshire	Subway	3.17	\$859.7	\$684.0	\$733.6	\$271.2	\$215.8	\$231.4	\$61.3	\$48.5	\$52.0	\$6.5
	3		Busway - At-Grade (with branching routes)	LA CBD to Santa Monica (4th and Colorado) via Exposition ROW	At-grade, separate and mixed ROW (Use Exposition ROW)	18.5	\$264.3	\$316.1	\$231.1	\$14.3	\$17.1	\$12.5	\$19.5	\$23.0	\$17.0	\$14.7
	2	W3	Light Rail - At-Grade	Figueroa St. to Santa Monica (4th and Colorado) via Exposition ROW	At-grade, separate and mixed ROW (Use Exposition ROW)	18	\$930.8	\$739.2	\$842.9	\$51.7	\$41.1	\$46.8	\$67.1	\$52.6	\$60.4	\$21.2

Г — — — — — — — — — — — — — — — — — — —						1	Capita	I Cost	BEST	Cost p	er Mile	BEST	Annualize	d Cap Cost	1																					
Planning Area	Model Run Ranking	Model Notes	Aliemative	Alignment	Characteristics	Route Miles	MTA	LOWER BOUND	BEST ESTIMATE	MTA	BAH	BEST	MTA	BAH	BEST	Annual OAM Costs																				
San Fernando Valley	1	V1	Red Line Extension to I- 405	North Hollywood to I- 405 Sepulveda	Burbank/Chandler ROW	6.01	\$920.0	\$728.1	\$827.7	\$153.1	\$121.1	\$137.7	\$65.3	\$51.7	\$58.6	\$12.7																				
	3	V3	Busway (with branching routes)	Warner Center to North Hollywood Red Line Station	Burbank/Chandler ROW	14	\$173.0	\$140.8	\$143.8	\$12.4	\$10.1	\$10.3	\$13.0	\$10.6	\$10.8	\$14.0																				
	2	V2	Light Rail	Warner Center to North Hollywood Red Line Station	Burbank/Chandler ROW	13.8	\$1,126.1	\$878.4	\$934.5	\$81.6	\$34.6	\$67.7	\$80.7	\$61.7	\$66.7	\$22.6																				
Systemwide	5	B5	Expanded Rapid Bus Network (Includes Rapid Bus Base Routes plus additional routes. Costs are in addition to those included in the high technology option))	Ventura (Univ. City to Warner Ctr.)	At-grade, peak-hour exclusive lane, bus priority signalization	338.5	\$221.4	\$199.2	\$206.9	\$0.7	\$0.6	\$0.6	\$19.4	\$17.6	\$18.2	\$80.6																				
				Sherman Way (No. Hollywood to Warner Ctr.) Van Nuys (San Fernando / Sylmar to																																
				Ventura to Univ. City) Santa Monica Boulevard Vermont Avenue																																
				Western Avenue Crenshaw Avenue Long Beach Boulevard									· · · ·																							
				Hollywood - Pasadena														-		-		-		-												
				Florence																																
				Garvey												<u> </u>																				

Notes: Per mile O&M costs for busways is \$92 thousand for Pittsburgh (including snow removal) and \$100 thousand for CALTRANS Use \$ 100,000 per lane mile

· ·

Safety and Security Use \$ 0.11 per pax mile

COST ESTIMATE COVERSHEET

PROJECT: SYSTEMWIDE RAPID BUS 16 LINES 0	EST. HTL DATE 11/5/98 REV.: 2 \$: 1988 Dollars	SHT OF	1 2		
	\$. 1500 Dollars		MTA	LOWER	PROJECTED
			ESTIMATED	BOUND	FINAL
			COST	COST	COST
1A) GUIDEWAYS AND STRUCTURES			\$0	\$0	\$0
1B) HAZARDOUS WASTE HANDLING ALLOWANCE			\$0	\$0	\$0 \$0
2) STATIONS			\$43,350,000	\$43,350,000	\$43,350,000
3) MAIN YARD AND SHOP			\$10,830,240	\$10,830,240	\$10,830,240
4) SYSTEMWIDE EQUIPMENT			\$33,468,000	\$33,468,000	\$33,468,000
5) VEHICLES			\$76,500,000	\$73,158,200	\$73,158,200
SUBTOTAL (A) (see page 2 for details)			\$164,148,240	\$160,806,440	\$160,806,440
6) PRE REVENUE OPERATION		2.9%	\$4,760,299	\$4,663,387	\$4,663,387
7) OWNERS INSURANCE		0.0%	\$0	\$0	\$0
8) MASTER AGREEMENTS		0.0%	\$0	\$0	\$0
SUBTOTAL (B)			\$4,760,299	\$4,663,387	\$4,663,387
9) ART FOR TRANSIT (C)		0.0%	\$0	\$0	\$0
SUBTOTAL (C)			\$0	\$0	\$0
			* 0	¢0	¢0
10) RIGHT OF WAY (D) ALLOWANCE			\$0 \$0	\$0 \$0	\$0 \$0
SUBTUTAL (D)			4 0	4 0	\$U
11) PROF. SERVICES (E)			\$32,342,989	\$15,639,237	\$22,616,349
SUBTOTAL (E)			\$32,342,989	\$15,639,237	\$22,616,349
12) CONTINGENCY (F) A) ITEM 1A	12%		\$0	\$0	\$0
ITEM 1B	12%		\$0 \$0	\$0 \$0	\$0 \$0
B) ITEM 2	10%		\$4,335,000	\$4,335,000	\$4,335,000
C) ITEM 3, 4, & 5	10%		\$12,079,824	\$11,745,644	\$11,745,644
D) ITEM 6, 7, & 8	10%		\$476,030	\$466,339	\$466,339
E) ITEM 10	10%		\$0	\$0	\$0
F) ITEM 11	10%		\$3,234,299	\$1,563,924	\$2,261,635
SUBTOTAL (F)			\$20,125,153	\$18,110,906	\$18,808,618

GRAND TOTAL + 1998 DOLLARS \$221,376,680 \$199,219,970 \$206,894,793

ì

PROJECT:	SYSTEMWIDE RAPID BUS 16 LINES	EST DATE REV.	HTL 11/5/98 2		SHT OF XLS	2		
		\$:	1998 Dollars	BAH UNIT		MTA	LOWER	ESTIMATED PROJECT
DESCRIPTIO	ON	QTY	PRICE	PRICE	UNIT	COST	BOUND	COST
GUIDEWAY	COSTS							
SUBTOTAL	(GUIDEWAY COST)	0				\$0	\$0	\$0
SUBTUTAL	(GOIDEWAT COST)	v				40	30	\$0
	IS WASTE HANDLING						1.000	
ALLOWANC		0	\$1,500,000	NA	LS	\$0	\$0	\$0
SUBTOTAL	(HAZ MAT)					\$0	\$0	\$0
STATION CO	OST							
RAPID BUS	STATION STOPS	387	\$50,000	\$50,000	EA	\$19,350,000	\$19,350,000	\$19,350,000
(total cost pe	er directional pair including shelters, pedestrian crossw	valks, landsc	aping, lighting, sign	age, information ki	osks, bus	pads)		
TRANSIT CI	ENTERS	6	\$4,000,000	\$4,000,000	EA	\$24,000,000	\$24,000,000	\$24,000,000
SUBTOTAL	(STATION COST)					\$43,350,000	\$43,350,000	\$43,350,000
	CIL & YARD COSTS					41 22		
the second se	NCE FACILITIES (ALLOWANCE)	200	\$54,151	\$54,151	VEH	\$10,830,240	\$10,830,240	\$10,830,240
SUBTOTAL	(MAINT. FACIL.)					\$10,830,240	\$10,830,240	\$10,830,240
VEHICLE C	<u>OST</u>							
production of the local division of the loca	/EHICLE (including diagnostics, counters, onboard G	200	\$382,500	\$365,791	EA	\$76,500,000	\$73,158,200	\$73,158,200
SUBTOTAL	(VEHICLE COST)		3			\$76,500,000	\$73,158,200	\$73,158,200
SVSTEM W	IDE EQUIPMENT COST							
	GIGNALIZATION (BY INTERSECTION)	1255	\$25,000	\$25,000	EA	\$31,375,000	\$31,375,000	\$31,375,000
	RE SYSTEM (INCL RAIL COSTS, EXCL BUS VEH.)	1200	\$22,315,960	\$22,315,960	LS	\$0	\$0	\$0
	RE SYSTEM - BUS FARE BOXES	200	\$5,500	\$5,500	VEH	\$1,100,000	\$1,100,000	\$1,100,000
	RE SYSTEM - CARD/TRANSFER PROCESSORS	200	\$3,600	\$3,600	VEH	\$720,000	\$720,000	\$720,000
UNIFIED FA	RE SYSTEM - PARTS AND SERVICES	1	\$273,000	\$273,000	LS	\$273,000	\$273,000	\$273,000
GPS/AVL - 0	ON-BOARD VEHICLE EQUIP.	0	\$25,000	\$25,000	VEH	\$0	\$0	\$0
GPS/AVL - 1	TRANSMISSION TOWERS		\$394,000	\$394,000	EA	\$0	\$0	\$0
	CENTRAL CONTROL		\$1,800,000	\$1,800,000	EA	\$0	\$0	\$0
BUS DIAGN	OSTICS PACKAGE (new vehicles only)	0	\$5,000	\$5,000	VEH	\$0	\$0	\$0
	PASSENGER COUNTERS W/ AVL	0	\$2,500	\$2,500	VEH	\$0	\$0	\$0
	PASSENGER COUNTERS W/0 AVL		\$7,500	\$7,500	VEH	\$0	\$0	\$0
PASSENGE	R COUNTER SYSTEM SOFTWARE		\$30,000	\$30,000	RF	\$0	\$0	\$0
ON-BOARD	CAMERAS	0	\$3,500	\$3,500	VEH	\$0	\$0	\$0
SUBTOTAL	(SYSTEM COST)					\$33,468,000	\$33,468,000	\$33,468,000
								,

•

TOTAL ESTIMATED COST - 1998 DOLLARS \$160,806,440 \$160,806,440

COST ESTIMATE COVERSHEET

1

PROJECT: RAPID BUS DEMONSTRATION 3 LINES	ESTHTL DATE 11/5/98	SHT OF	1 2		
	0 REV.: 2		£		
	0 \$: 1988 Dollars		MTA	LOWER	PROJECTED
			ESTIMATED	BOUND	FINAL
ITEM DESCRIPTION			COST	COST	COST
1A) GUIDEWAYS AND STRUCTURES			* 2	**	•
1B) HAZARDOUS WASTE HANDLING ALLOWANCE			\$0 \$0	\$0 \$0	\$0 \$0
2) STATIONS			\$7,250,000	\$7,250,000	\$7,250,000
3) MAIN YARD AND SHOP			\$2,166,048	\$2,166,048	\$2,166,048
4) SYSTEMWIDE EQUIPMENT			\$5,418,600	\$5,418,600	\$5,418,600
5) VEHICLES			\$15,300,000	\$14,631,640	\$14,631,640
SUBTOTAL (A) (see page 2 for details)			\$30,134,648	\$29,466,288	\$29,466,288
6) PRE REVENUE OPERATION		2.9%	\$873,905	\$854,522	\$854,522
7) OWNERS INSURANCE		0.0%	\$0	\$0	\$0
8) MASTER AGREEMENTS		0.0%	\$0	\$0	\$0
SUBTOTAL (B)			\$873,905	\$854,522	\$854,522
9) ART FOR TRANSIT (C)		0.0%	\$0	\$0	\$0
SUBTOTAL (C)			\$0	\$0	\$0
10) RIGHT OF WAY (D) ALLOWANCE			\$0	\$0	\$0
SUBTOTAL (D)	×.		\$0	\$0	\$0
11) PROF. SERVICES (E)			\$5,497,993	\$2,658,025	\$3,843,847
SUBTOTAL (E)			\$5,497,993	\$2,658,025	\$3,843,847
12) CONTINGENCY (F)					
A) ITEM 1A	12%		\$0	\$0	\$0
ITEM 1B	12%		\$0	\$0	\$0
B) ITEM 2	10%		\$725,000	\$725,000	\$725,000
C) ITEM 3, 4, & 5	10%		\$2,288,465	\$2,221,629	\$2,221,629
D) ITEM 6, 7, & 8	10%		\$87,390	\$85,452	\$85,452
E) ITEM 10	10%		\$0	\$0	\$0
F) ITEM 11	10%		\$549,799	\$265,803	\$384,385
SUBTOTAL (F)			\$3,650,655	\$3,297,884	\$3,416,466

GRAND TOTAL - 1996 DOLLARS \$40,157,201 \$36,276,719 \$37,581,123

i.

	DATE REV.	11/5/98 2		OF XLS	2 2		
	\$:	1998 Dollars MTA UNIT	BAH UNIT		МТА	LOWER	ESTIMATED PROJECT
DESCRIPTION	QTY	PRICE	PRICE	UNIT	COST	BOUND	COST
GUIDEWAY COSTS							
SUBTOTAL (GUIDEWAY COST)	0		in an		\$0	\$0	\$0
HAZARDOUS WASTE HANDLING ALLOWANCE	0	\$1,500,000	NA	LS	\$0	\$0	\$0
SUBTOTAL (HAZ MAT)		\$1,000,000			\$0	\$0	\$0
SUBTOTAL (HAZ MAT)					ψŪ	φu	φυ
STATION COST							
RAPID BUS STATION STOPS	65	\$50,000	\$50,000	EA	\$3,250,000	\$3,250,000	\$3,250,000
(total cost per directional pair including shelters, pedestrian cros	swalks, landso	aping, lighting, sign	age, information ki	osks, bus	pads)		
TRANSIT CENTERS	1	\$4,000,000	\$4,000,000	EA	\$4,000,000	\$4,000,000	\$4,000,000
	Anner Constant				47 050 000		
SUBTOTAL (STATION COST)					\$7,250,000	\$7,250,000	\$7,250,000
MAINT. FACIL & YARD COSTS							
MAINTENANCE FACILITIES (ALLOWANCE)	40	\$54,151	\$54,151	VEH	\$2,166,048	\$2,166,048	\$2,166,048
SUBTOTAL (MAINT. FACIL.)		•• 11.01	••• 11.01		\$2,166,048	\$2,166,048	\$2,166,048
					\$2,100,040	<i>42,100,040</i>	<i>\$2,100,040</i>
VEHICLE COST							
REVENUE VEHICLE (including diagnostics, counters, onboard	G 40	\$382,500	\$365,791	EA	\$15,300,000	\$14,631,640	\$14,631,640
SUBTOTAL (VEHICLE COST)					\$15,300,000	\$14,631,640	\$14,631,640
Bandiar and a second standard from the second residence of the second second second second second second second						Ch. C. A. Martin Contractor	
SYSTEM WIDE EQUIPMENT COST							
PRIORITY SIGNALIZATION (BY INTERSECTION)	200	\$25,000	\$25,000	EA	\$5,000,000	\$5,000,000	\$5,000,000
UNIFIED FARE SYSTEM (INCL RAIL COSTS, EXCL BUS VEH		\$22,315,960	\$22,315,960	LS	\$0	\$0	\$0
UNIFIED FARE SYSTEM - BUS FARE BOXES	40	\$5,500	\$5,500	VEH	\$220,000	\$220,000	\$220,000
UNIFIED FARE SYSTEM - CARD/TRANSFER PROCESSORS		\$3,600	\$3,600	VEH	\$144,000	\$144,000	\$144,000
UNIFIED FARE SYSTEM - PARTS AND SERVICES	1	\$54,600	\$54,600	LS	\$54,600	\$54,600	\$54,600
GPS/AVL - ON-BOARD VEHICLE EQUIP.	0	\$25,000	\$25,000	VEH	\$0	\$0	\$0
GPS/AVL - TRANSMISSION TOWERS		\$394,000	\$394,000	EA	\$0	\$0	\$0
GPS/AVL - CENTRAL CONTROL	~	\$1,800,000	\$1,800,000	EA	\$0	\$0	\$0
BUS DIAGNOSTICS PACKAGE (new vehicles only)	0	\$5,000	\$5,000	VEH	\$0	\$0	\$0
ON-BOARD PASSENGER COUNTERS W/ AVL	0	\$2,500	\$2,500	VEH	\$0	\$0	\$0 \$0
ON-BOARD PASSENGER COUNTERS W/0 AVL		\$7,500	\$7,500	VEH RF	\$0 \$0	\$0	40
PASSENGER COUNTER SYSTEM SOFTWARE ON-BOARD CAMERAS	0	\$30,000 \$3,500	\$30,000 \$3,500	VEH	\$0	• \$0 \$0	\$0 \$0
	0	\$3,300	φ3,500	VEN	and the second state of th		and the second state of th
SUBTOTAL (SYSTEM COST)					\$5,418,600	\$5,418,600	\$5,418,600

1

TOTAL ESTIMATED COST - 1998 DOLLARS \$30,134,648 \$29,466,288 \$29,466,288

1

à

PROJECT:	EASTSIDE HEAVY RAIL UNION STATION TO 1ST/LORENA	EST. <u>HTL</u> DATE <u>11/5/98</u>	SHT OF	1 2		
		REV.: 0	- in _			
		\$: 1988 Dollars		МТА	LOWER	PROJECTED
				ESTIMATED	BOUND	FINAL
ITEM DESCR	IPTION			COST	COST	COST
,	AYS AND STRUCTURES			\$211,839,000	\$198,384,257	\$211,839,000
,	OUS WASTE HANDLING ALLOWANCE			\$2,470,000	\$2,470,000	\$2,470,000
2) STATIONS				\$220,000,000	\$206,652,593	\$206,652,593
and a second residue of the second	D AND SHOP			\$0	\$0	\$0
	VIDE EQUIPMENT			\$66,806,700	\$51,900,046	\$49,860,695
5) VEHICLES				\$0	\$0	\$0
SUBTOTAL (A) (see page 2 for details)			\$501,115,700	\$459,406,896	\$470,822,288
6) PRE REVE	NUE OPERATION		2.5%	\$12,527,893	\$11,485,172	\$11,770,557
7) OWNERS	INSURANCE		8.0%	\$40,089,256	\$36,752,552	\$37,665,783
8) MASTER A	AGREEMENTS		2.5%	\$12,527,893	\$11,485,172	\$11,770,557
SUBTOTAL (B)			\$65,145,041	\$59,722,897	\$61,206,897
9) ART FOR	TRANSIT (C)		0.5%	\$2,505,579	\$2,297,034	\$2,354,111
SUBTOTAL (C)			\$2,505,579	\$2,297,034	\$2,354,111
10) RIGHT O	F WAY (D) INCL. COST TO DATE (\$17,728,0	000)		\$36,609,000	\$36,609,000	\$36,609,000
SUBTOTAL (\$36,609,000	\$36,609,000	\$36,609,000
	ERVICES (E) INCL. COST TO DATE (\$90,000	,000)		\$242,150,128	\$122,803,491	\$159,877,843
SUBTOTAL (E)			\$242,150,128	\$122,803,491	\$159,877,843
12) CONTING	SENCY (E)					
A) ITEM 1A		10%		\$21,183,900	\$19,838,426	\$21,183,900
ITEM 1B		10%		\$247,000	\$247,000	\$247,000
B) ITEM 2		8%		\$17,600,000	\$16,532,207	\$16,532,207
C) ITEM 3, 4	8.5	8%		\$5,344,536	\$4,152,004	\$3,988,856
D) ITEM 6, 7		10%		\$6,514,504	\$5,972,290	\$6,120,690
E) ITEM 10 E	·	0%		INCL. IN ITEM	INCL. IN ITEM	INCL. IN ITEM
F) ITEM 11		10%		\$24,215,013	\$12,280,349	\$15,987,784
SUBTOTAL (F)	1070		\$75,104,953	\$59,022,276	\$64,060,437
CODICIAL (• •			<i>\$10,104,000</i>	400,022,270	\$01,000,101
				i		

GRAND TOTAL - 1998 DOLLARS \$922,630,400 \$739,861,594 \$794,930,577

PROJECT: EASTSIDE HEAVY RAIL	EST.	HTL		SHT.	2		
UNION STATION TO 1ST/LORENA	DATE	11/5/98		OF	2		
	REV.	0		XLS			
	\$:	1988 Dollars		_			
	_						ESTIMATED
		A 4 10 A 4 4 A 4 4 1 4 10 10 10 10 10 10 10 10 10 10 10 10 10				LOWER	DDO IFOT
		MTA UNIT	BAH UNIT		MTA	LOWER	PROJECT
DESCRIPTION	QTY	PRICE	PRICE	UNIT	COST	BOUND	COST
DESCRIPTION GUIDEWAY COSTS	QTY			UNIT			
	QTY 19124			UNIT RF			
GUIDEWAY COSTS		PRICE	PRICE		COST	BOUND	COST

1

.

А.

SUBTOTAL (GUIDEWAY COST)	19124		alaren latina dillar lehendurgian		\$211,839,000	\$198,384,257	\$211,839,000
HAZARDOUS WASTE HANDLING						×	
ALLOWANCE	3800	\$650	NA	RF	\$2,470,000	\$2,470,000	\$2,470,000
SUBTOTAL (HAZ MAT)					\$2,470,000	\$2,470,000	\$2,470,000
STATION COST		* • • • • • • • • • •	* ***			* =• •••	
SUBWAY STATIONS	2	\$40,000,000	\$36,663,148	EA	\$80,000,000	\$73,326,297	\$73,326,297
SUBWAY STATIONS W/ CROSSOVER	2	\$70,000,000	\$66,663,148	EA	\$140,000,000	\$133,326,297	\$133,326,297
SUBTOTAL (STATION COST)					\$220,000,000	\$206,652,593	\$206,652,593
MAINT. FACIL & YARD COSTS					••	••	
MAINTENANCE FACILITIES (ALLOWANCE)				LS	\$0	\$0	\$0
SUBTOTAL (MAINT. FACIL.)					\$0	\$0	\$0
VEHICLE COST							
REVENUE VEHICLE				EA	\$0	\$0	\$0
SUBTOTAL (VEHICLE COST)					\$0	\$0	\$0
SYSTEM WIDE EQUIPMENT COST							
TRACKWORK (INCL. SPECIAL TRACKWORK)	19124	\$575	\$674	RF	\$10,996,300	\$12,890,891	\$10,996,300
TRAIN CONTROL STA.	4	\$1,100,000	NA	EA	\$4,400,000	NA	\$4,400,000
TRAIN CONTROL GDWY	19124	\$1,100	\$880	RF	\$21,036,400	\$16,835,347	\$21,036,400
TRACTION POWER STA. (XFMR)	3	\$1,750,000	\$4,235,377	EA	\$5,250,000	\$12,706,132	\$5,250,000
COMMUNICATIONS	19124	\$1,000	\$208	RF	\$19,124,000	\$3,969,375	\$3,969,375
FARE COLLECTION	4	\$750,000	\$1,072,420	LS	\$3,000,000	\$4,289,681	\$3,000,000
SIGNAGE & GRAPHICS	4	\$750,000	\$302,155	LS	\$3,000,000	\$1,208,620	\$1,208,620
SUBTOTAL (SYSTEM COST)					\$66,806,700	\$51,900,046	\$49,860,695

TOTAL ESTIMATED COST - 1998 DOLLARS \$501,115,700 \$459,406,896 \$470,822,288

.

,

PROJECT:	EASTSIDE HEAVEY RAIL	EST. <u>HTL</u> DATE 11/5/98	SHT OF	1 2		
		REV.: 0	- ¹⁰			
ITEM DESCF		\$:1988 Dollars		MTA ESTIMATED COST	LOWER BOUND COST	PROJECTED FINAL COST
TIEM DESCR				0031	0031	0031
	AYS AND STRUCTURES DOUS WASTE HANDLING ALLOWANCE S			\$112,751,000 \$2,470,000 \$110,000,000	\$105,633,861 \$2,470,000 \$103,326,297	\$112,751,000 \$2,470,000 \$103,326,297
	AD AND SHOP	34		\$0	\$0	\$0
	VIDE EQUIPMENT			\$35,760,300 \$0	\$27,294,227 \$0	\$26,848,285 \$0
	(A) (see page 2 for details)					
SUBIUIAL	(A) (see page 2 for details)			\$260,981,300	\$238,724,385	\$245,395,582
6) PRE REVE	ENUE OPERATION		2.5%	\$6,524,533	\$5,968,110	\$6,134,890
	INSURANCE		8.0%	\$20,878,504	\$19,097,951	\$19,631,647
	AGREEMENTS		2.5%	\$6,524,533	\$5,968,110	\$6,134,890
SUBTOTAL (\$33,927,569	\$31,034,170	\$31,901,426
9) ART FOR	TRANSIT (C)		0.5%	\$1,304,907	\$1,193,622	\$1,226,978
SUBTOTAL ((C)			\$1,304,907	\$1,193,622	\$1,226,978
	F WAY (D) INCL. COST TO DATE (\$17,728,00	00)		\$19,402,770	\$19,402,770	\$19,402,770
SUBTOTAL ((D)			\$19,402,770	\$19,402,770	\$19,402,770
11) PROF. SI	ERVICES (E) INCL. COST TO DATE (approx \$	32,500,000)		\$126,246,618	\$63,896,616.02	\$83,419,491.57
SUBTOTAL ((E)			\$126,246,618	\$63,896,616	\$83,419,492
12) CONTINO	GENCY (F)					
A) ITEM 1A		10%		\$11,275,100	\$10,563,386	\$11,275,100
ITEM 1B		10%		\$247,000	\$247,000	\$247,000
B) ITEM 2		8%		\$8,800,000	\$8,266,104	\$8,266,104
C) ITEM 3, 4	, & 5	8%		\$2,860,824	\$2,183,538	\$2,147,863
D) ITEM 6, 7	, & 8	10%		\$3,392,756.90	\$3,103,417.00	\$3,190,142.57
E) ITEM 10 E	Β.	0%		INCL. IN ITEM	INCL. IN ITEM	INCL. IN ITEM
F) ITEM 11		10%		\$12,624,661.82	\$6,389,661.60	\$8,341,949.16
SUBTOTAL ((F)			\$39,200,343	\$30,753,107	\$33,468,158
GRAND TOT	AL - 1998 DOLLARS			\$481,063,506	\$385,004,669	\$414,814,405

.

ì

PROJECT: EASTSIDE HEAVY RAIL UNION STATION TO CHAVEZ/SOTO	EST DATE REV.	HTL 11/5/98 0		SHT OF XLS	2 2		
DESCRIPTION	\$:_	1988 Dollars MTA UNIT PRICE	BAH UNIT PRICE	UNIT	MTA COST	LOWER	ESTIMATED PROJECT COST
GUIDEWAY COSTS TWIN TUNNEL SEISMIC SECTION ADDER	10116 295	\$11,000 \$5,000	\$10,296 \$5,000	RF RF	\$111,276,000 \$1,475,000	\$104,158,861 \$1,475,000	\$111,276,000 \$1,475,000

,

>

SUBTOTAL (GUIDEWAY COST)	10116				\$112,751,000	\$105,633,861	\$112,751,000
HAZARDOUS WASTE HANDLING							
ALLOWANCE	3800	\$650	NA	RF	\$2,470,000	\$2,470,000	\$2,470,000
SUBTOTAL (HAZ MAT)					\$2,470,000	\$2,470,000	\$2,470,000
STATION COST							
SUBWAY STATIONS	1	\$40,000,000	\$36,663,148	EA	\$40,000,000	\$36,663,148	\$36,663,148
SUBWAY STATIONS W/ CROSSOVER	1	\$70,000,000	\$66,663,148	EA	\$70,000,000	\$66,663,148	\$66,663,148
						4100 000 007	A100 000 007
SUBTOTAL (STATION COST)					\$110,000,000	\$103,326,297	\$103,326,297
MAINT. FACIL & YARD COSTS							
MAINTENANCE FACILITIES (ALLOWANCE)				LS	\$0	\$0	\$0
SUBTOTAL (MAINT. FACIL.)					\$0	\$0	\$0
VEHICLE COST							
REVENUE VEHICLE				EA	\$0	\$0	\$0
SUBTOTAL (VEHICLE COST)					\$0	\$0	\$0
SYSTEM WIDE EQUIPMENT COST							
TRACKWORK (INCL. SPECIAL TRACKWORK)	10116	\$575	\$674	RF	\$5,816,700	\$6,818,879	\$5,816,700
TRAIN CONTROL STA.	2	\$1,100,000	NA	EA	\$2,200,000	NA	\$2,200,000
TRAIN CONTROL GDWY	10116	\$1,100	\$880	RF	\$11,127,600	\$8,905,374	\$11,127,600
TRACTION POWER STA. (XFMR)	2	\$1,750,000	\$3,360,574	EA	\$3,500,000	\$6,721,148	\$3,500,000
COMMUNICATIONS	10116	\$1,000	\$208	RF	\$10,116,000	\$2,099,675	\$2,099,675
FARE COLLECTION	2	\$750,000	\$1,072,420	LS	\$1,500,000	\$2,144,841	\$1,500,000
SIGNAGE & GRAPHICS	2	\$750,000	\$302,155	LS	\$1,500,000	\$604,310	\$604,310
SUBTOTAL (SYSTEM COST)					\$35,760,300	\$27,294,227	\$26,848,285
TOTAL ESTIMATED COST - 1998 DOLLARS	ala kati sa	al a Cologia dat	a Arthur agai	- b-Ro	\$260,981,300	\$238,724,385	\$245,395,582

,

*

GRAND TOTAL - 1998 DOLLARS

PROJECT: EASTSIDE LRT	EST. HTL	SHT.	1		
UNION STATION TO WHITTIER/ATLANTIC	DATE11/5/98 REV.: 0	OF_	2		
	\$: 1988 Dollars				
			MTA	LOWER	PROJECTED
ITEM DESCRIPTION			ESTIMATED COST	BOUND COST	FINAL
TIEM DESCRIPTION			0051	COST	COST
1A) GUIDEWAYS AND STRUCTURES			\$84,025,000	\$77,334,311	\$84,025,000
1B) HAZARDOUS WASTE HANDLING ALLOWANCE			\$1,500,000	\$1,500,000	\$1,500,000
2) STATIONS			\$3,500,000	\$4,593,819	\$3,500,000
3) MAIN YARD AND SHOP			\$35,000,000	\$27,048,316	\$35,000,000
4) SYSTEMWIDE EQUIPMENT			\$37,657,050	\$46,792,559	\$37,657,050
5) VEHICLES			\$85,000,000	\$68,281,115	\$68,281,115
SUBTOTAL (A) (see page 2 for details)			\$246,682,050	\$225,550,120	\$229,963,165
6) PRE REVENUE OPERATION		2.5%	\$6,167,051	\$5,638,753	\$5,749,079
7) OWNERS INSURANCE		8.0%	\$19,734,564	\$18,044,010	\$18,397,053
8) MASTER AGREEMENTS		2.5%	\$6,167,051	\$5,638,753	\$5,749,079
SUBTOTAL (B)			\$32,068,667	\$29,321,516	\$29,895,211
9) ART FOR TRANSIT (C)		0.5%	\$1,233,410	\$1,127,751	\$1,149,816
SUBTOTAL (C)			\$1,233,410	\$1,127,751	\$1,149,816
10) RIGHT OF WAY (D)			\$5,000,000	\$5,000,000	\$5,000,000
SUBTOTAL (D)			\$5,000,000	\$5,000,000	\$5,000,000
11) PROF. SERVICES (E)			\$110,195,811	\$61,624,777	\$74,482,294
SUBTOTAL (E)			\$110,195,811	\$61,624,777	\$74,482,294
SOBIOTAL (E)			\$110,195,011	\$01,024,777	\$74,402,294
12) CONTINGENCY (F)					
A) ITEM 1A	10%		\$8,402,500	\$7,733,431	\$8,402,500
ITEM 1B	10%		\$150,000	\$150,000	\$150,000
B) ITEM 2	8%		\$280,000	\$367,505	\$280,000
C) ITEM 3, 4, & 5	8%		\$12,612,564	\$11,369,759	\$11,275,053
D) ITEM 6, 7, & 8	10%		\$3,206,867	\$2,932,151.56	\$2,989,521
E) ITEM 10	0%		\$0	\$0	\$0
F) ITEM 11	10%		\$11,019,581	\$6,162,478	\$7,448,229
SUBTOTAL (F)			\$35,671,512	\$28,715,325	\$30,545,304

\$430,851,450 \$351,339,488 \$371,035,790

PROJECT: EASTSIDE LRT UNION STATION TO WHITTIER/ATLANTIC	DATE REV	HTL 11/5/98 0		SHT. OF XLS	2 2		
DESCRIPTION	\$:	1988 Dollars MTA UNIT PRICE	BAH UNIT PRICE	UNIT	MTA COST	LOWER BOUND	ESTIMATED PROJECT COST
GUIDEWAY COSTS BRIDGE OVER 101 FREEWAY (SEGMENTAL) AT-GRADE-GUIDEWAY (including street restoration @ \$250 RF and sidewalk reconstructio	800 30250 n @ \$400 RF)	\$10,500 \$2,500	\$3,750 \$2,457	RF RF	\$8,400,000 \$75,625,000	\$3,000,045 \$74,334,266	\$8,400,000 \$75,625,000
SUBTOTAL (GUIDEWAY COST)					\$84,025,000	\$77,334,311	\$84,025,000
HAZARDOUS WASTE HANDLING ALLOWANCE	1	\$1,500,000		LS	\$1,500,000	\$1,500,000	\$1,500,000
SUBTOTAL (HAZ MAT)					\$1,500,000	\$1,500,000	\$1,500,000
STATION COST PASSENGER LOADING/UNLOADING FACILITIES	7	\$500,000	\$656,260	EA	\$3,500,000	\$4,593,819	\$3,500,000
SUBTOTAL (STATION COST)					\$3,500,000	\$4,593,819	\$3,500,000
MAINT. FACIL & YARD COSTS MAINTENANCE FACILITIES (ALLOWANCE)	1	\$35,000,000		LS	\$35,000,000	\$27,048,316	\$35,000,000
SUBTOTAL (MAINT. FACIL.)					\$35,000,000	\$27,048,316	\$35,000,000
VEHICLE COST REVENUE VEHICLE	34	\$2,500,000	\$2,008,268		\$85,000,000	\$68,281,115	\$68,281,115
SUBTOTAL (VEHICLE COST)					\$85,000,000	\$68,281,115	\$68,281,115
SYSTEM WIDE EQUIPMENT COST TRACKWORK (INCL. SPECIAL TRACKWORK)	31050	\$421	\$522	RF	\$13,072,050	\$16,207,294	\$13,072,050
TRAIN CONTROL STA.	6	\$160,000	Included below	EA	\$960,000	Included below	\$960,000
TRAIN CONTROL GDWY TRACTION POWER STA. (XFMR)	31050 6	\$500 \$1,100,000	\$485 \$1,927,875	RF EA	\$15,525,000 \$6,600,000	\$15,055,647 \$11,567,248	\$15,525,000 \$6,600,000
COMMUNICATIONS	31050	\$0	\$90	RF	\$0	\$2,807,414	\$0
FARE COLLECTION SIGNAGE & GRAPHICS	6 6	\$250,000 \$0	\$151,477 \$41,016	EA EA	\$1,500,000 \$0	\$908,860 \$246,097	\$1,500,000 \$0
SUBTOTAL (SYSTEM COST)			ψ 1,010		\$37,657,050	\$46,792,559	\$37,657,050

,

4

TOTAL ESTIMATED COST - 1998 DOLLARS \$246,682,050 \$225,550,120 \$229,963,165

4

PROJECT: EASTSIDE BUS TRANSITWAY UNION STATION TO	EST. HTL DATE <u>11/6/98</u> REV.: <u>0</u>	SHT OF	1 2		
WHITTIER/ATLANTIC VIA ALAMEDA	\$: <u>1988 Dollars</u>		MTA ESTIMATED COST	LOWER BOUND COST	PROJECTED FINAL COST
1A) GUIDEWAYS AND STRUCTURES			\$15,499,200	\$17,882,006	\$15,499,200
1B) HAZARDOUS WASTE HANDLING ALLOWANCE			\$1,500,000	\$1,500,000	\$1,500,000
2) STATIONS			\$3,535,000	\$3,684,224	\$3,535,000
3) MAIN YARD AND SHOP			\$5,000,000	\$5,000,000	\$5,000,000
4) SYSTEMWIDE EQUIPMENT			\$11,640,000	\$5,873,817	\$5,873,817
5) VEHICLES			\$11,900,000	\$11,331,894	\$11,331,894
SUBTOTAL (A) (see page 2 for details)			\$49,074,200	\$45,271,941	\$42,739,911
6) PRE REVENUE OPERATION		2.5%	\$1,226,855	\$1,131,799	\$1,068,498
7) OWNERS INSURANCE		8.0%	\$3,925,936	\$3,621,755	\$3,419,193
8) MASTER AGREEMENTS		5.0%	\$2,453,710	\$2,263,597	\$2,136,996
SUBTOTAL (B)			\$7,606,501	\$7,017,151	\$6,624,686
9) ART FOR TRANSIT (C)		0.5%	\$245,371	\$226,360	\$213,700
SUBTOTAL (C)			\$245.371	\$226,360	\$213,700
56B101AE (0)			4210,011	4220,000	4210,700
10) RIGHT OF WAY (D)			\$0	\$0	\$0
SUBTOTAL (D)			\$0	\$0	\$0
11) PROF. SERVICES (E)			\$22,770,429	\$8,897,055	\$13,881,923
SUBTOTAL (E)			\$22,770,429	\$8,897,055	\$13,881,923
· · ·					
12) CONTINGENCY (F)					
A) ITEM 1A	12%		\$1,859,904	\$2,145,841	\$1,859,904
ITEM 1B	12%		\$180,000	\$180,000	\$180,000
B) ITEM 2	17%		\$600,950	\$626,318	\$600,950
C) ITEM 3, 4, & 5	10%		\$2,854,000	\$2,220,571	\$2,220,571
D) ITEM 6, 7, & 8	10%		\$760,650	\$701,715	\$662,469
E) ITEM 10	10%		\$0	\$0	\$0
F) ITEM 11	10%		\$2,277,043	\$889,705	\$1,388,192
SUBTOTAL (F)			\$8,532,547	\$6,764,150	\$6,912,086

GRAND TOTAL - 1998 DOLLARS \$88,229,048 \$68,176,656 \$70,372,306

PROJECT: EASTSIDE BUS TRANSITWAY UNION STATION TO	EST. DATE REV.	HTL 11/6/98		SHT OF XLS_	2 2		
WHITTIER/ATLANTIC VIA ALAMEDA	. \$:_ QTY	1998 Dollars MTA UNIT PRICE	BAH UNIT PRICE	UNIT	MTA COST	LOWER BOUND	ESTIMATED PROJECT COST
GUIDEWAY COSTS	00070	¢000	£400	RF	¢0.000.400	¢10.005.000	£0.000.400
AT GRADE BUSWAY AT GRADE BUSWAY @ STATION	29370 2880	\$320 \$535	\$466 Incl in above	RF	\$9,398,400 \$1,540,800	\$13,685,288 Incl in above	\$9,398,400 \$1,540,800
STREET IMPROVEMENTS @ XINGS	2000	\$152,000	\$139,891	EA	\$4,560,000	\$4,196,718	\$4,560,000
STREET IMPROVEMENTS & XINGS	30	\$152,000	\$139,091	LA	\$4,500,000	\$4,190,710	\$4,500,000
SUBTOTAL (GUIDEWAY COST)	32280				\$15,499,200	\$17,882,006	\$15,499,200
HAZARDOUS WASTE HANDLING							
ALLOWANCE	1	\$1,500,000	NA .	LS	\$1,500,000	\$1,500,000	\$1,500,000
SUBTOTAL (HAZ MAT)					\$1,500,000	\$1,500,000	\$1,500,000
STATION COST AT GRADE STATION (120 FT. SIDE PLATFORM) (including finishes, landscaping, canopies, lighting & sign	7 nage)	\$505,000	\$526,318	EA	\$3,535,000	\$3,684,224	\$3,535,000
SUBTOTAL (STATION COST)					\$3,535,000	\$3,684,224	\$3,535,000
MAINT. FACIL & YARD COSTS MAINTENANCE FACILITIES (ALLOWANCE) SUBTOTAL (MAINT. FACIL.)	1	\$5,000,000	\$5,000,000		\$5,000,000 \$5,000,000	\$5,000,000 \$5,000,000	\$5,000,000 \$5,000,000
VEHICLE COST							
REVENUE VEHICLE	34	\$350,000	\$333,291		\$11,900,000	\$11,331,894	\$11,331,894
SUBTOTAL (VEHICLE COST)					\$11,900,000	\$11,331,894	\$11,331,894
SYSTEM WIDE EQUIPMENT COST							
PRIORITY SIGNALIZATION	1	\$2,580,000	\$750,000	LS	\$2,580,000	\$750,000	\$750,000
TICKET VENDING MACHINES COMMUNICATIONS	52 32250	\$75,000 \$50	NA \$24	EA RF	\$3,900,000 \$1,612,500	\$908,859 \$774,418	\$908,859 \$774,418
GUIDEWAY LIGHTING INCL. ELECTRIFICATION	32250	\$50 \$60	\$24 \$60	RF	\$1,935,000	\$1,935,000	\$1,935,000
SECURITY	32250	\$30	\$30	RF	\$967.500	\$967,500	\$967,500
SIGNAGE/GRAPHICS (OTHER THAN STATIONS)	32250	\$20	\$17	RF	\$645,000	\$538,040	\$538,040
SUBTOTAL (SYSTEM COST)	02200	220			\$11,640,000	\$5,873,817	\$5,873,817

)

TOTAL ESTIMATED COST - 1998 DOLLARS \$49,074,200 \$45,271,941 \$42,739,911

.

4

PROJECT:	WESTSIDE HEAVY RAIL	EST. HTL	SHT.	1		
-	WILSHIRE/WESTERN TO	DATE 11/5/98	OF	2		
-	VENICE/SAN VICENTE SUBWAY	REV.: 0 \$: 1988 Dollar				
-	SUBWAT	2: 1909 Dollar	5	МТА	LOWER	PROJECTED
				ESTIMATED	BOUND	FINAL
ITEM DESCRI	PTION			COST	COST	COST
1A) GUIDEWA	YS AND STRUCTURES			\$136,959,000	\$137,766,958	\$136,959,000
1B) HAZARDO	US WASTE HANDLING ALLOWANCE			\$6,773,500	\$6,773,500	\$6,773,500
2) STATIONS				\$108,000,000	\$84,954,348	\$84,954,348
3) MAIN YARD				\$0	\$0	\$0
	DE EQUIPMENT			\$44,938,225	\$35,619,075	\$33,307,348
5) VEHICLES				\$0	\$0	\$0
SUBTOTAL (A	.) (see page 2 for details)			\$296,670,725	\$265,113,881	\$261,994,196
	UE OPERATION		2.5%	\$7,416,768	\$6,627,847	\$6,549,855
7) OWNERS IN			8.0%	\$23,733,658	\$21,209,110	\$20,959,536
8) MASTER AC			2.5%	\$7,416,768	\$6,627,847	\$6,549,855
SUBTOTAL (B			2.070	\$38,567,194	\$34,464,805	\$34,059,245
CODICIAL (D	,			<i>400,001,104</i>	<i>401,101,000</i>	\$04,000,£40
9) ART FOR TI			0.5%	\$1,483,354	\$1,325,569	\$1,309,971
SUBTOTAL (C		<i>2</i> .		\$1,483,354	\$1,325,569	\$1,309,971
10) RIGHT OF	WAY (D) ALLOWANCE EQUIVALENT TO	ADOPTED ALIGNMENT		\$44,000,000	\$44,000,000	\$44,000,000
SUBTOTAL (D				\$44,000,000	\$44,000,000	\$44,000,000
And Andrews and Annual Article					. , ,	
11) PROF. SER	RVICES (E) INCL. COST TO DATE			\$162,129,050	\$75,900,945	\$95,581,755
SUBTOTAL (E)			\$162,129,050	\$75,900,945	\$95,581,755
12) CONTINGE	ENCY (F)					
A) ITEM 1A		12%		\$16,435,080	\$16,532,035	\$16,435,080
ITEM 1B		12%		\$812,820	\$812,820	\$812,820
B) ITEM 2		17%		\$18,360,000	\$14,442,239	\$14,442,239
C) ITEM 3, 4,		10%		\$4,493,823	\$3,561,908	\$3,330,735
D) ITEM 6, 7,	δ. ð	10%		\$3,856,719	\$3,446,480	\$3,405,925
E) ITEM 10		10% 10%		\$4,400,000	\$4,400,000	\$4,400,000
F) ITEM 11 SUBTOTAL (F	\	1070		\$16,212,905	\$7,590,094	\$9,558,176
SUBIUIAL (F)			\$64,571,347	\$50,785,576	\$52,384,974

GRAND TOTAL - 1998 DOLLARS \$607,421,670 \$471,590,776 \$489,330,142

VENICE/SAN VICENTE	DATE	11/5/98		SHT. OF	2 2		
	REV	0		XLS			
SUBWAY	\$:	1988 Dollars					ESTIMATED
		MTA UNIT	BAH UNIT		MTA	LOWER	PROJECT
DESCRIPTION	QTY	PRICE	PRICE	UNIT	COST	BOUND	COST
GUIDEWAY COSTS	10100	\$ 40,000	* + • • • • •	-	A 404 000 000	A	A 101 000 000
TWIN TUNNEL CUT & COVER GUIDEWAY	10190	\$10,000	\$10,296	RF	\$101,900,000	\$104,920,798	\$101,900,000
	2407	\$12,000	\$12,255	RF RF	\$28,884,000	\$29,497,228	\$28,884,000
OPEN TRENCH GUIDEWAY	950	\$6,500	\$3,525	RF	\$6,175,000	\$3,348,933	\$6,175,000
					\$0 \$0	\$0 \$0	\$0 \$0
SUBTOTAL (GUIDEWAY COST)	13547				\$136,959,000	\$137,766,958	\$136,959,000
300101AE (0010E11A1 0031)	15547				\$150,555,000	\$157,700,550	\$130,333,000
HAZARDOUS WASTE HANDLING							
ALLOWANCE (incl. La Brea Tar Pits)	13547	\$500	NA	RF	\$6,773,500	\$6,773,500	\$6,773,500
SUBTOTAL (HAZ MAT)			8		\$6,773,500	\$6,773,500	\$6,773,500
STATION COST							
SUBWAY STATION	1	\$65,000,000	\$53,037,724	EA	\$65,000,000	\$53,037,724	\$53,037,724
OPEN TRENCH STATION	1	\$35,000,000	\$23,916,624	EA	\$35,000,000	\$23,916,624	\$23,916,624
BUS FACILITIES	1	\$3,000,000	\$3,000,000	EA	\$3,000,000	\$3,000,000	\$3,000,000
PARKING STRUCTURE	· 1	\$5,000,000	\$5,000,000	EA	\$5,000,000	\$5,000,000	\$5,000,000
SUBTOTAL (STATION COST)					\$108,000,000	\$84,954,348	\$84,954,348
MAINT. FACIL & YARD COSTS							
MAINTENANCE FACILITIES (ALLOWANCE)					\$0	\$0	\$0
SUBTOTAL (MAINT. FACIL.)					\$0	\$0	\$0
VEHICLE COST							
REVENUE VEHICLE					\$0	\$0	\$0
SUBTOTAL (VEHICLE COST)					\$0	\$0	\$0
SYSTEM WIDE EQUIPMENT COST							
TRACKWORK (INCL. SPECIAL TRACKWORK)	13547	\$575	\$674	RF	\$7,789,525	\$9,131,609	\$7,789,525
TRAIN CONTROL STA.	2	\$1,100,000	NA \$074	EA	\$2,200,000	NA	\$2,200,000
TRAIN CONTROL GDWY	13547	\$1,100	\$880	RF	\$14,901,700	\$11,925,771	\$14,901,700
TRACTION POWER STA. (XFMR)	2	\$1,750,000	\$4,500,365	EA	\$3,500,000	\$9,000,731	\$3,500,000
COMMUNICATIONS	13547	\$1,000	\$208	RF	\$13,547,000	\$2,811,813	\$2,811,813
FARE COLLECTION	2	\$750,000	\$1,072,420	LS	\$1,500,000	\$2,144,841	\$1,500,000
SIGNAGE & GRAPHICS	2	\$750,000	\$302,155	LS	\$1,500,000	\$604,310	\$604,310
SUBTOTAL (SYSTEM COST)					\$44,938,225	\$35.619.075	\$33,307,348

TOTAL ESTIMATED COST - 1998 DOLLARS \$296,670,725 \$265,113,881 \$261,994,196

.

4

PROJECT:	WESTSIDE HEAVY RAIL	EST.	HTL	SHT.	1		
_	WILSHIRE/WESTERN TO	DATE	11/5/98	OF_	2		
-	WILSHIRE/FAIRFAX	REV.:	0				
<u></u>	SUBWAY ALIGNMENT	\$:_	1988 Dollars				
					MTA	LOWER	PROJECTED
	PTION				ESTIMATED	BOUND	FINAL
ITEM DESCRI	PTION				COST	COST	COST
	YS AND STRUCTURES				\$184,250,000	\$172,465,492	\$184,250,000
,	US WASTE HANDLING ALLOWANCE				\$16,750,000	\$16,750,000	\$16,750,000
2) STATIONS					\$150,000,000	\$147,789,673	\$147,789,673
3) MAIN YARD	AND SHOP				\$0	\$0	\$0
,	DE EQUIPMENT				\$57,856,250	\$44,765,287	\$43,239,342
5) VEHICLES					\$0	\$0	\$0
SUBTOTAL (A	(see page 2 for details)				\$408,856,250	\$381,770,452	\$392,029,015
	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,						
6) PRE REVE	NUE OPERATION			2.5%	\$10,221,406	\$9,544,261	\$9,800,725
7) OWNERS I	ISURANCE			8.0%	\$32,708,500	\$30,541,636	\$31,362,321
8) MASTER A	GREEMENTS			2.5%	\$10,221,406	\$9,544,261	\$9,800,725
SUBTOTAL (E	3)				\$53,151,313	\$49,630,159	\$50,963,772
9) ART FOR T	RANSIT (C)			0.5%	\$2,044,281	\$1,908,852	\$1,960,145
SUBTOTAL (C	;)				\$2,044,281	\$1,908,852	\$1,960,145
10) RIGHT OF	WAY (D) ALLOWANCE EQUIVALENT TO		DALIGNMENT		\$66,000,000	\$66,000,000	\$66,000,000
SUBTOTAL (D					\$66,000,000	\$66,000,000	\$66,000,000
	,					+,,,	+,,
11) PROF. SE	RVICES (E) INCL. COST TO DATE			(MTA - 45%, BAH - 22%)	\$238,523,330	\$109,879,943	\$143,066,821.09
SUBTOTAL (E	·)				\$238,523,330	\$109,879,943	\$143,066,821
12) CONTINGI	ENCY (F)						
A) ITEM 1A		12%			\$22,110,000	\$20,695,859	
ITEM 1B		12%			\$2,010,000	\$2,010,000	\$2,010,000
B) ITEM 2		17%			\$25,500,000	\$25,124,244	\$25,124,244
C) ITEM 3, 4,		10%			\$5,785,625	\$4,476,529	\$4,323,934
D) ITEM 6, 7,	& 8	10%			\$5,315,131	\$4,963,016	\$5,096,377
E) ITEM 10		10%			\$6,600,000	\$6,600,000	\$6,600,000
F) ITEM 11		10%			\$23,852,333	\$10,987,994	\$14,306,682
SUBTOTAL (F)			¥.	\$91,173,089	\$74,857,642	\$79,571,238

GRAND TOTAL - 1998 DOLLARS \$859,748,263 \$684,047,049 \$733,590,991

MTA UNIT DESCRIPTION MTA UNIT PRICE BAH UNIT PRICE MTA UNIT MTA COST LOWER BOUND ESTIMATE PROJECT COST GUIDEWAY COSTS GUIDEWAY COSTS 16750 \$11,000 \$10,296 RF \$184,250,000 \$172,465,492 \$184,250,000 SUBTOTAL (GUIDEWAY COST) 16750 \$11,000 \$10,296 RF \$184,250,000 \$172,465,492 \$184,250,000 HAZARDOUS WASTE HANDLING ALLOWANCE (Incl. La Brea Tar Pits) 16750 \$1,000 NA RF \$16,750,000	PROJECT: WESTSIDE HEAVY RAIL WILSHIRE/WESTERN TO WILSHIRE/FAIRFAX SUBWAY ALIGNMENT	EST DATE REV \$:	HTL 11/5/98 0 1988 Dollars		SHT. OF XLS	2 2		,
TWIN BORE TUNNEL 16750 \$11,000 \$10,296 RF \$184,250,000 \$172,465,492 \$184,250,00 SUBTOTAL (GUIDEWAY COST) 16750 \$10 \$10,296 RF \$184,250,000 \$172,465,492 \$184,250,00 HAZARDOUS WASTE HANDLING ALLOWANCE (Incl. La Brea Tar Pits) 16750 \$1,000 NA RF \$16,750,000 \$10,750,82,224 \$39,263,224 \$39,263,224 \$39,263,224	DESCRIPTION		MTA UNIT		UNIT			ESTIMATED PROJECT COST
SUB \$0 \$0 SUBTOTAL (GUIDEWAY COST) 16750 \$184,250,000 \$172,465,492 \$184,250,000 ALLOWANCE (incl. La Brea Tar Pits) 16750 \$1,000 NA RF \$16,750,000 \$10,72,845,873 \$14,74,789,673 \$14,74,789,673 \$14,74,789,673 \$14,74,789,673 \$14,747,789,673 \$14,747,789,673 \$14,747,789,673 \$14,747,789,673 \$14,747,789,673		16750	\$11,000	\$10,296	RF	\$184,250,000	\$172,465,492	\$184,250,000
HAZARDOUS WASTE HANDLING ALLOWANCE (incl. La Brea Tar Pits) 16750 \$1,000 NA RF \$16,750,000 \$39,263,224 \$39								
ALLOWANCE (incl. La Brea Tar Pits) 16750 \$1,000 NA RF \$16,750,000 \$10,739,613,224 \$39,263,224 \$39,263,224 \$39,263,224 \$39,263,224 \$39,263,224 \$39,263,224 \$39,263,224 \$39,263,224 \$39,263,224 \$39,263,224 \$39,263,224 \$39,263,224 \$39,263,224 \$39,263,224 \$39,263,224 \$\$39,263,224 \$\$39,263,224 \$\$39,263,224 \$\$39,263,224 \$\$39,263,224 \$\$39,263,224 \$\$39,263,224	SUBTOTAL (GUIDEWAY COST)	16750				\$184,250,000	\$172,465,492	\$184,250,000
SUBTOTAL (HAZ MAT) \$16,750,000 \$16,750,224 \$39,263,224 \$39,263,224 \$39,263,224 \$39,263,224 \$39,263,224 \$39,263,224 \$69,263,226 \$69,263,224 \$69,263,226 <td></td> <td>16750</td> <td>\$1.000</td> <td>NA</td> <td>BF</td> <td>\$16.750.000</td> <td>\$16.750.000</td> <td>\$16,750,000</td>		16750	\$1.000	NA	BF	\$16.750.000	\$16.750.000	\$16,750,000
STATION COST Sign 263,224 EA \$40,000,000 \$39,263,224 EA \$40,000,000 \$39,263,224 \$39,263,224 \$39,263,224 \$39,263,224 \$39,263,224 \$39,263,224 \$39,263,224 \$39,263,224 \$39,263,224 \$39,263,224 \$39,263,224 \$39,263,224 \$39,263,224 \$\$39,263,224 \$\$39,263,224 \$\$39,263,224 \$\$39,263,224 \$\$39,263,224 \$\$59,263,224			÷.,000				tant the second s	\$16,750,000
MAINT. FACIL & YARD COSTS MAINTENANCE FACILITIES (ALLOWANCE) \$0 \$0 SUBTOTAL (MAINT. FACIL.) \$0 \$0 VEHICLE COST REVENUE VEHICLE \$0 \$0 SUBTOTAL (VEHICLE COST) \$0 \$0 SUBTOTAL (VEHICLE COST) \$0 \$0 SYSTEM WIDE EQUIPMENT COST \$0 \$0 TRACKWORK (INCL. SPECIAL TRACKWORK) 16750 \$575 \$674 RF \$9,631,250 \$11,290,651 \$9,631,250 TRAIN CONTROL STA. 3 \$1,100,000 NA EA \$3,300,000 NA \$3,300,000 TRAIN CONTROL GDWY 16750 \$11,100 \$880 RF \$18,425,000 \$14,745,454 \$18,425,000 COMMUNICATIONS 16750 \$1,100 \$880 RF \$18,6,750,000 \$3,476,627 \$3,476,627 \$3,476,627 \$3,476,627 \$3,476,627 \$3,476,627 \$3,476,627 \$3,476,627 \$3,476,627 \$3,476,627 \$3,476,627 \$3,476,627 \$3,476,627 \$3,476,627 \$3,476,627 \$3,476,627 \$3,476,627 \$3,476,627 \$3,476,627 <td< td=""><td>WILSHIRE/CRENSHAW STATION WILSHIRE/LA BREA STATION</td><td>1 1 1</td><td>\$40,000,000</td><td>\$39,263,224</td><td>EA</td><td>\$40,000,000</td><td>\$39,263,224</td><td>\$39,263,224 \$39,263,224 \$69,263,224</td></td<>	WILSHIRE/CRENSHAW STATION WILSHIRE/LA BREA STATION	1 1 1	\$40,000,000	\$39,263,224	EA	\$40,000,000	\$39,263,224	\$39,263,224 \$39,263,224 \$69,263,224
MAINTENANCE FACILITIES (ALLOWANCE) \$0 \$0 SUBTOTAL (MAINT. FACIL.) \$0 \$0 \$0 VEHICLE COST REVENUE VEHICLE \$0 \$0 \$0 SUBTOTAL (VEHICLE COST) \$0 \$0 \$0 SUBTOTAL (VEHICLE COST) \$0 \$0 \$0 SYSTEM WIDE EQUIPMENT COST \$0 \$0 \$0 TRACKWORK (INCL. SPECIAL TRACKWORK) 16750 \$575 \$674 RF \$9,631,250 \$11,290,651 \$9,631,250 TRACKWORK (INCL. SPECIAL TRACKWORK) 16750 \$575 \$674 RF \$9,631,250 \$11,290,651 \$9,631,250 TRACKWORK (INCL. SPECIAL TRACKWORK) 16750 \$17,100,000 NA EA \$3,300,00 NA \$3,300,00 TRACKION POWER STA. 3 \$1,100,000 NA EA \$3,300,00 \$14,745,454 \$18,425,00 TRACTION POWER STA. (XFMR) 3 \$1,750,000 \$3,709,610 EA \$5,250,000 \$11,128,829 \$5,250,000 \$3,476,627 \$3,476,627 \$3,476,627 \$3,476,627 \$3,476,627 <td>SUBTOTAL (STATION COST)</td> <td></td> <td></td> <td></td> <td></td> <td>\$150,000,000</td> <td>\$147,789,673</td> <td>\$147,789,673</td>	SUBTOTAL (STATION COST)					\$150,000,000	\$147,789,673	\$147,789,673
REVENUE VEHICLE \$0 \$0 SUBTOTAL (VEHICLE COST) \$0 \$0 SYSTEM WIDE EQUIPMENT COST \$0 \$0 TRACKWORK (INCL. SPECIAL TRACKWORK) 16750 \$575 \$674 RF \$9,631,250 \$11,290,651 \$9,631,250 TRAIN CONTROL STA. 3 \$1,100,000 NA EA \$3,300,000 NA \$3,300,000 TRAIN CONTROL GDWY 16750 \$11,100 \$880 RF \$18,425,000 \$14,745,454 \$18,425,000 TRACTION POWER STA. (XFMR) 3 \$1,750,000 \$3,709,610 EA \$5,250,000 \$11,128,829 \$5,250,000 COMMUNICATIONS 16750 \$1,000 \$208 RF \$16,750,000 \$3,476,627 \$3,476,627 FARE COLLECTION 3 \$750,000 \$1,072,420 LS \$2,250,000 \$3,217,261 \$2,250,000 SIGNAGE & GRAPHICS 3 \$750,000 \$302,155 LS \$2,250,000 \$906,465 \$906,465	MAINTENANCE FACILITIES (ALLOWANCE)		an a					\$0 \$0
SYSTEM WIDE EQUIPMENT COST TRACKWORK (INCL. SPECIAL TRACKWORK) 16750 \$575 \$674 RF \$9,631,250 \$11,290,651 \$9,631,250 TRAIN CONTROL STA. 3 \$1,100,000 NA EA \$3,300,000 NA \$3,300,000 TRAIN CONTROL GDWY 16750 \$11,100 \$880 RF \$18,425,000 \$14,745,454 \$18,425,000 TRACTION POWER STA. (XFMR) 3 \$1,750,000 \$3,709,610 EA \$5,250,000 \$11,128,829 \$5,250,000 COMMUNICATIONS 16750 \$1,000 \$208 RF \$16,750,000 \$3,476,627 \$3,476,627 FARE COLLECTION 3 \$750,000 \$1,072,420 LS \$2,250,000 \$3,217,261 \$2,250,000 SIGNAGE & GRAPHICS 3 \$750,000 \$302,155 LS \$2,250,000 \$906,465 \$906,465	REVENUE VEHICLE					and the second se		\$0
TRACKWORK (INCL. SPECIAL TRACKWORK)16750\$575\$674RF\$9,631,250\$11,290,651\$9,631,2TRAIN CONTROL STA.3\$1,100,000NAEA\$3,300,000NA\$3,300,00TRAIN CONTROL GDWY16750\$11,100\$880RF\$18,425,000\$14,745,454\$18,425,00TRACTION POWER STA. (XFMR)3\$1,750,000\$3,709,610EA\$5,250,000\$11,128,829\$5,250,00COMMUNICATIONS16750\$1,000\$208RF\$16,750,000\$3,476,627\$3,476,627FARE COLLECTION3\$750,000\$1,072,420LS\$2,250,000\$3,217,261\$2,250,00SIGNAGE & GRAPHICS3\$750,000\$302,155LS\$2,250,000\$906,465\$906,465	SUBTOTAL (VEHICLE COST)					\$0	\$0	\$0
TRAIN CONTROL STA.3\$1,100,000NAEA\$3,300,000NA\$3,300,00TRAIN CONTROL GDWY16750\$11,100\$880RF\$18,425,000\$14,745,454\$18,425,00TRACTION POWER STA. (XFMR)3\$1,750,000\$3,709,610EA\$5,250,000\$11,128,829\$5,250,00COMMUNICATIONS16750\$1,000\$208RF\$16,750,000\$3,476,627\$3,476,627FARE COLLECTION3\$750,000\$1,072,420LS\$2,250,000\$3,217,261\$2,250,000SIGNAGE & GRAPHICS3\$750,000\$302,155LS\$2,250,000\$906,465\$906,465		16750	\$575	\$674	BF	\$9.631.250	\$11.290.651	\$9,631,250
TRACTION POWER STA. (XFMR)3\$1,750,000\$3,709,610EA\$5,250,000\$11,128,829\$5,250,00COMMUNICATIONS16750\$1,000\$208RF\$16,750,000\$3,476,627\$3,476,627FARE COLLECTION3\$750,000\$1,072,420LS\$2,250,000\$3,217,261\$2,250,00SIGNAGE & GRAPHICS3\$750,000\$302,155LS\$2,250,000\$906,465\$906,465	TRAIN CONTROL STA.	3	\$1,100,000	NA	EA	\$3,300,000	NA	\$3,300,000 \$18,425,000
FARE COLLECTION3\$750,000\$1,072,420LS\$2,250,000\$3,217,261\$2,250,00SIGNAGE & GRAPHICS3\$750,000\$302,155LS\$2,250,000\$906,465\$906,465	TRACTION POWER STA. (XFMR)	3	\$1,750,000	\$3,709,610	EA	\$5,250,000	\$11,128,829	\$5,250,000 \$3,476,627
	FARE COLLECTION	3	\$750,000	\$1,072,420	LS	\$2,250,000	\$3,217,261	\$2,250,000 \$906,465
SUBTOTAL (SYSTEM COST) \$57,856.250 \$44,765.287 \$43.239.3	SUBTOTAL (SYSTEM COST)	J	φ/30,000	ψυυς, 100	20	\$57,856,250	\$44,765,287	\$43,239,342

*

*

TOTAL ESTIMATED COST - 1998 DOLLARS \$408,856,250 \$381,770,452 \$392,029,015

Note: Vehicle costs are zero as vehicles have already been purchased for this line. MPA estimates 4 vehicle fleet required to operate this segment.

.

PROJECT: WESTSIDE CORRIDOR	EST. HT DATE 11/5		1 2		
USC TO SANTA MONICA	REV.: 0 \$: 1988 D				
En	¢. <u></u>		MTA ESTIMATED	LOWER BOUND	PROJECTED FINAL
ITEM DESCRIPTION			COST	COST	COST
1A) GUIDEWAYS AND STRUCTURES			\$27,617,000	\$30,206,742	\$27,617,000
1B) HAZARDOUS WASTE HANDLING ALLOWANCE			\$0	\$0	\$0
2) STATIONS			\$3,600,000	\$2,268,784	\$2,268,784
			\$0 \$19,066,885	\$0 \$13,219,217	\$0
4) SYSTEMWIDE EQUIPMENT 5) VEHICLES			\$19,000,005 \$0	\$13,219,217	\$17,830,355 \$0
SUBTOTAL (A) (see page 2 for details)			\$50,283,885	\$45,694,742	\$47,716,139
				••••••	
6) PRE REVENUE OPERATION		2.5%	\$1,257,097	\$1,142,369	\$1,192,903
7) OWNERS INSURANCE		8.0% 2.5%	\$4,022,711 \$1,257,097	\$3,655,579 \$1,142,369	\$3,817,291 \$1,192,903
8) MASTER AGREEMENTS		2.5%	\$6,536,905	\$5,940,317	\$6,203,098
SUBTOTAL (B)			40,000,900	\$5,940,317	\$0,203,090
9) ART FOR TRANSIT (C)		0.5%	\$251,419	\$228,474	\$238,581
SUBTOTAL (C)			\$251,419	\$228,474	\$238,581
10) RIGHT OF WAY (D) PER BUDGET OF 81/25/92			\$12,292,553	\$12,292,553	\$12,292,553
SUBTOTAL (D)			\$12,292,553	\$12,292,553	\$12,292,553
11) PROF. SERVICES (E)			\$20,809,429	\$15,147,945	\$18,606,104
SUBTOTAL (E)			\$20,809,429	\$15,147,945	\$18,606,104
12) CONTINGENCY (F)					
A) ITEM 1A	11%		\$3,037,870	\$3,322,742	\$3,037,870
ITEM 1B	11% 11%		\$0 \$396,000	\$0 \$249,566	\$0 \$240 566
B) ITEM 2 C) ITEM 3, 4, & 5	11%		\$396,000 \$2,097,357	\$249,566 \$1,454,114	\$249,566 \$1,961,339
D) ITEM 6, 7, & 8	11%		\$719,060	\$653,434.82	\$682,341
E) ITEM 10	25%		\$3,073,138	\$3,073,138	\$3,073,138
F) ITEM 11	10%		\$2,080,943	\$1,514,795	\$1,860,610
SUBTOTAL (F)			\$11,404,368	\$10,267,789	\$10,864,865
				· · · · · · · · · · · · · · · · · · ·	

GRAND TOTAL - 1998 DOLLARS \$101,578,560 \$89,571,821 \$95,921,340

GRAND TOTAL Including USC to Santa Monica Segment - 1998 DOLLARS \$930,840,960 \$739,170,790 \$842,876,711

PROJECT: WESTSIDE CORRIDOR EXPOSITION LINE	_ EST DATE	HTL 11/5/98		SHT. OF	2		
USC TO SANTA MONICA	REV.	0		XLS			
LRT	\$:	1988 Dollars					
		MTA UNIT	BAH UNIT		MTA	LOWER	ESTIMATED
DESCRIPTION	QTY	PRICE	PRICE	UNIT	COST	BOUND	PROJECT COST
GUIDEWAY COSTS	dill	THICE	THICE	UNIT	0001	BOOND	0031
AT GRADE (IN STREET CONST.)	7755	\$1,800	\$2,457	RF	\$13,959,000	\$19,056,603	\$13,959,000
AERIAL GUIDEWAY	1760	\$4,500	\$5,284	RF	\$7,920,000	\$9,300,139	\$7,920,000
AERIAL GUIDEWAY (OVER 110 FRWY)	720	\$5,400	included above	RF	\$3,888,000	included above	\$3,888,000
SPECIAL BENT STRUCTURES	3	\$350,000	\$350,000	EA	\$1,050,000	\$1,050,000	\$1,050,000
SPECIAL TRAFFIC MAINTENANCE	1	\$800,000	\$800,000	LS	\$800,000	\$800,000	\$800,000
SUBTOTAL (GUIDEWAY COST)					\$27,617,000	\$30,206,742	\$27,617,000
HAZADDOUG WASTE HANDLING							
HAZARDOUS WASTE HANDLING ALLOWANCE				RF	\$0	\$0	
SUBTOTAL (HAZ MAT)					\$0	\$0	
					4 0	v u	
STATION COST							
AT GRADE STATION (2 CAR PLATFORM)	3	\$1,200,000	\$756,261	EA	\$3,600,000	\$2,268,784	\$2,268,784
					¢2 000 000	¢0.000.704	¢0.000.704
SUBTOTAL (STATION COST)					\$3,600,000	\$2,268,784	\$2,268,784
MAINT. FACIL & YARD COSTS							
MAINTENANCE FACILITIES (ALLOWANCE)					\$0	\$0	\$0
SUBTOTAL (MAINT. FACIL.)					\$0	\$0	\$0
VEHICLE COST	te Cente Men	ing about)			¢0.	¢0	¢o
REVENUE VEHICLE (all vehicle costs covered in USC	to Santa Mon	ica sneet)			\$0 \$0	\$0 \$0	\$0 \$0
SUBTOTAL (VEHICLE COST)					20	\$0	\$0
SYSTEM WIDE EQUIPMENT COST							
TRACKWORK (INCL. SPECIAL TRACKWORK)	10235	\$421	\$288	RF	\$4,308,935	\$2,943,540	\$4,308,935
TRAIN CONTROL STA.	3	\$160,000	Included below	EA	\$480,000	Included below	\$480,000
TRAIN CONTROL GDWY	10235	\$500	\$485	RF	\$5,117,500	\$4,962,787	\$5,117,500
TRACTION POWER STA. (XFMR)	3	\$1,100,000	\$309,956	EA	\$3,300,000	\$929,869	\$3,300,000
TRACTION POWER GDWY. (CATENARY)	10235	\$270	\$282	RF	\$2,763,450	\$2,883,038	\$2,763,450
COMMUNICATIONS	10235	\$200	\$98	RF	\$2,047,000	\$1,005,000	\$1,005,000
FARE COLLECTION	3	\$250,000	\$129,837	EA	\$750,000	\$389,511	\$750,000
SIGNAGE & GRAPHICS	3	\$100,000	\$35,157	EA	\$300,000	\$105,470	\$105,470
SUBTOTAL (SYSTEM COST)					\$19,066,885	\$13,219,217	\$17,830,355
TOTAL ESTIMATED COST - 1998 DOLLARS					\$50,283,885	\$45,694,742	\$47,716,139
							•

.

PROJECT: WESTSIDE CORRIDOR	EST. <u>HTL</u> DATE 11/5/98	SHT OF	2		
USC TO SANTA MONICA	REV.: 0				
	\$:1988 Dollars		MTA ESTIMATED	LOWER	PROJECTED FINAL
ITEM DESCRIPTION			COST	COST	COST
1A) GUIDEWAYS AND STRUCTURES			\$142,147,750	\$117,300,154	\$142,147,750
1B) HAZARDOUS WASTE HANDLING ALLOWANCE			\$1,738,438	\$1,738,438	\$1,738,438
2) STATIONS			\$40,166,667	\$26,235,735	\$26,235,735
3) MAIN YARD AND SHOP			\$35,000,000	\$31,026,010	\$35,000,000
4) SYSTEMWIDE EQUIPMENT			\$107,290,400	\$81,812,117	\$99,565,790
5) VEHICLES			\$97,500,000	\$78,322,456	\$78,322,456
SUBTOTAL (A) (see page 2 for details)			\$423,843,255	\$336,434,910	\$383,010,169
6) PRE REVENUE OPERATION		2.5%	\$10,596,081	\$8,410,873	\$9,575,254
7) OWNERS INSURANCE		8.0%	\$33,907,460	\$26,914,793	\$30,640,814
8) MASTER AGREEMENTS		2.5%	\$10,596,081	\$8,410,873	\$9,575,254
SUBTOTAL (B)			\$55,099,623	\$43,736,538	\$49,791,322
9) ART FOR TRANSIT (C)		0.5%	\$2,119,216	\$1,682,175	\$1,915,051
SUBTOTAL (C)			\$2,119,216	\$1,682,175	\$1,915,051
10) RIGHT OF WAY (D) PER UPDATE OF 11/23/93			\$82,588,736	\$82,588,736	\$82,588,736
SUBTOTAL (D)			\$82,588,736	\$82,588,736	\$82,588,736
11) PROF. SERVICES (E)			\$172,923,592	\$109,659,862	\$144,845,478
SUBTOTAL (E)			\$172,923,592	\$109,659,862	\$144,845,478
12) CONTINGENCY (F)					
A) ITEM 1A	11%		\$15,636,253	\$12,903,017	\$15,636,253
ITEM 1B	11%		\$191,228	\$191,228	\$191,228
B) ITEM 2	11%		\$4,418,333	\$2,885,931	\$2,885,931
C) ITEM 3, 4, & 5	11%		\$26,376,944	\$21,027,664	\$23,417,707
D) ITEM 6, 7, & 8	11%		\$6,060,959	\$4,811,019.21	\$5,477,045
E) ITEM 10	28%		\$22,711,903	\$22,711,903	\$22,711,903
F) ITEM 11	10%		\$17,292,359	\$10,965,986	\$14,484,548
SUBTOTAL (F)			\$92,687,978	\$75,496,748	\$84,804,614

GRAND TOTAL + 1996 DOLLARS \$829,262,401 \$649,598,969 \$746,955,371

ì

PROJECT: WESTSIDE CORRIDO EXPOSITION LINE USC TO SANTA MONI LRT	DATE	HTL 11/5/98 0 1988 Dollars		SHT OF XLS_	2 2		
	QTY	MTA UNIT PRICE	BAH UNIT PRICE	UNIT	MTA COST	LOWER BOUND	ESTIMATED PROJECT COST
GUIDEWAY COSTS							
AT GRADE (IN STREET CONST.)	6500	\$1,800	\$2,457	RF	\$11,700,000	\$15,972,652	\$11,700,000
AT GRADE (IN RAILROAD ROW)	43350	\$1,200	\$757	RF	\$52,020,000	\$32,828,779	\$52,020,000
AERIAL GUIDEWAY (FLYOVER)	12600	\$4,500	\$3,750	RF	\$56,700,000	\$47,250,706	\$56,700,000
SUBWAY GUIDEWAY (UNDERCRO		\$11,400	\$12,867	RF	\$17,100,000	\$19,299,817	\$17,100,000
BRIDGE WIDENING	450	\$2,000	\$2,000	RF	\$900,000	\$900,000	\$900,000
REMOVE EXISTING TRACKS	57350	\$65	\$18	TF	\$3,727,750	\$1,048,199	\$3,727,750
SUBTOTAL (GUIDEWAY COST)	121750				\$142,147,750	\$117,300,154	\$142,147,750
HAZARDOUS WASTE HANDLING							
ALLOWANCE	1	\$1,738,438	NA	RF	\$1,738,438	\$1,738,438	\$1,738,438
SUBTOTAL (HAZ MAT)					\$1,738,438	\$1,738,438	\$1,738,438
STATION COST							
AT GRADE STATION (2 CAR PLATE	ORM) 9	\$1,500,000	\$756,261	EA	\$13,500,000	\$6.806.352	\$6,806,352
AERIAL STATION (2 CAR PLATFOR		\$4,333,333	\$2,667,216	EA	\$21,666,667	\$13,336,080	\$13,336,080
PARK & RIDE (SURFACE LOT)	2500	\$2,000		Spaces	\$5,000,000	\$6,093,304	\$6,093,304
SUBTOTAL (STATION COST)					\$40,166,667	\$26,235,735	\$26,235,735
MAINT. FACIL & YARD COSTS							
MAINTENANCE FACILITIES (ALLO	WANCE) 1	\$35,000,000	\$31,026,010		\$35,000,000	\$31,026,010	\$35,000,000
SUBTOTAL (MAINT. FACIL.)					\$35,000,000	\$31,026,010	\$35,000,000
VEHICLE COST							
REVENUE VEHICLES	39	\$2,500,000	\$2,002,330		\$97,500,000	\$78,322,456	\$78,322,456
(for complete Expo alignment, LA LR		\$2,000,000	\$2,002,000		\$07,000,000	\$10,0LL,400	<i>\$10,022,400</i>
SUBTOTAL (VEHICLE COST)					\$97,500,000	\$78,322,456	\$78,322,456
SYSTEM WIDE EQUIPMENT COST							
TRACKWORK (INCL. SPECIAL TRACKWORK	ACKWORK) 64400	\$421	\$288	BF	\$27,112,400	\$18,521,152	\$27,112,400
TRACKWORK (INCL. SPECIAL TRA	11	\$160.000	Included below	EA	\$1,760,000	Included below	\$1,760,000
TRAIN CONTROL STA.	64400	\$100,000	\$485	RF	\$32,200,000	\$31,226,528	\$32,200,000
TRACTION POWER STA. (XFMR)	11	\$1,100,000	\$531.897	EA	\$12,100,000	\$5.850.862	\$12,100,000
TRACTION POWER STA. (APMR)		\$1,100,000	\$531,697	RF	\$17,388,000	\$18,140,466	\$17,388,000
COMMUNICATIONS	64400	\$200	\$89	RF	\$12,880,000	\$5,763,195	\$5,763,195
FARE COLLECTION	11	\$250,000	\$165.247	EA	\$2,750,000	\$1,817,719	\$2,750,000
SIGNAGE & GRAPHICS	11	\$100,000	\$44,745	EA	\$1,100,000	\$492,195	\$492,195
SUBTOTAL (SYSTEM COST)		φ100,000	ψ 1 ,145	L A	\$107,290,400	\$81,812,117	
SUBIUIAL (STSTEM CUST)					\$107,290,400	əo1,612,117	\$99,565,790
							i.
TOTAL COTINATED COST 1000	0011400						

٠

.

*

TOTAL ESTIMATED COST - 1998 DOLLARS \$423,843,255 \$336,434,910 \$383,010,169

PROJECT: EXPOSITION BUS TRANSITWAY	EST. HTL DATE 11/6/98	SHT OF	1 2		
SANTA MONICA TO	REV.: 2		<u> </u>		
	\$: <u>1988 Dolla</u>	r <u>s</u>	MTA ESTIMATED COST	LOWER BOUND COST	PROJECTED FINAL COST
1A) GUIDEWAYS AND STRUCTURES			\$87,624,600	\$154,066,577	\$87,624,600
1B) HAZARDOUS WASTE HANDLING ALLOWANCE			\$1,500,000	\$1,500,000	\$1,500,000
2) STATIONS			\$15,405,000	\$17,007,758	\$16,029,337
3) MAIN YARD AND SHOP			\$5,000,000	\$5,000,000	\$5,000,000
4) SYSTEMWIDE EQUIPMENT			\$19,870,500	\$17,552,349	\$15,696,299
5) VEHICLES			\$10,150,000	\$9,665,439	\$9,665,439
SUBTOTAL (A) (see page 2 for details)			\$139,550,100	\$204,792,123	\$135,515,676
6) PRE REVENUE OPERATION		2.5%	\$3,488,753	\$5,119,803	\$3,387,892
7) OWNERS INSURANCE		8.0%	\$11,164,008	\$16,383,370	\$10,841,254
8) MASTER AGREEMENTS		5.0%	\$6,977,505	\$10,239,606	\$6,775,784
SUBTOTAL (B)			\$21,630,266	\$31,742,779	\$21,004,930
9) ART FOR TRANSIT (C)		0.5%	\$697,751	\$1,023,961	\$677,578
SUBTOTAL (C)			\$697,751	\$1,023,961	\$677,578
10) RIGHT OF WAY (D) ALLOWANCE FOR 4 PARK-N-R	DES		\$4,900,000	\$4,900,000	\$4,900,000
SUBTOTAL (D)			\$4,900,000	\$4,900,000	\$4,900,000
11) PROF. SERVICES (E)			\$70,927,410	\$41,076,859	\$45,387,491
SUBTOTAL (E)			\$70,927,410	\$41,076,859	\$45,387,491
12) CONTINGENCY (F)					
A) ITEM 1A	12%	9	\$10,514,952	\$18,487,989	\$10,514,952
ITEM 1B	12%		\$180,000	\$180.000	\$180,000
B) ITEM 2	17%		\$2,618,850	\$2,891,319	\$2,724,987
C) ITEM 3, 4, & 5	10%		\$3,502,050	\$3,221,779	\$3,036,174
D) ITEM 6, 7, & 8	10%		\$2,163,027	\$3,174,278	\$2,100,493
E) ITEM 10	10%		\$490,000	\$490,000	\$490,000
F) ITEM 11	10%		\$7,092,741	\$4,107,686	\$4,538,749
SUBTOTAL (F)			\$26,561,620	\$32,553,051	\$23,585,355

GRAND TOTAL - 1998 DOLLARS \$264,267,146 \$316,088,772 \$231,071,031

÷

PROJECT: EXPOSITION BUS TRANSITWA	Y EST DATE	HTL 11/6/98		SHT OF	2		
SANTA MONICA TO	REV.	2		XLS	-		
GATEWAY	\$:	1998 Dollars					
							ESTIMATE
DESCRIPTION	QTY	MTA UNIT PRICE	BAH UNIT PRICE	UNIT	MTA COST	LOWER	PROJECT COST
GUIDEWAY COSTS							
AT GRADE BUSWAY	63360	\$320	\$1,676	RF	\$20,275,200	\$106,195,985	\$20,275,
AT GRADE BUSWAY @ STATION	7800	\$535	Incl in above	RF	\$4,173,000	Incl in above	\$4,173,
STREET IMPROVEMENTS @ XINGS	110	\$152,000	\$139.891	EA	\$16,720,000	\$15,387,966	\$16,720,
TRACK REMOVAL	63360	\$65	\$18	RF	\$4,118,400	\$1,114,819	\$4,118,
AERIAL OVERPASS	5400	\$5,000	\$2,708	RF	\$27,000,000	\$14,620,824	\$27,000,
BELOW GRADE UNDERPAS	1	\$5,000,000	\$5,000,000	EA	\$5,000,000	\$5,000,000	\$5,000.
RAILROAD BRIDGE REPLACEMENT	3	\$2,000,000	\$2,000,000	EA	\$6,000,000	\$6,000,000	\$6,000,
MIXED FLOW DEDICATED BUSWAY	2020	\$150	\$2,845	RF	\$303,000	\$5,746,982	\$303.
DOWNTOWN CONNECTOR (GRAND/OLIVE)	26900	\$150	Incl in above	RF	\$4,035,000	Incl in above	\$4,035,
SUBTOTAL (GUIDEWAY COST)	168954				\$87,624,600	\$154,066,577	\$87,624,
HAZARDOUS WASTE HANDLING							
ALLOWANCE	1	\$1,500,000	NA	LS	\$1,500,000	\$1,500,000	\$1,500,
SUBTOTAL (HAZ MAT)					\$1,500,000	\$1,500,000	\$1,500.
(including 2 elevators, finishes, canopies, lightin AT GRADE STATION (120 FT. SIDE PLATFOF (including finishes, landscaping, canopies, lighti CURBSIDE STATION (INCL. CANOPY, BENCI	RM) 21 ng & signage)	\$505,000 \$27,500	\$526,318 \$25.000	EA EA	\$10,605,000 \$55,000	\$11,052,672 \$50,000	\$11,052, \$55.
PARKING FACILITIES (MINIMAL AMENITIES)	1800	\$1,800	+	Spaces	\$3,240,000	\$4,223,421	\$3,240,
SUBTOTAL (STATION COST)					\$15,405,000	\$17,007,758	\$16,029,
MAINT FACE A VARD COSTS							
MAINT. FACIL & YARD COSTS MAINTENANCE FACILITIES (ALLOWANCE)	1	\$5,000,000	\$5,000,000		\$5,000,000	\$5,000,000	\$5,000
MAINTENANCE FACILITIES (ALLOWANCE)	1	\$5,000,000	\$5,000,000		\$5,000,000 \$5,000,000	\$5,000,000 \$5,000,000	and the second se
MAINTENANCE FACILITIES (ALLOWANCE) SUBTOTAL (MAINT. FACIL.) VEHICLE COST						the second s	and the second se
MAINTENANCE FACILITIES (ÅLLOWANCE) SUBTOTAL (MAINT. FACIL.)	1 29	\$5,000,000 \$350,000	\$5,000,000			the second s	\$5,000,
MAINTENANCE FACILITIES (ALLOWANCE) SUBTOTAL (MAINT. FACIL.) VEHICLE COST					\$5,000,000	\$5,000,000	\$5,000 , \$9,665
SUBTOTAL (MAINT. FACIL.) VEHICLE COST REVENUE VEHICLE SUBTOTAL (VEHICLE COST) SYSTEM WIDE EQUIPMENT COST	29	\$350,000	\$333,291		\$5,000,000 \$10,150,000 \$10,150,000	\$5,000,000 \$9,665,439 \$9,665,439	\$5,000 \$9,665 \$9,665
MAINTENANCE FACILITIES (ALLOWANCE) SUBTOTAL (MAINT. FACIL.) VEHICLE COST REVENUE VEHICLE SUBTOTAL (VEHICLE COST) SYSTEM WIDE EQUIPMENT COST PRIORITY SIGNALIZATION	29	\$350,000 \$5,596,500	\$333,291 \$2,750,000	LS	\$5,000,000 \$10,150,000 \$10,150,000 \$5,596,500	\$5,000,000 \$9,665,439 \$9,665,439 \$2,750,000	\$5,000, \$9,665, \$9,665, \$2,750,
MAINTENANCE FACILITIES (ALLOWANCE) SUBTOTAL (MAINT. FACIL.) VEHICLE COST REVENUE VEHICLE SUBTOTAL (VEHICLE COST) SYSTEM WIDE EQUIPMENT COST	29 1 46	\$350,000 \$5,596,500 \$75,000	\$333,291 \$2,750,000 NA	EA	\$5,000,000 \$10,150,000 \$10,150,000 \$5,596,500 \$3,450,000	\$5,000,000 \$9,665,439 \$9,665,439 \$2,750,000 \$2,856,414	\$5,000, \$9,665, \$9,665 , \$2,750, \$2,856,
MAINTENANCE FACILITIES (ALLOWANCE) SUBTOTAL (MAINT. FACIL.) VEHICLE COST REVENUE VEHICLE SUBTOTAL (VEHICLE COST) SYSTEM WIDE EQUIPMENT COST PRIORITY SIGNALIZATION	29	\$350,000 \$5,596,500	\$333,291 \$2,750,000		\$5,000,000 \$10,150,000 \$10,150,000 \$5,596,500	\$5,000,000 \$9,665,439 \$9,665,439 \$2,750,000	\$5,000, \$9,665, \$9,665 , \$2,750, \$2,856,
MAINTENANCE FACILITIES (ALLOWANCE) SUBTOTAL (MAINT. FACIL.) VEHICLE COST REVENUE VEHICLE SUBTOTAL (VEHICLE COST) SYSTEM WIDE EQUIPMENT COST PRIORITY SIGNALIZATION TICKET VENDING MACHINES	29 1 46 63360 ON 63360	\$350,000 \$5,596,500 \$75,000 \$50 \$60	\$333,291 \$2,750,000 NA \$38 \$60	EA RF RF	\$5,000,000 \$10,150,000 \$10,150,000 \$5,596,500 \$3,450,000	\$5,000,000 \$9,665,439 \$9,665,439 \$2,750,000 \$2,856,414	\$5,000, \$9,665, \$9,665, \$2,750, \$2,856, \$2,433,
MAINTENANCE FACILITIES (ALLOWANCE) SUBTOTAL (MAINT. FACIL.) VEHICLE COST REVENUE VEHICLE SUBTOTAL (VEHICLE COST) SYSTEM WIDE EQUIPMENT COST PRIORITY SIGNALIZATION TICKET VENDING MACHINES COMMUNICATIONS	29 1 46 63360	\$350,000 \$5,596,500 \$75,000 \$50	\$333,291 \$2,750,000 NA \$38	EA RF	\$5,000,000 \$10,150,000 \$10,150,000 \$5,596,500 \$3,450,000 \$3,168,000	\$5,000,000 \$9,665,439 \$9,665,439 \$2,750,000 \$2,856,414 \$2,433,885	\$5,000, \$5,000, \$9,665, \$9,665, \$2,750, \$2,856, \$2,856, \$2,433, \$3,801, \$1,900,

3

A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A
 A

TOTAL ESTIMATED COST - 1998 DOLLARS \$139,550,100 \$204,792,123 \$135,515,676

COST ESTIMATE COVERSHEET

Y

PROJECT:	VALLEY HEAVY RAIL	EST.	HTL	SHT.	1		
	NO HOLLYWOOD TO I-405	DATE	11/5/98	OF	2		
	STA 420+00 TO 736+00	REV.:	0				
		\$:_	1988 Dollars				
					MTA	LOWER	PROJECTED
ITEM DESCR	INTION				ESTIMATED COST	BOUND COST	FINAL COST
TIEM DESCR					0001	0001	COST
	AYS AND STRUCTURES				\$324,776,949	\$253,711,325	\$324,776,949
	OUS WASTE HANDLING ALLOWANCE				\$861,973	\$861,973	\$861,973
2) STATIONS					\$85,750,000	\$79,040,019	\$79,040,019
3) MAIN YAR					\$0	\$0	\$0
	IDE EQUIPMENT				\$101,443,115	\$80,009,482	\$75,250,477
5) VEHICLES					\$0	\$0	\$0
the second se	A) (see page 2 for details)				\$512,832,037	\$413,622,799	\$479,929,418
	., (+,,	,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,,	+,
6) PRE REVE	INUE OPERATION			2.5%	\$12,820,801	\$10,340,570	\$11,998,235
7) OWNERS	INSURANCE			8.0%	\$41,026,563	\$33,089,824	\$38,394,353
8) MASTER A	AGREEMENTS			2.5%	\$12,820,801	\$10,340,570	\$11,998,235
SUBTOTAL (B)				\$66,668,165	\$53,770,964	\$62,390,824
	-						
9) ART FOR	TRANSIT (C)			0.5%	\$2,564,160	\$2,068,114	\$2,399,647
SUBTOTAL (C)	~			\$2,564,160	\$2,068,114	\$2,399,647
	OF WAY (MTA)				\$79,500,000	\$79,500,000	\$79,500,000
	OF WAY (PROPOSED TAKES)				\$9,711,568	\$9,711,568	\$9,711,568
SUBTOTAL (D)				\$89,211,568	\$89,211,568	\$89,211,568
11) PROF. SE	ERVICES (E) INCL. COST TO DATE				\$165,962,524	\$105,448,734	\$119,493,017
SUBTOTAL (\$165,962,524	\$105,448,734	\$119,493,017
					****	<i></i>	÷,,
12) CONTING	GENCY (F)						
A) ITEM 1A		12%			\$38,973,234	\$30,445,359	\$103,437
ITEM 1B		10%			\$86,197	\$86,197	\$7,904,002
B) ITEM 2		12%			\$10,290,000	\$9,484,802	\$0
C) ITEM 3, 4	, & 5	10%			\$10,144,312	\$8,000,948	\$55,517,989
D) ITEM 6, 7	, & 8	10%			\$6,666,816	\$5,377,096	\$0
E) ITEM 10 E	3				INCL. IN ITEM	INCL. IN ITEM	INCL. IN ITEM
F) ITEM 11		10%			\$16,596,252	\$10,544,873	\$11,949,302
SUBTOTAL ((F)				\$82,756,812	\$63,939,277	\$75,474,730

GRAND TOTAL - 1998 DOLLARS \$919,995,266 \$728,061,455 \$828,899,204

PROJECT: VALLEY HEAVY RAIL	EST.	HTL		SHT.	2		
NO HOLLYWOOD TO I-405 STA 420+00 TO 736+00	DATE REV.	11/5/98 0		OF XLS	2		
STA 420+00 TO 736+00	NEV\$:	1988 Dollars		ALS			
	a	1900 Dollars					ESTIMATED
		MTA UNIT	BAH UNIT		MTA	LOWER	PROJECT
DESCRIPTION	QTY	PRICE	PRICE	UNIT	COST	BOUND	COST
GUIDEWAY COSTS							
AERIAL	6750	\$6,500	\$6,125	RF	\$43,875,000	\$41,341,930	\$43,875,000
AT-GRADE	1100	\$2,250	\$1,005	RF	\$2,475,000	\$1,105,212	\$2,475,000
OPEN GUIDEWAY	1660	\$6,500	\$3,525	RF	\$9,906,949	\$5,851,819	\$9,906,949
RETAINED FILL	1500	\$4,500	\$1,763	RF	\$6,750,000	\$2,643,894	\$6,750,000
BORED TUNNEL	2939	\$10,000	\$10,296	RF	\$29,390,000	\$30,261,259	\$29,390,000
CUT & COVER GUIDEWAY	17690	\$12,000	\$8,615	RF	\$212,280,000	\$152,407,212	\$212,280,000
OTHER IMPROVEMENTS	1	\$10,000,000	\$10,000,000	LS	\$10,000,000	\$10,000,000	\$10,000,000
BRIDGE WORK	100	\$101,000	\$101,000	RF	\$10,100,000	\$10,100,000	\$10,100,000
SUBTOTAL (GUIDEWAY COST)	31740				\$324,776,949	\$253,711,325	\$324,776,949
HAZARDOUS WASTE HANDLING							
ALLOWANCE	31739	\$27	NA	RF	\$861,973	\$861,973	\$861,973
SUBTOTAL (HAZ MAT)					\$861,973	\$861,973	\$861,973
STATION COST							
AERIAL (6 CAR PLATFORM)	3	\$15,000,000	\$9,086,250	EA	\$45,000,000	\$27,258,751	\$27,258,751
OPEN STATION (6 CAR PLATFORM W/ XOVE	ER) 1	\$36,000,000	\$40,888,127	EA	\$36,000,000	\$40,888,127	\$40,888,127
PARK & RIDE (SURFACE)	2000	\$2,375	\$5,447	EA	\$4,750,000	\$10,893,141	\$10,893,141
SUBTOTAL (STATION COST)					\$85,750,000	\$79,040,019	\$79,040,019
MAINT. FACIL & YARD COSTS							
MAINTENANCE FACILITIES (ALLOWANCE)	0	\$2,045,000		LS	\$0	\$0	\$0
SUBTOTAL (MAINT. FACIL.)					\$0	\$0	\$0
VEHICLE COST							
REVENUE VEHICLE	0			EA	\$0	\$0	\$0
SUBTOTAL (VEHICLE COST)					\$0	\$0	\$0
SYSTEM WIDE EQUIPMENT COST		A			A 10 0 10 0		
TRACKWORK (INCL. SPECIAL TRACKWORK		\$575	\$595	RF	\$18,249,925	\$18,895,149	\$18,249,925
TRAIN CONTROL STA.	3	\$1,100,000	NA	EA	\$3,300,000	NA	\$3,300,000
TRAIN CONTROL GDWY	31739	\$1,100	\$880	RF	\$34,912,900	\$27,940,655	\$34,912,900
TRACTION POWER STA. (XFMR)	3	\$1,750,000	\$3,435,027	EA	\$5,250,000	\$10,305,082	\$5,250,000
TRACTION POWER GDWY (THIRD RAIL)	31739	\$110	\$340	EA	\$3,491,290	\$10,782,553	\$3,491,290
COMMUNICATIONS	31739	\$1,000	\$208	RF	\$31,739,000	\$6,587,742	\$6,587,742
FARE COLLECTION	3	\$750,000	\$1,429,894	LS	\$2,250,000	\$4,289,681	\$2,250,000
SIGNAGE & GRAPHICS	3	\$750,000	\$402,873	LS	\$2,250,000	\$1,208,620	\$1,208,620
SUBTOTAL (SYSTEM COST)					\$101,443,115	\$80,009,482	\$75,250,477
TOTAL ESTIMATED COST - 1998 DOLLARS)				\$512,832,037	\$413,622,799	\$479,929,418

7

.

COST ESTIMATE COVERSHEET

,

.

PROJECT:	VALLEY LRT NO HOLLYWOOD TO WARNER CTR	EST. HTL DATE 11/5/98		1 2		
	STA 4+54 TO 736+00	REV.: 0 \$: 1988 Dollars				
		\$: 1900 Dollars	_	MTA ESTIMATED	LOWER BOUND	PROJECTED FINAL
ITEM DESC	RIPTION			COST	COST	COST
1A) GUIDEV	WAYS AND STRUCTURES			\$222,484,500	\$158,390,776	\$221,476,728
,	DOUS WASTE HANDLING ALLOWANCE			\$1,723,947	\$1,723,947	\$1,723,947
2) STATION				\$62,091,667	\$47,572,248	\$49,041,837
3) MAIN YAI	RD AND SHOP			\$25,000,000	\$26,252,777	\$25,000,000
4) SYSTEM	WIDE EQUIPMENT			\$121,066,086	\$91,311,432	\$111,756,307
5) VEHICLE				\$79,200,000	\$64,659,492	\$64,659,492
SUBTOTAL	. (A) (see page 2 for details)			\$511,566,200	\$389,910,673	\$473,658,312
6) PRE REV	ENUE OPERATION		2.5%	\$12,789,155	\$9,747,767	\$11,841,458
7) OWNERS	SINSURANCE		8.0%	\$40,925,296	\$31,192,854	\$37,892,665
8) MASTER	AGREEMENTS		2.5%	\$12,789,155	\$9,747,767	\$11,841,458
SUBTOTAL	. (B)			\$66,503,606	\$50,688,387	\$61,575,581
9) ART FOR	TRANSIT (C)		0.5%	\$2,557,831	\$1,949,553	\$2,368,292
SUBTOTAL				\$2,557,831	\$1,949,553	\$2,368,292
10 A) RIGHT	T OF WAY (MTA PROPERTIES)			\$159,000,000	\$159,000,000	\$159,000,000
10) RIGHT (OF WAY (PROPOSED TAKES)			\$57,464,899	\$57,464,899	\$57,464,899
SUBTOTAL	. (D)			\$216,464,899	\$216,464,899	\$216,464,899
11) PROF. 5	SERVICES (E)			\$241,327,646	\$155,600,215	\$211,138,783
SUBTOTAL	. (E)			\$241,327,646	\$155,600,215	\$211,138,783
12) CONTIN	IGENCY (F)					
A) ITEM 1A		12%		\$26,698,140	\$19,006,893	\$26,577,207
ITEM 1B		10%		\$172,395	\$172,395	\$172,395
B) ITEM 2		12%		\$7,451,000	\$5,708,670	\$5,885,020
C) ITEM 3,	4, & 5	10%		\$22,526,609	\$18,222,370	\$20,141,580
D) ITEM 6,	7, & 8	10%		\$6,650,361	\$5,068,839	\$6,157,558
E) ITEM 10		0% INCLUDED IN ITE	M	\$0	\$0	\$0
F) ITEM 11		10%		\$24,132,765	\$15,560,021	\$21,113,878
SUBTOTAL	. (F)			\$87,631,268	\$63,739,188	\$80,047,639
GRAND TO	TAL - 1998 DOLLARS			\$1,126,051,450	\$878,352,915	\$934,515,141
10						

PROJECT:	VALLEY LRT	EST.	HTL		SHT.	2		
	NO HOLLYWOOD TO WARNER CTR	DATE	11/5/98		OF_	2		
	STA 4+54 TO 736+00	REV.	0 1988 Dollars		XLS_			
		\$:	1988 Dollars					ESTIMATED
			MTA UNIT	BAH UNIT		MTA	LOWER	PROJECT
DESCRIPTIC	N	QTY	PRICE	PRICE	UNIT	COST	BOUND	COST
GUIDEWAY	COSTS							
AT GRADE		44175	\$1,800	\$1,557	RF	\$79,515,000	\$68,790,468	\$79,515,000
RETAINED O	GUIDEWAY	15225	\$3,500	\$711	RF	\$53,287,500	\$10,822,340	\$53,287,500
AERIAL GUI	DEWAY	13196	\$4,500	\$3,750	RF	\$59,382,000	\$49,485,740	\$59,382,000
BRIDGES LA	A River, Arroyo Seco (Actuals)	100	\$100,000	\$100,000	EA	\$10,000,000	\$10,000,000	\$10,000,000
	DEWAY IMPROVEMENTS	1	\$16,550,000	\$16,550,000	EA	\$16,550,000	\$16,550,000	\$16,550,000
GRADE CRO	DSSINGS	15	\$250,000	\$182,815	LS	\$3,750,000	\$2,742,228	\$2,742,228
SUBTOTAL	(GUIDEWAY COST)	72712				\$222,484,500	\$158,390,776	\$221,476,728
	S WASTE HANDLING							
ALLOWANC		1	\$1,723,947	NA	RF	\$1,723,947	\$1,723,947	\$1,723,947
SUBTOTAL				n		\$1,723,947	\$1,723,947	\$1,723,947
STATION CO		-						
	STATION (2 CAR PLATFORM)	5	\$1,500,000	\$756,261	EA	\$7,500,000	\$3,781,307	\$3,781,30
	TION (2 CAR PLATFORM)	5	\$3,333,333	\$1,778,144	EA	\$16,666,667	\$8,890,720	\$8,890,72
	TION (2 CAR PLATFORM W/XOVER)	1	\$3,333,333	\$1,778,144	EA	\$3,333,333	\$1,778,144	\$1,778,14
	ION (2 CAR PLAT. W/ CROSSOVER)	1	\$16,666,667	\$16,666,667	EA	\$16,666,667	\$16,666,667	\$16,666,66
	R TRANSFER PORTAL AT NO. HOLLEY	1	\$5,000,000	\$5,000,000	EA	\$5,000,000	\$5,000,000	\$5,000,00
	E (SURFACE LOT)	4700	\$2,750	\$2,437	Spaces	\$12,925,000	\$11,455,411	\$12,925,00
SUBTOTAL	(STATION COST)					\$62,091,667	\$47,572,248	\$49,041,83
MAINT. FAC	CIL & YARD COSTS							
MAINTENAN	NCE FACILITIES (ALLOWANCE)	1	\$25,000,000	\$26,252,777		\$25,000,000	\$26,252,777	\$25,000,000
SUBTOTAL	(MAINT. FACIL.)					\$25,000,000	\$26,252,777	\$25,000,000
VEHICLE CO	OST							
REVENUE V		33	\$2,400,000	\$1,959,379		\$79,200,000	\$64,659,492	\$64,659,492
SUBTOTAL	(VEHICLE COST)					\$79,200,000	\$64,659,492	\$64,659,492
SYSTEM WI	DE EQUIPMENT COST							
	RK (INCL. SPECIAL TRACKWORK)	73146	\$421	\$288	RF	\$30,794,466	\$21,036,462	\$30,794,466
TRAIN CON	and a second that the second construction of the second se	12	\$160,000	NA	EA	\$1,920,000	NA	\$1,920,00
	TROL GDWY	73146	\$500	\$485	RF	\$36,573,000	\$35,467,323	\$36,573,00
	POWER STA. (XFMR)	12	\$1,100,000	\$2.270.794	EA	\$13,200,000	\$27,249,530	\$13,200,00
	POWER GDWY. (CATENARY)	73146	\$270	NA	RF	\$19,749,420	Included in Tract	\$19,749,42
COMMUNIC		73146	\$200	\$83	RF	\$14,629,200	\$6,097,540	\$6,097,54
FARE COLL		12	\$250,000	\$86,558	LS	\$3,000,000	\$1,038,697	\$3,000,00
	GRAPHICS	12	\$100,000	\$35,157	LS	\$1,200,000	\$421,881	\$421,88
A DEVENDED OF	GIAFIIUG	12	\$100,000	\$55,157	L0	\$1,200,000	φ 4 ∠1,001	\$421,00

.

×

TOTAL ESTIMATED COST + 1998 DOLLARS \$511,566,200 \$389,910,673 \$473,658,312

COST ESTIMATE COVERSHEET

....

PROJECT: VALLEY BUS TRANSITWAY	EST. HTL	SHTOF	1		
0 NORTH HOLLYWOOD TO	DATE 11/6/'98 REV.: 0	OF_	2		
WARNER CENTER	\$: 1988 Dollars				
			MTA	LOWER	PROJECTED
			ESTIMATED	BOUND	FINAL
ITEM DESCRIPTION			COST	COST	COST
			A 10 100 100		
1A) GUIDEWAYS AND STRUCTURES 1B) HAZARDOUS WASTE HANDLING ALLOWANCE			\$43,102,480	\$46,082,214	\$43,102,480
2) STATIONS			\$1,500,000 \$15,502,000	\$1,500,000 \$18,491,733	\$1,500,000 \$15,502,000
3) MAIN YARD AND SHOP			\$5,000,000	\$5,000,000	\$5,000,000
4) SYSTEMWIDE EQUIPMENT			\$17,794,400	\$12,386,283	\$12,190,686
5) VEHICLES			\$7,700,000	\$7,332,402	\$7,332,402
SUBTOTAL (A) (see page 2 for details)			\$90,598,880	\$90,792,631	\$84,627,568
			,,	,	
6) PRE REVENUE OPERATION		2.5%	\$2,264,972	\$2,269,816	\$2,115,689
7) OWNERS INSURANCE		8.0%	\$7,247,910	\$7,263,410	\$6,770,205
8) MASTER AGREEMENTS		2.5%	\$2,264,972	\$2,269,816	\$2,115,689
SUBTOTAL (B)			\$11,777,854	\$11,803,042	\$11,001,584
9) ART FOR TRANSIT (C)		0.5%	\$452,994.40	\$453,963.16	\$423,138
SUBTOTAL (C)			\$452,994	\$453,963	\$423,138
10) RIGHT OF WAY (D) ALLOWANCE FOR 4 PARK-N-	RIDES		\$4,680,000	\$4,680,000	\$4,680,000
SUBTOTAL (D)			\$4,680,000	\$4,680,000	\$4,680,000
		8	•	•	• .,,
11) PROF. SERVICES (E)			\$48,008,577	\$18,251,323	\$28,205,041
SUBTOTAL (E)			\$48,008,577	\$18,251,323	\$28,205,041
12) CONTINGENCY (F)					
A) ITEM 1A	12%		\$5,172,298	\$5,529,866	\$5,172,298
ITEM 1B	12%		\$180,000	\$180,000	\$180,000
B) ITEM 2	17%		\$2,635,340	\$3,143,595	\$2,635,340
C) ITEM 3, 4, & 5	10%		\$3,049,440	\$2,471,868	\$2,452,309
D) ITEM 6, 7, & 8	10%		\$1,177,785	\$1,180,304	\$1,100,158
E) ITEM 10	10%		\$468,000	\$468,000	\$468,000
F) ITEM 11	10%		\$4,800,858	\$1,825,132	\$2,820,504
SUBTOTAL (F)			\$17,483,721	\$14,798,765	\$14,828,609

GRAND TOTAL - 1998 DOLLARS \$173,002,027 \$140,779,725 \$143,765,940

PROJECT: VALLEY BUS TRANSITWAY	EST DATE REV \$:	HTL 11/6/'98 0 1998 Dollars		SHT OF XLS	2 2		
DESCRIPTION	QTY	MTA UNIT PRICE	BAH UNIT PRICE	UNIT	MTA COST	LOWER	ESTIMATED PROJECT COST
GUIDEWAY COSTS		7					
AT GRADE BUSWAY	72864	\$320	\$466	RF	\$23,316,480	\$33,975,158	\$23,316,480
AT GRADE BUSWAY @ STATION	7200	\$535	Incl in above	RF	\$3,852,000	Incl in above	\$3,852,000
STREET IMPROVEMENTS @ XINGS	42	\$152,000	\$139,891	EA	\$6,384,000	\$5,875,405	\$6,384,000
TRACK REMOVAL	70000	\$65	\$18	RF	\$4,550,000	\$1,231,650	\$4,550,000
SPECIAL BRIDGE WORK @ TUJUNGA WASH	1	\$5,000,000	\$5,000,000	LS	\$5,000,000	\$5,000,000	\$5,000,000
SUBTOTAL (GUIDEWAY COST)	150107				\$43,102,480	\$46,082,214	\$43,102,480
HAZARDOUS WASTE HANDLING							
ALLOWANCE	1	\$1,500,000	NA	LS	\$1,500,000	\$1,500,000	\$1,500,000
SUBTOTAL (HAZ MAT)					\$1,500,000	\$1,500,000	\$1,500,000
STATION COST							2
AT GRADE STATION (120 FT. SIDE PLATFORM)	13	\$505,000	\$526,318	EA	\$6,565,000	\$6,842,130	\$6,565,000
(including finishes, landscaping, canopies, lighting & sig	nage)						
PARKING FACILITIES (MINIMAL AMENITIES)	4965	\$1,800	\$2,346	Spaces	\$8,937,000	\$11,649,603	\$8,937,000
SUBTOTAL (STATION COST)					\$15,502,000	\$18,491,733	\$15,502,000
MAINT. FACIL & YARD COSTS							
MAINTENANCE FACILITIES (ALLOWANCE)	1	\$5,000,000	\$5,000,000		\$5,000,000	\$5,000,000	\$5,000,000
SUBTOTAL (MAINT. FACIL.)			2		\$5,000,000	\$5,000,000	\$5,000,000
VEHICLE COST							
REVENUE VEHICLE	22	\$350,000	\$333,291		\$7,700,000	\$7,332,402	\$7,332,402
SUBTOTAL (VEHICLE COST)					\$7,700,000	\$7,332,402	\$7,332,402
SYSTEM WIDE EQUIPMENT COST							
PRIORITY SIGNALIZATION	1	\$4,336,800	\$1,050,000	LS	\$4,336,800	\$1,050,000	\$1,050,000
TICKET VENDING MACHINES	24	\$75,000	NA	EA	\$1,800,000	\$1,687,881	\$1,687,881
COMMUNICATIONS	72860	\$50	\$20	RF	\$3,643,000	\$1,438,205	\$1,438,205
GUIDEWAY LIGHTING INCL. ELECTRIFICATION	72860	\$60	\$60	RF	\$4,371,600	\$4,371,600	\$4,371,600
SECURITY	72860	\$30	\$30	RF	\$2,185,800	\$2,185,800	\$2,185,800
SIGNAGE/GRAPHICS (OTHER THAN STATIONS)	72860	\$20	\$23	RF	\$1,457,200	\$1,652,797	\$1,457,200
SUBTOTAL (SYSTEM COST)					\$17,794,400	\$12,386,283	\$12,190,686
						- An Theory Barry Announcement (Children)	and stand francisco for factorial and

TOTAL ESTIMATED COST - 1998 DOLLARS \$90,598,880 \$90,792,631 \$84,627,568

.

-

OCT IS THE RESIDEM COUNCILMEN FLAKON

TEANSIT alternative analysis

TESTIMONY

for Councilman Richard Alarcon

ASSEMBLY TRANSPORTATION COMMITTEE HEARING October 16, 1998

"Regional Transit Alternatives Analysis"

Mr. Chairman, members of the Committee, I appreciate the opportunity to address you regarding the "Regional Transit Alternatives Analysis" (RTAA) Study, developed by Booz-Allen & Hamilton, for the MTA.

As all of you are aware, the California Transportation Commission (CTC) approved the MTA's Rail Recovery Plan, and provided approximately \$134 million in construction funds on June 2, 1998.

However, these construction funds are contingent upon the MTA developing a viable transportation plan to reprogram approximately \$409 million, in State Transportation Improvement Program (STIP) funds, currently being held in reserve.

As you are also aware, the RTAA has been developed to respond to the request of the CTC, which is very simple: how should we reprogram the S409 million in STIP funds, since work has been suspended on transit improvements in the East Side, Mid-City, Pasadena, and San Fernando Valley.

I want to thank you and the CTC for asking the "right question," and I will do my very best to provide the "right answers" to help solve the transportation problems facing not only

the City of Los Angeles, but the Region, as a whole.

With the recent signing of State legislation by the Governor to establish a Joint Powers Authority for constructing the Pasadena Blue Line, there will be more local control over the deliver/of transportation services, an arrangement I support.

In addition, the City of Los Angeles has developed a project entitled "The Priority Bus Project" to serve transit-dependent communities throughout the City. This project will initially be utilized in the East Los Angeles and in the Mid-City areas as an interim solution in response to the suspension of the Metro Red Line Project in these two (2) corridors.

At my Transportation Committee Meeting, on October 14,

1998, I considered and recommended for approval by the City Council, various recommendations to improve bus services to residents in the Eastside and Mid-City areas. Once adopted by the City Council, this report will be transmitted to the MTA for approval and implementation. These Priority Bus Corridors will include: priority signalization, improved transit amenities (lighting, landscaping) and fewer stops.

r.3

As far as the San Fernando Valley is concerned, the North Hollywood leg of the Metro Red Line Project will be opening in the Year 2000. Currently, the City is in negotiations with the MTA regarding the financial agreement to assist with the construction of rail projects to the North Hollywood, East L.A., and Mid-City areas. As you may be aware, when this agreement

was approved by the City Council and MTA there were several milestones which MTA had to attain to maintain this agreement. When the Federal Government required the MTA to develop a realistic construction plan, the MTA put the development of the East L.A. and Mid-City Line on hold, indefinitately, creating a default in the agreement. It is my intent to develop a new agreement with the MTA which continues the City's commitment to complete the North Hollywood Line.

The current RTAA is studying alternative rail projects, as well as bus improvements, to extend and expand transit services in East L.A., Mid-city and the Valley areas.

As you may know, I introduced a Motion in the Los Angeles

City Council, almost a year ago, to create a "San Fernando Valley Transportation Zone," to improve transit service in the Valley and provide for local control in the delivery of services to residents.

mi councilimi memocon

My efforts, along with those of my colleagues, representatives of nine jurisdictions, and staff, have led to the completion of a "Notice of Intent to File" a transportation zone application to the MTA. I am very excited about the establishment of a transportation zone in this area, because I believe that it can be successful, and that we can provide the type of seamless transportation system that will become a model throughout the L.A. region, for other cities in the State, and possibly, the Nation.

We are currently working with eight (8) other cities, and the

County of Los Angeles, and we will submit, to the MTA, an application for a transportation zone to help improve transit services in the San Fernando Valley.

In inviting me to attend this hearing, you requested my viewpoint on how the MTA can provide adequate transit services to all parts of Los Angeles.

The MTA's dual role of being both the regional planning and programming agency, and the second largest transit agency in the Nation, has created a conflict of interest in some respect.

Therefore, when the MTA addresses the question of "the adequate need of transit services, and how they can provide that service," it is necessary for the MTA to "look outside the box" as a transit operator, and look at itself as a planning and programming agency, in order to find better ways to provide transit service.

I believe that the MTA has access to a great deal of funds from various sources and has an opportunity and a responsibility to improve public transit service in Los Angeles, and there is a toolbox of ideas to make this happen. It must continue to focus on the two concepts I touched on earlier – greater local control and improved bus service.

As previously explained, I have recommended, and received support for, the creation of a Transportation Zone in the San Fernando Valley. We are talking about saving at least 25% in

operating costs from current MTA costs. We believe we can do this while maintaining the collective bargaining arrangement and upholding existing agreements.

If those costs could be converted into providing more service, obviously we can increase service in the San Fernando Valley.

There are other members of the MTA Board, and members of our community, who are talking about the possibility of additional zones in the rest of the region-which I believe should be fully explored.

Inclusive in the Bus Priority proposal that I will be submitting to the MTA will be the complete reconfiguration of the City's

previous \$200 million to assist with the construction of the three rail segments. As previously stated, it is my intent that the City continue its commitment to the completion of the North Hollywood segment, which I believe will be approximately \$93 million total. Additionally, I am proposing funds to be used to purchase 20 new buses and expand the City's highly successful community DASH service by four new lines. The community DASH is a popular bus service that the City of L.A. provides in communities throughout the City. The service uses clean fuel buses to operate on circular routes and provide trips for only 25 cents. Recently, the City has also begun to purchase low-floor vehicles, which will improve services for both the elderly and disabled. In addition to the DASH services, my plan includes funds for new Park-and-Ride, additional street resurfacing of

P.11

transit street to improve bus service, purchasing and operation of 40 new shuttles which can provide flexible and/or paratransit trips to better serve our residents, and the priority bus corridors that I mentioned previously. The plan will also include funding to provide a required local match to the federally approved ISTEA-2 or TEA-21 projects in the MTA's own Call-for-Project process allowing the City to leverage its critical transportation dollars. This proposal may provide a model of services for all jurisdictions to consider to implement as they develop programs to better serve their residents.

P.12

The MTA has funded \$2.5 million of transit restructuring studies in the City of Los Angles, and has funded a couple of other studies outside the City, in the San Gabriel Valley, and in the

Southeastern Los Angeles County.

These transit restructuring studies were intended to improve transit service through the entire MTA service area, help eliminate service redundancy, and better coordinate MTA service with the municipal operators. In this vein, the MTA has spent over a year in each community in the region, obtaining input to improve transit service and efficiency. As such, the MTA should expeditiously move to implement the recommendations from te restructuring studies, and work to eliminate barriers that prohibit their implementation.

F.10

The MTA should also seek partnerships, as in the Priority Bus Project that we are recommending in the East Los Angeles and the

Mid-City areas, to help improve both surface street operations, and streetscapes along transit corridors.

F.14

We should continue to work with local jurisdictions and CALTRANS to develop projects to move buses more quickly in the existing street system, and in that manner, we could save operating costs for the MTA.

It is my observation that the MTA should also take a leadership role in technology, and advocate high-capacity, cleanfuel, low-floor buses with electronic fare media, and other ITS technologies, to improve boarding and alighting of bus passengers, to improve the efficiency of our bus system-both locally and on a regional basis.

13

In closing, I would like to thank you for providing me the opportunity to express my viewpoints on this important matter, and I hope that we can continue our dialog on improving transportation services for resident in the greater Los Angeles area.

P.15

Thank you Mr. Chairman and members.

Purpose and Direction of the RTAA

- The Metro Rail System Plan defined the "mission" of the MTA
- Suspension of the rail projects required a re-examination of the mission statement
- Board adopted Restructuring Plan on May 13, 1998 and required study of "viable and effective options" for all parts of the County (with an emphasis on the corridors with the suspended rail lines)

Subsequent Developments

- MOU with California Transportation Commission required re-programming of 1998 STIP and completion of RTAA
- New Funding provided by TEA-21 and requirement to amend the 1998 STIP expanded the scope of the study

Framework of RTAA

- Addresses funding allocations
- Examines transit dependency
- Studies "viable and effective options"
- Identifies immediate improvements
- Sets the direction for further project development

What the RTAA is and What it is Not

<u>It Is</u>

It Is Not

• A policy framework	• (except with respect to the STIP amendment submitted for Board approval) adoption of a budget or procurement authorization
• A funding plan which generally coincides with the STIP and TEA-21 funding cycles (1999-2004)	• A Long Range Plan (a new LRP will begin in FY '99 and will be completed in FY '00)

RTAA Accomplishments/Limitations

Accomplishments


• Equitable allocation of funds between:

	%	<u>Dollars</u>
Highway	31	5,242
Rail	22	3,771
Bus	47	7,913

Limitations

- Subject to final approval of the Board of funding for Call-for-Projects, Rapid Bus and Technology purchases
- MTA operating deficit not resolved

RTAA Distribution of Funds FY 1999 - FY 2004 (\$millions)



RTAA Accomplishments/Limitations

Accomplishments

- Satisfies requirements of CTC MOU
- \$151 million programmed to fully funded projects
- Rapid Bus/Fixed Guideway Study/plan to respond to needs of transit dependent in parts of L.A. County

Limitations

• Pasadena Blue Line not fully funded

RTAA Accomplishments/Limitations

Accomplishments

- Rapid Bus will improve service to transit dependent in all parts of the county
- Priority to East Side, Mid-Cities and San Fernando Valley with suspended rail projects

Limitations

 Rapid Bus does not <u>replace</u> the commitment to fixed guideway transit in the corridors with suspended subway projects